

Hot Spot Skate Park Office

Addendum # 1

Additional information:

1. The drawing show the exterior siding as Hardi-Board or equal. Behind the siding, the contractor shall install one layer of OSB board and wrap with house wrap.
2. The dimension is missing on the elevation now shown on Addendum # 1 Drawing.
3. The roof pitch is 2/12.
4. The speaker on the exterior are not in contract. They will be removed.
5. The bathroom fixture and equipment will be remove and returned to contractor for placement in the bathrooms.
6. The exterior ramp and stairs, both front and back will be remove from site or demolished.
7. The new building will be extended forward from the skate surface 42".
8. Contractor may use the existing electrical panel in the old structure and place in the storage room.