

EXHIBIT B (CONTINUED) - BID SCHEDULE
Lower East Fork Laterals of the Trinity Watershed
Floodwater Retarding Structure No. 3 Upgrade
Kaufman-Van Zandt Soil and Water Conservation District

<i>BID ITEMS</i>						
ITEM NO.	WORK OR MATERIAL	SPEC NO.	QTY	UNIT	UNIT PRICE	TOTAL AMOUNT
1	Structure Removal – Principal Spillway	3	1	LS		\$ -
2	Structure Removal – Fences	3	1	LS		\$ -
3	Silt Fence	5	2,150	LF		\$ -
4	Pollution Control	5	1	LS		\$ -
5	Vegetation, Seeding	6	33	AC		\$ -
6	Irrigation System	6	1	LS		\$ -
7	Irrigation Water	6	6,721	1,000 GAL		\$ -
8	Construction Survey	7	1	LS		\$ -
9	Mobilization and Demobilization	8	1	LS		\$ -
10	Removal of Water	11	1	LS		\$ -
11	Excavation, Common	21	7,240	CY		\$ -
12	Earthfill, Zone 1	23	42,260	CY		\$ -
13	Earthfill, Zone 2	23	2,150	CY		\$ -
14	Earthfill, Zone 3	23	530	CY		\$ -
15	Earthfill, Zone 4	23	400	CY		\$ -
16	Drainfill, Fine	24	410	CY		\$ -
17	Drainfill, Coarse	24	70	CY		\$ -
18	Topsoil	26	159,530	SY		\$ -
19	Diversions	27	60	LF		\$ -
20	Concrete, Structural, Riser	31	61	CY		\$ -
21	Concrete, Pipe Cradle	31	35	CY		\$ -
22	Concrete, Structural, Impact Basin	31	77	CY		\$ -
23	Reinforcing Steel	34	25,270	LB		\$ -
24	Open Trench, 48" I.D. Pipe Installation	41	70	LF		\$ -
25	Slip Lining, 48" I.D. Pipe Installation	41	120	LF		\$ -
26	Plastic Pipe, PVC	45	1,120	LF		\$ -
27	Boring and Jacking	54	120	LF		\$ -
28	Rock Riprap, Outlet Channel	61	510	TN		\$ -
29	Rock Riprap, Upstream Berm	61	810	TN		\$ -
30	Slide Gate, 18" x 18"	71	1	EA		\$ -
31	Metal Fabrications	81	1	LS		\$ -
32	Fence, Chain Link	91	100	LF		\$ -
33	Field Fence, Barbed Wire	92	3,800	LF		\$ -
34	Contractor Quality Control	94	1	LS		\$ -
35	Conduit Abandonment	99	1	LS		\$ -
TOTAL						\$ -