OWNER DEPARTMENT OF **ENVIRONMENTAL SERVICES**

WATER, SEWER, STREETS BUREAU 4200 28TH STREET SOUTH ARLINGTON, VA 22206

PHONE: 703.228.6555 FAX: 703.228.7865 WWW.ARLINGTONVA.US


ENGINEER CDM SMITH INC.


10560 ARROWHEAD DRIVE, SUITE 500 FAIRFAX, VA 22030

PHONE: 703.691.6500

CONTRACTOR TO BE DETERMINED

LOCATION MAP






ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES

VIRGINIA - ALL RIGHTS RESERVED



Nicole Dean

REVISIONS

DATE

GENERAL NOTES:

SPOUT RUN DEEP SEWER REHABILITATION

GENERAL CONSTRUCTION NOTES

PROJECT NUMBER: SA60

ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS, AND WHERE APPLICABLE THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS, AND ROAD AND BRIDGE STANDARDS. THE LATEST EDITIONS OF EACH RELEVANT MANUAL SHALL BE USED.

CONSTRUCTION DRAWINGS FOR:

- ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND ALL OTHER RELEVANT WORK SAFETY REQUIREMENTS, LATEST EDITIONS.
- 3. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES

BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS.

- THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES (i.e. WATER, SEWER, GAS, TELEPHONE, ELECTRIC, AND CABLE TV) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION OR CONSTRUCTION. THE CONTRACTOR IS REQUIRED TO IDENTIFY AND PROTECT ALL OTHER UTILITY LINES FOUND IN THE WORK SITE AREA BELONGING TO OTHER OWNERS THAT ARE NOT MEMBERS OF "MISS UTILITY". PRIVATE WATER, SEWER AND GAS LATERALS WILL NOT BE MARKED BY MISS UTILITY OR THE COUNTY. THE CONTRACTOR SHALL LOCATE AND PROTECT THESE SERVICES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALL NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A COPY OF ALL CUT SHEETS FOR REVIEW, PER THE SPECIFICATIONS. THE COST OF ALL NECESSARY SURVEYING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND, UNLESS OTHERWISE SPECIFIED, THE COST SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- . THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE. WHEN CONSTRUCTION ACTIVITY REACHES IN PROXIMITY TO EXISTING UTILITIES, THE TRENCH(ES) SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK OR TEST PITS SHALL BE MADE TO VERIFY THE EXACT LOCATION AND INVERTS OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN THE LINE OR GRADE AS DIRECTED BY THE PROJECT OFFICER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE EXISTING UTILITIES AND THE RELATED STRUCTURES. ALL EXISTING UTILITY SYSTEMS SHALL BE PROTECTED TO PREVENT DAMAGE DURING THE CONTRACTOR'S OPERATIONS. ANY SYSTEM DAMAGED SHALL BE PROMPTLY REPAIRED AT NO COST TO THE OWNER.
- EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY. UNLESS OTHERWISE SPECIFIED, THE COST FOR THIS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE INCORPORATED INTO THE
- COSTS FOR RELEVANT ITEMS. THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE.
- ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

10. THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

11. TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION STANDARD.

TRAFFIC CONTROL

- 12. CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL
- 13. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE, CHALK, OR LUMBER CRAYONS. THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE
- 14. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- 15. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH
- 16. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS THE CONTRACTOR SHALL NOT CLOSE, RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REQUEST OF THE PROJECT OFFICER. ANY RELOCATION OR CLOSURE OF A BUS STOP SHALL REQUIRE AT LEAST FOUR WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR - 703-228-3049.
- 17. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

- 18. UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY WATER VALVES OR APPURTENANCES. CONTRACTORS SHALL SUBMIT ALL REQUESTS FOR VALVE OPERATIONS TO THE PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED OPERATION
- 19. IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER.
- 20. THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMENT WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED

FIRE DEPARTMENT NOTES:

TRAFFIC ENGINEERING AND OPERATIONS.

- 21. ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 22. ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 23. IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

TABLE OF CONTENTS

- Overall Site Plan
- Plan and Profile I Plan and Profile II Plan and Profile III
- Plan and Profile IV Plan and Profile V
- Plan and Profile VI Suggested Temporary Bypass Approach I Suggested Temporary Bypass Approach II
- Suggested Temporary Bypass Approach III Suggested Temporary Bypass Approach IV
- Cured in Place Lining Table Erosion and Sediment Control Plan
- **Erosion and Sediment Control Narrative Erosion and Sediment Control Details**
- Erosion and Sediment Control Details
- Details II
- Details III
- Details IV
- 23 NPS Pavement Standard Details
- NPS Pavement Standard Details NPS Pavement Standard Details
- NPS Guardrail Standard Details
- NPS Guardrail Standard Details
- Transportation Management Plan
- Maintenance of Traffic Notes Legend and Details Maintenance of Traffic Standard Notes and Details
- Maintenance of Traffic Standard Notes and Details Maintenance of Traffic - Phase 1
- Maintenance of Traffic Phase 2 Maintenance of Traffic - Phase 3 Maintenance of Traffic - Phase 4
- Maintenance of Traffic Phase 5 Maintenance of Traffic - Phase 6
- Maintenance of Traffic Phase 8 & 9 Maintenance of Traffic - Phase 10

Maintenance of Traffic - Phase 7

- Maintenance of Traffic Phase 11 Maintenance of Traffic - Phase 12 Tree Inventory Plan 1
- Tree Inventory Plan 2 Tree Inventory Table 1
- Tree Inventory Table 2

ADDITIONAL NOTES

- 1. CONTRACTOR IS RESPONSIBLE TO INSTALL CIPP LINER INSIDE EXISTING 33" SANITARY SEWER FROM MH 750 TO MH 740.
- 2. TEMPORARY BYPASS PUMPING SYSTEM SHALL BE IN PLACE AND OPERATIONAL BEFORE CIPP LINING WORK CAN BE PERFORMED.
- 3. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING ALL MANHOLE LOCATIONS, MANHOLE DEPTHS, AND PIPE LENGTHS, PRIOR TO LINING OPERATIONS.

SWM#

1,800 - N NASH ST (FROM KEY BLVD TO US 29) - 2021 - VDOT 5,700 - FROM 21ST ST N AND N UHLE ST TO N SCOTT ST AND LANGSTON BLVD - 2021 - VDOT

5,300 - LANGSTON BLVD (FROM N SCOTT ST AND LANGSTON BLVD TO N NASH ST AND LANGSTON BLVD) - 2021 - VDOT 15,000 - LANGSTON BLVD (FROM N NASH ST AND LANGSTON BLVD TO N QUINN ST AND LANGSTON BLVD) - 2021 - VDOT 18,000 - SPOUT RUN PKWY (FROM LORCOM LANE TO GW PKWY) - 2021 - VDOT

55,000 - CUSTIS MEMORIAL PKWY (I-66) (FROM 20TH RD N TO LANGSTON BLVD TO LYNN ST) - 2021 - VDOT

STREET CLASSIFICATION

NEIGHBORHOOD MINOR - N QUINN ST, N TAFT ST, N SCOTT ST NEIGHBORHOOD PRINCIPAL - 21ST ST N MINOR ARTERIAL - N NASH ST

PRINCIPAL ARTERIAL - LANGSTON BLVD MINOR ARTERIAL - SPOUT RUN PKWY INTERSTATE - I-66

POSTED SPEED

25 MPH - N TAFT ST, N SCOTT ST, N QUINN ST, 21ST ST N, N NASH ST

30 MPH - LANGSTON BLVD (SR 29) SB 40 MPH - LANGSTON BLVD (SR 29) NB

35 MPH - SPOUT RUN PKWY (NATIONAL PARK SERVICE) 55 MPH - CUSTIS MEMORIAL PKWY (I-66)

DESIGNED: R. PANNEERSELVAM DRAWN: J. SOSA

CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022



Fairfax, VA 22030

Tel: (703) 691-6500

SHEET 1 OF 46

10560 Arrowhead Drive, Suite 500

	LINETYPE	LEGEND	<u>S</u>	YMBOL LEGE	<u>ND</u>			SYMBOL	<u>LEGEND</u>
FEATURE	EXISTING	PROPOSED	EXISTING FEATURE	<u>P</u>	ROPOSED FEATURE		EXISTING FEATURE		PROPOSED FEATURE
BUILDING			EX CABLE PEDESTAL	С			EX STRIPING	(A)	PROP STRIPING
CENTERLINE / BASELINE			EX ELECTRIC BOX	E			EX BUS STOP	F	PROP BUS STOP
COMMUNICATIONS CABLE	COM	COM	EX FIRE HYDRANT	-	PROP FIRE HYDRANT	-			
CONTOURS - MAJOR, MINOR		250	EX GAS VALVE	•	PROP GAS VALVE	0		LABEL	LEGEND
CRITICAL ROOT ZONE	——————————————————————————————————————		EX GROUND LIGHT	•			EXISTING EXISTING SANITARY		PROPOSED PROPOSED SANITARY SEWER
EASEMENT			EX GUY WIRES	>-			STRUCTURE NUMBER EXISTING STORM SEWER		STRUCTURE NUMBER PROPOSED STORM SEWER
ELECTRIC (UNDERGROUND)	——————————————————————————————————————	——— UGE———	EX IRON PIPE OR PIN	•			STRUCTURE NUMBER	<u> </u>	STRUCTURE NUMBER
FENCE (MATERIAL NOTED)	xxxx	_xxxx	EX LIGHT POLE	•	PROP LIGHT POLE			НАТСН	LEGEND
FIBER OPTIC	FO	—— FO ——	EX MAILBOX				PROP MILL & OVERLAY		<u>LEGEND</u>
	——— GAS ———	—— GAS ———	EX MONUMENT	•			PROP FULL DEPTH ASPHALT		
X" GAS LINE (SIZE INCLUDED IF AVAILABLE)	— #"g— #"g— #"g—	#" G#" G	EX PARKING METER	\odot			SEE TYPICAL SECTION FOR DI	ETAILS	
GUARDRAIL	. 0 0 0 0 0 0	. 0 0 0 0 0 0 0	EX PAY STATION	PS	PROP PAY STATION	PS	REPLACE & MATCH EXISTING OR LEADWALK. SEE CONSTRU		
HARDSCAPE FEATURE (MATERIAL NOTED)			EX SANITARY MANHOLE	0	PROP SANITARY MANHOLE	0	DEMOLITION AREA		
LIMITS OF DISTURBANCE	LOD	— LOD — LOD —	EX STORM BASIN		PROP STORM CATCH BASIN (TO SCALE)	0			
LIMITS OF WORK	LOW	LOW	EX STORM MANHOLE	[6]	PROP STORM MANHOLE	0	<u>ABBREVIA</u>		
OVERHEAD WIRES			EX TELEPHONE PEDESTAL	Т			AF APPROX.	ARLINGTON FIBER APPROXIMATE	
PAVEMENT MINI SKIP LINE			EX TRAFFIC CONTROL BOX				DIP EB EX.	DUCTILE IRON PIPE EAST BOUND EXISTING	
PAVEMENT SKIP LINE			EX TRAFFIC SIGN	-•-	PROP TRAFFIC SIGN	•	FH INV	FIRE HYDRANT INVERT	
PROPERTY LINE			EX TRASH CAN	*	PROP TRASH CAN	*	LOD MH	LIMIT OF DISTURBANG	CE
RIGHT-OF-WAY LINE			EX TRAVERSE	√ _o /			MOT SAN	MAINTENANCE TRAFF: SANITARY	IC
ROOT PRUNING	—— RP —— RP ——	—— RP —— RP ——	EX TREES, WOODED AREA	E .	PROPOSED TREE	+	SB SEW	SOUTH BOUND SEWER	
SANITARY SEWER	SAN	SAN					UGE	TELEPHONE UNDERGROUND ELEC	TRIC
SANITARY SEWER UNDER 20" (SIZE INCLUDED IF AVAILABLE)	#"s				PROPOSED TREE REMOVAL	X	UGT UNK	UNDERGROUND TELEF UNKNOWN	PHONE
SANITARY SEWER OVER 20"		-	EX UTILITY MANHOLE TYPE INDICATED ELEC, TELE, ETC				WM X-ING CIPP	WATER MAIN CROSSING	
SILT FENCE	xxxx	xxxx	EX UTILITY POLE	•	PROP UTILITY POLE	•	RCP	CURED IN PLACE PIPE REINFORCED CONCRE	
STORM (SIZE NOTED)	STM		EX WATER MANHOLE	0	PROP WATER MANHOLE				
STREAM			EX WATER METER		PROP WATER METER	•			
STREET LIGHT CONDUIT	—— SL ———	SL	EX WATER VALVE	\otimes	PROP WATER VALVE	*			
TELEPHONE (UNDERGROUND)	——— UGT———	—— UGT———	EX YARD INLET		PROP YARD INLET (TO SCALE)				
TREE LINE			EX BENCHMARK		CONSTRUCTION NOTES (LEADER TO AREA AFFECTED)	<u>/</u>			
TREE PROTECTION FENCE	—— TP ——	—— TP ——		1	DETAIL NUMBER (SEE NOTE)	D#)			
			NORTH ARROW	Ñ	CURVE NUMBER (SEE CURVE TABLE)	C #)			
WATERLINE UNDER 20" (SIZE INCLUDED IF AVAILABLE)	#" w			I	LINE NUMBER (SEE LINE TABLE	E) (L#)			
WATERLINE OVER 20"					TEST HOLE	•			
					PHOTO (NTS)	6 Photo num #5 Sheet when	oer e photo is taken		

ARLINGTON VIRGINIA

DEPARTMENT OF
ENVIRONMENTAL SERVICES
Water Sewer Streets Bureau

Water Sewer Streets Bureau 4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

Dan Hilly 2

Daniel G. Gilroy
Lic. No. 0402022914

2/7/2022

XXXX

 $\langle XXXX \rangle$

DATE
12/13/2022
UPERVISOR
ENT SUPERVISOR 12/14/22
BUREAU CHIEF h 12/14/22
OR 12/15/2022

REVISIONS

AND ABBREVIATIONS

LEGEND


DESIGNED: R. PANNEERSELVAM
DRAWN: J. SOSA
CHECKED: D. GILROY


CDM Smith


PLOTTED: DECEMBER 7 2022


10560 Arrowhead Drive, Suite 500 Fairfax, VA 22030 Tel: (703) 691-6500


SHEET 2 OF 46




















ARLINGTON VIRGINIA

ENVIRONMENTAL SERVICES

4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNT VIRGINIA - ALL RIGHTS RESERVED

> DANIEL G. GILROY Lic. No. 0402022914 12/7/2022

DATE 12/13/2022 DESIGNATION DE PROPERTOR DE LA CONTRACTOR DE LA CONTRAC

WATER, SEWER, STREETS BUREAU CHIEF

12/15/2022

DATE

ED TEMPORARY APPROACH I SUGGEST

DESIGNED: R. PANNEERSELVAM DRAWN: J. SOSA CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022



Fairfax, VA 22030 Tel: (703) 691-6500

SHEET 10 OF 46

2. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK ASSOCIATED WITH TEMPORARY BYPASS PUMPING, INCLUDING BUT NOT LIMITED TO, PLACING AND MAINTAINING/FUELING BYPASS PUMPS, LAYING PIPES OVER LAND,

1. SUGGESTED TEMPORARY BYPASS APPROACH WAS DEVELOPED TO SECURE

NATIONAL PARK SERVICE AND VDOT LAND USE PERMITS. CONTRACTOR MAY ELECT TO FOLLOW A DIFFERENT BYPASS PLAN, HOWEVER, WILL BE

AND MAINTAINING/FUELING BYPASS PUMPS, LAYING PIPES OVER LAND, AND OPEN CUT ROAD CROSSINGS AS SHOWN ON THE PLANS.3. CONTRACTOR TO STABILIZE AND ANCHOR THE BYPASS PIPES TO PREVENT

RESPONSIBLE FOR SECURING PERMITS, AND ANY RESULTING

CONSTRUCTION SCHEDULE DELAYS OR COSTS.

PIPES FROM MOVING DURING OPERATION.

ARLINGTON VIRGINIA

DEPARTMENT OF ENVIRONMENTAL SERVICES

Water Sewer Streets Bureau 4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

Dan Hilrey

Daniel G. Gilroy
Lic. No. 0402022914

APPROVALS DATE

12/13/2022

DESIGNATION MANAGEMENT SUPERVISOR

12/15/2022

CONSTRUCTION MANAGEMENT SUPERVISOR

CONSTRUCTION MANAGEMENT SUPERVISOR

12/14/22

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach
TRANSPORTATION DIRECTOR

12/14/22

Nicole Dean
PROJECT MANAGER

12/15/2022

REVISIONS DATE

SEWER REHABILITATION

DEEP

RUN

SUGGESTED TEMPORARY APPROACH II

DESIGNED: R. PANNEERSELVAM
DRAWN: J. SOSA
CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022



Fairfax, VA 22030 Tel: (703) 691-6500

SHEET 11 OF 46

Bypass #1

Bypass #2

Bypass #3

Existing Sewer

Proposed New Manhole

Existing Manhole

Rehab Access


Manhole

Rehab Sewer //// Open Cut Road Crossing


Pump Platform

Bypass Generator

Gravel Pad



SPOUT RUN DEEP SEWER REHABILITATION



SPOUT RUN DEEP SEWER REHABILITATION

CURED IN PLACE LINING TABLE											
SHEET NO.	PIPE SEGMENT	STREET /ACCESS	UPSTREAM MH	DOWNSTREAM MH	LENGTH (FT)*	DIA. (IN)	PIPE MATERIAL	UPSTREAM MH DEPTH (FT)*	DOWNSTREAM MH DEPTH (FT)*	SLOPE (%)	NOTES
4	750-749	EAST BOUND OF SPOUT RUN PKWY	MH-750	MH-749	32	33	REINFORCED CONCRETE PIPE	11	14	0.15	
4	749-748	EAST BOUND OF SPOUT RUN PKWY AND 2148 N. TAFT STREET	MH-749	MH-748	505	33	REINFORCED CONCRETE PIPE	14	119	0.15	
5	748-747	2148 N. TAFT STREET AND 2135 TO 2123 N. SCOTT STREET	MH-748	MH-747	450	33	REINFORCED CONCRETE PIPE	119	101	0.15	INVERT OF MH 747 IS NOT ACCESSIBLE FROM THE SURFACE AND CAN NOT BE USED FOR LINING.
5	747-746	2135 TO 2123 N. SCOTT STREET AND 2109 N. QUINN STREET	MH-747	MH-746	496	33	REINFORCED CONCRETE PIPE	101	108	0.15	INVERT OF MH 747 IS NOT ACCESSIBLE FROM THE SURFACE AND CAN NOT BE USED FOR LINING.
6	746-745	2109 N. QUINN STREET	MH-746	MH-745	537	33	REINFORCED CONCRETE PIPE	108	83	0.15	MH 745 IS LOCATED ON PRIVATE PROPERTY AND HAS LIMITED ACCESS. IT CAN NOT BE USED TO LAUNCH THE LINER.
7	745-742	1658 21ST STREET N	MH-745	MH-742	414	33	REINFORCED CONCRETE PIPE	83	40	0.15	MH 745 IS LOCATED ON PRIVATE PROPERTY AND HAS LIMITED ACCESS. IT CAN NOT BE USED TO LAUNCH THE LINER. MH 742 IS LOCATED IN I-66 MEDIAN AND CAN NOT BE USED TO LAUNCH THE LINER.
8	742-741	I-66 (EAST BOUND)	MH-742	MH-741	437	33	REINFORCED CONCRETE PIPE	40	67	0.16	MH 742 IS LOCATED IN I-66 MEDIAN AND CAN NOT BE USED TO LAUNCH THE LINER. MH 741 TOP IS BURIED APPROXIMATELY 20 FT BELOW GROUND AND SHALL BE RAISED TO GRADE.
9	741-740	PARKING LOT OF 1593 N. COLONIAL TERRACE	MH-741	MH-740	500	33	REINFORCED CONCRETE PIPE	67	40	0.16	MH 741 TOP IS BURIED APPROXIMATELY 20 FT BELOW GROUND AND SHALL BE RAISED TO GRADE.
	1			1			1		1		

NOTES:

- 1. *CONTRACTOR TO FIELD VERIFY THE MANHOLE DEPTHS AND PIPE SEGMENT LENGTHS. MANHOLE DEPTHS AND PIPE SEGMENT LENGTHS AND SLOPES PROVIDED IN TABLE ABOVE ARE FROM AS-BUILT RECORDS. NOTE THAT SEWER LENGTHS SHOWN ARE MH CENTER TO MH CENTER.
- 2. PRIOR CCTV INSPECTION VIDEOS ARE AVAILABLE UPON REQUEST.
- 3. REMOVE MANHOLE STEPS PRIOR TO REHABILITATION, EXCEPT FOR MH 747 (NOT ACCESSIBLE FROM THE SURFACE).
- 4. CONTRACTOR SHALL GENERATE MACP REPORTS FOR THE FOLLOWING MANHOLES: MH 750, MH 749, MH 748, MH 746, MH 745, MH 742, MH 741, MH 740.

DEPARTMENT OF
ENVIRONMENTAL SERVICES
Water Sewer Streets Bureau

Water Sewer Streets Bureau 4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SEAL

Dan Silver Z DANIEL G. GILROY Lic. No. 0402022914

APPROVALS DATE

12/13/2022

DESIGNENGINEER TEAM SUPERVISOR

TRANSPORTATION DIRECTOR

12/15/2022

12/15/2022

12/14/22

12/14/22

12/14/22

12/14/22

Nicole Dean
PROJECT MANAGER

REVISIONS DA

12/15/2022

SEWER REHABILITATION


CURED IN PLACE LINING

DESIGNED: R. PANNEERSELVAM
DRAWN: J. SOSA
CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022



SHEET 14 OF 46



PROJECT DESCRIPTION:

THE SPOUT RUN DEEP SEWER CIPP LINING PROJECT INCLUDES REHABILITATION OF APPROXIMATELY 3,371 LINEAR FEET OF 33-INCH REINFORCED CONCRETE PIPE (RCP) WITH 33-INCH CIPP CONVENTIONAL CURING. THIS PROJECT APPROXIMATELY RUNS FROM EAST BOUND OF SPOUT RUN PARKWAY, ACROSS INTERSTATE I-66 TO NORTH NASH STREET. THE APPROXIMATE DISTURBED AREA FOR THIS PROJECT IS 1,100 SQFT.

EXISTING SITE CONDITIONS:

CONTRACTOR SHALL FIELD VERIFY ALL MANHOLE ELEVATIONS AND PIPE LENGTHS PRIOR TO CONSTRUCTION.

MANHOLE 750 AND 749 ARE LOCATED BY SPOUT RUN CREEK. THE WATER LEVEL OF THIS CREEK CAN FLUCTUATE DURING THE SUMMER IN WET

MANHOLE 748, 747, AND 746 ARE LOCATED ON PAVED LOCAL ROADS IN RESIDENTIAL AREAS. STREET PARKING ON EITHER SIDE IS ALLOWED EXCEPT FOR NORTH SCOTT STREET. MH-748 IS LOCATED NEAR PROTECTED HISTORICAL PROPERTY, DAWSON-BAILEY HOUSE.

MANHOLE 745 IS INACCESSIBLE DUE TO ITS LOCATION IN BETWEEN TWO CONDOMINIUM BUILDINGS.

MANHOLE 742 IS LOCATED IN THE MEDIAN OF I-66.

MANHOLE 741 IS LOCATED IN NORTH COLONIAL TERRACE PARKING LOT

MANHOLE 740 IS LOCATED BY THE PARKING LOT ENTRANCE OF GEORGETOWN VISTA CONDOMINIUM.

ADJACENT PROPERTIES:

MANHOLE 750 AND 749 ARE LOCATED IN NATIONAL PARK SERVICE (NPS) PROPERTY.

MANHOLE 748 IS LOCATED NEAR PROTECTED HISTORICAL PROPERTY, THE DAWSON-BAILEY HOUSE. THIS HISTORICAL AREA CANNOT BE DISTURBED. THERE ARE ALSO RESIDENTIAL PROPERTIES ON THE WEST SIDE OF NORTH TAFT STREET.

MANHOLE 747, 746, 745, 741, AND 740 ARE IN RESIDENTIAL AREAS.

CONTRACTOR'S LAYDOWN AREA: TO BE DETERMINED.

POTENTIAL PARKING AREAS: TO BE DETERMINED.

THERE ARE NO STEEP SLOPES WITHIN THE LIMITS OF DISTURBANCE. THE FOLLOWING ARE THE CRITICAL AREAS WITHIN THE LIMITS OF DISTURBANCE:

MANHOLE 750 AND 749 ARE LOCATED BY SPOUT RUN CREEK. THE WATER LEVEL OF THIS CREEK CAN FLUCTUATE DURING THE SUMMER IN WET CONDITION.

MANHOLE 748 IS LOCATED NEAR PROTECTED HISTORICAL PROPERTY, THE DAWSON-BAILEY HOUSE. THIS HISTORICAL AREA CANNOT BE DISTURBED.

MANHOLE 745 IS INACCESSIBLE DUE TO ITS LOCATION IN BETWEEN TWO CONDOMINIUM BUILDINGS.

MANHOLE 742 IS LOCATED IN THE MEDIAN OF I-66.

EROSION AND SEDIMENT CONTROL MEASURES:

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDE SILT FENCE AND INLET PROTECTION. INLET PROTECTION IS REQUIRED OUTSIDE THE PROJECT LIMITS WHEN/WHERE SURFACE WATER FROM DISTURBED AREA FLOWS.

PERMANENT STABILIZATION:

ALL NON-PAVED AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH GRASS, MULCH OR SOD. SEE THE PROPOSED PLANS FOR ADDITIONAL INFORMATION.

STORMWATER RUNOFF CONSIDERATIONS:

NO ADDITIONAL IMPERVIOUS AREA WILL BE ADDED TO THIS PROJECT.

TOTAL LAND DISTURBANCE = 1,100 SF (0.03 ACRES)

SOILS INFORMATION:

THE FOLLOWING SOILS ARE FOUND ON SITE (SEE SOIL MAP ON SHEET 18 FOR LOCATION)

- GLENELG-MANOR COMPLEX URBAN LAND-UDORTHENTS COMPLEX
- URBAN LAND-SASSAFRAS-NEABSCO COMPLEX
- URBAN LAND-GLENELG COMPLEX 10C
- 10D URBAN LAND-GLENELG COMPLEX

FLOODPLAIN AND RESOURCE PROTECTION AREA (RPA):

THERE ARE NO FLOODPLAIN OR RESOURCE PROTECTION AREAS LOCATED WITHIN THIS PROJECT SITE

EROSION & SEDIMENT CONTROL PROJECT PHASING

1. PHASE I:

- a. PRE-CONSTRUCTION MEETING WITH THE PROJECT OFFICER, CONTRACTOR, AND COUNTY INSPECTOR.
- b. INSTALL THE TEMPORARY CONSTRUCTION ENTRANCE (IF NEEDED) IN THE LOCATION SHOWN ON THE E&S PHASE I PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL TRUCKS EXITING THE SITE.
- c. INSTALL PERIMETER TREE DEMARCATION FENCING IN THE FORM OF TREE PROTECTION FENCE (TP) AS SHOWN ON E&S PHASE I PLAN.
- d. PERFORM INITIAL PERIMETER CLEARING TO INSTALL REMAINDER OF PERIMETER CONTROLS SUCH AS DIVERSION DIKE (DD), SILT FENCE (SF), AND SUPER SILT FENCE (SSF) AS PER THE PHASE I PLAN.
- e. SEED AND MULCH ALL EARTHEN CONTROLS.
- f. CONTACT ARLINGTON COUNTY PROJECT OFFICER FOR A PERIMETER INSPECTION PRIOR TO CLEARING THE REMAINDER OF THE SITE IN ORDER TO OBTAIN PHASE II GRADING PERMIT.
- g. CLEAR THE SITE TO THE LIMITS AS SHOWN ON THE CONSTRUCTION PLANS.

2. PHASE II:

- a. BEGIN UTILITY CONSTRUCTION, INSTALL ALL UNDERGROUND UTILITIES AND BEGIN SITE GRADING.
- b. INLET PROTECTION (IP) SHALL BE PROVIDED AT STORM DRAIN INLETS AS SHOWN.
- c. ONCE THE SITE IS BROUGHT TO NEAR FINAL GRADE, AND THE UTILITY CONSTRUCTION IS COMPLETE, COMMENCE CONSTRUCTION OF CURB & GUTTER, STREET, SIDEWALKS, AND OTHER IMPROVEMENTS.
- d. THE CONTROL MEASURES MAY NOT BE REMOVED UNTIL ALL OF THE DISTURBED AREAS HAVE BEEN STABILIZED AND ONLY AS APPROVED AND DIRECTED BY THE INSPECTOR.

RUNOFF SHALL BE TREATED WITH SILT FENCE AND INLET PROTECTION PRIOR TO ENTERING MAJOR STORM SEWER SYSTEMS.

EROSION AND SEDIMENT CONTROL MEASURES

MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE ADHERED TO UNLESS OTHERWISE WAIVED OR APPROVED BY A VARIANCE.

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND

1. STRUCTURAL PRACTICES

- a. TEMPORARY CONSTRUCTION ENTRANCE VESCH 3.02
- a.a. A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE EXISTING ACCESS POINT TO THE SITE. DURING MUDDY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE RE-ENTERING THE LOCAL ROADWAYS.
- a.b. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC WASHING OF THE MATS AND/OR REPLACEMENT OF WOOD CHIPS AS NECESSARY
- a.c. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED IMMEDIATELY.
- a.d. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED INTO ROADWAYS WILL NOT BE PERMITTED UNDER ANY CIRCUMSTANCES.
- b. SILT FENCE VESCH 3.05

- b.a. SILT FENCE WILL BE INSTALLED WITH THE E&S PLAN TO FILTER RUNOFF FROM DISTURBED AREAS. RUNOFF SHALL NOT BE DIRECTED PARALLEL TO THE INSTALLATION OF SILT FENCE.
- b.b. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- b.c. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM UNDERCUTTING.
- b.d. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE, THE FABRIC SHALL BE REPLACED IMMEDIATELY.
- b.e. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY
- ONE-HALF THE HEIGHT OF THE BARRIER. b.f. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH
- THE EXISTING GRADE, THEN PREPARED AND SEEDED.
- c. TEMPORARY DIVERSION DIKE VESCH 3.09 c.a. A SYSTEM OF TEMPORARY DIKES, TO DIRECT FLOW INTO PROPOSED & EXISTING STORM SEWER STRUCTURES WILL BE INSTALLED AS
- c.b. THE STRUCTURES SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY. d. STORM DRAIN INLET PROTECTION - VESCH 3.07
- d.a. ALL EXISTING & PROPOSED STORM SEWER INLETS IN AND AROUND THE PROJECT LIMITS SHALL BE PROTECTED DURING CONSTRUCTION.
- SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS. d.b. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
- d.c. Structures shall be removed and the area stabilized when the remaining drainage area has been properly stabilized. e. DEWATERING STRUCTURE - VESCH 3.26
- e.a. SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED PRIOR TO DISCHARGE.
- e.b. THE FILTERING DEVICES MUST BE INSPECTED FREQUENTLY AND REPAIRED OR REPLACED ONCE THE SEDIMENT BUILD-UP PREVENTS THE STRUCTURE FROM FUNCTIONING AS DESIGNED.
- e.c. THE ACCUMULATED SEDIMENT WHICH IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER THE APPROVED PLAN.

f. TREE PROTECTION - VESCH 3.38

INDICATED IN EROSION & SEDIMENT CONTROL PLAN.

- f.a. ALL TREES ARE TO BE PROTECTED UNLESS OTHERWISE DIRECTED BY THE COUNTY INSPECTOR AND URBAN FORESTER. THE COUNTY'S URBAN FORESTER (703-228-1863) SHALL INSPECT ALL TREE PROTECTION 72 HOURS PRIOR TO THE START OF CONSTRUCTION. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, THE FOLLOWING MAINTENANCE GUIDELINES SHALL BE
- f.a.a. SOIL AERATION: IF THE SOIL HAS BECOME COMPACTED OVER THE ROOT ZONE OF ANY TREE, THE GROUND SHALL BE AERATED BY PUNCHING HOLES WITH AN IRON BAR. THE BAR SHALL BE DRIVEN 1-FOOT DEEP AND THEN MOVED BACK AND FORTH UNTIL THE SOIL IS LOOSENED. THIS PROCEDURE SHALL BE REPEATED EVERY 18 INCHES UNTIL ALL OF THE COMPACTED SOIL BENEATH THE CROWN OF THE TREE HAS BEEN LOOSENED.

f.a.b. REPAIR OF DAMAGE:

- ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM OF ANY TREE RETAINED ON THE SITE SHALL BE REPAIRED IMMEDIATELY.
- WHENEVER MAJOR ROOT OR BARK DAMAGE OCCURS, REMOVE SOME FOLIAGE TO REDUCE THE DEMAND FOR WATER AND **NUTRIENTS** DAMAGED ROOTS SHALL IMMEDIATELY BE CUT OFF CLEANLY INSIDE THE EXPOSED OR DAMAGED AREA. CUT SURFACES SHALL BE
- PAINTED WITH APPROVED TREE PAINT, AND MOIST PEAT MOSS, BURLAP, OR TOPSOIL SHALL BE SPREAD OVER THE EXPOSED AREA. TO TREAT BARK DAMAGE, CAREFULLY CUT AWAY ALL LOOSENED BARK BACK INTO THE UNDAMAGED AREA, TAPER THE CUT AT THE
- TOP AND BOTTOM, AND PROVIDE DRAINAGE AT THE BASE OF THE WOUND. ALL TREE LIMBS DAMAGED DURING CONSTRUCTION OR REMOVED FOR ANY OTHER REASON SHALL BE CUT OFF ABOVE THE COLLAR
- AT THE PRECEDING BRANCH JUNCTION.
- CARE FOR SERIOUS INJURIES SHALL BE PRESCRIBED BY A FORESTER OR A TREE SPECIALIST. f.b. FERTILIZATION: BROADLEAF TREES THAT HAVE BEEN STRESSED OR DAMAGED SHALL RECEIVE A HEAVY APPLICATION OF FERTILIZER TO AID
- THEIR RECOVERY. TREES SHALL BE FERTILIZED IN THE LATE FALL (AFTER OCTOBER 1) OR THE EARLY SPRING (FROM THE TIME FROST IS OUT OF THE GROUND UNTIL MAY 1). FALL APPLICATIONS ARE PREFERRED, AS THE NUTRIENTS WILL BE MADE AVAILABLE OVER A LONGER PERIOD
- f.b.b. FERTILIZER SHALL BE APPLIED TO THE SOIL OVER THE FEEDER ROOTS. IN NO CASE SHALL IT BE APPLIED CLOSER THAN 3 FEET TO THE TRUNK. THE ROOT SYSTEM OF CONIFERS EXTENDS SOME DISTANCE BEYOND THE DRIP LINE. INCREASE THE AREA TO BE FERTILIZED BY ONE FOURTH THE AREA OF THE CROWN.
- f.b.c. FERTILIZER SHALL BE APPLIED USING APPROVED FERTILIZATION METHODS AND EQUIPMENT.
- f.b.d. FORMULATIONS AND APPLICATION RATES SHALL CONFORM TO THE GUIDELINES GIVEN IN TABLE 3.38-A OF VESCH.

2. VEGETATIVE PRACTICES

- a. TOPSOILING (STOCKPILE) VESCH 3.30
- a.a. TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS MAY HAVE TO BE LOCATED OFF-SITE AND ARE TO BE STABILIZED WITH TEMPORARY VEGETATION. PRIOR TO LAND-DISTURBING ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY E&S PLAN (IF THE STOCKPILE IS LOCATED OFF-SITE). THIS SUPPLEMENTAL PLAN WOULD HAVE TO BE APPROVED BY THE PLAN APPROVING AUTHORITY BEFORE ANY OFF-SITE ACTIVITY COMMENCES.
- b. TEMPORARY SEEDING VESCH 3.31
- b.a. ALL DENUDED AREAS, WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED.
- b.b. SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE PLANTING REQUIREMENTS OF THE "SOUTH" SHALL BE FOLLOWED. LIMING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT SUMMER MONTHS SHALL BE MULCHED.
- c. EROSION CONTROL BLANKET AND MULCHING VESCH 3.36 AND 3.35

HOURS, AND SHALL BE INSTALLED PER PAGE III-339 OF VESCH.

- c.a. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND TO ALLOW SEED TO GERMINATE PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS AND WILL BE APPLIED AS A SECOND STEP IN SEEDING OPERATION.
- d. DUST CONTROL VESCH 3.39 d.a. DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS SUCH AS VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER
- SECTION 3.39 OF VESCH e. PERMANENT SEEDING - VESCH 3.32
- e.a. SINCE THE SUBJECT SITE IS LOCATED WITHIN THE COASTAL PLAIN AREA OF VIRGINIA, SHEET III-304 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE FOLLOWED FOR FINAL SEEDING MATERIAL, SEEDING RATES, AND DATES OF APPLICATION.
- f.a. SODDED AREAS SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLANS. SOIL TESTS SHALL BE MADE TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS AND LARGE OBJECTS. QUALITY OF SOD SHALL BE STATE CERTIFIED TO ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID ON FROZEN SOIL SURFACE, OR IN EXCESSIVELY WET OR DRY WEATHER. SOD SHALL BE DELIVERED AND INSTALLED WITHIN 36
- THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND SEDIMENT CONTROLS AS NEEDED IN THE FIELD. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MANAGEMENT MEASURES

PRIOR TO ANY LAND DISTURBING ACTIVITY, THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION.

LAND CONSERVATION NOTES:

LANDSCAPE / TREE PRESERVATION NOTES

f. SODDING - VESCH 3.33

- 1. NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT. 2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED
- ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS. 3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 100
- FEET ARE TO BE OPEN AT ANY ONE TIME.
- 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILLING.
- 5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES.
- 6. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION.
- 7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

EROSION & SEDIMENT CONTROL PROGRAM:

- 1. THE EROSION CONTROL PLAN IS INTENDED TO ESTABLISH ENTRANCES AND PERIMETER CONTROL MEASURES WHICH INCLUDES SILT FENCE (SF), INLET PROTECTION (IP), AND OTHER CONTROLS SPECIFIED ON THE PLANS.
- 2. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL SHALL BE PLACED IN STREAMBEDS. ANY STOCKPILED MATERIAL WHICH WILL REMAIN IN PLACE LONGER THAN 7 DAYS SHALL BE SEEDED AND MULCHED. WHEN SPOIL IS PLACED ON THE DOWNHILL SIDE OF TRENCH, IT SHALL BE BACKSLOPED TO DRAIN TOWARD THE TRENCH. WHEN NECESSARY TO DEWATER THE TRENCH, THE PUMP DISCHARGE HOSE SHALL OUTLET IN A STABILIZED AREA OR A SEDIMENT TRAPPING DEVICE.
- 3. ALL PRACTICES AND CONTROL DEVICES DESCRIBED HEREIN SHALL CONFORM TO THE CURRENT VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH). IN ADDITION, THE CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO MINIMIZE THE VOLUME OF SILT:
- a. CONTRACTOR SHALL EVALUATE THE SITE TO DETERMINE EXTENSIVE CUT AND FILL AREAS, AND SHALL WORK THOSE AREAS TO MINIMIZE THE USE OF HEAVY EQUIPMENT. CONTRACTOR SHALL BRING DISTURBED AREAS TO GRADE (ROUGH OR FINISHED) AND STABILIZE THOSE AREAS WITH TEMPORARY OR PERMANENT VEGETATION. THESE DISTURBED AREAS SHALL BE STABILIZED PRIOR TO BEGINNING WORK IN ANOTHER AREA.
- b. FILL AREAS SHALL BE COMPACTED COMPLETELY PRIOR TO THE END OF EACH WORK DAY. FILL SLOPE SURFACES SHALL BE KEPT ROUGH TO REDUCE SHEET EROSION OF THE SLOPES. CONTRACTOR SHALL RE-DIRECT CONCENTRATED RUNOFF, BY EARTH BERMS OR OTHER DEVICES, AROUND ACTIVELY DISTURBED AREAS TO STABILIZED OUTLETS.
- c. CUT SLOPES SHALL BE PROTECTED FROM CONCENTRATED FLOW BY BERMS (ABOVE THE SLOPE) AND DIRECTED AROUND THE DISTURBED AREA
- 4. MEASURES TO CONTROL EROSION AND SILTATION SHALL BE PROVIDED PURSUANT TO AND IN COMPLIANCE WITH CURRENT STATE AND LOCAL REGULATIONS. THE INFORMATION CONTAINED IN THE CONSTRUCTION PLANS AND/OR THE APPROVAL OF THE PLANS SHALL IN NO WAY RELIEVE THE CONTRACTOR OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA AND CHAPTER 57 OF THE
- 5. ALL AREAS, ON OR OFF-SITE, THAT ARE DISTURBED BY THIS CONSTRUCTION AND WHICH ARE NOT PAVED OR BUILT UPON SHALL BE ADEQUATELY STABILIZED TO CONTROL EROSION AND SEDIMENTATION. ACCEPTABLE STABILIZATION SHALL CONSIST OF PERMANENT GRASS SEED MIXTURE OR SOD THAT IS INSTALLED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. ALL SLOPES 3:1 AND GREATER SHALL BE RECEIVE SOIL STABILIZATION IN ACCORDANCE WITH THE SPECIFICATIONS.
- 6. WHERE STREAM CROSSINGS ARE REQUIRED FOR EQUIPMENT, TEMPORARY CULVERTS SHALL BE PROVIDED.
- 7. FOR FURTHER REQUIREMENTS AND DETAILS OF TREE PRESERVATION, PLANTING, EROSION AND SEDIMENT CONTROL, SEE COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK.

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.
- 2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES. 5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN THE AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO THE OWNER
- FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY. 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- 7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND
- DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED. 8. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
- 9. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- 10. ALL BIOFILTERS SHALL BE KEPT OFF-LINE UNTIL CONSTRUCTION IS COMPLETED AND ALL AREAS HAVE BEEN PROPERLY STABILIZED. THIS SHALL BE ACHIEVED BY USING INLET PROTECTION AT THE CURB CUTS AND STORMWATER CATCH BASINS LEADING DIRECTLY INTO THE BIOFILTERS.
- 11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.

PRE-STORM EROSION & SEDIMENTATION CHECKLIST:

PER GENERAL EROSION AND SEDIMENT CONTROL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN EROSION AND SEDIMENT CONTROL PLAN. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR

LARGE VOLUME RAINFALL.

- 1. PERIMETER CONTROLS a. SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETERIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY II THE FABRIC IS DAMAGED OR WON. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (VESCH STD & SPEC 3.09).
- b. WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED POSTS OR STAKES MUST BE REPLACED. c. SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHALL BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL REACHES ONE-HALF THE HEIGHT OF THE FENCING.
- d. HAY BALES OR A STONE BERM SHALL BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION SITE.

2. EXPOSED SLOPES AND SOIL

- a. EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARPS, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED.
- b. CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT/EXPOSED SLOPES TO DIRECT STORM FLOW AROUND THE DISTURBED AREA. c. EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL
- STABILIZATION BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH STD & SPEC 3.36). BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SLOPE USING STAPLES, PINS, OR STAKES. d. SEEDED AREAS SHALL BE CHECKED AND RESEEDED AS NECESSARY TO COVER EXPOSED SOIL. RECENTLY SEEDED AREAS SHALL BE PROTECTED BY

STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY.

4. INLET PROTECTION

- 3. STOCKPILES a. STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED/ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHALL BE PLACED ALONG THE PERIMETER OF THE STOCKPILE (DOWNHILL SIDE).
- a. INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW/BYPASS OF STORMWATER RUNOFF DURING SIGNIFICANT STORM EVENTS.

IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT RAINFALL.

POLLUTION PREVENTION PLAN NOTES (STORMWATER MANUAL - SECTION 2.4)

- 1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS: a. WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER
- INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIREFIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION. 2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G.,
- COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK. 3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE
- STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON




VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES

Water Sewer Streets Bureau

4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS 12/13/2022 DESIGNATION DESIGNATION DESIGNATION DESIGNATION DESIGNATION DE L'ALTRE DE L'A CONSTRUCTION MANAGEMENT SUPERVISOR

REVISIONS

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach 12/14/22

TRANSPORTATION DIRECTOR

Nicole Dean

PROJECT MANAGER

BIL

REH

EEP

DA

田公 S S N V 0 0

DESIGNED: R. PANNEERSELVAM DRAWN: J. SOSA

CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022


Fairfax, VA 22030


Tel: (703) 691-6500


SHEET 16 OF 46


10560 Arrowhead Drive. Suite 500

SPOUT RUN DEEP SEWER REHABILITATION













REVISIONS



AND **EROSION**

DESIGNED: R. PANNEERSELVAM DRAWN: J. SOSA CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022

CDM Smit Fairfax, VA 22030 Tel: (703) 691-6500

SHEET 17 OF 46








PLATE: 3.36-1

SOURCE: ADAPTED FROM LUDLOW PRODUCTS BROCHURE










- 1. NO MORE THAN 100 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
- 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
- 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
- 5. STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
- 6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH.
- 9. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.
- 10. AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

MAINTENANCE PROGRAM:

- THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:
- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO ENSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.
- 2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
- 3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWNSTREAM WATER WAYS. SHOULD OFF-SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE AFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.
- 4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY REMAINING DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH THE APPROVAL OF THE COUNTY INSPECTOR.
- 5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.

COUNTY SOILS MAP DATA



Potential Sources of Pollution & Pollution Prevention Practices

Identify the pollutant-generating activities likely to be present at the project site; implement and maintain the corresponding pollution prevention practices. If an unlisted pollutant-generating activity is likely to be present at the project site, describe it, identify the associated

pollutant(s), and provide the corresponding pollution prevention practice(s) to be implemented and maintained.

		A.D	i	Polluta								
Pollutant-Generating Activity	Likely Present at your Project Site?	Sediment	Nutrients	Heavy Metals	pH (acids and bases)	Pesticides & Herbicides	Oil & Grease	Bacteria & Viruses	Trash, Debris, Solids	Other Toxic Chemicals	Pollution Prevention Practice	Responsible Party
Clearing, grading, excavating, and un-stabilized areas	☐ Yes ⊠ No	х							×		(1)	
Paving operations	⊠ Yes □ No	X					х		х		(2)	
Concrete washout and cement waste	☐ Yes ⊠ No			х	х				X		(3)	
Structure construction, stucco, painting, and cleaning	☐ Yes ⊠ No			Х	×				х	Х	(4)	
Dewatering operations	⊠ Yes □ No	х	х						х		(5)	
Material delivery and storage	⊠ Yes □ No	Х	х	х	×		Х		x	х	(6)	Construction Activity Operator
Material use during building process	☐ Yes ⊠ No		Х	Х	Х		Х		×	х	(7)	>
Solid waste disposal	⊠ Yes □ No								х	х	(8)	
Sanitary waste	⊠ Yes □ No		Х		Х			Х			(9)	
Landscaping operations	⊠ Yes □ No	Х	Х			х			×	х	(10)	
Equipment and vehicle maintenance	⊠ Yes □ No				Х		Х		Х	Х	(11)	

Authorized Non-Stormwater Discharges

Identify the authorized non-stormwater discharges likely to be present at the project site. If an unlisted authorized non-stormwater discharge is likely to be present at the project site, provide it here.

Type of Authorized Non-Stormwater Discharge	Likely Prese	nt at Your Project Site?
External buildings wash down	Yes	⊠ No
Uncontaminated foundation or footing drains Uncontaminated excavation dewatering	☐ Yes ⊠ Yes	⊠ No □ No
Landscape irrigation	☐ Yes	⊠ No

Spill Prevention & Response

Most spills can be cleaned up following manufacturer specifications. The priority should be to protect all people, equipment, property, and the environment. Enter the telephone number of your local fire and police departments.

Most spills can be cleaned up using a spill kit. Absorbent/oil dry, sealable containers, plastic bags, and shovels/brooms are suggested minimum spill response items that should be available at the project site.

1st Priority: Protect all people

Protect equipment and property 2nd Priority:

3rd Priority: Protect the environment

- 1. Check for hazards (flammable material, noxious fumes, cause of spill) if flammable liquid, turn off engines and nearby electrical equipment. If serious hazards are present leave the area and call 911. LARGE SPILLS ARE LIKELY TO PRESENT A HAZARD.
- 2. Ensure the spill area is safe to enter and that it does not pose an immediate threat to health or safety of any
- 3. Stop the spill source.
- 4. Call co-workers and supervisor for assistance and to make them aware of the spill and potential dangers.
- 5. If possible, stop spill from spreading and/or entering storm drains (use absorbent or other materials as
- 6. If spilled material has entered a storm drain; contact Arlington County Fire Department and project manager.
- 7. Clean up spilled material according to manufacturer specifications, for liquid spills use absorbent materials and do not flush area with water.
- 8. Properly dispose of cleanup materials and used absorbent material according to manufacturer specifications.

Emergency Contacts:

Local Contacts

Arlington County Fire & Police 703-558-2222 DES Water, Sewer, Streets 24-Hour Emergency 703-228-6555 Washington Gas Emergency 703-750-1400

Nights, Holidays & Weekends

VA Dept. of Emergency Management 804-674-2400

24 Hour Reporting Service


Spill kit on site: Yes No	
Location(s) of spill kit:	



DEPARTMENT OF **ENVIRONMENTAL SERVICES**

Water Sewer Streets Bureau 4200 28th St S, TWA 1st Fl Arlington, VA 22202 Phone: 703.228.7865 Fax: 703.228.6585

COPYRIGHT © 2022 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS	DATE
W878	12/13/2022
DESIGNAÇÃO GINEER TEAM SUI	PERVISOR 12/15/202
CONSTRUCTION MANAGEMEN	
pxln	12/14/22
WATER, SEWER, STREETS BU	
Dennis M. Leach	12/14/22
TRANSPORTATION DIRECTOR	3
Nicole Dean	12/15/2022

R	REVISIONS	DATE
-		
-		
-		

PROJECT MANAGER

'ATION

REHABILIT

SEWER

DEEP

O SEDIMENT O DETAILS AND **EROSION**

DESIGNED: R. PANNEERSELVAM DRAWN: J. SOSA CHECKED: D. GILROY

PLOTTED: DECEMBER 7 2022



Fairfax, VA 22030 Tel: (703) 691-6500

SHEET 18 OF 46