

**ARLINGTON COUNTY, VIRGINIA**  
**OFFICE OF THE PURCHASING AGENT**

**INVITATION TO BID NO. 23-DES-ITBPW-425**

**ADDENDUM NO. 2**

Arlington County Invitation to Bid No. 23-DES-ITBPW-425 for S Arlington Ridge Road Intersection Improvements is amended as follows:

**ELECTRONIC SEALED BIDS WILL BE RECEIVED BY ARLINGTON COUNTY VIA VENDOR REGISTRY UNTIL 2:00 P.M. ON THE 12TH DAY OF JANUARY 2023**

**QUESTIONS REGARDING THE ORIGINAL SOLICITATION MUST BE SUBMITTED BY FRIDAY, DECEMBER 30, AT 5:00 PM EASTERN TIME TO BE CONSIDERED FOR AN ADDENDUM. ALL QUESTIONS RECEIVED BY THE QUESTION DEADLINE WILL BE RESPONDED TO WITHIN VENDOR REGISTRY AND POSTED FOR ALL BIDDERS. THE SYSTEM WILL NOT ACCEPT ANY QUESTIONS AFTER THIS DATE AND TIME.**

Arlington County Invitation to Bid No. 23-DES-ITBPW-425 for S Arlington Ridge Road Intersection Improvements received the following questions:

1. Will the County provide VDOT's estimated cost for the Land Use Permit?
  - a. County will provide the VDOT-LUP for this project.
2. Will the County provide a staging area?
  - a. NO. The county is not providing a staging area for this project. The contractor can request NO PARKING signs for an area closer to the Lynn intersection to serve as a staging area.
3. May we have a geotechnical report?
  - a. None was done.
4. Will the owner reimburse for existing utilities damaged if not shown on the plans?
  - a. No. Per Arlington County specification Section 01000-Part 1 - 1.10-D-E
5. Due to current supply chain issues, will the owner consider issuing a second NTP for delays due to material availability?
  - a. NO – We have several projects that have started during the pandemic and if there are delay issues with specific materials the contractor can discuss with Construction Manager in advance (example – signal poles). This project is mostly concrete and a rapid flash beacon so there should be no major delays in deliveries.
6. Can you provide a website or documentation showing all actual existing utilities?
  - a. Existing utilities can be found in the Existing conditions plan Sheet C011.1. However, per Arlington County Specifications Section 02100 Part 1-1.5-C; “the completeness or accuracy of the information is not guaranteed. Contractor shall notify “Miss Utility” in accordance with the provisions stipulated in the Underground Utility Protection Ordinance (chapter 55) of the Arlington County code.”
7. Detail CR-1 on sheet C043.3 indicates Brick on the sidewalk, Please confirm all the sidewalks will be concrete per Arlington Standard detail R-2.0.
  - a. Correct. All sidewalks are concrete per Arlington Std detail R-2.0
8. The drawings indicate “Utility Pole relocated by others”, Is this pole going to be relocated before the beginning of this project? Or shall be coordinated by the contractor?
  - a. Utility pole has been relocated.

9. If the pole at the corner of 15th St and S Lynn St is not relocated before the commencement of this project, will the County consider a time extension due to possible delays caused by this relocation?
  - a. Utility pole has been relocated
10. Per drawing C121.0 Note 18, will the county consider performing Phase IV of the TCP prior to other phases?
  - a. Per General TMP note 15 Sheet C121.0, "This TMP/MOT/SOC Plan is intended as a guide. It is not to enumerate every detail which must be considered in the construction of each phase, but only to show the general handling of existing traffic. If the contractor is to deviate from the approved TMP, a new or revised TMP must be submitted to the Engineer for review and approval.

The balance of the solicitation remains unchanged.

Arlington County, Virginia

Lucas Alexander, VCO, VCA  
Procurement Officer

**RETURN THIS PAGE, FULLY COMPLETED AND SIGNED, WITH YOUR BID:**

**BIDDER ACKNOWLEDGES RECEIPT OF ADDENDUM NUMBER 2.**

**FIRM NAME:** \_\_\_\_\_

**AUTHORIZED SIGNATURE:** \_\_\_\_\_ **DATE:** \_\_\_\_\_