



**Peralta Community College District
Laney Library & Learning Resource Center
(Building 100 Replacement)**

900 Fallon Street, Oakland, CA 94607

ISSUE DATE	03/19/23
NAT. JOB NUMBER	21942
REVISIONS	
DATE	DESCRIPTION
3/05/16/2024	Addendum No. 03



03 - SLAB PLAN
1/8" = 1'-0"

SLAB PLAN LEGEND

- | | | | |
|--|---|--|--|
| | STRUCTURAL CONCRETE SLAB 0'-0", SSD SMOOTH FLOAT FINISH UNDER FINISHED FLOOR SYSTEM | | CONCRETE CURB, MATCH STUD WIDTH AND LOCATION UON |
| | DEPRESSED STRUCTURAL CONC SLAB FOR CONCRETE TOPPING SLAB, S.S.D. | | CONCRETE WALL |
| | DEPRESSED STRUCTURAL CONC SLAB FOR CERAMIC FLOOR TILE AND MORTAR BED, S.S.D. | | IN-SLAB FLOOR BOX/POKE-THRU DEVICE - FOR SLAB ON DECK SEE 10/E7.02, 12/T9.01 - FOR SLAB ON GRADE SEE 16 / AB.42, 17 / AB.42 AND 11/E7.01 |
| | DEPRESSED & SLOPED STRUCTURAL CONC SLAB, SLOPES / HTS AS NOTED | | |
| | DEPRESSION IN STRUCTURAL CONC SLAB FOR ENTRANCE GRILL | | |

GENERAL NOTES

- TOP OF FIRST FLOOR STRUCTURAL SLAB DATUM ELEVATION 0'-0" = 16.25, SSD
- SSD FOR ADDITIONAL INFORMATION
- SEE LAYOUT PLANS AND WINDOW ELEVATIONS FOR ADDITIONAL DIMENSION INFORMATION
- SEE FINISH PLANS AND SCHEDULE FOR ADDITIONAL INFORMATION
- SEE LAYOUT PLANS AND FLOOR PLANS FOR ROOM NAMES
- SPD FOR ALL FLOOR DRAIN LOCATIONS
- SLOPE FLOORS TO DRAIN WHERE INDICATED, SPD FOR ADDITIONAL INFORMATION
- WHERE FLOOR TILE OCCURS PROVIDE AND INSTALL BUILT-UP MORTAR BED OR LEVELING COMPOUND TO ACHIEVE FINISH FLOOR REQUIREMENTS
- WHERE DEPRESSED FLOOR MAT OCCURS PROVIDE AND INSTALL BUILT-UP MORTAR BED OR LEVELING COMPOUND TO ACHIEVE FINISH FLOOR REQUIREMENTS
- FOR STRUCTURAL SLAB CONTROL JOINTS SSD
- FOR TOPPING SLAB CONTROL JOINTS SEE FINISH PLANS