



**03 - SHELVING PLAN**  
1/8" = 1'-0"

STACK SCHEDULE - L3									
Type Mark	Count	Type Comments	Width	Height	Total Shelf Count	Adjustable Shelf Depth	Industrial Shelf Depth	Canopy Top	End Panel
A2	4	STACKS - ONE SIDE	3'-0"	7'-0"	7	10"		PLAM, PL-2	PLAM, PL-2
A2.1	4	STACKS - ONE SIDE	3'-0"	7'-0"	7	10"		NONE	NONE
A3	9	STACKS - TWO SIDES	3'-0"	7'-0"	7	12"		PLAM, PL-2	PLAM, PL-2
A4	18	STACKS - ONE SIDE	3'-0"	7'-0"	7	12"		PLAM, PL-2	PLAM, PL-2
A4.1	3	STACKS - ONE SIDE	3'-0"	7'-0"	7	12"		NONE	NONE
A5	133	STACKS - TWO SIDES	3'-0"	7'-0"	7	10"		NONE	RESIN
A6	7	STACKS - TWO SIDES	3'-0"	7'-0"	7	10" AND 12"		NONE	RESIN
A7.1	4	STACKS - ONE SIDE	3'-0"	3'-9"	3	10"		RESIN, SS-3	RESIN, SS-3
B1	6	MOBILE STACKS - TWO SIDES	3'-0"	3'-9"	3	10"		RESIN, SS-3	RESIN, SS-3
B2	4	MOBILE STACKS - TWO SIDES	3'-0"	4'-11"	5	10"		RESIN, SS-3	RESIN, SS-3
B4	4	MOBILE STACKS - TWO SIDES	3'-0"	4'-11"	5	10"		RESIN, SS-3	RESIN, SS-3
C1	2	INDUSTRIAL SHELVING	4'-0"	7'-0"			18"		
C2	3	INDUSTRIAL SHELVING	3'-6"	7'-0"			18"		

- GENERAL NOTES**
- FOR TYPICAL STACK DETAILS SEE: A8.76
  - LIBRARY SHELVING (TYPES A AND B) PER SPECIFICATION SECTION 11 51 23 UNLESS OTHERWISE NOTED.
  - INDUSTRIAL SHELVING (TYPE C) PER SPECIFICATION SECTION 10 56 13 UNLESS OTHERWISE NOTED.
  - SEE STRUCTURAL DRAWINGS FOR BACKING DETAILS
  - MOBILE SHELVING UNITS SHALL HAVE END PANELS AND CANOPES PER GROUP OF 4 SHELVING UNITS

PROJECT TITLE  
**Perla Community College District Laney Library & Learning Resource Center (Building 100 Replacement)**  
900 Fallon Street, Oakland, CA 94607

ISSUE FOR BID  
ISSUE DATE: 03/19/23  
NAT. JOB NUMBER: 21942  
REVISIONS:  
DATE: 05/16/2024  
DESCRIPTION: Addendum No. 03

SHEET TITLE  
**SHELVING PLAN - 3RD FLOOR**

SHEET NUMBER  
**A9.33**