



Front Street UG System Upgrade Project #1919 Construction – ADDENDUM II Pre-bid Meeting Clarifications and Alternates.

Notice to bidders: the specifications have been revised per the following:

The manhole walls are estimated to be 12 inches thick. The interior wall dimensions have been added to drawing E012 Cable Racking Details Manhole T1A. All manhole wall dimensions are the same as shown on drawing E012.

The pullbox walls are 8 inches thick. The pullbox dimensions have been added to drawing E021 Cable Racking Details Pullbox PB1. All pullbox wall dimensions are the same as shown on drawing E021.

In the Request for Bid, Section 1.7 SUBMITTAL INSTRUCTIONS, Item 16, delete the fifth bullet item “Professional Liability.” Professional Liability insurance is not required for this project.

In the Request for Bid, Section 2 BID FORM, add the following alternate pricing under the lump sum price at the bottom of Page 2-1.

“Adjustment (plus or minus) for installing direct bore conduits from Transformers T1B to Manhole MHT1B instead of duct bank.

\$ _____

Adjustment (plus or minus) for installing direct bore conduits from Transformers T3 to Manhole MHT3 instead of duck bank.

\$ _____”

The following drawings have been revised:

E012	CABLE RACKING DETAILS MANHOLE T1A
E021	CABLE RACKING DETAILS PULLBOX 1