


PRELIMINARY PLANS FOR:

CITY OF GEORGETOWN WATER MAIN UPGRADES

GEORGETOWN, SOUTH CAROLINA PROJECT FUNDED BY A CDBG GRANT #4-CI-21-008 PROJECT #1515







SHEET INDEX

1 - COVER SHEET 2 - LEGEND SHEET 3 - NOTE SHEET 4 - DETAIL SHEET

- WATER MAIN PLAN SHEET-DAVIS ALLEY STA 600+50 TO 604+75

<u>OWNER</u>

CITY OF GEORGETOWN 2377 MAYBANK DRIVE GEORGETOWN, SC 29440

CONTACT: ORLANDO P. ARTEAGA, P.E., CITY ENGINEER

PHONE: (843) 545-4501

TECHNICAL CONSULTANT

ROWE PROFESSIONAL SERVICES COMPANY

6009 N. KINGS HIGHWAY MYRTLE BEACH, SC 29577 CONTACT: RYAN HARVEY, P.E. PHONE: (843) 444-1020

<u>AGENCIES</u>

WATER & SEWER CITY OF GEORGETOWN CITY OF GEORGETOWN ELECTRIC HTC / SPECTRUM TELEPHONE

CABLE T.V. GAS SCDOT ROADWAY

SHEET NO.

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA CALL 1-888-721-7877

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006

OWN IN UPGRADES

SCALE: NTS
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022




LOCATION MAP


NOT TO SCALE

Bourne Street — Henry Street John Street

STRUCTURE SYMBOLS UTILITY SYMBOLS EXISTING CATCH BASIN IN CURB LINE UTILITY POLE PROPOSED CATCH BASIN IN CURB LINE GUY ANCHOR CABLE EXISTING CATCH BASIN IN GREEN SPACE LIGHT POLE / ORNAMENTAL LIGHT PROPOSED CATCH BASIN IN GREEN SPACE POWER LIGHT POLE EXISTING STORM MANHOLE TELEPHONE MANHOLE PROPOSED STORM MANHOLE UNDERGROUND GAS LINE MARKER PROPOSED CULVERT END SECTION GAS RISER EXISTING HEADWALL GAS VENT GAS VALVE PROPOSED HEADWALL EXISTING GATE VALVE AND BOX RAILROAD SIGNAL EXISTING WATER SHUT OFF (CURB BOX) METAL LIGHT POLE OUTLET PROPOSED GATE VALVE AND BOX CIRCUIT BREAKER PANEL EXISTING GATE VALVE AND WELL PROPOSED GATE VALVE AND WELL ELECTRICAL TRANSFORMER PAD ELECTRICAL TRANSFORMER RISER EXISTING SPRINKLER HEAD ELECTRIC METER EXISTING WATER WELL 0 TELEPHONE PEDESTAL / RISER EXISTING FIRE HYDRANT PROPOSED FIRE HYDRANT TRAFFIC SIGNAL ON POLE PHONE BOOTH / PAY PHONE PROPOSED WATER MAIN FITTINGS EXISTING CLEAN OUT **SURVEY SYMBOLS** EXISTING SANITARY SEWER MANHOLE MONUMENT PROPOSED SANITARY SEWER MANHOLE BENCHMARK EXISTING MONITORING WELL TRAVERSE POINT SECTION CORNER EXISTING TOPOGRAPHICAL SYMBOLS FOUND SURVEY MONUMENTATION SIGN STREET SIGN MISCELLANEOUS SYMBOLS END OF PIPE EXISTING STORM SEWER STRUCTURE NUMBER SWAMP OR WETLAND علا علا EX 5236 EXISTING SANITARY SEWER STRUCTURE NUMBER DECIDUOUS TREE PROPOSED STORM SEWER STRUCTURE NUMBER CONIFEROUS TREE A PROPOSED SANITARY SEWER STRUCTURE NUMBER TREE STUMP FLOW DIRECTION **~**~ MAIL BOX EXISTING RIP-RAP SOIL BORING PROPOSED RIP-RAP ROCK 0 METAL POST **CAUTION SYMBOLS** ••CAUTION•• HAZARDOUS FLAMMABLE MATERIAL UNDERGROUND BUMPER BLOCK USED WITH UNDERGROUND GAS & ELECTRICAL LINES ••CAUTION•• FIBER OPTIC USED WITH FIBER OPTICS LINES

12" STM	EXISTING STORM SEWER
===12" CONC	EXISTING CULVERT
	PROPOSED STORM SEWER LESS THAN 24"
	PROPOSED STORM SEWER 24" AND GREATER
12" SAN	EVICTIVE CANITARY OF UER
	PROPOSED SANITARY SEWER
	— EXISTING WATER MAIN
	PROPOSED WATER MAIN
	- SECTION LINE
60' ROW	— EXISTING RIGHT OF WAY
60' ROW	- PROPOSED RIGHT OF WAY
	PROPOSED EASEMENT
	— EXISTING CENTER LINE DITCH
	PROPOSED DITCH CENTERLINE
	— EXISTING CENTER LINE ROADWAY
	— PARCEL LINE / LOT LINE
0/H	— EXISTING OVERHEAD UTILITIES
U/G ELEC	— UNDERGROUND ELECTRICAL LINE
	— GAS LINE OR PETROLEUM PIPELIN
U/G TEL	— UNDERGROUND TELEPHONE LINE
U/G CATV	— UNDERGROUND CABLE TV LINE
U/G FIBER OPTIC ————	— UNDERGROUND FIBER OPTIC
11+00	PROJECT CONTROL LINE
	TDEE LINE
	√· BRUSH LINE
xxxxxxx	— EXISTING FENCE
xxx	— PROPOSED FENCE
	→· EXISTING GUARD RAIL
	···· PROPOSED SLOPE STAKE LINE
	— PROPOSED SILT FENCE
	TOPOGRAPHY
	EXISTING CONTOURS MAJOR
960	
958	EXISTING CONTOURS MINOR
960	PROPOSED CONTOUR MAJOR
958	PROPOSED CONTOURS MINOR
PARC	CEL INFORMATION
401-069	PARCEL/TAX IDENTIFICATION NUM





SOUTH CAROLINA

CALL 1-888-721-7877

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006

O: (843) 444-1020 F: (843) 448-3936

ROWE PROFESSIONAL SERVICES COMPANY

GENERAL

- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THESE PLANS. SCDOT STANDARD SPECIFICATIONS ed. 2007, AND DHEC STANDARD
- SPECIFICATIONS AND GENERAL DESIGN STANDARDS. WHEREVER A CONFLICT IN STANDARDS AND SPECIFICATIONS OCCUR THE MOST RESTRICTIVE STANDARD OR SPECIFICATION WILL GOVERN.
- THREE WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO CONTACT PALMETTO UTILITY PROTECTION SERVICE (1-888-721-7877) TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING OR VERIFYING THAT ALL PERMITS AND APPROVALS ARE OBTAINED FROM THE PERSPECTIVE CITY, COUNTY AND STATE AGENCIES PRIOR TO STARTING CONSTRUCTION.
- 5. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONSTRUCT THIS PROJECT ACCORDING TO THE DETAILS PROVIDED IN THE PLAN SET. THE CONTRACTOR IS RESPONSIBLE FOR KEEPING EXISTING UTILITIES IN FULL SERVICE FOR THE DURATION OF THE WORK. IN THE EVENT THAT SOME SERVICES WOULD BE TEMPORARILY SUSPENDED TO CONDUCT WORK, ARRANGEMENTS MUST BE MADE TO COMPLETE THE WORK AFTER HOURS OR ON WEEKENDS AT NO ADDITIONAL COST TO THE OWNER
- ALL INFORMATION REGARDING HOW THE PROJECT IS TO BE CONSTRUCTED MUST BE FOLLOWED, FAILURE TO DO SO WILL RESULT IN WORK THAT MAY BE REMOVED AND REPLACED AT THE CONTRACTOR'S EXPENSE.
- ANY MATERIALS USED SHALL BE NEW AND OF THE QUALITY CALLED OUT IN THE PLANS AND SPECIFICATIONS AND PLACED ACCORDING TO
- THE DETAILS AND AGENCY REQUIREMENTS. REGULATORY AGENCIES' REQUIREMENTS AND SPECIFICATIONS SHALL BE FOLLOWED ON THIS PROJECT. ANY DISCREPANCIES BETWEEN THEIR
- STANDARDS AND THESE PLANS SHALL BE BROUGHT TO THE ENGINEER'S ATTENTION IMMEDIATELY. 10. THIS PROJECT IS NOT LOCATED WITHIN A REGULATED FLOODPLAIN PER MARCH 16, 1989 PANEL NOS. 450085 0243 D AND 450087 0001 D, NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP. THE PROJECT IS LOCATED WITHIN ZONE X.
- 11. A PRE-CONSTRUCTION CONFERENCE AT THE SITE IS MANDATORY. THE DEVELOPER, ENGINEER OF RECORD, CONTRACTOR AND ALL SUBCONTRACTORS WITH SWPPP RESPONSIBILITIES ARE REQUIRED TO ATTEND. AN ATTENDANCE SHEET MUST BE SIGNED AND RETAINED WITHIN
- 12. NO WORK IS TO BE PERFORMED ON THE PROJECT UNTIL PLANS HAVE BEEN APPROVED BY THE STATE.
- 13. ANY WORK PERFORMED WITHOUT PROPER INSPECTIONS MAY BE REQUIRED TO BE REMOVED AND REINSTALLED. 14. CONTRACTOR TO PROVIDE A MAILBOX THAT WILL CONTAIN THE OS-SWPPP AT THE CONSTRUCTION SITE THAT WILL BE ACCESSIBLE DURING NORMAL BUSINESS HOURS FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 15. CONTRACTOR TO INSTALL A TEMPORARY RAIN GAGE ONSITE AND ENTER RAINFALL AMOUNTS IN THE OS-SWPPP DAILY.

CONSTRUCTION SEQUENCE

- OBTAIN PERMITS FROM THE STATE
- PRE-CONSTRUCTION MEETING ON-SITE
- MOBILIZATION ON-SITE
- INSTALL SILT FENCING AND TREE PROTECTION, CLEAR ONLY AS NECESSARY TO INSTALL THESE DEVICES
- CALL FOR ON-SITE INSPECTION BY OCRM INSPECTOR. WHEN

SILT FENCE INSTALLATION

- APPROVED, BEGIN CLEARING AND GRUBBING. DEMOLITION OF EXISTING FACILITIES (AS REQUIRED)
- FOUNDATION PREPARATION / CONSTRUCTION
- INSTALL DRAINAGE FACILITIES FINE GRADING
- SITE CLEANUP
- ESTABLISH TURF / LANDSCAPE EROSION CONTROL DEVICE REMOVAL
- DEMOBILIZATION

SITE WORK

- PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL LOCATE AND EXPOSE ALL EXISTING UTILITIES THAT CROSS THE PROPOSED CONSTRUCTION SO THAT THE ENGINEER MAY DETERMINE IF A VERTICAL CONFLICT EXISTS BETWEEN THE EXISTING UTILITY AND THE PROPOSED CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING THE EXISTING UTILITIES WITHIN THE SCOPE OF CONSTRUCTION, IF ANY DAMAGE OCCURS THE CONTRACTOR WILL REMOVE AND REPLACE THEM AT THEIR OWN EXPENSE.
- THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN ADEQUATE SITE DRAINAGE DURING ALL PHASES OF CONSTRUCTION. THE CONTRACTOR SHALL INSTALL SILT FENCES (OR OTHER METHODS APPROVED BY THE ENGINEER AND OCRM) AS REQUIRED TO PREVENT SILT AND CONSTRUCTION DEBRIS FROM FLOWING OFF THE SITE. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE FEDERAL, STATE, OR LOCAL EROSION, CONSERVATION AND SILTATION ORDINANCES. THE CONTRACTOR SHALL REMOVE ALL TEMPORARY EROSION CONTROL DEVICES UPON COMPLETION OF PERMANENT DRAINAGE FACILITIES AND THE ESTABLISHMENT OF VEGETATION TO PREVENT EROSION.
- BEFORE EARTH MOVING ACTIVITIES START THE CONTRACTOR SHALL VISIBLY STAKE OUT THE CLEARING LIMITS. 4. THE CONTRACTOR IS RESPONSIBLE FOR MEETING THE REQUIREMENTS OF THE ARCHITECTURAL PLANS AS
- PREPARED BY GOFORTH. BROWN AND ASSOCIATES. 5. THE EXCAVATION CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANIES FOR ANY REQUIRED UTILITY ADJUSTMENTS AND/OR RELOCATIONS.
- 6. REFER TO SHEET K1.05-K1.10 FOR EROSION CONTROL DEVICES TO BE INSTALLED PRIOR TO COMMENCING CONSTRUCTION.
- 7. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY DISPOSING OF EXCESS MATERIAL AT A LOCATION PROVIDED BY THE CONTRACTOR AT THEIR EXPENSE.
- THE CONTRACTOR SHALL BRACE, SHEET, AND SUPPORT TRENCH WALLS IN SUCH A MANNER THAT THEY WILL BE SAFE AND THAT THE GROUND ALONGSIDE THE EXCAVATION WILL NOT SLIDE OR SETTLE, AND THAT ALL EXISTING IMPROVEMENTS OF EVERY KIND, WHETHER ON PUBLIC OR PRIVATE PROPERTY, WILL BE FULLY PROTECTED FROM
- 9. ALL GRADING SHALL BE PERFORMED IN ACCORDANCE WITH GEOTECHNICAL REPORT PREPARED BY GS2 ENGINEERING DATED 01-03-18.
- 10. CONTRACTOR SHALL COORDINATE SHUTDOWNS OF UTILITIES TO EXISTING BUILDINGS AND LIMITATIONS IN SITE ACCESS WITH M.B. KAHN.

HEAVY DUTY PLASTIC TIES 1.25 LB./LINEAR FT. STEEL POSTS PLAN SYMBOL COMPACTED FILTER FABRIC EARTH —SF —SF — RUNOFF 24-IN. (MINIMUM) BACKFILL TRENCH WITH HEAVY DUTY PLASTIC TII COMPACTED EARTH ____ FOR STEEL POSTS (RESTRICT TO TOP 8-INCHES OF FABRIC) V-SHAPED TRENCH DETAIL HEAVY DUTY PLASTIC TIES USE EITHER FLAT-BOTTOM OR V-BOTTOM TRENCH SEE DETAILS -COMPACTED 8-IN. TO 24-IN. RUNOFF SILT FENCE — GENERAL NOTES 1. Do not place silt fence across channels or in other areas subject to concentrated flows. Silt fence should not be used as a velocity control BMP. Concentrated flows are any flows greater than 0.5 cfs. Maximum sheet or overland flow path length to the silt fence shall be 100-feet. . Maximum slope steepness (normal [perpendicular] to the fence line) shall be 2:1. 4. Silt fence joints, when necessary, shall be completed by one of the following options: - Wrap each fabric together at a support post with both ends fastened to the post, with a 1-foot _BURY FILTER FABRIC - Overlap silt fence by installing 3-feet passed the support post to which the new silt fence roll is AT LEAST 12-INCHES attached. Attach old roll to new roll with heavy-duty plastic ties; or, Overlap entire width of each silt fence roll from one support post to the next support post South Carolina Department of Attach filter fabric to the steel posts using heavy-duty plastic ties that are evenly spaced within the top Health and Environmental Contro

SILT FENCE - POST REQUIREMENTS

1. Silt Fence posts must be 48-inch long steel posts that meet, at a minimum, the following physical characteristics. — Composed of a high strength steel with a minimum yield strength of - Include a standard "T" section with a nominal face width of 1.38-inches and a nominal "T" length of 1.48—inches. - Weigh 1.25 pounds per foot (± 8%)

Install the silt fence perpendicular to the direction of the stormwater flow and place the silt fence the proper

distance from the toe of steep slopes to provide sediment storage and access for maintenance and cleanout.

Install Silt Fence Checks (Tie-Backs) every 50-100 feet, dependent on slope, along silt fence that is installed

with slope and where concentrated flows are expected or are documented along the proposed/installed silt

- 2. Posts shall be equipped with projections to aid in fastening of filter fabric. 3. Steel posts may need to have a metal soil stabilization plate welded near the bottom when installed along steep slopes or installed in loose soils. The plate should have a minimum cross section of 17-saugre inches and be composed of 15 gauge steel, at a minimum. The metal soil stabilization plate should be
- 4. Install posts to a minimum of 24-inches. A minimum height of 1- to 2inches above the fabric shall be maintained, and a maximum height of 3 feet shall be maintained above the ground.
- 5. Post spacing shall be at a maximum of 6-feet on center.

SILT FENCE - FABRIC REQUIREMENTS

the following requirements: — Composed of fibers consisting of long chain synthetic polymers of at least 85% by weight of polyolefins, polyesters, or polyamides that are formed into a network such that the filaments or yarns retain dimensional stability relative to each other: - Free of any treatment or coating which might adversely alter its physical properties after installation: - Free of any defects or flaws that significantly affect its physical and/or filtering properties: and. - Have a minimum width of 36-inches

Silt fence must be composed of woven geotextile filter fabric that consists of

- 2. Use only fabric appearing on SC DOT's Qualified Products Listing (QPL), Approval Sheet #34, meeting the requirements of the most current edition of the SC DOT Standard Specifications for Highway Construction.
- 3. 12-inches of the fabric should be placed within excavated trench and toed in when the trench is backfilled.
- 4. Filter Fabric shall be purchased in continuous rolls and cut to the length of
- the barrier to avoid joints. 5. Filter Fabric shall be installed at a minimum of 24-inches above the ground.

- SILT FENCE INSPECTION & MAINTENANCE . The key to functional silt fence is weekly inspections, routine maintenance, and regular sediment removal
- 2. Regular inspections of silt fence shall be conducted once every calendar week and, as recommended, within 24-hours after each rainfall even that produces 1/2-inch or more of precipitation.

CANDARD DRAWING NO. S(-)

FLAT-BOTTOM TRENCH DETAIL

- Attention to sediment accumulations along the silt fence is extremely important. Accumulated sediment should be continually monitored and removed when
- 4. Remove accumulated sediment when it reaches 1/3 the height of the silt
- 5. Removed sediment shall be placed in stockpile storage areas or spread think across disturbed area. Stabilize the removed sediment after it is relocated.
- 6. Check for areas where stormwater runoff has eroded a channel beneath the silt fence, or where the fence has sagged or collapsed due to runoff overtopping the silt fence. Install checks/tie-backs and/or reinstall silt fence,
- 7. Check for tears within the silt fence, areas where silt fence has begun to decompose, and for any other circumstance that may render the silt fence ineffective. Removed damaged silt fence and reinstall new silt fence
- 8. Silt fence should be removed within 30 days after final stabilization is achieved and once it is removed, the resulting disturbed area shall be permanently

South Carolina Department of Health and Environmental Control

SILT FENCE

PAGE 2 of 2 STANDARD DRAWING NO.

FEBRUARY 2014

FEBRUARY 2014

EROSION CONTROL NOTES

- 1. IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS
- STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE
- INITIATED ON THAT PORTION OF THE SITE. 3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY SEVEN (7) DAYS. IF SITE INSPECTIONS IDENTIFY BMPS THAT ARE DAMAGED OR ARE NOT OPERATING EFFECTIVELY, MAINTENANCE MUST BE PERFORMED AS SOON AS PRACTICAL OR AS REASONABLY POSSIBLE AND BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE.
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT. AS MAY BE REQUIRED.
- 7. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- 8. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- 9. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 10. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 11. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR
- 12. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL. 13. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT
- PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE; 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE
- DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.). 15. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED: WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
 - WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; - FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING. 16. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 17. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS. IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE. THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 18. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON—SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

SEEDBED PREPARATION

- CHISEL COMPACTED AREAS AND SPREAD TOPSOIL 3 INCHES DEEP OVER ADVERSE SOIL CONDITIONS, IF AVAILABLE.
- RIP THE ENTIRE AREA TO 6 INCHES DEPTH.
- REMOVE ALL LOOSE ROCK, ROOTS, AND OTHER OBSTRUCTIONS LEAVING SURFACE REASONABLY
- APPLY AGRICULTURAL LIME, FERTILIZER. AND SUPERPHOSPHATE UNIFORMLY AND MIX WITH SOIL. CONTINUE TILLAGE UNTIL A WELL-PULVERIZED. FIRM REASONABLY UNIFORM SEEDBED IS
- PREPARED 4 TO 6 INCHES DEEP.
- SEED ON A FRESHLY PREPARED SEEDBED AND COVER SEED LIGHTLY WITH SEEDING EQUIPMENT OR CULTIPACK AFTER SEEDING.
- MULCH IMMEDIATELY AFTER SEEDING AND ANCHOR MULCH INSPECT ALL SEEDED AREAS AND MAKE NECESSARY REPAIRS OR RESEED WITHIN THE PLANTING SEASON, IF POSSIBLE. IF STAND IS OVER 60% DAMAGED, RE-ESTABLISH ORIGINAL
- LIME. FERTILIZER AND SEEDING RATES. CONSULT CONSERVATION INSPECTOR ON MAINTENANCE AND FERTILIZATION AFTER PERMANENT COVER IS ESTABLISHED. * APPLY: AGRICULTURAL LIME - 2 TONS/ ACRE (3 TONS/ACRE IN CLAY SOILS)

DI ANTING PATE

FERTILIZER - 1,000 lbs. / ACRE -10-10-10 SUPERPHOSPHATE - 500 lbs. / ACRE -20% ANALYSIS MULCH - 2 TONS / ACRE - SMALL GRAIN STRAW ADHESIVE - ASPHALT EMULSION @ 300 GALS. / ACRE

SEEDING SCHEDULE

DATE	TYPE	PLANTING RATE
AUG 15 - NOV 1	TALL FESCUE	300 lbs/acre
NOV 1 - MAR 1	TALL FESCUE	300 lbs/acre
	& ABRUZZI RYE	25 lbs/acre
MAR 1 - APR 15	TALL FESCUE	300 lbs/acre
APR 15 - JUN 30	HULLED COMMON BERMUDAGRASS	25 lbs/acre
JUL 1 - AUG 15	TALL RESCUE &	120 lbs/acre
	***BROWN TOP MILLET	35 lbs/acre
	*** or SORGHUM-SUDAN HYBRIDS	30 lbs/acre
	SLOPES (3:1 TO 2:1)	
MAR 1 - JUN 1	SERICEA LESPEDEZA (SCARIFIED)	50 lbs/acre
(MAR 1 - APR 15)	ADD TALL FESCUE	120 lbs/acre
(MAR 1 – JUN 30)	or ADD WEEPING LOVEGRASS	10 lbs/acre
(MAR 1 – JUN 30)	or ADD HULLED COMMON BERMUDAGRASS	25 lbs/acre
JUN 1 - SEP 1	***TALL FESCUE &	120 lbs/acre
	***BROWNTOP MILLET	25 lbs/acre
	*** or SORGHUM-SUDAN HYBRIDS	30 lbs/acre
SEP 1 - MAR 1	SERICEA LESPEDEZA	70 lbs/acre
	(UNHULLED-UNSCARIFIED)	
	& TALL FESCUE	120 lbs/acre
(NOV 1 - MAR 1)	ADD ABRUZZI RYE	25 lbs/acre

CONSULT CONSERVATION ENGINEER OR SOIL CONSERVATION SERVICE FOR ADDITIONAL INFORMATION CONCERNING OTHER ALTERNATIVES FOR VEGETATION OF DENUDED AREAS. THE ABOVE VEGETATION RATES ARE THOSE WHICH DO WELL UNDER LOCAL CONDITIONS; OTHER SEEDING RATE COMBINATIONS ARE POSSIBLE

*** TEMPORARY - RESEED ACCORDING TO OPTIMUM SEASON FOR DESIRED PERMANENT VEGETATION. DO NOT ALLOW TEMPORARY COVER TO GROW OVER 12" IN HEIGHT BEFORE MOWING, OTHERWISE FESCUE MAY BE SHADED OUT.

NOTE: SHOULDER AND DITCH GRASSING WILL BE REQUIRED. THE FULL SITE SHALL BE AT 70% COVERAGE PRIOR TO FINAL INSPECTION. A GOOD STAND OF PERMANENT GRASS (70% COVERAGE) SHALL BE PRESENT BY THE FINAL INSPECTION OR THE AREA SHALL BE RE-SEEDED OR SODDED. I A GOOD STAND OF PERMANENT GRASS (70% COVERAGE) HAS NOT BECOME ESTABLISHED WITHIN 180 DAYS, SODDING MAY BE REQUIRED BY THE COUNTY ENGINEER.

ROWE SERVICI

(843) (843)

О Н

OWN IN UPGRADE MAI THE 回の光 川京市 S S S S

SCALE: NTS PROJECT MGR: REH


DESIGNED BY: REH CHECKED BY: XX DATE ISSUED: JAN 2022


MO. 24332

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA

CALL 1-888-721-787[°]

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006






NOTES:


1. UTILITY LINES IN THIS DRAWING CONSIST OF WATER,

- WASTEWATER, AND STORMWATER LINES.
 2. WATER LINE AND WASTEWATER LINES SHALL BE PVC
- UNLESS VERTICAL SEPARATION DISTANCE BETWEEN LINES ARE LESS THAN 18", THEN USE DIP.
- ALL UTILITY LINES SHALL BE CENTERED TO ALLOW FOR THE GREATEST DISTANCE BETWEEN PIPE JOINTS.
 MATERIAL BETWEEN LINES SHALL BE COMPACTED TO

PREVENT SETTLING OF ABOVE PIPING.

UTILITY LINE CROSSING NO. I






<u>SECTION</u>

NOTES: 1. ALL REPAIRS TO BE IN ACCORDANCE WITH THE SCDOT SPECIFICATIONS AND THESE SPECIFICATIONS.

- 2. TRENCH SHALL BE BACKFILLED AND THOROUGHLY TAMPED WITH SUITABLE MATERIAL TO THE LEVEL OF THE STONE.
- 3. REPAIRS BY THE CONTRACTOR SHALL BE CONDUCTED WITH THE LEAST INTERFERENCE TO TRAFFIC.
 4. WHERE EXISTING ASPHALT IS INSUFFICIENT THICKNESS TO DEVELOP A TIGHT SEAL WITH THE NEW
- SURFACE, OVERLAP EXISTING SURFACE AS PER SPECIFICATIONS.
- 5. SEE SPECS. FOR UTILITY LINE BEDDING / BACKFILL REQUIREMENTS.
 6. 3'-0" MINIMUM COVER FOR WATER MAINS AND WASTEWATER LINES.
- 7. ASPHALT DRIVEWAYS IN SCDOT RIGHT-OF-WAY TO BE RESURFACED FROM EDGE OF PAVEMENT TO THE RIGHT-OF-WAY LINE.
- 8. INSTALL 10" BASE COURSE TO TOP OF EXISTING ASPHALT. EXCAVATE 2" BASE COURSE TO PLACE ASPHALT COURSE (TYPE B) FLUSH TO EXISTING ASPHALT.

UTILITY MAIN IN PAVED DRIVE



CITY OF GEORGETOWN, SC			
	ICAL TRENC RASSED ARE		
UPDATED 10/02/14	SCALE N.T.S.	NO.	
DRAWN A.J.K	CHECKED		

(2) DETAIL SHEET SINDARD WATER MAIN UPGRADES STANDARD WATER MAIN DETAILS GEORGETOWN, COUNTY MAIN DETAILS STANDARD WATER MAIN DETAILS GEORGETOWN, COUNTY

SHEET NO.

3 DAYS BEFORE DIGGING IN

SOUTH CAROLINA


CALL 1-888-721-7877

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006


(843) (843)

О П

ROWE SERVICE







STRUCTURE INFORMATION

MH# 239 TYPE: SANITARY COVER: SOLID RIM= 17.63 8"± CONC NE INV.=12.43 8"± CONC NW INV.=12.53 8"± CONC SW INV.=12.53 8"± CONC SE INV.=12.63

MH# 261 TYPE: SANITARY COVER: SOLID RIM= 17.84 8"± CONC N INV.=14.14 8"± CONC NW INV.=13.74 8"± CONC SE INV.=13.74

MH# 287 TYPE: SANITARY COVER: SOLID RIM = 18.308"± CONC NW INV.=12.40 8"± CONC SE INV.=12.40

	WATER MAIN FITTINGS			
POINT	DESCRIPTION	STATION	OFFSET	
100	6" X 6" TAPPING SLEEVE	100+59.14	21.46' L	
101	6" TEE	103+13.19	18.00' L	
102	6" TEE	105+09.42	18.00' L	
103	6" X 6" TAPPING SLEEVE	107+10.55	18.00' L	

WATER SERVICES:

107+00

BOURNE STREET NO SERVICES

WATER MAIN NOTES:

- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW 6-IN. PVC MAIN AND SERVICE TAPS.
- 2. OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND DISPOSE OF THEM.
- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER METER BOXES.
- CONTRACTOR IS RESPONSIBLE FOR RE—INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR CHANGE OVER.
- NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES
- TO MINIMIZE SHUTDOWN DISRUPTION. CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT
- WATER SERVICES TO AND FROM METER BOXES. CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION
- TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND
- CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING. 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS
- CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS).

10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.

WATER MAIN PLAN SECTO CITY OF GEORGETOM BOURNE STREET STA 100+00 TO STA 1 GEORGETOWN, COUNTY SCALE: 1"=30'
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022

O: (843) ² F: (843) ²

ROWE | Service

SHEET

OWN
IN UPGRADE



6 PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA CALL 1-888-721-7877

SHEET NO.

BOURNE STREET

PROPOSED 6" GATE — __PROPOSED 6" GATE _ VALVE & WELL 20 EX. GRADE OVER WATER MAIN EX. 2" WATER MAIN (TO BE REMOVED) EX. 1.5" WATER MAIN—
(TO BE REMOVED) ___ EX. 8" SAN ___ ĖX. 8" SAN PROPOSED 6"X6" -PROPOSED 6"X6"
TAPPING SLEEVE TAPPING SLEEVE PROPOSED 6"X6" TEE PROPOSED 6" C900 - Proposed 6"x6", tee DIRECTIONAL DRILL 85 FT 10"
HDPE PIPE MATERIAL W/ 6"
HDPE WATER LINE INSIDE & VALVE PVC WATER MAIN & VALVE PROPOSED 6"-45° VT BEND (TYP. BOTH SIDES)

103+00

101+00

102+00


PLACE CRUSHED 6AA STONE AT UTILITY CROSSINGS

104+00

105+00

106+00





HENRY STREET 3/4 INCH LONG SERVICE - 3 EA 3/4 INCH SHORT SERVICE - 5 EA

PROPOSED PROPOSED 6" GATE $\overline{}$ FIRE HYDRANT $\overline{}$ VALVE & BOX EX. GRADE OVER WATER MAIN PROPOSED -6"X6" TEE PROPOSED 6" $\overline{}$ HYDRANT TEE $\overline{}$ - PROPOSED 6"-45° VT PROPOSED 6" C900 PROPOSED 6"X6" BEND (TYP. BOTH SIDES) TAPPING SLEEVE PVC WATER MAIN -& VALVE _proposed -6"-45° HZ 200+00 201+00 202+00 203+00 204+00 205+00

PLACE CRUSHED 6AA STONE AT UTILITY CROSSINGS

STRUCTURE INFORMATION

MH# 543 TYPE: SANITARY COVER: SOLID RIM= 17.54 8"± CONC SW INV.=12.64 8"± CONC NE INV.=12.64

MH# 601 TYPE: STORM COVER: FLAT GRATE RIM= 16.29 15" CPP SE INV.=13.79 15" CPP NE INV.=13.79

MH# 624 TYPE: STORM COVER: FLAT GRATE RIM = 15.7215" CPP NE INV.=12.82 15" CPP SW INV.=12.82 15" CPP SE INV.=12.82

MH# 659 TYPE: STORM COVER: FLAT GRATE RIM= 15.66 15" CPP SW INV.=11.56 15" CPP NE INV.=11.56

MH# 672 TYPE: SANITARY COVER: SOLID RIM = 16.328"± CONC SW INV.=8.62 8"± CONC NW INV.=8.32 8"± CONC SE INV.=8.32

	WATER MAIN FITTINGS			
POINT	DESCRIPTION	STATION	OFFSET	
200	6" HYDRANT TEE	202+47.28	14.00' F	
201	45° HZ BEND	204+65.23	14.00' F	
202	45° HZ BEND	204+80.86	29.73'	
203	6" X 6" TAPPING SLEEVE	205+00.49	29.79'	

WATER MAIN NOTES:


- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW
- 6-IN. PVC MAIN AND SERVICE TAPS. 2. OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND DISPOSE OF THEM.
- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER METER BOXES.
- CONTRACTOR IS RESPONSIBLE FOR RE—INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR CHANGE OVER.
- NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES
- TO MINIMIZE SHUTDOWN DISRUPTION. CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT
- WATER SERVICES TO AND FROM METER BOXES. CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND
- REPORTING. CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING.
- 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS
- CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS). 10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.

WAIER MAIN PLAN SHEEI	CITY OF GEORGETOWN	FEND DISTRICT WATER MAIN UPGRAD	HENRY STREET STA 200+00 TO 205+50	GEORGETOWN, COUNTY	
-----------------------	--------------------	---------------------------------	-----------------------------------	--------------------	--

O: (843) ² F: (843) ²

ROWE | Service


SCALE: 1"=30'
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022




3 DAYS BEFORE DIGGING IN SOUTH CAROLINA

CALL 1-888-721-7877 PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006





JOHN STREET 3/4 INCH LONG SERVICE - 6 EA 3/4 INCH SHORT SERVICE - 1 EA



STRUCTURE INFORMATION

MH# 308 TYPE: SANITARY COVER: SOLID RIM= 17.24 8"± CONC NW INV.=13.04 8"± CONC S INV.=13.04 8"± CONC NE INV.=12.84

MH# 403 TYPE: SANITARY COVER: SOLID RIM= 16.80 8"± CONC SW INV.=8.40 8"± CONC NW INV.=8.00 8"± CONC SE INV.=8.00

WATER MAIN FITTINGS			
POINT	DESCRIPTION	STATION	OFFSET
300	6" HYDRANT TEE	302+67.33	15.00' R
301	6" X 6" TAPPING SLEEVE	305+10.55	15.00' R

WATER MAIN NOTES:

- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW 6-IN. PVC MAIN AND SERVICE TAPS.
- 2. OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND DISPOSE OF THEM.
- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER METER BOXES.
- CONTRACTOR IS RESPONSIBLE FOR RE—INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR CHANGE OVER.
- NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES TO MINIMIZE SHUTDOWN DISRUPTION.
- CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT
- WATER SERVICES TO AND FROM METER BOXES. CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND
- REPORTING. CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING.
- 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS
- CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS). 10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.

ROWE PROFESSIONAL SERVICES COMPANY

O: (843) ² F: (843) ²


CHECKED BY: XX DATE ISSUED: JAN 2022




3 DAYS BEFORE DIGGING IN SOUTH CAROLINA CALL 1-888-721-7877

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006





EMMANUEL STREET (S KAMINSKI ST TO MATCHLINE) 3/4 INCH SHORT SERVICE - 6 EA




EX STRUCTURE INVENTORIES	EX STRUCTURE INVENTORIES
EX 1159 RIM = 17.59 12" NW = 11.62 12" SE = 11.52 6" SW = 14.12 EX 1205 RIM = 17.56 12" SE = 12.78 12" SW = 13.28 12" NW = 12.96 12" NE = 13.18 EX 1345 RIM = 16.11 12" NW = 9.81 12" SW = 9.51 12" NE = 9.31	EX 950 RIM = 15.00 12" NE = 12.30 EX 951 RIM = 14.86 12" NW = 11.56 12" SE = 11.26 12" SW = 12.16 EX 1201 RIM = 17.01 12" NW = 15.26 EX 1202 RIM = 16.99 12" SE = 15.24 12" SW = 15.04 EX 1203 RIM = 17.00 12" NE = 14.20 12" NE = 14.20 12" NW = 14.20 12" SW = 14.20 EX 1204 RIM = 16.61 12" SE = 14.21 EX 1400 RIM = 15.09 12" SE = 11.89 EX 1401 RIM = 15.04
	12" NE = 12.54

	WATER MAIN FITTINGS			
POINT	DESCRIPTION	STATION	OFFSET	
500	6" X 6" TAPPING SLEEVE	501+71.60	17.00'	
501	22.5° HZ BEND	502+70.83	17.00' I	
502	22.5° HZ BEND	502+80.49	13.00'	
503	22.5° HZ BEND	503+00.49	13.00'	
504	22.5° HZ BEND	503+10.15	17.00'	
505	45° HZ BEND	505+93.56	17.00'	
506	45° HZ BEND	506+03.56	27.00'	
507	6" X 6" CROSS	506+42.84	27.00'	
	<u> </u>			

WATER MAIN NOTES:

- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW 6-IN. PVC MAIN AND SERVICE TAPS.
 OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND DISPOSE OF THEM.
- 3. CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER METER BOXES.
- CONTRACTOR IS RESPONSIBLE FOR RE—INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR
- NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES TO MINIMIZE SHUTDOWN DISRUPTION.
- CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT WATER SERVICES TO AND FROM METER BOXES.
- CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND
- 8. CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING. 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS
- CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS).
- 10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.



3 DAYS BEFORE DIGGING IN SOUTH CAROLINA CALL 1-888-721-7877

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006

(843) (843)


ROWE | Service

SHEET


OWN
IN UPGRADE

WATER MAIN PLAN SI
CITY OF GEORGETC
ST END DISTRICT WATER MAIN
EMANUEL STREET STA 500+50 TO 50


SCALE: 1"=30'
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022







EMMANUEL STREET (MATCHLINE TO S FRASER ST) NO SERVICES



PLACE CRUSHED 6AA STONE AT UTILITY CROSSINGS

EX STRUCTURE **INVENTORIES**

EX STRUCTURE INVENTORIES

EX 956 RIM = 12.5812" NW = 6.7812" SE = 6.08

EX 1001 RIM = 12.7212" NW = 10.1212" SE = 10.12

EX 957 RIM = 12.8012" NW = 8.5012" SE = 6.20EX 1000 RIM = 13.6410" NE = 8.84

12" SE = 8.64

	WATER MAIN FIT	TINGS	
POINT	DESCRIPTION	STATION	OFFSET
508	6" HYDRANT TEE	508+17.82	29.00' L
509	6" X6" TEE	508+77.82	29.00' L
510	10" X 6" TAPPING SLEEVE	511+24.41	25.00' L

WATER MAIN NOTES:

- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW
- 6-IN. PVC MAIN AND SERVICE TAPS. 2. OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND DISPOSE OF THEM.
- CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER
- METER BOXES. CONTRACTOR IS RESPONSIBLE FOR RE—INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR CHANGE OVER.
- NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES
- TO MINIMIZE SHUTDOWN DISRUPTION. CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT
- WATER SERVICES TO AND FROM METER BOXES. CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND
- REPORTING. CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING.
- 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS
- CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS). 10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.

WATER MAIN PLAN SHEET

CITY OF GEORGETOWN

ST END DISTRICT WATER MAIN UPGRADES

EMANUEL STREET STA 507+50 TO 507+50

GEORGETOWN, COUNTY

PROFESSIONAL SES COMPANY

ROWE | Service

O: (843) ² F: (843) ²

SCALE: 1"=30'
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA


CALL 1-888-721-7877 PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006



DAVIS ALLEY **EMANUEL STREET** #218 DAVIS ALLEY #220 DAVIS ALLEY
- PROPOSED CONSTRUCTION #228 DAVIS ALLEY #224 DAVIS ALLEY PROPOSED CONSTRUCTION (TEE TO HYDRANT) STA 601+85, 14' L Water Main, C900 PVC, 6 inch Gate Valve and Box, 6 inch — 1 Ea PROPOSED CONSTRUCTION - PROPOSED WATER - ABANDON EXISTING STA 604+34, 18' L SERVICE (TYP.) WATER MAIN Fire Hydrant w/ Assembly — 1 Ea — EX GATE — ₹ 603+00 🔁 601+00 ⁷ 604+00 ∤ 604+75 PROJECT CONTROL LINE FOR EMANUEL STREET WATER MAIN SEE SHEET 10 #230 S. FRASER STREET #218 S. FRASER #216 S. FRASER #214/212/208/206 STREET STREET S. FRASER STREET

WATER SERVICES:

DAVIS ALLEY 3/4 INCH SHORT SERVICE — 3 EA



PLACE CRUSHED 6AA STONE AT UTILITY CROSSINGS

EX STRUCTURE INVENTORIES

EX STRUCTURE INVENTORIES

EX 1031 RIM = 15.6010" SW = 10.60 EX 1001 RIM = 12.7212" NW = 10.1212" SE = 10.12

ROWE PROSERVICES

WATER MAIN PLAN SHEET

CITY OF GEORGETOWN

ST END DISTRICT WATER MAIN UPGRADES

DAVIS ALLEY STA 600+50 TO 604+75

WE

SCALE: 1"=30'
PROJECT MGR: REH
DESIGNED BY: REH
CHECKED BY: XX
DATE ISSUED: JAN 2022

CONTRACTOR IS RESPONSIBLE FOR ALL SOIL BACKFILL COMPACTION TESTING, WATER LINE PRESSURE TESTING, BAC-T TESTING AND CITY STAFF WILL MONITOR INSTALLATION AND WITNESS TESTING. 9. CONTRACTOR IS RESPONSIBLE TO PROVIDE AS-BUILT DRAWINGS

CERTIFIED BY A PROFESSIONAL LAND SURVEYOR (PLS). 10. THE CONTRACTOR SHALL FOLLOW THE CITY'S CLOSEOUT PROCEDURES.

CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL THE NEW 6-IN. PVC MAIN AND SERVICE TAPS. 2. OLD WATER MAIN AND SERVICES TO BE ABANDONED IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO REMOVE OLD METER BOXES AND

CONTRACTOR IS RESPONSIBLE TO FURNISH AND INSTALL NEW WATER

CONTRACTOR IS RESPONSIBLE FOR RE-INSTALLING EXISTING WATER METERS OR INSTALLING NEW METERS IN METER BOXES. THE CONTRACTOR IS RESPONSIBLE TO COORDINATE WITH CITY STAFF FOR

NEW METER BOXES SHALL BE PLACED IN PARALLEL TO EXISTING ONES

CONTRACTOR IS RESPONSIBLE TO DISCONNECT AND RE-CONNECT

WATER MAIN NOTES:

TO MINIMIZE SHUTDOWN DISRUPTION.

WATER SERVICES TO AND FROM METER BOXES.

DISPOSE OF THEM.

METER BOXES.

CHANGE OVER.

REPORTING.



3 DAYS BEFORE DIGGING IN SOUTH CAROLINA

CALL 1-888-721-7877

SHEET NO.

PALMETTO UTILITY PROTECTION SERVICE JOB No: 2250006

