



**West End District Water Main Upgrades
Project #1515 – CDBG #4-CI-21-008**

REQUEST FOR BID (RFB)

**ADDENDUM III
Answers to Questions
October 3, 2022**

1. Due to the current labor market, are the Construction Start Date & Construction Finish Date from Addendum 1 set in stone?
This project is funded by a Community Block Development Grant (CDBG). The schedule is firm per the CDBG timeline.
2. Is there an asphalt replacement detail available for roadways, especially S Fraser Street?
Refer to pavement detail on bid plans, Sheet no. 4
3. Will there be a line item or detail added for storm drain crossings?
This is inclusive to the cost of the installation of new 6-in. PVC water line.
4. Are overlays required? Our interpretation is that asphalt is only cut & patch from plans.
No pavement overlay is required.
5. Please define line item '2" Asphalt Paving & Milling' on various streets in bid tab. Is this considered asphalt removal and patching?
This bid line item refers to open cut within paved areas for the new water line. Contractor shall sawcut, remove asphalt, and pave. Refer to pavement detail on drawings and Section 02510-Paving Repair. No milling is required.
6. Is there any concrete under asphalt sections that is required to be removed and replaced?
Not to our knowledge.



7. There are fittings called out on plans. Will there be a line item added? How will fittings be paid for?
All necessary fittings are inclusive to the new 6-in. PVC water line bid item as noted on the Bid Form.
8. Will there be a pay item for restraint joint pipe?
No. This is inclusive of the 6-in. PVC 900 bid line item.
9. Will the job be awarded if there are less than 3 bids?
Yes, pending CDBG and council approval.