

Andy Devine ADA Improvements ENG23-0032 Addendum 1 Q&A

1. Will a 2' Patch Back of asphalt be required along any curb removals?
Preference is to pour back near to the edge of asphalt. If the edge of asphalt is damaged during construction, a two foot repair will be required.
2. Bid Item 11 'Grading, Excavation and Embankment' has a quantity of 463 CY. Can you provide the locations of earthwork?
The grading quantities are in various locations throughout the project and are associated with the ramps/driveways. There are areas where matching of existing parking areas is needed as well.
3. In the Advertisement for Bids there is a contract time of 180 Calendar Days, however in the Proposal Form the contract time is listed a 120 Calendar Days. Can you confirm what contract duration is correct?
Construction time will be 180 days.
4. What Bid Item should the work for Demolition Note 24 ' Existing Wall to Be Removed' be paid under?
The item is a single row of block at the back of the sidewalk on the northwest corner of Johnson Ave and Andy Devine Ave. Removals will be paid from Item 6 on the schedule of values.
5. What bid item should the adjustment of the monument controls and removal of the monumentation be paid under?
There are no monument adjust required under this project.