


- DEMOLITION NOTES:**
1. SEQUENCE DEMOLITION TO MINIMIZE DISRUPTION TO EXISTING ACTIVITIES WITHIN THE CONSTRUCTION ZONE.
  2. VERIFY LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. COORDINATE RELOCATION AND PROTECTION OF ALL UNDERGROUND UTILITIES WITH LOCAL SERVICING AGENCIES.
  3. ALL CONSTRUCTION ACTIVITIES ARE TO BE SECURED AND BARRICADED.
  4. CARE MUST BE TAKEN TO PROTECT PRIVATE PROPERTY. DAMAGE CLAIMS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
  5. PROVIDE BARRICADES AS REQUIRED DURING CONSTRUCTION.
  6. PROVIDE INLET PROTECTION FOR EROSION CONTROL AS NOTED.
  7. ANY ASPHALT DAMAGED DURING THE COURSE OF CONSTRUCTION SHALL BE REPAIRED BY THE CONTRACTOR.



**BPE**  
 BRYAN PRICE ENGINEERING  
 865 COKER FORD ROAD  
 PORTLAND, TENNESSEE 37148  
 PHONE: 615-481-3176 EMAIL: BRYAN.PRICE@REACAN.COM

DATE	01-13-2019
REVISIONS	
REVISED AFTER BID	
DATE:	JANUARY 2019
DRAWN BY:	PRICE
CHECKED BY:	PRICE
APPROVED BY:	PRICE

DEMOLITION PLAN  
 PEAY PARK SPLASH PAD  
 CITY OF GOODLETTSVILLE  
 DAVIDSON COUNTY, TENNESSEE

SHEET NO.  
**C2.0**

JOB NO. 0301-02