

City of Laurinburg

Electric Shed Repair Scope of Work

Labor and Materials for the following:

Demolition and removal of the existing metal roof panels

Demolition and removal of the existing 2X4 wood purlins

Install new 2X4 wood purlins

Install new 29 Gauge metal roof panels

Add Alternate 1:

Remove and replace all other wood members (Excluding Poles)

Add Alternate 2:

Use 8 – 10 of the existing metal roof panels to replace the missing panels on the street department shed