

Exhibit C
W Street Sign Bid/Quote Tab

				Contractor's Name	
Hurricane Sally Repairs, Group 5, LOT 1 - W Street Tax Office Sign					
Bid Item No.	Bid Item Description	Quantity	Unit	Unit Price	Bid Price
1	Mobilization & Safety (Include all equipment rental/pricing)	1	LS		\$ -
2	Detach & Reset Signage, 2 EA	1	LS		\$ -
3	Remove Existing EIFS System, 600 SF	1	LS		\$ -
4	Remove Existing Plywood Sheathing, 600 SF	1	LS		\$ -
5	Remove and Replace Moisture Damaged Framing, Metal, 300 LF	1	LS		\$ -
6	Install 1/2" Plywood Sheathing, 600 SF	1	LS		\$ -
7	Install Moisture Barrier, 600 SF	1	LS		\$ -
8	Install PVC Corner/Casing Beads (Include fasteners), 200 LF	1	LS		\$ -
9	Install 1" Expanded Polystyrene Board (Include fasteners), 600 SF	1	LS		\$ -
10	Install Reinforcement Mesh, 600 SF	1	LS		\$ -
11	Install Base and Finish Coat, 600 SF	1	LS		\$ -
12	Prep and Coat, Elastomeric, 600 SF	1	LS		\$ -
13	Project Closeout	1	LS		\$ -
W Street Tax/Probation Sign Bid Total					\$ -

Notes

- 1 - As required by FEMA, Contractor shall submit to the County a record of disposed materials. The record shall include site name, date of disposal, and GPS coordinates of the site. If the demolished materials are recycled, the Contractor shall submit a statement to the County certifying the materials have been recycled.
- 2 - All items shall be bid as Furnish and Install, to include all appurtenances necessary to complete the project.
- 3 - All material replacements shall be of like kind and quality, unless otherwise specified in the bid documents.