

Item #	Description	Quantity	Unit	Unit Price	Total
General Conditions					
1	Construction Management	1	LS		
2	Mobilization and Demobilization	1	LS		
3	Bonds	1	LS		
4	Construction Staking	1	LS		
5	Traffic Control	1	LS		
6	Road/Sidewalk Closed Signage	6	EA		
Demolition and Erosion Control					
7	Tree Protection Fencing	626	LF		
8	Inlet Protection	5	EA		
9	Erosion Control Maintenance and SWPPP Monitoring	1	LS		
10	Demolition (Little Main, SCDOT Roadways)	1	LS		
11	Demolition (Parking Lot)	1	LS		
12	Demolition of Storm Drain	1	LS		
Overhead to Underground Conversion					
13	4" Conduit installed via HDD for AT&T	200	LF		
14	2" Conduit installed via HDD for WOW!	200	LF		
15	2" Conduit installed via HDD for Time Warner Company	200	LF		
16	3" Conduit installed via HDD for SCE&G - into the park	72	LF		
17	3" Conduit installed via HDD for SCE&G - to existing light pole at tracks	125	LF		
18	Hand Hole	1	LS		
19	Open trench connections at existing Poles	1	LS		
Little Main Street Construction					
20	Grading Roadway	1790	SY		
21	Asphalt - Binder Course - Little Main	1790	SY		

22 Asphalt - Surface Course - Little Main	1790 SY
23 Road Base Course	796 TN
24 18" Curb and Gutter - Non SCDOT	470 LF
25 Brick Pavers, set in GABC	3440 SF
26 Ribbon Curb - Brick Pavers	250 LF
27 Fine Grading	1790 SY
28 24" Stop Bar	1 EA
29 Parking Lot Stripping	1 LS
30 "Stop", "Do Not Enter" and "Right Turn Only" Sign - Little Main	1 EA
31 ADA Stripping and Decal	1 EA
32 Brick Paver Crosswalks	430 SF
33 Ribbon Curb at Crosswalks	75 LF
34 Turn Back Curb for Future Ramp (Little Main and Richardson)	1 LS
35 Wheel Stops (Replace Existing)	36 EA
36 Wheel Stops (additional wheel stops)	32 EA
37 Removable Bollards	12 EA
Storm Drainage	
38 12" RCP - Across West Richardson	87 LF
39 Connect to Existing Storm box	1 EA
40 New Grate Inlet	1 EA
41 12" RCP - Little Main	82 LF
42 New Grate Inlet	3 EA
43 New Junction Box	1 EA
West Richardson	
44 Mill Existing Roadway	660 SY
45 Asphalt Overlay	660 SY
46 Replace Existing Pavement Markings	1 LS
47 Crosswalk Thermoplastic Traffic Scapes Patterns LT (W. Richardson)	400 SF
48 Crosswalk Thermoplastic Traffic Scapes Patterns LT (Main Street)	950 SF
49 Re-Paint Crosswalk Painting at Main Street and W. Richardson	1 LS
50 18" Curb and Gutter	120 LF

West Doty

51 18" Curb and Gutter	157 LF
52 Eradicate Existing Pavement Markings	1 LS
53 West Doty Pavement Markings	1 LS
54 Re-Paint Crosswalk Painting at Main Street and W. Doty	1 LS
55 Crosswalk Thermoplastic Traffic Scapes Patterns LT	490 SF

Main Street

56 Eradicate Existing Parallel Parking Spaces	1 LS
57 Re-Paint Parallel Parking Spaces	1 LS