

SPALDING COUNTY
TSPLOST RESURFACING PHASE I
RFP NO. 2022-0006

FROM: SPALDING COUNTY
PURCHASING
119 EAST SOLOMON STREET
GRIFFIN, GA 30223

TO: ALL BIDDERS

RE: Addendum No. 1, dated March 28, 2022

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated March 4, 2022.

This Addendum consists of two (2) pages. Attached documents include a revised Bid Tabulation (dated 03/25/2022) and a list of Roadway Patch Measurements consisting of 32 pages.

- Add. 1.1 Modification: The Roadway Patch Measurements list for all roadways in the project is attached to this addendum. The data includes the length, width, and approximate tonnage for each area designated for patching.
- Add. 1.2 Modification: The Bid Tabulation has been revised and is attached to this addendum. The bulk of the traffic striping has been removed from the Base Bid and two Alternates added for high build paint and thermoplastic striping. The apparent low bidder will be selected based on the Base Bid and Alternate chosen by the Owner.
- Add. 1.3 Clarification: Patching areas are marked in pink for all roads in the project and will be repainted by Spalding County Public Works as needed during the bid process and prior to a notice to proceed being issued. The Contractor is to mill each patch area to a depth of three inches.
- Add. 1.4 Clarification: The Contractor is to haul the millings generated from patching the roads to Spalding County's property on Justice Boulevard in Griffin. The GPS coordinates for the property entrance are: 33.235792, -84.291601
- Add. 1.5 Clarification: Patching and overlay on roads which approach a GDOT roadway should stop prior to signal loops and any GDOT gore striping.
- Add. 1.6 Clarification: The Contractor is required to install temporary for each road. Tape or paint is acceptable for temporary striping.

- Add. 1.7 Clarification: The Contractor is required to “run the gate out” at all side roads and driveways to provide a smooth transition. Overlay will include accel/decel/turn lanes at schools and subdivisions.
- Add. 1.8 Clarification: The Contractor is not required to provide shoulder building or low/soft shoulder signs. Spalding County Public Works will provide these items as needed.
- Add. 1.9 Clarification: Post mounted advance warning signs are not required. Tripod mounting signs are acceptable.
- Add. 1.10 Clarification: Water valve boxes are to be adjusted in the following manner: Valve box is to be raised flush and even with the resurfaced pavement using a cast iron riser. The new riser should accept the existing cover or contractor must supply a new cover matching the existing cover. Asphalt overlay shall be flush against the riser; no concrete is required. The contractor is to take necessary precautions to prevent gravel and debris from entering the valve box during ring and cover adjustment. Any debris entering valve box must be removed.

End of Addendum No. 1