

**SPALDING COUNTY TSPLOST
RESURFACING PHASE I
BID TABULATION (REVISED 03/25/2022)
2022-0006**

| Item | Description | Estimated Quantity | Unit | Unit Price | Item Total |
|------|----------------------------------------------------------------------------------------|--------------------|------|------------|------------|
| 1 | PAYMENT & PERFORMANCE BONDS | 1 | LS | | |
| 2 | MOBILIZATION | 1 | LS | | |
| 3 | TRAFFIC CONTROL | 1 | LS | | |
| 4 | RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME (330 LBS/SY) | 14,443 | TN | | |
| 5 | RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME, TP 1 (85 LBS/SY) | 3,635 | TN | | |
| 6 | RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (165 LBS/SY) | 29,274 | TN | | |
| 7 | BITUMINOUS TACK COAT | 17,446 | GAL | | |
| 8 | THERMOPLASTIC PAVEMENT MARKING, 24" WHITE STOP BAR | 32 | EA | | |
| 9 | THERMOPLASTIC CROSSWALK STRIPING (JOHN JONES ROAD) | 1 | LS | | |
| 10 | THERMOPLASTIC CROSSWALK STRIPING (COWAN ROAD AT ELEMENTARY SCHOOL) | 1 | LS | | |
| 11 | ADJUST WATER MAIN VALVE BOX TO GRADE | 13 | EA | | |

BASE BID TOTAL =

ALTERNATE NO. 1

| | | | | | |
|----|------------------------------------------------------------------------|-------|-----|--|--|
| 12 | SOLID TRAFFIC STRIPE, HIGH BUILD, 5 INCH, WHITE | 48.28 | LM | | |
| 13 | SOLID TRAFFIC STRIPE, HIGH BUILD, 5 INCH, YELLOW | 38.65 | LM | | |
| 14 | SKIP TRAFFIC STRIPE, HIGH BUILD, 5 INCH, YELLOW | 5.94 | GLM | | |
| 15 | PAVEMENT MARKING, ARROW, TYPE 2, WHITE | 10 | EA | | |
| 16 | GORE STRIPING, WHITE (W. ELLIS AT LUKE DRIVE) | 1 | LS | | |
| 17 | GORE STRIPING, WHITE (COWAN ROAD AT ELEMENTARY SCHOOL & MIDDLE SCHOOL) | 1 | LS | | |

ALTERNATE NO. 1 TOTAL =

ALTERNATE NO. 2

| | | | | | |
|----|--------------------------------------------------------------------------------------|-------|-----|--|--|
| 18 | THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE | 48.28 | LM | | |
| 19 | THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, YELLOW | 38.65 | LM | | |
| 20 | THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 INCH, YELLOW | 5.94 | GLM | | |
| 21 | THERMOPLASTIC ARROW, TYPE 2, WHITE | 10 | EA | | |
| 22 | THERMOPLASTIC GORE STRIPING, WHITE (W. ELLIS AT LUKE DRIVE) | 1 | LS | | |
| 23 | THERMOPLASTIC GORE STRIPING, WHITE (COWAN ROAD AT ELEMENTARY SCHOOL & MIDDLE SCHOOL) | 1 | LS | | |

ALTERNATE NO. 2 TOTAL =