

**SPALDING COUNTY  
TSPLOT RESURFACING PROJECT PHASE II (2023)  
BID TABULATION  
2023-0009**

Item	Description	Unit	Estimated Quantity	Unit Price	Item Total
<b>ROAD RESURFACING</b>					
1	PAYMENT & PERFORMANCE BONDS	LS	1		
2	MOBILIZATION	LS	1		
3	TRAFFIC CONTROL	LS	1		
4	RECYCLED ASPH CONC 19 MM PATCHING, INCL BITUM MATL & H LIME (330 LBS/SY), INCLUDING MILLING	TN	500		
5	ASPHALTIC CONCRETE OPEN GRADED CRACKED RELIEF INTERLAYER, GP BLEND, INCL BITUM MATL & H LIME	TN	24,917		
6	RECYCLED ASPH CONC 9.5 MM LEVELING, INCL BITUM MATL & H LIME, TP 1 (85 LBS/SY)	TN	4,972		
7	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (165 LBS/SY)	TN	33,165		
8	BITUMINOUS TACK COAT	GAL	20,973		
9	MILLING TRANSITIONS AS REQUIRED IN RFP	LS	1		
10	THERMOPLASTIC PAVEMENT MARKING, 24" WHITE STOP BAR	EA	55		
11	THERMOPLASTIC CROSSWALK STRIPING (MACON ROAD)	EA	2		
12	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE	LM	56.97		
13	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, YELLOW	LM	50.11		
14	THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 INCH, YELLOW	GLM	4.83		
15	THERMOPLASTIC ARROW, TYPE 2, WHITE	EA	13		
16	THERMOPLASTIC GORE STRIPING, YELLOW (MERIWETHER STREET)	LS	1		
17	THERMOPLASTIC GORE STRIPING, YELLOW (MACON ROAD AT FUTRAL ROAD )	LS	1		
18	THERMOPLASTIC R/R MARKING, WHITE (MACON ROAD AT GREEN VALLEY ROAD)	LS	1		
19	WARNING STRIPS (MACON ROAD AT COUNTY LINE ROAD)	EA	4		
20	ADJUST WATER MAIN VALVE BOX TO GRADE	EA	25		
21	ADJUST SEWER MANHOLE TO GRADE	EA	13		
<b>CARVER ROAD FIRE STATION (FULL-DEPTH RECLAMATION &amp; PAVING)</b>					
22	FULL DEPTH RECLAMATION (60 LBS/SY AT 12 INCHES)	SY	9,225		
23	RECYCLED ASPH CONC 19 MM, INCL BITUM MATL & H LIME (220 LBS/SY)	TN	1,025		
24	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (165 LBS/SY)	TN	770		
25	BITUMINOUS TACK COAT	GAL	750		
26	THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE	LF	622		
27	GORE STRIPING AND HANDICAP SYMBOLS	LS	1		
				<b>TOTAL CONSTRUCTION =</b>	