

**SPALDING COUNTY
 TSPLIT RESURFACING PROJECT PHASE II (2023)
 BID TABULATION
 2023-0009**

| Item | Description | Unit | Estimated Quantity | Unit Price | Item Total |
|---|--|------|-----------------------------|------------|------------|
| ROAD RESURFACING | | | | | |
| 1 | PAYMENT & PERFORMANCE BONDS | LS | 1 | | |
| 2 | MOBILIZATION | LS | 1 | | |
| 3 | TRAFFIC CONTROL | LS | 1 | | |
| 4 | RECYCLED ASPH CONC 19 MM PATCHING, INCL BITUM MATL & H LIME (330 LBS/SY), INCLUDING MILLING | TN | 500 | | |
| 5 | ASPHALTIC CONCRETE OPEN GRADED CRACKED RELIEF INTERLAYER, GP BLEND, INCL BITUM MATL & H LIME | TN | 16,923 | | |
| 6 | RECYCLED ASPH CONC 9.5 MM LEVELING, INCL BITUM MATL & H LIME, TP 1 (85 LBS/SY) | TN | 3,154 | | |
| 7 | RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (165 LBS/SY) | TN | 25,384 | | |
| 8 | BITUMINOUS TACK COAT | GAL | 54,089 | | |
| 9 | MILLING TRANSITIONS AS REQUIRED IN RFP | SY | 673 | | |
| 10 | SHOULDER BUILDING, INCLUDING GRASSING (SPALDING COUNTY TO PROVIDE FILL MATERIAL) | LM | 16.44 | | |
| 11 | THERMOPLASTIC PAVEMENT MARKING, 24" WHITE STOP BAR | EA | 34 | | |
| 12 | THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE | LM | 36.14 | | |
| 13 | THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, YELLOW | LM | 31.97 | | |
| 14 | THERMOPLASTIC SKIP TRAFFIC STRIPE, 5 INCH, YELLOW | GLM | 3.18 | | |
| 15 | THERMOPLASTIC ARROW, TYPE 2, WHITE | EA | 11 | | |
| 16 | THERMOPLASTIC GORE STRIPING, YELLOW (MACON ROAD AT FUTRAL ROAD) | LS | 1 | | |
| 17 | THERMOPLASTIC R/R MARKING, WHITE (MACON ROAD AT GREEN VALLEY ROAD) | LS | 1 | | |
| 18 | THERMOPLASTIC WARNING STRIPS (MACON ROAD AT COUNTY LINE ROAD) | EA | 6 | | |
| 19 | ADJUST WATER MAIN VALVE BOX TO GRADE | EA | 25 | | |
| 20 | ADJUST SEWER MANHOLE TO GRADE | EA | 13 | | |
| | | | TOTAL CONSTRUCTION = | | |
| CARVER ROAD FIRE STATION (FULL-DEPTH RECLAMATION & PAVING) | | | | | |
| 21 | MOBILIZATION | LS | 1 | | |
| 22 | FULL DEPTH RECLAMATION (60 LBS/SY AT 12 INCHES) | SY | 9,225 | | |
| 23 | RECYCLED ASPH CONC 19 MM, INCL BITUM MATL & H LIME (220 LBS/SY) | TN | 1,025 | | |
| 24 | RECYCLED ASPH CONC 12.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (165 LBS/SY) | TN | 770 | | |
| 25 | BITUMINOUS TACK COAT | GAL | 750 | | |
| 26 | THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE | LF | 622 | | |
| 27 | GORE STRIPING AND HANDICAP SYMBOLS | LS | 1 | | |
| | | | TOTAL CONSTRUCTION = | | |