

SPALDING COUNTY
2023 TSPLOST RESURFACING PHASE II
RFP NO. 2023-0009

FROM: SPALDING COUNTY
PURCHASING
119 EAST SOLOMON STREET
GRIFFIN, GA 30223

TO: ALL BIDDERS

RE: Addendum No. 1, dated March 17, 2023

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 24, 2023.

The Addendum consists of two (2) pages. Attached documents include a revised Bid Tabulation (dated 03/13/2023), a list containing roadway widths, and an aerial map of the Carver Road Fire Station.

- Add. 1.1 Modification: A revised Bid Tabulation dated 03/13/2023 is attached to this addendum. Contractors must use the revised Bid Tabulation for submittal.
- Add. 1.2 Modification: The unit for Pay Item 11 THERMOPLASTIC CROSSWALK STRIPING (MACON ROAD) on the Bid Tabulation has been changed from LS (Lump Sum) to EA (Each).
- Add. 1.3 Modification: The quantity for Pay Item 13 THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, YELLOW has been changed from 3.97 LM to 50.11 LM.
- Add. 1.4 Modification: The quantity for Pay Item 21 ADJUST SEWER MANHOLE TO GRADE has been changed from 10 EA to 13 EA.
- Add. 1.5 Modification: The overall project has been separated into three parts: ROAD RESURFACING (YEAR 2), ROAD RESURFACING (YEAR 3), and CARVER ROAD FIRE STATION (FULL-DEPTH RECLAMATION & PAVING).
- Add. 1.6 Modification: An aerial map of the Carver Road Fire Station is attached. The two asphalt driveways off Carver Road, the asphalt parking lot north of the fire station, and the large asphalt lot east of the fire station are included in the areas proposed for full-depth reclamation and paving. The concrete paving adjacent to the fire station, the recycling center drives, and the paved area inside the recycling center fence are excluded.

- Add. 1.7 Clarification: Pay Item 26 THERMOPLASTIC SOLID TRAFFIC STRIPE, 5 INCH, WHITE, which is being paid based on a LF (Linear Foot) unit, consists of the parking space striping in the Carver Road Fire Station parking lot.
- Add. 1.8 Clarification: Pay Item 27 GORE STRIPING AND HANDICAP SYMBOLS consists of additional striping in the Carver Road Fire Station parking lot.
- Add. 1.9 Clarification: Both Evans Road and Hollonville Road will required approximately 140 tons of patching each.
- Add. 1.10 Clarification: Spalding County and the City of Griffin will provide water valve risers and manhole risers to the Contractor for the required adjustments of each.
- Add. 1.11 Clarification: Final thermoplastic pavement markings may be placed on a road seven (7) days after resurfacing is completed for that road.
- Add. 1.12 Clarification: The contractor is not required to use tape for temporary striping but may also use paint.

End of Addendum No. 1