

**SPALDING COUNTY
AQUATIC CENTER
CIVIL WORK BID TABULATION
REVISED 04/18/2022**

Item	Description	Unit	Quantity	Unit Price	Item Total
GENERAL					
1.	PAYMENT & PERFORMANCE BONDS	LS	1		
2.	GENERAL CONDITIONS	LS	1		
3.	CONSTRUCTION STAKING (LAYOUT) BY REGISTERED SURVEYOR	LS	1		
4.	AS-BUILT SURVEY PLAN BY REGISTERED SURVEYOR	LS	1		
<i>General Subtotal =</i>					
SITE DEMOLITION/REMOVAL					
5.	EXISTING SHED A DEMOLITION AND REMOVAL	LS	1		
<i>Site Demolition/Removal Subtotal =</i>					
GRADING					
6.	STRIP AND STOCKPILE TOPSOIL	LS	1		
7.	MASS GRADING	LS	1		
8.	TOPSOIL PLACEMENT ON SLOPES AND LANDSCAPE AREAS	LS	1		
<i>Grading Subtotal =</i>					
SITE IMPROVEMENTS					
9.	CONCRETE WALKS	SF	14,600		
10.	24" CURB AND GUTTER	LF	2,576		
11.	CONCRETE AT DUMPSTER INCLUDING CURB	SF	200		
12.	WHEEL STOPS	EA	16		
13.	CONCRETE PEDESTRIAN CROSSING "HUMP"	EA	1		
14.	#3 STONE FOR POND	TN	650		
15.	FLUME AT LANDSCAPE ISLAND	LF	15		
16.	FLUME AT PARKING LOT	LF	15		
<i>Site Improvements Subtotal =</i>					
PAVING					
17.	LIGHT DUTY ASPHALT PAVING (6:2 SECTION)	SY	3,423		
18.	HEAVY DUTY ASPHALT PAVING (8: 2 : 1 SECTION)	SY	3,146		
<i>Paving Subtotal =</i>					
STORM SEWER SYSTEM					
19.	15"HDPE STORM PIPE	LF	75		
20.	18" HDPE STORM PIPE	LF	190		
21.	30" HDPE STORM PIPE	LF	408		
22.	4' DIAMETER JUNCTION BOX BASE (4' HIGH)	EA	7		
23.	4' DIAMETER BOX RISER SECTION	VF	58		
24.	18" X 24" GRATE INLET (GDOT 1019A) IN LANDSCAPE AREA	EA	2		

Item	Description	Unit	Quantity	Unit Price	Item Total
25.	CATCH BASIN TOP (GDOT 1034D)	EA	4		
26.	RAISED LID INLET	EA	1		
27.	TEMPORARY CONCRETE PAD AT DWCB C-2 (INCLUDING REMOVAL)	EA	1		
28.	15" CONCRETE HEADWALL (MEETING GDOT STANDARDS)	EA	1		
29.	18" CONCRETE HEADWALL (MEETING GDOT STANDARDS)	EA	1		
30.	30" CONCRETE HEADWALL (MEETING GDOT STANDARDS)	EA	1		
Storm Sewer System Subtotal =					
SANITARY SEWER - PUBLIC					
31.	8" DIP CLASS 350 SEWER MAIN	LF	604		
32.	4' DIAMETER SANITARY SEWER MANHOLE (4' BASE SECTION)	EA	4		
33.	4' DIAMETER SANITARY SEWER MANHOLE (ADDITIONAL VERTICAL FOOTAGE)	VF	5		
34.	4' SSMH CONE 3' HEIGHT OFFSET	EA	3		
35.	4' SSMH CONE 2' HEIGHT OFFSET	EA	1		
36.	SSMH RING AND COVER (CITY OF GRIFFIN STD) CAST IN CONE	EA	4		
37.	CORE AND BOOT MANHOLE	LS	1		
38.	MODIFY TABLE/INVERT OF EXISTING SANITARY SEWER MANHOLE	LS	1		
39.	6" SDR 26 PVC PIPE (SANITARY SEWER LATERAL)	LF	867		
40.	CLEANOUT ASSEMBLY COMPLETE	EA	12		
Sanitary Sewer - Public Subtotal =					
WATER SYSTEM - DOMESTIC					
41.	3" SCHEDULE 80 PVC	LF	486		
42.	45 DEGREE BEND WITH CONCRETE BLOCKING	EA	3		
43.	90 DEGREE BEND WITH CONCRETE BLOCKING	EA	3		
44.	3" GATE VALVE WITH 2" SQUARE NUT	EA	1		
45.	3" NEPTUNE METER	EA	1		
46.	3" ZURN RPZ	LS	1		
47.	INSULATED RPZ COVER	LS	1		
48.	CONCRETE METER BOX WITH LID	EA	1		
Water System - Domestic Subtotal =					
WATER SYSTEM - FIRE					
49.	6" DIP CLASS 350	LF	479		
50.	6" DIP 45 DEGREE M.J. BEND WITH CONCRETE BLOCKING AND M.J. RESTRAINTS	EA	3		
51.	6" DIP 90 DEGREE M.J. BEND WITH CONCRETE BLOCKING AND M.J. RESTRAINTS	LF	2		
52.	6" X 6" M.J. TEE WITH CONCRETE BLOCKING AND M.J. RESTRAINTS	EA	1		
53.	6" x 3" M.J. REDUCER	EA	1		
54.	12" X 6" TAPPING SLEEVE AND VALVE (FULL CIRCLE STAINLESS STEEL)	EA	1		
Water System - Fire Subtotal =					

Item	Description	Unit	Quantity	Unit Price	Item Total
EROSION CONTROL					
55.	CONSTRUCTION EXIT	EA	1		
56.	Sd1-S SILT FENCE INCLUDING MAINTENANCE AND REMOVAL	LF	3,500		
57.	SD2-F	EA	7		
58.	St	EA	3		
59.	DETENTION POND SKIMMER COMPLETE	LS	1		
60.	PERMANT GRASSING	AC	1.53		
61.	TEMP GRASSING	AC	1.53		
62.	STRAW MATTING	SF	33,700		
<i>Erosion Control Subtotal =</i>					
STRIPING AND SIGNAGE					
63.	STOP SIGN	EA	1		
64.	ONE WAY DO NOT ENTER	EA	1		
65.	H/C PARKING STRIPING AND SYMBOL	EA	12		
66.	H/C SIGN	EA	12		
67.	4" WHITE PARKING SPACE STRIPING	LF	1,262		
68.	4" WHITE BUS PARKING SPACE STRIPING	LS	1		
<i>Striping and Signage Subtotal =</i>					
MISCELLANEOUS					
69.	BLACK VINYL COATED CHAIN LINK FENCE	LF	461		
70.	12' WIDE CHAIN LINK DOUBLE SWING GATE	LS	1		
71.	IRRIGATION SYSTEM (PER PLANS)	LS	1		
72.	LANDSCAPING, SHRUBS AND SOD (PER PLANS)	LS	1		
<i>Miscellaneous Subtotal =</i>					
TOTAL CIVIL BASE BID =					

Total Civil Base Bid to be entered into 'CIVIL' line item in Bid Form (Page BF-4, Paragraph 5.01)

Item	Description	Unit	Quantity	Unit Price	Item Total
ALTERNATE 1 (ADDITIONAL PARKING AND CIRCULAR DROPOFF)					
1.	MODULAR BLOCK WALL	SF	6,615		
2.	LIGHT DUTY ASPHALT (ADDITIONAL)	SY	2,763		
3.	CONCRETE (FLATWORK)	SF	1,453		
4.	24" CURB AND GUTTER	LF	726		
5.	GRADING	LS	1		
6.	4' WHITE STRIPING	LF	468		
7.	WHEEL STOPS	EA	26		
8.	BLACK VINYL COATED CHAIN LINK FENCE	LF	570		
9.	12" DIP CLASS 350 WATER MAIN	LF	372		
10.	12" DIP 45 DEGREE M.J. BEND WITH CONCRETE BLOCKING AND M.J. RESTRAINTS	EA	4		
11.	ASPHALT DEMO (VARIOUS THICKNESSES)	SF	140		
12.	SAW CUT (VARIOUS THICKNESSES)	LF	70		
13.	SERVICE CONNECTION	EA	1		
14.	12" X 12" X 8" M.J. TEE WITH CONCRETE BLOCKING AND M.J. RESTRAINTS	EA	1		
15.	8" M.J. GATE VALVE	EA	1		
16.	12" M.J. SLEEVE (IF NEEDED)	EA	1		
17.	8" M.J. SLEEVE	EA	1		
18.	DISENFECTION AND TESTING	LS	1		
19.	FIBERGLASS MARKERS	EA	3		
			Alternate 1 Subtotal =		

Alternate 1 Subtotal to be entered into 'Alternate 1' line item in Bid Form under 'ALTERNATES' (Page BF-4, Paragraph 5.01)