



# Addendum

June 14, 2023

PKMR – 22.637

PROJECT: KCK Harmon High School  
Electrical Upgrades

Notice to Contractor:

The following described changes, corrections, clarifications, deletions, additions and approvals for the Contract Documents, which comprise of Addendum No. 1, are hereby made a part of the Contract Documents dated May 8, 2023, and shall govern in the performance of the Work. The contractor shall acknowledge receipt of this Addendum.

1. A BPU approved meter section shall be added to the 3000a main switch section and BPU meter shall be located in the new secondary feeders from the transformer.
2. BPU may elect to replace the existing 2000KVA transformer to remain. BPU is responsible for all reconnections of primary feeders and will leave both primary feeds to the building and loop through the remaining or replaced transformer for cable redundancy. Contractor shall coordinate with BPU prior to routing new secondaries if BPU elects to replace the 2000KVA transformer with a smaller transformer.
3. Panelboard Main Circuit Breakers
  - a. LD-1 shall be provided with a 100A MCB
  - b. LA shall be provided with 50A MCB
  - c. GL shall be provided with 50A MCB in lieu of 100A.

**END OF ADDENDUM**