

21-30 VIEWSONIC INTERACTIVE PANELS SPECIFICATIONS

Jones County School System seeks to enter into a contract for FY21 for a company to provide Viewsonic Interactive Panels and installation. The focus of this eRFP will be on projects at all schools since there is a need. Proposed pricing for this project shall be in effect for the term of the contract, which will expire on 6/30/2021 for additional projects that the system chooses to add.

PRODUCT SPECIFICATIONS:

Viewsonic IFP7550- Gen 3 Interactive flat panels with wireless network card, wall mount, and 5 year warranty.

No substitutions will be accepted for continuity of product reasons.

CONTRACTOR WILL:

- Remove existing interactive whiteboard, projector, projector mount, and cabling.
- Mount panel on wall at designated height.
- Install surface mount raceway, box, and wall plate (HDMI, Ethernet RJ-45, 3.5 mm audio) at teacher desk location.
- Install surface mount raceway at panel location.
- Install cables (HDMI, Ethernet, VGA) from panel location to wall plate location.
- Install 3.5 mm audio cable from teacher desk location to existing speaker mounted in ceiling grid.
- Be responsible for removal of all trash debris off of system property. Vendor cannot use the compactor or any roll offs on the system property.

CURRENT PROJECT INFORMATION:

21 Interactive panels will be placed throughout the system. Provided with as part of the specifications document will be folders for each school with installation instructions, room lay out map and location pictures.