



KNOXVILLE'S COMMUNITY DEVELOPMENT CORPORATION (KCDC) WESTERN HEIGHTS PHASE 2 INFRASTRUCTURE DEMOLITION

PREPARED FOR:
KNOXVILLE'S COMMUNITY DEVELOPMENT CORPORATION
DECEMBER 2023




U.S.G.S. MAP

USGS TOPOGRAPHIC MAP
KNOXVILLE, TN
N.T.S.



VICINITY MAP

N.T.S.



Sheet List Table	
Sheet Number	Sheet Title
C000	COVER SHEET
C001	GENERAL NOTES
C100	EXISTING CONDITIONS & DEMOLITION PLAN
C900	INITIAL EPSC PLAN
C901	FINAL EPSC PLAN
C902	EPSC PLAN DETAILS

REVISION RECORD

NO. DATE DESCRIPTION

CEE
Civil & Environmental Consultants, Inc.
2704 Cherokee Farm Way - Suite 101 - Knoxville, TN 37920
Ph: 865.977.9997 - Fax: 865.977.9919
www.ceecinc.com

KNOXVILLE COMMUNITY DEVELOPMENT CORPORATION (KCDC)
WESTERN HEIGHTS PHASE 2 INFRASTRUCTURE DEMOLITION
KNOXVILLE TN, 37921

UTILITY COMPANIES

WATER & WASTE WATER SERVICE
KUB NEW SERVICES DEPARTMENT CS26
4505 MIDDLEBROOK PIKE,
KNOXVILLE, TN 37921
PHONE: (865) 558-22294
CONTACT: TIM RIDENHOUR
EMAIL: TIMOTHY.RIDENOUR@KUB.ORG

ELECTRIC
KUB NEW SERVICES DEPARTMENT CS26
4505 MIDDLEBROOK PIKE,
KNOXVILLE, TN 37921
PHONE: (865) 558-2294
CONTACT: TIM RIDENHOUR
EMAIL: TIMOTHY.RIDENOUR@KUB.ORG

ENGINEER

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.
2704 CHEROKEE FARM WAY, STE. 101
KNOXVILLE, TN 37920
PH: (865) 977-9997
CONTACT: ADAM WILSON, PE.

REVIEWING AGENCY

CITY OF KNOXVILLE ENGINEERING DEPARTMENT
400 MAIN ST. SUITE 475, P.O. BOX 1631
KNOXVILLE, TN 37901
PH: (865)215-2148
CONTACT: JOSHUA FRERICHS, PE.

OWNER/DEVELOPER

KNOXVILLE'S COMMUNITY DEVELOPMENT CORPORATION (KCDC)
901 N. BROADWAY
KNOXVILLE, TENNESSEE 37917
PHONE: 865-403-1169
EMAIL: JHATFIELD@KCDC.ORG
CONTACT: JIM HATFIELD

PROPERTY INFORMATION

TOTAL ACREAGE: ± 28.74 ACRES
ZONING: RN-5 (GENERAL RESIDENTIAL NEIGHBORHOOD ZONING DISTRICT)
REZONING TO C-N (NEIGHBORHOOD COMMERCIAL) IS PENDING
PROPOSED USE: MULTI-FAMILY RESIDENTIAL
PARCEL ID'S: 094BC002, 094BC004, 094BC003, 094BC00201
ADDRESSES: 1500 FORT PROMISE DR, 1331 W. OLDHAM AVE, 1203 W OLDHAM AVE, 1101 W OLDHAM AVE
CITY BLOCK: 20140
CITY WARD: 20
PARCEL NUMBERS: 2, 4, 3, 2.01
CLT MAP: 94

DRAFT

C000



COVER SHEET

DRAWING NO.:
DATE: DECEMBER 2023
DRAWN BY: AVW
CHECKED BY: AVW
PROJECT NO.: 393-385
APPROVED BY:
DRAFT

EROSION AND SEDIMENT CONTROL NOTES:

1. A SPECIFIC INDIVIDUAL SHALL BE DESIGNATED TO BE RESPONSIBLE FOR EROSION AND SEDIMENT CONTROLS ON PROJECT SITE. THIS INDIVIDUAL MUST HAVE COMPLETED THE "FUNDAMENTALS OF EROSION PREVENTION AND SEDIMENT CONTROL" COURSE OR AN EQUIVALENT COURSE.
2. REFER TO THE TENNESSEE EROSION AND SEDIMENT CONTROL HANDBOOK FOR DESIGN CRITERIA AND GUIDELINES FOR EROSION CONTROL MEASURES.
3. CLEARING AND GRUBBING MUST BE HELD TO THE MINIMUM NECESSARY FOR GRADING AND EQUIPMENT OPERATION.
4. CONSTRUCTION MUST BE SEQUENCED TO MINIMIZE THE EXPOSURE TIME OF CLEARED SURFACE AREA.
5. CONSTRUCTION STAGING AND PHASING IS CRITICAL TO REDUCING SEDIMENT RUNOFF FROM SITE.
6. EROSION CONTROL MEASURES MUST BE IN PLACE AND FUNCTIONAL BEFORE EARTH MOVING OPERATIONS BEGIN, AND MUST BE PROPERLY CONSTRUCTED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
7. ALL EROSION CONTROL MEASURES SHALL BE CHECKED TWICE WEEKLY AND AFTER EACH RAINFALL. CHECK DAILY DURING PROLONGED RAINFALL.
8. CONSTRUCTION DEBRIS MUST BE KEPT FROM ENTERING THE STORM MANAGEMENT SYSTEM.
9. STOCKPILED SOIL SHALL BE PROTECTED AND LOCATED FAR ENOUGH FROM STREAMS AND DRAINAGEWAYS SO THAT RUNOFF CANNOT CARRY SEDIMENT DOWNSTREAM.
10. VEGETATIVE GROUND COVER SHALL NOT BE DESTROYED, REMOVED OR DISTURBED MORE THAN 10 CALENDAR DAYS PRIOR TO GRADING.
11. TEMPORARY SOIL STABILIZATION WITH APPROPRIATE ANNUAL VEGETATION IS REQUIRED WHEN GRADING OPERATIONS ARE TEMPORARILY HALTED FOR OVER 14 DAYS AND ON SOIL STOCKPILES.
12. PERMANENT SOIL STABILIZATION WITH PERENNIAL VEGETATION IS REQUIRED WHEN GRADING OPERATIONS ARE COMPLETE AND/OR CONSTRUCTION OPERATIONS WILL NOT IMPACT THE DISTURBED AREA. CONTRACTOR SHALL INSPECT THE SITE PERIODICALLY TO REPAIR AND RE-ESTABLISH VEGETATION TO DAMAGED AREAS.
13. STAKED AND ENTRENCHED SILT FENCE MUST BE INSTALLED ALONG THE BASE OF ALL FILLS AND CUTS, ON THE DOWNHILL SIDES OF STOCKPILED SOIL, AND ALONG STREAM BANKS IN CLEARED AREAS TO PREVENT EROSION INTO STREAMS. SILT FENCE MAY BE REMOVED AT THE BEGINNING OF THE WORK DAY, BUT MUST BE REPLACED AT THE END OF THE WORK DAY OR PRIOR TO FORECASTING RAIN EVENTS.
14. WHERE APPROPRIATE, SURFACE WATER FLOWING TOWARD CONSTRUCTION AREA SHALL BE DIVERTED AROUND THE CONSTRUCTION AREA USING DIKES, TO REDUCE EROSION POTENTIAL.
15. ALL ROCK SHALL BE CLEAN, HARD ROCK CONTAINING NO SAND, DUST, OR ORGANIC MATERIAL.
16. CONTRACTOR SHALL MAINTAIN SILT FENCES AND OTHER EROSION CONTROL DEVICES FOR THE DURATION OF THE PROJECT, TO ENSURE EFFECTIVENESS, UNTIL ACCEPTED BY THE OWNER. AT NO ADDITIONAL EXPENSE TO THE OWNER, IF CONSTRUCTION ACTIVITIES CEASE DUE TO WEATHER RELATED CAUSES, THEN THE CONTRACTOR WILL ENSURE THAT THE SITE IS PROPERLY STABILIZED AND ALL EROSION CONTROL DEVICES ARE MAINTAINED AND FUNCTIONAL DURING THOSE PERIODS OF INACTIVITY.
17. CONSTRUCTION EXIT - CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION EXIT PRIOR TO ANY EARTHWORK OPERATIONS. CONSTRUCTION EXIT SHALL BE LOCATED AS SHOWN. CONSTRUCTION EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD TO PUBLIC RIGHTS-OF-WAYS. ALL MATERIAL SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES OR SITE ONTO ADJACENT ROADWAYS SHALL BE REMOVED IMMEDIATELY FROM THE ROADWAY.
18. CONTRACTOR IS RESPONSIBLE FOR CLEANING OUT AND PROPER DISPOSAL OF ALL DEBRIS WITHIN THE STORM DRAINAGE STRUCTURES, INCLUDING SILT FROM FLUMES, PIPES, ECT., PRIOR TO COMPLETION OF THE PROJECT.
19. MEASURES SHOWN FOR SEDIMENT AND EROSION CONTROL REPRESENT THE MINIMUM ANTICIPATED. ADDITIONAL PROTECTION SHALL BE PROVIDED AS NECESSARY THAT WILL PREVENT SEDIMENT FROM LEAVING THE SITE DUE TO UNFORESEEN CONDITIONS OR ACCIDENTS.
20. THE GRADING CONTRACTOR AND BUILDING CONTRACTOR WILL REFRAIN FROM DOING ANY WORK OUTSIDE OF THE DELINEATED LIMITS OF DISTURBANCE.
21. ROADS SHALL BE STABILIZED BY APPLYING STONE ONCE SUBGRADE ELEVATION IS ACHIEVED.
22. ALL SILT FENCE IS TO BE TYPE A EXCEPT WHERE SPECIFIED DIFFERENTLY.
23. EROSION CONTROL MATTING TO BE JUTE MESH (OR APPROVED EQUAL) AND INSTALLED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.

**DETAIL 900
EPSC GENERAL NOTES**
N.T.S.



PERMANENT SEEDING MIXTURES

SEEDING DATES	GRASS SEED	PERCENTAGES
FEBRUARY 1 TO JULY 1	KENTUCKY 31 FESCUE	88%
	ENGLISH RYE	12%
JUNE 1 TO AUGUST 15	KENTUCKY 31 FESCUE	60%
	ENGLISH RYE	25%
	GERMAN MILLET	15%
AUGUST 1 TO DECEMBER 1	KENTUCKY 31 FESCUE	70%
	ENGLISH RYE	20%
	WHITE CLOVER	10%
DECEMBER 1 TO FEBRUARY 1	KENTUCKY 31 FESCUE	83%
	ENGLISH RYE	17%

SOURCE: TDOT STANDARDS SPECIFICATIONS

TEMPORARY SEEDING MIXTURES

SEEDING DATES	GRASS SEED	PERCENTAGES
JANUARY 1 TO MAY 1	ITALIAN RYE	50%
	SUMMER OATS	50%
MAY 1 TO JULY 15	SUDAN-SORGHURM	100%
MAY 1 TO JULY 15	STARR MILLET	100%
JULY 15 TO JANUARY 1	BALBOA RYE	67%
	ITALIAN RYE	33%

SOURCE: TDOT STANDARDS SPECIFICATIONS

**DETAIL 903
SEEDING CHART**
N.T.S.

NO.	DATE	REVISION RECORD	DESCRIPTION

CEE
Civil & Environmental Consultants, Inc.
2704 Cherokee Farm Way - Suite 101 - Knoxville, TN 37920
Ph: 865.977.9997 - Fax: 865.977.9919
www.ceeinc.com

**KNOXVILLE COMMUNITY
DEVELOPMENT CORPORATION (KCDC)
WESTERN HEIGHTS PHASE 2 INFRASTRUCTURE
DEMOLITION
KNOXVILLE TN, 37921**

EPSC PLAN DETAILS

DRAWING NO.: **C903**

DATE: DECEMBER 2023
DRAWN BY: ESS
CHECKED BY: AVW
PROJECT NO.: 393-285
APPROVED BY: DRAFT

DRAFT