FINAL PLAN SIGNATURES

DATE: January 18, 2022

TO: Amy Pflaum, County Standards Engineer, DES

Kamal 'Nick' Taktak, Construction Management Supervisor, DES

Dave Hundelt, Planning Supervisor, WSS Bureau, DES

Dennis Leach, Deputy Director, Transportation and Development, DES John Mir, Project Manager, Facilities Design & Construction Bureau, DES

FROM: Sara Buckley, Design Engineer

PROJECT: SLT1 - NORTHSIDE SALT STORAGE SITE

SE CORNER OF OLD DOMINION DR & 26TH ST N

ATTACHMENT: FINAL DESIGN PLAN SET (26 SHEETS)

Attached you will find the final design plan for the above-referenced project. Please conduct a final review of the set to confirm all the comments have been addressed. Once your final review is complete, please sign your name in your designated space on the signature block below, ensuring both your signature and date stay within the borders. Upon receiving all signatures, the signature block will be inserted into each sheet of the final design plan set to be included in the construction documents.

SEAL SOLOMON W SHIKUR Lic. No. 44276 1/18/2022	A A A A A A A A A A A A A A A A A A A
APPROVALS	DATE
Amy Pflaum QUALITY CONTROL ENGINEER	01/18/22
CONSTRUCTION MANAGEMENT	<u>1/20/22</u> T SUPERVISOR
WATER, SEWER, STREETS BUF	1.21.2022 REAU CHIEF
Dennis W. Leach TRANSPORTATION DIRECTOR	01/27/22
John Mir PROJECT MANAGER	1/27/22

Reviewing Bureau/Agency	Reviewer	Review Completed Date
TE&O (Traffic Signal, MOT Plan, Pavement Markings and Signage	Nazia Ahzan	12/21/2021
Transit	Diane Trent/Mark Mainardi	12/09/2021
Water, Sewer, Streets	Jon Lawler	1/18/2022
DPR Forestry and Landscaping	Vincent Verweij	12/23/2021
Engineering Bureau	Amy Pflaum	12/15/2021
Transportation Planning	Allison Bullock	12/09/2021
Facilities Design & Construction	John Mir	12/09/2021
OSEM	Christine Simpson	12/13/2021
DPR Planning and Development	Walter Gonzalez	12/16/2021
Development Services	Diana McColgan	12/09/2021
Construction	Mannan Qureshi	1/4/2022

For 100% Signature Submissions only: I certify that all required approvals (LDA, WMATA, VDOT, TEO, etc) have been secured.

Design Team Supervisor

NOTE: DO NOT FORWARD. PLEASE RETURN THE PLAN SET AND THIS SIGNATURE SHEET TO SARA BUCKLEY.


ARLINGTON **VIRGINIA**

ENGINEER DEPARTMENT OF **ENVIRONMENTAL SERVICES**

WWW.ARLINGTONVA.US


FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

OWNER DES/OD/WSS CONTRACTOR TO BE DETERMINED LOCATION MAP



ARLINGTON

DEPARTMENT OF ENVIRONMENTAL SERVICES



APPROVALS

OJECT MANAGER

REVISIONS

GENERAL NOTES:

SE CORNER OF OLD DOMINION DR & 26TH ST N

NORTHSIDE SALT STORAGE SITE

GENERAL CONSTRUCTION NOTES

PROJECT NUMBER: SLT1

ALL CONSTRUCTION WORK FOR THIS PROJECT SHALL CONFORM TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, CONSTRUCTION STANDARDS AND SPECIFICATIONS, AND WHERE APPLICABLE THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) ROAD AND BRIDGE SPECIFICATIONS, AND ROAD AND BRIDGE STANDARDS. THE LATEST EDITIONS OF EACH RELEVANT MANUAL SHALL BE USED.

CONSTRUCTION DRAWINGS FOR:

- ALL CONSTRUCTION AND WORK ACTIVITIES SHALL COMPLY WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND ALL OTHER RELEVANT WORK SAFETY REQUIREMENTS, LATEST EDITIONS.
- 3. THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT OFFICER OF ANY DISCREPANCIES BETWEEN ACTUAL FIELD CONDITIONS AND THE APPROVED PLANS.
- 4. THE CONTRACTOR SHALL CONTACT "MISS UTILITY" AT 811 FOR MARKING THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES (i.e. WATER, SEWER, GAS, TELEPHONE, ELECTRIC, AND CABLE TV) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION OR CONSTRUCTION. THE CONTRACTOR IS REQUIRED TO IDENTIFY AND PROTECT ALL OTHER UTILITY LINES FOUND IN THE WORK SITE AREA BELONGING TO OTHER OWNERS THAT ARE NOT MEMBERS OF "MISS UTILITY". PRIVATE WATER, SEWER AND GAS LATERALS WILL NOT BE MARKED BY MISS UTILITY OR THE COUNTY. THE CONTRACTOR SHALL LOCATE AND PROTECT THESE SERVICES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LAYING OUT THE WORK AND SHALL RETAIN A PROFESSIONAL LAND SURVEYOR LICENSED IN THE COMMONWEALTH OF VIRGINIA TO PROVIDE ALL NECESSARY CONSTRUCTION LAYOUTS AND ESTABLISH ALL CONTROL LINES, GRADES, AND ELEVATION DURING CONSTRUCTION. THE CONTRACTOR SHALL SUBMIT A COPY OF ALL CUT SHEETS FOR REVIEW, PER THE SPECIFICATIONS. THE COST OF ALL NECESSARY SURVEYING SERVICES SHALL BE CONSIDERED INCIDENTAL TO THE WORK AND, UNLESS OTHERWISE SPECIFIED, THE COST SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS ARE FROM BEST AVAILABLE RECORDS AND SHALL BE CONSIDERED TO BE APPROXIMATE. WHEN CONSTRUCTION ACTIVITY REACHES IN PROXIMITY TO EXISTING UTILITIES, THE TRENCH(ES) SHALL BE OPENED A SUFFICIENT DISTANCE AHEAD OF THE WORK OR TEST PITS SHALL BE MADE TO VERIFY THE EXACT LOCATION AND INVERTS OF THE UTILITY TO ALLOW FOR POSSIBLE CHANGES IN THE LINE OR GRADE AS DIRECTED BY OFFICER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE EXISTING UTILITIES AND THE RELATED STRUCTURES. ALL EXISTING UTILITY SYSTEMS SHALL BE PROTECTED TO PREVENT DAMAGE DURING THE CONTRACTOR'S OPERATIONS. ANY SYSTEM DAMAGED SHALL BE PROMPTLY REPAIRED AT NO COST TO THE OWNER.
- EXISTING MANHOLE FRAMES, COVERS, VALVE BOXES, AND OTHER APPURTENANCES SHALL BE ADJUSTED TO THE FINAL GRADE OR REPLACED, AS NECESSARY. UNLESS OTHERWISE SPECIFIED, THE COST FOR THIS SHALL BE CONSIDERED INCIDENTAL TO THE WORK, AND SHALL BE INCORPORATED INTO THE COSTS FOR RELEVANT ITEMS.
- THE CONTRACTOR SHALL PROVIDE ADA COMPLIANT ACCESS THROUGH OR AROUND THE SITE AT ALL TIMES AND SHALL ENSURE THE SAFETY OF ALL THOSE PASSING THROUGH OR ADJACENT TO THE SITE.
- 9. ALL SIDEWALK AND CURB AND GUTTER DEMOLITION SHALL BEGIN AND END AT THE CONSTRUCTION JOINT NEAREST TO THE DEPICTED DEMOLITION EXTENTS WITH A NEAT SAWCUT LINE TO FULL DEPTH OF PAVEMENT SECTION.

STORMWATER AND ENVIRONMENTAL PROTECTION

10. THE CONTRACTOR SHALL CONFINE ALL ACTIVITIES AT THE SITE ASSOCIATED WITH CONSTRUCTION ACTIVITIES, TO INCLUDE STORAGE OF EQUIPMENT AND OR MATERIALS, ACCESS TO THE WORK, FORMWORK, ETC. TO WITHIN THE DESIGNATED LIMITS OF DISTURBANCE (LOD).

TREE PROTECTION

11. TREES SHALL BE PROTECTED PER THE REQUIREMENTS OF ARLINGTON PARKS & RECREATION STANDARD.

TRAFFIC CONTROL

- 12. CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER AT LEAST 3 WORKING DAYS PRIOR TO DISTURBING ANY EXISTING, OR INSTALLING ANY NEW, TRAFFIC SIGNS, SIGNALS, OR OTHER TRAFFIC CONTROL
- 13. THE CONTRACTOR SHALL PREMARK THE LAYOUT OF ANY PERMANENT TRAFFIC CONTROL STRIPING, INDICATING THE PROPOSED LOCATION AND TYPE OF MARKING TO BE INSTALLED. THE PREMARKING MAY CONSIST OF TYPE D TAPE, CHALK, OR LUMBER CRAYONS, THE CONTRACTOR SHALL ALLOW 3 WORKING DAYS FOR THE INSPECTION AND APPROVAL OF THE PREMARKINGS PRIOR TO PLACING THE
- 14. THE CONTRACTOR SHALL SUBMIT ANY REQUESTS FOR TEMPORARY "NO PARKING" RESTRICTIONS TO THE PROJECT OFFICER AT LEAST 5 BUSINESS DAYS PRIOR TO THE DESIRED ONSET OF RESTRICTIONS. PRIOR TO A REQUEST FOR THE REMOVAL OF ACCESS TO ANY ADA PARKING SPACE THE CONTRACTOR MUST HAVE MADE PROVISION FOR ALTERNATIVE ADA PARKING AS INDICATED ON THE APPROVED PLAN OR AS DIRECTED BY THE PROJECT OFFICER.
- 15. WHEN THE APPROVED PLAN CALLS FOR THE REMOVAL OF ANY PARKING METER THE CONTRACTOR MUST MAKE A REQUEST TO THE PROJECT OFFICER AT LEAST ONE WEEK IN ADVANCE OF THE DESIRED REMOVAL. THE PROJECT OFFICER WILL THEN COORDINATE THE PARKING METER REMOVAL WITH TRAFFIC ENGINEERING AND OPERATIONS.
- 16. THE CONTRACTOR SHALL PRESERVE ALL BUS STOPS, INCLUDING MAINTAINING ADEQUATE ACCESSIBILITY THROUGH AND ADJACENT TO THE CONSTRUCTION FOR BUSES AND THEIR PASSENGERS. THE CONTRACTOR SHALL NOT CLOSE, RELOCATE, OR OTHERWISE MODIFY A BUS STOP WITHOUT PRIOR REQUEST OF THE PROJECT OFFICER. ANY RELOCATION OR CLOSURE OF A BUS STOP SHALL REQUIRE AT LEAST FOUR WEEKS ADVANCE NOTICE FOR COORDINATION WITH THE COUNTY'S BUS STOP COORDINATOR - 703-228-3049.
- 17. WHEN CONDITIONS WARRANT DUE TO TRAFFIC VOLUMES, PATTERNS, OR SPECIAL EVENTS, THE COUNTY MAY SUSPEND OR OTHERWISE DIRECT THE CONTRACTOR'S ACTIVITIES TO PROTECT THE PUBLIC AND OR THE COUNTY'S TRANSPORTATION NETWORK.

WATER DISTRIBUTION, STORM AND SANITARY SEWER SYSTEMS

- 18. UNLESS OTHERWISE DIRECTED, CONTRACTORS ARE EXPRESSLY PROHIBITED FROM OPERATING ANY WATER VALVES OR APPURTENANCES. CONTRACTORS SHALL SUBMIT ALL REQUESTS FOR VALVE OPERATIONS TO THE PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED OPERATION.
- 19. IN THE EVENT OF A WATER OR SEWER EMERGENCY, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE COUNTY'S WATER CONTROL CENTER AT 703-228-6555 AND THE PROJECT OFFICER.
- 20. THE CONTRACTOR SHALL COORDINATE ALL UTILITY SHUTOFFS, DISCONNECTS, AND/OR ABANDONMENT WITH UTILITY OWNER AND PROJECT OFFICER AT LEAST 1 WEEK IN ADVANCE OF THE REQUIRED

FIRE DEPARTMENT NOTES:

- 21. ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 22. ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- 23. IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION.

Sheet List Table

COVER SHEET

DETAILS - 1

C000.1

C002.1

C002.2	DETAILS - 2
C006.1	LEGEND
C011.1	EXISTING CONDITIONS PLAN
C021.1	DEMOLITION PLAN
C031.1	EROSION AND SEDIMENT CONTROL PLAN PHASE 1
C031.2	EROSION AND SEDIMENT CONTROL PLAN PHASE 2
C031.3	TREE PROTECTION AND REMOVAL PLAN
C031.4	TREE INVENTORY
C031.5	TREE PLANTING PLAN
C032.1	EROSION AND SEDIMENT CONTROL NOTES
C032.2	EROSION AND SEDIMENT CONTROL NOTES AND DETAILS
C035.1	SWPPP
C041.1	SITE PLAN
C041.2	GRADING PLAN
C045.1	GEOMETRIC CONTROL PLAN
C071.1	STORM SEWER DRAINAGE DIVIDES (PRE-EXISTING)
C071.2	STORM SEWER DRAINAGE DIVIDES (PROPOSED)
C073.1	STORM SEWER PROFILES
C075.1	STORM COMPUTATIONS
C082.1	SWM NOTES AND DETAILS
C083.1	SWM PLAN
C085.1	SWM CALCULATIONS
C085.2	STORMWATER DETENTION CALCULATIONS
C121.1	MAINTENANCE OF TRAFFIC PLAN

PROJECT NOTE: IF APPLICABLE, THE ON-CALL CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING THE APPROVED MOT PLAN BY THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES.

SWM #18-0199 LDA-41281

14,000 - OLD DOMINION DR BETWEEN 22ND ST N AND N GLEBE RD - 2019 - VDOT TRAFFIC STUDY

STREET CLASSIFICATION

25TH STREET NORTH - MINOR ARTERIAL

OLD DOMINION DRIVE - MAJOR ARTERIAL

POSTED SPEED OLD DOMINION DRIVE - 30 MPH 25TH STREET NORTH - 25 MPH

Ŋ THSIDI DESIGNED: SEB DRAWN: SEB CHECKED: SWS PLOTTED: JANUARY 6 2022 SCALE:

NORTHSIDE SALT STORAGE SITE SLT1

DEPARTMENT OF ENVIRONMENTAL SERVICES Director's Office

2100 Clarendon Boulevard, Suite 900, Arlington, VA 22201 TEL 703-228-3620 FAX 703-228-3594 www.arlingtonva.us

October 1, 2018

Mr. George May, P.E. Deputy Director, DES Facilities and Engineering 1400 N. Uhle Street, Suite 403 Arlington, VA 22201

Re: Temporary salt storage structure at Old Dominion Drive and 25th Street North, SWM No.18-0199

Dear Mr. May:

Your request for a partial exception to the post-construction stormwater management (SWM) requirements of Arlington County's Stormwater Management Ordinance (§60-11.A of the County Code) for the land disturbing activity related to the above-named project is approved, subject to the following conditions:

- 1. You must provide on-site detention and conveyance of stormwater to mitigate impacts from the temporary salt storage structure to adjacent properties and the downstream storm drainage system, per your approved plans.
- 2. The temporary structure shall be in place for no more than five (5) years from the date of LDA permit issuance.
- 3. The stormwater compliance calculations for the permanent development of the site shall use the existing site conditions (prior to the installation of any temporary structures) as the baseline. Your current LDA plan must show these baseline computations.

These conditions shall be reflected in the design and mitigation measures and details shown on your project's grading plan, LDA18212, before it will be approved.

In granting this exception with conditions, I have concluded that the required findings established under Section 60-11.D of the County Code have been met due to the following considerations:


• Finding (i). The exception is the minimum necessary to afford relief. The condition that the temporary use provide on-site detention and conveyance of stormwater to mitigate impacts to adjacent properties and the downstream storm drainage system satisfies this finding.


- Finding (ii). Reasonable and appropriate conditions are imposed so that the intent of the Act, the Regulations, and this chapter are preserved. The conditions imposed above satisfy this
- Finding (iii). Granting the exception will not confer any special privileges that are denied in other similar circumstances. The critical public safety function of the facility is unique. There are not other parties in similar circumstances regulated under the code. In addition, the requirements that the temporary structure be removed within five (5) years and that the permanent development use existing conditions as the baseline means that full compliance with Chapter 60 will ultimately be required.
- Finding (iv). Exception requests are not based upon conditions or circumstances that are self-imposed or self-created. The determination that the current facility is unsafe occurred in May 2018, without sufficient time to plan, design, and construct a new permanent facility before the start of the winter snow season. I have concluded that this is not a self-imposed or self-created circumstance.


In addition, although not a requirement of Chapter 60, I am noting in this letter that your landscape plan must document, in addition to the usual requirement to provide tree condition. tree removal, and tree replacement computations, the quantity of replacement trees required should any of the trees that have been pruned fail to survive. These replacement trees shall be provided with the implementation of the permanent plan.


Thank you for your efforts to work with my team to address the stormwater compliance challenges for this project. If you have any additional questions, please contact Qiangian Li at 703) 228-0129 or <u>qli@arlingtonva.us</u>.


Luis Araya, DES/DS Lisa Maher, DES/DS Qianqian Li, DES/DS Demetra McBride, DES/OSEM Jason Papacosma, DES/OSEM Julie Massie, CAO












	COUNTY METER INSTALLATION. PLUMBER SHALL NOT ENTER METER BOX.							
w	ATER SERVICE CONNECTIONS 2-INCH AND SMALLER	1 REVISIO	7/01/2020 ON & DATE					
ARLINGTON	ARLINGTON COUNTY, VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES		VING NO. V-8.0	A R	LINGTON VIRGINIA			


SERVICES WILL BE INSTALLED AFTER ALL FEES HAVE BEEN PAID AND ALL SITE


CONDITIONS FOR SETTING THE METER HAVE BEEN MET.



DEPARTMENT OF ENVIRONMENTAL SERVICES

R-1.1





ARLINGTON

VIRGINIA

DEPARTMENT OF

ENVIRONMENTAL SERVICES

FACILITIES & ENGINEERING DIVISION

ENGINEERING BUREAU

2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629

FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY


VIRGINIA - ALL RIGHTS RESERVED


olaman

SOLOMON W SHIKUR

Lic. No. 44276

C002.





DF-HOOK BOLTS

OR TIE BARS (STD.PR-2) @ 20"

C.C. (OR SPACED @ 40"

ALONG FULL 20' LENGTH)

PLAN-RAMP & MAIN LINE CONNECTION EDGE OF PAVEMENT

→ TRANSVERSE CONSTRUCTION JOINT

8' ** C

NO LAP WITHIN 8' AHEAD OF CONSTRUCTION JOINT

SECTION B-B

EXTRA BAR METHOD

BARS 6'-0" LONG CENTERED OVER LAP

SEPARATION DURING CONCRETE PLACEMENT

6'-0" LONG SYMMETRICAL WITH LAP SPLICE.

ROAD AND BRIDGE STANDARDS

REVISION DATE SHEET 2 OF 4

301.07

7/12

SECTION C-C

A WITH 36' PAVEMENT

TRANSVERSE CONSTRUCTION JOINT

IGKAUL 60)

SECTION B-B

#4 TRANSVERSE BARS AND

OR TIE BAR

BAR METHOD APPLY ONLY TO LAPS FALLING WITHIN AN AREA OF 8'BEYOND THE CONSTRUCTION JOINT.

A COPY OF THE ORIGINAL SEALED AND SIGNED DRAWING IS ON FILE IN THE CENTRAL OFFICE

8" THICK CONTINUOUSLY REINFORCED CONC. PAVE.

(STEEL BAR REINFORCEMENT)

VIRGINIA DEPARTMENT OF TRANSPORTATION

2016 ROAD & BRIDGE STANDARDS

6 CHAIRS PER 12' LANE AT 2'-3" 6 CHAIRS PER 12' LANE AT 2'-3" LONGITUDINAL CONSTRUCTION
TO BASS AT 6" CC + 1" JOINT WITH 36' PAVEMENT.

#5 BARS AT 6" C.C. ± 1" #5 BARS AT 6" C.C. ± 1"

DOUBLE LAP METHOD ** DOUBLE LAP REQUIREMENT (38") AND THE EXTRA


SECTION A-A

T# 5 LONGITUDINAL BARS

NO LAP WITHIN 8' AHEAD OF CONSTRUCTION JOINT

END LAPS OF BARS TO BE STAGGERED ON ANGLE OF 45° DESIRABLE, 30° MIN.

30" INLINE DRAIN




— 3" DIA.

WEEP HOLE


X 6" WIDTH


-- 4" DEPTH AGGR.


#68, #78 OR #8



-- 1/4":1'








ARLINGTON

VIRGINIA



-----4'-2''-----

2'-7"--

BUILDING

EASEMENT

GAS LINE

STREAM

WALL

TREE PROTECTION FENCE

WATERLINE UNDER 20"

WATERLINE OVER 20"

—— TP —— TP ——

(SIZE INCLUDED IF AVAILABLE) — #" w — #" w — #" w

— TP — TP —

NORTH ARROW

(SEE NOTE)

TEST HOLE

CURVE NUMBER

(SEE CURVE TABLE)

LINE NUMBER (SEE LINE TABLE)

ARLINGTON VIRGINIA PROPOSED FEATURE

XXXX

 $\langle XXXX \rangle$

ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY

DEPARTMENT OF

VIRGINIA - ALL RIGHTS RESERVED 70laman V

SOLOMON W SHIKUR Lic. No. 44276 1/6/2022

APPROVALS DATE Amy Pflaum 01/18/22
QUALITY CONTROL ENGINEER Odam & Kulaury CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach. 01/27/22 TRANSPORTATION DIRECTOR Oohn Mir PROJECT MANAGER 1/27/22

REVISIONS DATE

SITE STORAGE NORTHSIDE


DESIGNED: SEB DRAWN: SEB CHECKED: SWS


PLOTTED: JANUARY 6 2022


SCALE:


N/A


C006.1











_	
D BY: SBUCKL	
SBI	
	
<u>В</u>	
PLOTTE	
7	
Ą	
D/ACTIV	
Ą	
ģ	ı
5	
ESIGN	
ESI	
\Box	
Ξ.	
S	
ATA\SLT1\	
A D	
0:\D	
÷	
₽	
RY.DWG P/	
$\stackrel{\circ}{\ge}$	
Ö.	
X	
	ı
É,	
Z Z	ı
ECTION	ı
Ŋ	ı
PROT	ı
Ϋ́	ı
الس	
.5- -	

TREE#	DBH	SPECIES	CONDITION	SPECIES RATING	REPLACEMENT VALUE	REPLACEMENT	POSSIBLE FUTURE REPLACEMENT	PROPOERTY OWNERSHIP	сит	PRUNE	PRESERVE	RESERVE NOTE
T18	4"	NA	80	50	-	-		ACG	CUT	-	-	
⊺19	3"	NA	80	50	-	-		ACG	CUT	-	-	
T20	3"	NA	80	50	-	-		ACG		_	PRESERVE	
T21	3"	NA	80	50	-	-		ACG		-	PRESERVE	
T22	3"	NA	80	50	-	-		ACG	-	-	PRESERVE	
T23	3"	NA	80	50	-	-		ACG	-	-	PRESERVE	
T24	3"	NA	80	50	-	-		ACG	-	-	PRESERVE	
T25	4"	NA	80	50	-	-		ACG	-	_	PRESERVE	
T26	2"	NA	80	50	-	-		ACG	-	-	PRESERVE	
T27	na	NA	80	50	-	-		ACG	-	-	PRESERVE	
T28	2"	NA	80	50	_	-		ACG	-	_	PRESERVE	
T29	3"	NA	80	50	-	-		ACG	-	-	PRESERVE	
T30	3"	NA	80	50	-	_		ACG		-	PRESERVE	
T31	2"	NA	80	50	_	_		ACG	_	_	PRESERVE	
T33	22"	Willow Oak	65	75	_	-		ACG		<u> </u>	PRESERVE	
T34	30"	Black Locust	60		<u>-</u>	-		ACG	<u>-</u>	PRUNE	PRESERVE	
T36	14"	Pin Oak	80					ACG			PRESERVE	
					-	-			-	-	 	
T37	11"	American Elm	70	70	-	-		ACG	-	-	PRESERVE	
T38	14"	Black Locust	30	55	-	-		ACG	-	-	PRESERVE	
T38B	14"	Black Locust	30	55	-	-		ACG	-	-	PRESERVE	
T47	16"	Silver Maple	55	45	-	-		ACG	-	-	PRESERVE	
T48	18"	Siberian Elm	55	35	-	-		Private	-	-	PRESERVE	
T49	16"	Black Locust	65	55	-	-		Private	-	-	PRESERVE	
T50	24"	Silver Maple	35	45	-	-		ACG	-	PRUNE	PRESERVE	
T51	15"	Pin Oak	75	75	-	-		ACG	-	-	PRESERVE	
T52	22"	Black Locust	50	55	-	-		ACG	-	_	PRESERVE	
T53	16"	NA	80	80	-	-		ACG	-	-	PRESERVE	
T54	21"	NA	80	80	-	-		ACG	-	-	PRESERVE	
T56	18"	Black Locust	NA	-	-	-		ACG	-	PRUNE	PRESERVE	
T58	26"	Black Locust	NA	-	-	-		ACG	-	PRUNE	PRESERVE	
T59	30"	NA	NA	_	_	_		ACG	_	-	PRESERVE	
T61	3"	NA	NA	-	_	_		ACG	_	_	PRESERVE	
T62	6"	NA	NA NA	-	-	-		ACG	_	-	PRESERVE	
T65	4"	NA NA	NA	_	_	-		ACG		_	PRESERVE	
T66	4"	NA	NA NA	-	_	_		ACG		_	PRESERVE	
T67	9"	NA NA	NA NA			-		ACG			PRESERVE	
			NA NA		1					 	PRESERVE	
T67B	na 42"	NA NA	+	-	-	-		ACG	-	-	————	
T68	12"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T69	2"	NA	NA NA	-	-	-		ACG	-	-	PRESERVE	
T70	4"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T 71	4"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T72	12"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T 73	22"	NA	NA	-	-	-		ACG	-	PRUNE	PRESERVE	
T74	6"	NA	NA	•	-	-		ACG	-	-	PRESERVE	
T75	12"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T76	6"	NA	NA	-	-	-		ACG	-	_	PRESERVE	
T77	4"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T78	2"	NA	NA	-	-	-		ACG	-	-	PRESERVE	
T79	4"	NA	NA	-	-	-		ACG	-	_	PRESERVE	
T80	4"	NA	NA	_	_	_		ACG	-	_	PRESERVE	
T81	6"	NA NA	NA NA	-	_	-		ACG	_	-	PRESERVE	
T82	10"	NA NA	NA NA		1			ACG			PRESERVE	
			+	-	-	-			- CLIT	-		
#1	5" 7"	Cupressocyoaris leylandii	100					ACG	CUT	-	-	
#2		Cupressocyoaris leylandii			1			ACG	CUT	-	-	
#3	5.5"	Ulumus pumila	50					ACG	CUT	-	-	
#4	2"	Juniperus virginiana	100					ACG		PRUNE	PRESERVE	

TREE SUMMARY TABLE

TOTAL EXISTING TREES (AS OF 9/13/18): 91 TREES REMOVED FROM PROJECT FMP1: 39 TREES ADDED AFTER PROJECT FMP1: 10 EXISTING TREES (CURRENT): 66 TREES TO BE REMOVED: 5 TOTAL TREE REPLACEMENT: 5*


*SEE SHEET C031.5 - TREE PLANTING PLAN FOR TREE REPLACEMENT SCHEDULE

VIRGINIA **DEPARTMENT OF ENVIRONMENTAL SERVICES** FACILITIES & ENGINEERING DIVISION ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED SOLOMON W SHIKUR Lic. No. 44276 APPROVALS DATE QUALITY CONFROL ENGINEER

Oldan E Xulaury 1/20/22

CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach. 01/27/22 TRANSPORTATION DIRECTOR Oohn Mir PROJECT MANAGER 1/27/22 **REVISIONS** SITE NORTHSIDE DESIGNED: SEB DRAWN: SEB CHECKED: SWS PLOTTED: JANUARY 6 2022 SCALE: C031.4

ARLINGTON



EROSION AND SEDIMENT CONTROL NARRATIVE

PROJECT DESCRIPTION:

THE PROJECT IS LOCATED AT THE SOUTHEAST CORNER OF OLD DOMINION DRIVE AND 26TH STREET NORTH. THE NORTHSIDE SALT STORAGE SITE PROJECT CONSISTS OF STORMWATER QUALITY AND QUANTITY IMPROVEMENTS FOR PROJECT #LDA18212 (SWM#18-0199) WHICH WAS GRANTED A PARTIAL EXCEPTION TO THE POST-CONSTRUCTION SWM REQUIREMENTS (SEE SHEET C002.1 FOR APPROVED PARTIAL EXCEPTION LETTER). THE LIMITS OF DISTURBANCE ARE WITHIN THE EXISTING ARLINGTON COUNTY R.O.W. AND ARLINGTON COUNTY-OWNED PROPERTY. THE LIMITS OF DISTURBANCE IS 9,074 SF (0.2083 AC). THERE ARE NO PRESENT FOODPLAINS OR RESOURCE PROTECTION AREAS ON THE PROJECT SITE

EXISTING SITE CONDITIONS:

THE SITE CONSISTS OF AN EXISTING SALT STORAGE FACILITY, ASPHALT PARKING AREA AND SITE APPURTENANCE STORAGE AREA, AND TWO EXISTING GRAVEL STORMWATER DETENTION BASINS. THE PROJECT SITE IS LOCATED WITHIN THE DONALDSON RUN WATERSHED. THE EXISTING TOPOGRAPHY HAS SLOPES RANGING FROM 1% TO 10%. THERE IS AN EXISTING GRATE INLET DRAINAGE STRUCTURE LOCATED ON THE SUBJECT PROPERTY WHICH TIES INTO AN EXISTING CURB INLET LOCATED ON 25TH ROAD NORTH (AT THE CORNER OF 25TH ROAD NORTH AND 25TH STREET NORTH). THE EXISTING STORM SEWER NETWORK EVENTUALLY OUTFALLS AT DONALDSON RUN. THE CURRENT LAND COVER IS PRIMARILY IMPERVIOUS, AND ALSO FEATURES GRASSY AREAS. THE SITE HAS A HYDROLOGIC SOIL GROUP OF TYPE D SOIL, AND THE SOIL TYPE IS "4B - URBAN LAND-SASSAFRAS-NEABSCO COMPLEX".

ADJACENT PROPERTIES:

THE SUBJECT PROPERTY IS BOUND BY OLD DOMINION DRIVE, 25TH STREET NORTH, AND 25TH ROAD NORTH. SINGLE FAMILY RESIDENTIAL HOMES ARE LOCATED TO THE NORTHEAST OF THE SUBJECT PROPERTY.

CRITICAL AREAS:

THERE ARE NO STEEP SLOPES OR CRITICAL AREAS LOCATED WITHIN THE LIMITS OF DISTURBANCE.

EROSION AND SEDIMENT CONTROL MEASURES:

THE EROSION AND SEDIMENT CONTROL MEASURES FOR THIS PROJECT AREA INCLUDE CONSTRUCTION ENTRANCE, TREE PROTECTION FENCE, SILT FENCE WITH WIRE SUPPORT, AND INLET PROTECTION. INLET PROTECTION IS REQUIRED OUTSIDE THE PROJECT LIMITS WHEN/WHERE WATER FROM DISTURBED AREA

PERMANENT STABILIZATION:

ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE STABILIZED WITH GRASS, MULCH OR SOD. SEE THE PROPOSED PLANS FOR ADDITIONAL INFORMATION.

STORMWATER RUNOFF CONSIDERATIONS:

TOTAL LAND DISTURBANCE..... 9,074 SF* (0.2083 ACRES) PRE-IMPROVEMENT IMPERVIOUS AREA.... = 5,996 SF (0.1365 ACRES) POST-IMPROVEMENT IMPERVIOUS AREA... = 5,996 SF (0.1365 ACRES)

INCREASED IMPERVIOUS AREA..... N/A

*TOTAL LAND DISTURBANCE INCLUDES THE DISTURBANCE FOR PROPOSED WORK HEREIN THIS CONSTRUCTION PLAN SET. THERE IS NO INCREASE IN IMPERVIOUS AREA. PROPOSED WORK IS LIMITED TO INCLUDE STORMWATER IMPROVEMENTS.

SOILS INFORMATION:

THE FOLLOWING SOILS ARE FOUND ON SITE (SEE SOILS MAP ON SHEET C032.2 FOR LOCATION)

ERODABILITY: SOIL#: SOIL NAME: HYDROLOGIC GROUP:

URBAN LAND--SASSAFRAS-NEABSCO COMPLEX D

FLOODPLAIN AND RESOURCE PROTECTION AREA (RPA):

THERE ARE NO FLOODPLAIN OR RESOURCE PROTECTION AREAS LOCATED WITHIN THIS PROJECT SITE

EROSION & SEDIMENT CONTROL PROJECT PHASING

1. PHASE I:

- a. PRE-CONSTRUCTION MEETING WITH THE PROJECT OFFICER, CONTRACTOR, AND COUNTY INSPECTOR.
- b. INSTALL THE TEMPORARY CONSTRUCTION ENTRANCE IN THE LOCATION SHOWN ON THE E&S PHASE I PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL TRUCKS EXISTING THE SITE.
- c. INSTALL PERIMETER TREE DEMARCATION FENCING IN THE FORM OF TREE PROTECTION FENCE (TP) AS SHOWN ON E&S PHASE I PLAN.
- d. PERFORM INITIAL PERIMETER CLEARING TO INSTALL REMAINDER OF PERIMETER CONTROLS SUCH AS SILT FENCE (SF), SUPER SILT FENCE (SSF), AND
- INLET PROTECTION (IP) AS PER THE PHASE I PLAN. e. SEED AND MULCH ALL EARTHEN CONTROLS.
- f. CONTACT ARLINGTON COUNTY PROJECT OFFICER FOR A PERIMETER INSPECTION PRIOR TO CLEARING THE REMAINDER OF THE SITE IN ORDER TO OBTAIN PHASE II GRADING PERMIT.
- g. CLEAR THE SITE TO THE LIMITS AS SHOWN ON THE CONSTRUCTION PLANS.

2. PHASE II:

- a. BEGIN UTILITY CONSTRUCTION, INSTALL ALL UTILITIES UNDERGROUND UTILITIES AND BEGIN SITE GRADING.
- b. INLET PROTECTION (IP) SHALL BE PROVIDED AT STORM DRAIN INLETS AS THEY ARE CONSTRUCTED.
- c. ONCE THE SITE IS BOUGHT TO NEAR FINAL GRADE, AND THE UTILITY CONSTRUCTION IS COMPLETE, COMMENCE CONSTRUCTION OF CURB & GUTT STREET, SIDEWALKS, AND OTHER IMPROVEMENTS
- d. THE CONTROL MEASURES MAY NOT BE REMOVED UNTIL ALL OF THE DISTURBED AREAS HAVE BEEN STABILIZED AND ONLY AS APPROVED AND DIRECTED BY THE INSPECTOR.
- RUNOFF SHALL BE TREATED WITH SILT FENCE AND INLET PROTECTION PRIOR TO ENTERING MAJOR STORM SEWER SYSTEMS.

EROSION AND SEDIMENT CONTROL MEASURES

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND THE ARLINGTON COUNTY EROSION AND SEDIMENT CONTROL ORDINANCE. THE MINIMUM STANDARDS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE ADHERED TO UNLESS OTHERWISE WAIVED OR APPROVED BY A VARIANCE.

1. STRUCTURAL PRACTICES

- a. TEMPORARY CONSTRUCTION ENTRANCE VESCH 3.02
- a.a. A TEMPORARY CONSTRUCTION ENTRANCE WITH A WASH RACK SHALL BE INSTALLED AT THE EXISTING ACCESS POINT TO THE SITE. DURING MUDDY CONDITIONS, DRIVERS OF CONSTRUCTION VEHICLES WILL BE REQUIRED TO WASH THEIR WHEELS BEFORE RE-ENTERING THE LOCAL
- a.b. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC WASHING OF THE MATS AND/OR REPLACEMENT OF WOOD CHIPS AS NECESSARY.
- a.c. ALL MATERIALS SPILLED, DROPPED, WASHED, OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED
- a.d. THE USE OF WATER TRUCKS TO REMOVE MATERIALS DROPPED, WASHED, OR TRACKED INTO ROADWAYS WILL NOT BE PERMITTED UNDER ANY
- CIRCUMSTANCES. b. SILT FENCE - VESCH 3.05
- b.a. SILT FENCE WILL BE INSTALLED WITH THE E&S PLAN TO FILTER RUNOFF FROM DISTURBED AREAS. RUNOFF SHALL NOT BE DIRECTED PARALLEL TO THE INSTALLATION OF SILT FENCE.
- b.b. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.
- b.c. CLOSE ATTENTION SHALL BE PAID TO THE REPAIR OF DAMAGED SILT FENCE RESULTING FROM UNDERCUTTING
- b.d. SHOULD THE FABRIC ON A SILT FENCE DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE, THE FABRIC SHALL BE REPLACED IMMEDIATELY.
- b.e. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER.
- b.f. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SILT FENCE IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, THEN PREPARED AND SEEDED.
- c. TEMPORARY DIVERSION DIKE VESCH 3.09 c.a. A SYSTEM OF TEMPORARY DIKES, TO DIRECT FLOW INTO PROPOSED & EXISTING STORM SEWER STRUCTURES WILL BE INSTALLED AS INDICATED
- IN EROSION & SEDIMENT CONTROL PLAN.
- c.b. THE STRUCTURES SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY d. STORM DRAIN INLET PROTECTION - VESCH 3.07
- d.a. ALL EXISTING & PROPOSED STORM SEWER INLETS IN AND AROUND THE PROJECT LIMITS SHALL BE PROTECTED DURING CONSTRUCTION. SEDIMENT-LADEN WATER SHALL BE FILTERED BEFORE ENTERING THE STORM SEWER INLETS.
- d.b. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN EVENT AND REPAIRS SHALL BE MADE AS NECESSARY.
- d.c. STRUCTURES SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED. e. DEWATERING STRUCTURE - VESCH 3.26
- e.a. SEDIMENT LADEN OR TURBID WATER SHALL BE FILTERED, SETTLED OR SIMILARLY TREATED PRIOR TO DISCHARGE.
- e.b. THE FILTERING DEVICES MUST BE INSPECTED FREQUENTLY AND REPAIRED OR REPLACED ONCE THE SEDIMENT BUILD-UP PREVENTS THE

- STRUCTURE FROM FUNCTIONING AS DESIGNED.
- e.c. THE ACCUMULATED SEDIMENT WHICH IS REMOVED FROM A DEWATERING DEVICE MUST BE SPREAD ON-SITE AND STABILIZED OR DISPOSED OF AT AN APPROVED DISPOSAL SITE AS PER THE APPROVED PLAN.
- f. TREE PROTECTION VESCH 3.38
- f.a. ALL TREES ARE TO BE PROTECTED UNLESS OTHERWISE DIRECTED BY THE COUNTY INSPECTOR AND URBAN FORESTER. THE COUNTY'S URBAN FORESTER (703-228-1863) SHALL INSPECT ALL TREE PROTECTION 72 HOURS PRIOR TO THE START OF CONSTRUCTION. IN SPITE OF PRECAUTIONS, SOME DAMAGE TO PROTECTED TREES MAY OCCUR. IN SUCH CASES, THE FOLLOWING MAINTENANCE GUIDELINES SHALL BE FOLLOWED:
- f.a.a. SOIL AERATION: IF THE SOIL HAS BECOME COMPACTED OVER THE ROOT ZONE OF ANY TREE, THE GROUND SHALL BE AERATED BY PUNCHING HOLES WITH AN IRON BAR. THE BAR SHALL BE DRIVEN 1-FOOT DEEP AND THEN MOVED BACK AND FORTH UNTIL THE SOIL IS LOOSENED. THIS PROCEDURE SHALL BE REPEATED EVERY 18 INCHES UNTIL ALL OF THE COMPACTED SOIL BENEATH THE CROWN OF THE TREE HAS BEEN
- LOOSENED. f.a.b. REPAIR OF DAMAGE:
- f.a.A.a. ANY DAMAGE TO THE CROWN, TRUNK, OR ROOT SYSTEM OF ANY TREE RETAINED ON THE SITE SHALL BE REPAIRED IMMEDIATELY
- f.a.A.b. WHENEVER MAJOR ROOT OR BARK DAMAGE OCCURS, REMOVE SOME FOLIAGE TO REDUCE THE DEMAND FOR WATER AND NUTRIENTS DAMAGED ROOTS SHALL IMMEDIATELY BE CUT OFF CLEANLY INSIDE THE EXPOSED OR DAMAGED AREA. CUT SURFACES SHALL BE
- PAINTED WITH APPROVED TREE PAINT, AND MOIST PEAT MOSS, BURLAP, OR TOPSOIL SHALL BE SPREAD OVER THE EXPOSED AREA. TO TREAT BARK DAMAGE, CAREFULLY CUT AWAY ALL LOOSENED BARK BACK INTO THE UNDAMAGED AREA, TAPER THE CUT AT THE TOP AND BOTTOM, AND PROVIDE DRAINAGE AT THE BASE OF THE WOUND.
- ALL TREE LIMBS DAMAGED DURING CONSTRUCTION OR REMOVED FOR ANY OTHER REASON SHALL BE CUT OFF ABOVE THE COLLAR AT THE PRECEDING BRANCH JUNCTION.
- CARE FOR SERIOUS INJURIES SHALL BE PRESCRIBED BY A FORESTER OR A TREE SPECIALIST.
- f.b. FERTILIZATION: BROADLEAF TREES THAT HAVE BEEN STRESSED OR DAMAGED SHALL RECEIVE A HEAVY APPLICATION OF FERTILIZER TO AID THEIR RECOVERY.
- f.b.a. TREES SHALL BE FERTILIZED IN THE LATE FALL (AFTER OCTOBER 1) OR THE EARLY SPRING (FROM THE TIME FROST IS OUT OF THE GROUND UNTIL MAY 1). FALL APPLICATIONS ARE PREFERRED, AS THE NUTRIENTS WILL BE MADE AVAILABLE OVER A LONGER PERIOD OF TIME.
- f.b.b. FERTILIZER SHALL BE APPLIED TO THE SOIL OVER THE FEEDER ROOTS. IN NO CASE SHALL IT BE APPLIED CLOSER THAN 3 FEET TO THE TRUNK. THE ROOT SYSTEM OF CONIFERS EXTENDS SOME DISTANCE BEYOND THE DRIP LINE. INCREASE THE AREA TO BE FERTILIZED BY ONE FOURTH THE AREA OF THE CROWN.
- f.b.c. FERTILIZER SHALL BE APPLIED USING APPROVED FERTILIZATION METHODS AND EQUIPMENT.
- f.b.d. FORMULATIONS AND APPLICATION RATES SHALL CONFORM TO THE GUIDELINES GIVEN IN TABLE 3.38-A OF VESCH.

2. VEGETATIVE PRACTICES

- a. TOPSOILING (STOCKPILE) VESCH 3.30
- a.a. TOPSOIL WILL BE STRIPPED FROM AREAS TO BE GRADED AND STOCKPILED FOR LATER USE. STOCKPILE LOCATIONS MAY HAVE TO BE LOCATED OFF-SITE AND ARE TO BE STABILIZED WITH TEMPORARY VEGETATION. PRIOR TO LAND-DISTURBING ACTIVITIES, THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY E&S PLAN (IF THE STOCKPILE IS LOCATED OFF-SITE). THIS SUPPLEMENTAL PLAN WOULD HAVE TO BE APPROVED BY THE PLAN APPROVING AUTHORITY BEFORE ANY OFF-SITE ACTIVITY COMMENCES.
- b. TEMPORARY SEEDING VESCH 3.31
- b.a. ALL DENUDED AREAS, WHICH WILL BE LEFT DORMANT FOR EXTENDED PERIODS OF TIME SHALL BE SEEDED WITH FAST GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING. SELECTION OF THE SEED MIXTURE WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED.
- b.b. SEE SHEET III-288 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH) FOR ALLOWABLE PLANTING MATERIAL, SEEDING RATES, AND DATES. THE PLANTING REQUIREMENTS OF THE "SOUTH" SHALL BE FOLLOWED. LIMING SHALL BE BASED ON TABLE 3.31-A OF VESCH. FERTILIZERS SHALL BE APPLIED AS 600 LB/ACRE. THE FERTILIZER SHALL BE INCORPORATED INTO THE TOP 2-4" OF SOIL. SEED SHALL BE EVENLY APPLIED AND SMALL GRAINS SHALL BE PLANTED NO MORE THAN 1.5" DEEP. SEEDING MADE IN FALL FOR WINTER COVER AND DURING HOT
- SUMMER MONTHS SHALL BE MULCHED. c. EROSION CONTROL BLANKET AND MULCHING - VESCH 3.36 AND 3.35
- c.a. EROSION CONTROL BLANKETS WILL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT THE SLOPES FROM RILL AND GULLY EROSION AND TO ALLOW SEED TO GERMINATE PROPERLY. MULCH (STRAW OR FIBER) WILL BE USED ON RELATIVELY FLAT AREAS AND WILL BE APPLIED AS A SECOND STEP IN SEEDING OPERATION.
- d. DUST CONTROL VESCH 3.39
- d.a. DUST SHALL BE CONTROLLED USING A VARIETY OF METHODS SUCH AS VEGETATIVE COVER, MULCH, TILLAGE, IRRIGATION, SPRAY-ON ADHESIVES, STONE BARRIERS, AND CALCIUM CHLORIDE. THE IMPLEMENTATION OF THE DUST CONTROL METHODS SHALL BE INSTALLED PER SECTION 3.39 OF
- e. PERMANENT SEEDING VESCH 3.32
- e.a. SINCE THE SUBJECT SITE IS LOCATED WITHIN THE COASTAL PLAIN AREA OF VIRGINIA, SHEET III-304 OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK SHALL BE FOLLOWED FOR FINAL SEEDING MATERIAL, SEEDING RATES, AND DATES OF APPLICATION
- f. SODDING VESCH 3.33
- f.a. SODDED AREAS SHALL BE BROUGHT TO FINAL GRADE IN ACCORDANCE WITH THE APPROVED PLANS. SOIL TESTS SHALL BE MADE TO DETERMINE THE EXACT REQUIREMENTS FOR LIME AND FERTILIZER. PRIOR TO LAYING SOD, SOIL SURFACE SHALL BE CLEAR OF TRASH, DEBRIS AND LARGE OBJECTS. QUALITY OF SOD SHALL BE STATE CERTIFIED TO ENSURE GENETIC PURITY AND HIGH QUALITY. SOD SHALL NOT BE LAID ON FROZEN SOIL SURFACE, OR IN EXCESSIVELY WET OR DRY WEATHER. SOD SHALL BE DELIVERED AND INSTALLED WITHIN 36 HOURS, AND SHALL BE INSTALLED PER PAGE III-339 OF VESCH.
- FIELD. IN ADDITION, NO SEDIMENT TRAPS OR BASINS MAY BE REMOVED WITHOUT PRIOR APPROVAL OF THE INSPECTOR.

EROSION AND SEDIMENT CONTROL MANAGEMENT MEASURES

LANDSCAPE / TREE PRESERVATION NOTES

PRIOR TO ANY LAND DISTURBING ACTIVITY, THE CONTRACTOR SHALL CONTACT THE ARLINGTON COUNTY ARBORIST TO SCHEDULE AN INSPECTION.

LAND CONSERVATION NOTES:

- 1. NO DISTURBED AREA WILL REMAIN DENUDED FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT. 2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
- 3. ALL STORM AND SANITARY SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 100 FEET ARE TO BE OPEN AT ANY ONE TIME.
- 4. ELECTRIC POWER, TELEPHONE AND GAS SUPPLY TRENCHES ARE TO BE COMPACTED, SEEDED AND MULCHED WITHIN 5 DAYS AFTER BACKFILLING.
- 5. ALL TEMPORARY EARTH BERMS, DIVERSIONS AND SEDIMENT CONTROL DAMS ARE TO BE MULCHED AND SEEDED FOR TEMPORARY VEGETATIVE COVER IMMEDIATELY AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED. THE SAME APPLIES TO ALL SOIL STOCKPILES.
- DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION.
- 7. ANY DISTURBED AREA NOT COVERED BY NOTE 1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOV. 1, OR DISTURBED AFTER THAT DATE, SHALL BE UTILITY INSTALLATION: MULCHED IMMEDIATELY WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS/ACRE AND OVER-SEEDED BY APRIL 15.
- 8. AT THE COMPLETION OF ANY PROJECT CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED.

EROSION & SEDIMENT CONTROL PROGRAM:

- 1. THE EROSION CONTROL PLAN IS INTENDED TO ESTABLISH ENTRANCES AND PERIMETER CONTROL MEASURES WHICH INCLUDES SILT FENCE (SF), INLET PROTECTION (IP), AND OTHER CONTROLS SPECIFIED ON THE PLANS.
- 2. WHERE CONSISTENT WITH JOB SAFETY REQUIREMENTS, ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES. NO MATERIAL SHALL BE PLACED IN STREAMBEDS. ANY STOCKPILED MATERIAL WHICH WILL REMAIN IN PLACE LONGER THAN 7 DAYS SHALL BE SEEDED AND MULCHED. WHEN SPOIL IS PLACED ON THE DOWNHILL SIDE OF TRENCH, IT SHALL BE BACKSLOPED TO DRAIN TOWARD THE TRENCH. WHEN NECESSARY TO DEWATER 6. APPLICABLE SAFETY REGULATIONS SHALL BE COMPLIED WITH. THE TRENCH, THE PUMP DISCHARGE HOSE SHALL OUTLET IN A STABILIZED AREA OR A SEDIMENT TRAPPING DEVICE.
- 3. ALL PRACTICES AND CONTROL DEVICES DESCRIBED HEREIN SHALL CONFORM TO THE CURRENT VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH). IN ADDITION, THE CONTRACTOR SHALL TAKE THE FOLLOWING STEPS TO MINIMIZE THE VOLUME OF SILT:
- a. CONTRACTOR SHALL EVALUATE THE SITE TO DETERMINE EXTENSIVE CUT AND FILL AREAS, AND SHALL WORK THOSE AREAS TO MINIMIZE THE USE OF HEAVY EQUIPMENT. CONTRACTOR SHALL BRING DISTURBED AREAS TO GRADE (ROUGH OR FINISHED) AND STABILIZE THOSE AREAS WITH TEMPORARY OR PERMANENT VEGETATION. THESE DISTURBED AREAS SHALL BE STABILIZED PRIOR TO BEGINNING WORK IN ANOTHER AREA.
- b. FILL AREAS SHALL BE COMPACTED COMPLETELY PRIOR TO THE END OF EACH WORK DAY. FILL SLOPE SURFACES SHALL BE KEPT ROUGH TO REDUCE SHEET EROSION OF THE SLOPES. CONTRACTOR SHALL RE-DIRECT CONCENTRATED RUNOFF, BY EARTH BERMS OR OTHER DEVICES, AROUND ACTIVELY DISTURBED AREAS TO STABILIZED OUTLETS.
- c. CUT SLOPES SHALL BE PROTECTED FROM CONCENTRATED FLOW BY BERMS (ABOVE THE SLOPE) AND DIRECTED AROUND THE DISTURBED AREA TO STABILIZED OUTLETS. 4. MEASURES TO CONTROL EROSION AND SILTATION SHALL BE PROVIDED PURSUANT TO AND IN COMPLIANCE WITH CURRENT STATE AND LOCAL

REGULATIONS. THE INFORMATION CONTAINED IN THE CONSTRUCTION PLANS AND/OR THE APPROVAL OF THE PLANS SHALL IN NO WAY RELIEVE THE

COUNTY CODE. 5. ALL AREAS, ON OR OFF-SITE, THAT ARE DISTURBED BY THIS CONSTRUCTION AND WHICH ARE NOT PAVED OR BUILT UPON SHALL BE ADEQUATELY STABILIZED TO CONTROL EROSION AND SEDIMENTATION. ACCEPTABLE STABILIZATION SHALL CONSIST OF PERMANENT GRASS SEED MIXTURE OR SOD THAT IS INSTALLED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS. ALL SLOPES 3:1 AND GREATER SHALL BE RECEIVE SOIL STABILIZATION IN

CONTRACTOR OR HIS AGENT OF ANY LEGAL RESPONSIBILITY WHICH MAY BE REQUIRED BY THE CODE OF VIRGINIA AND CHAPTER 57 OF THE ARLINGTON

- ACCORDANCE WITH THE SPECIFICATIONS. 6. WHERE STREAM CROSSINGS ARE REQUIRED FOR EQUIPMENT, TEMPORARY CULVERTS SHALL BE PROVIDED.
- 7. FOR FURTHER REQUIREMENTS AND DETAILS OF TREE PRESERVATION, PLANTING, EROSION AND SEDIMENT CONTROL, SEE COUNTY CONSTRUCTION STANDARDS AND SPECIFICATIONS AND/OR THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- 1. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS.
- 2. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES. 5. PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN THE AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO THE OWNER FOR
- 6. THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY
- 7. ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- 8. DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING DEVICE.
- 9. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.
- 10. ALL BIOFILTERS SHALL BE KEPT OFF-LINE UNTIL CONSTRUCTION IS COMPLETED AND ALL AREAS HAVE BEEN PROPERLY STABILIZED. THIS SHALL BE ACHIEVED BY USING INLET PROTECTION AT THE CURB CUTS AND STORMWATER CATCH BASINS LEADING DIRECTLY INTO THE BIOFILTERS.
- 11. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED.

PRE-STORM EROSION & SEDIMENTATION CHECKLIST:

REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY

PER GENERAL EROSION AND SEDIMENT CONTROL NOTE 6, THE CONTRACTOR IS RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ANY ADDITIONAL EROSION AND SEDIMENT CONTROL (ESC) MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE COUNTY. THESE SUPPLEMENTARY PRACTICES ARE IN ADDITION TO THOSE SHOWN IN AN EROSION AND SEDIMENT CONTROL PLAN. EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MODIFIED AS NEEDED TO ENSURE ONLY CLEAR WATER IS DISCHARGED FROM THE SITE.

THE FOLLOWING ACTIONS SHALL BE TAKEN PRIOR TO STORM EVENTS WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL TO PREVENT SEDIMENT DISCHARGES FROM A CONSTRUCTION SITE. A TYPICAL SUMMER THUNDERSTORM IS AN EXAMPLE OF A STORM EVENT WITH PREDICTED HEAVY AND/OR LARGE VOLUME RAINFALL

1. PERIMETER CONTROLS

- a. SILT FENCE SHALL BE CHECKED FOR UNDERMINING, HOLES, OR DETERIORATION OF THE FABRIC. FENCING SHALL BE REPLACED IMMEDIATELY IF THE FABRIC IS DAMAGED OR WON. SILT FENCE MUST BE TRENCHED INTO THE GROUND PER STATE SPECIFICATIONS (VESCH STD & SPEC 3.09).
- b. WOODEN STAKES OR STEEL POSTS SHALL BE PROPERLY SECURED UPRIGHT INTO THE GROUND. DAMAGED POSTS OR STAKES MUST BE REPLACED. c. SEDIMENT THAT HAS ACCUMULATED AGAINST THE SILT FENCE SHALL BE REMOVED. ACCUMULATED SEDIMENT MUST BE REMOVED WHEN THE LEVEL
- REACHES ONE-HALF THE HEIGHT OF THE FENCING. d. HAY BALES OR A STONE BERM SHALL BE PLACED ACROSS THE CONSTRUCTION ENTRANCE TO PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION

2. EXPOSED SLOPES AND SOIL

- a. EXPOSED SLOPES NOT AT THE FINAL STABILIZATION PHASE SHALL BE COVERED WITH TARPS, PLASTIC SHEETING, OR EROSION CONTROL MATTING. COVERING MATERIAL SHALL BE PROPERLY SECURED/ANCHORED.
- b. CONTROLS SHALL BE INSTALLED TO PREVENT CONCENTRATED FLOW DOWN AN EXPOSED SLOPE. BERMS OR DIVERSION DIKES SHALL BE INSTALLED AT THE TOP OF CUT/EXPOSED SLOPES TO DIRECT STORM FLOW AROUND THE DISTURBED AREA. c. EXPOSED SLOPES AT THE FINAL STABILIZATION PHASE SHALL BE STABILIZED USING SLOPE STABILIZATION PRACTICES SUCH AS SOIL STABILIZATION
- BLANKETS OR MATTING AS SPECIFIED IN THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK (VESCH STD & SPEC 3.36). BLANKETS OR MATS MUST BE PROPERLY SECURED AND ANCHORED TO THE SLOPE USING STAPLES, PINS, OR STAKES. d. Seeded areas shall be checked and reseeded as necessary to cover exposed soil. Recently seeded areas shall be protected by

STRAW OR SOIL STABILIZATION BLANKETS TO PREVENT SEEDING FROM BEING WASHED AWAY. 3. STOCKPILES

4. INLET PROTECTION

- a. STOCKPILED SOIL AND OTHER LOOSE MATERIALS THAT CAN BE WASHED AWAY SHALL BE COVERED WITH A TARP, PLASTIC SHEETING, OR OTHER STABILIZATION MATTING. THE COVER MUST BE PROPERLY SECURED/ANCHORED DOWN TO PREVENT IT FROM BEING BLOWN OFF AND EXPOSING MATERIALS TO RAIN. CONTROLS SUCH AS HAY BALES OR BOOMS SHALL BE PLACED ALONG THE PERIMETER OF THE STOCKPILE (DOWNHILL SIDE).
- a. INLET PROTECTION CONTROLS SHALL BE INSPECTED TO ENSURE THEY ARE FUNCTIONING PROPERLY AND FLOODING WILL NOT OCCUR. CLOGGED OR DAMAGED CONTROLS MUST BE REPLACED IMMEDIATELY. ENSURE CONTROLS ALLOW FOR OVERFLOW/BYPASS OF STORMWATER RUNOFF DURING
- THE EROSION AND SEDIMENT CONTROL INSPECTOR SHALL HAVE THE AUTHORITY TO ADD OR DELETE EROSION AND SEDIMENT CONTROLS AS NEEDED IN THE IN ADDITION TO THESE PRE-STORM ACTIONS, ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES MUST BE CHECKED DAILY AND AFTER EACH SIGNIFICANT

POLLUTION PREVENTION PLAN NOTES (STORMWATER MANUAL - SECTION 2.4)

- 1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:
- a, WATER LINE FLUSHING: LANDSCAPE IRRIGATION: DIVERTED STREAM FLOWS: RISING GROUND WATERS: UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING: INDIVIDUAL RESIDENTIAL CAR WASHING: FLOWS FROM RIPARIAN HABITATS AND WETLANDS: DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIREFIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.
- 2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.
- 3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM

SEWER SYSTEM OR STATE WATERS.

- UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:
- 1. NO MORE THAN 100 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- 2. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
- 3. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.
- 4. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.
- 5. STABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THESE REGULATIONS.
- 9. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH
- 10. AT THE COMPLETION OF THE CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDED AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

MAINTENANCE PROGRAM:

- THE FOLLOWING IS A PROGRAM OF MAINTENANCE FOR THE MECHANICAL CONTROLS SPECIFIED IN THIS NARRATIVE AND ON THE PLAN:
- 1. THE SITE SUPERINTENDENT OR HIS/HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREA (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS; ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO ENSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORK DAY INCLUDING RE-SEEDING AND MULCHING OR RE-SODDING IF NECESSARY.
- 2. ALL SEDIMENT TRAPPING DEVICES SHALL BE CLEARED OUT AT 50% TRAP CAPACITY AND THE SEDIMENT SHALL BE DISPOSED OF BY SPREADING ON THE SITE OR IF NOT SUITABLE FOR FILL, HAULING AWAY AND DEPOSITING AT AN ACCEPTABLE DUMP SITE.
- 3. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PREVENT MUD AND/OR OTHER DEBRIS FROM BEING ENTERED ONTO EXISTING SWM/BMP FACILITIES OR DOWNSTREAM WATER WAYS. SHOULD OFF-SITE AREAS BECOME POLLUTED BY CONSTRUCTION ACTIVITIES, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE AFFECTED AREAS TO THE SATISFACTION OF THE INSPECTOR.

4. AT THE COMPLETION OF CONSTRUCTION AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ANY REMAINING

DENUDED AREAS SHALL BE STABILIZED. CERTAIN DEVICES MAY BE REMOVED PRIOR TO CONSTRUCTION COMPLETION BUT ONLY WITH THE APPROVAL OF

THE COUNTY INSPECTOR. 5. AFTER CONSTRUCTION OPERATIONS HAVE ENDED, ALL DISTURBED AREAS SHALL BE STABILIZED. UPON APPROVAL OF THE COUNTY INSPECTOR, MECHANICAL SEDIMENT CONTROLS SHALL BE REMOVED AND THE GROUND PERMANENTLY STABILIZED WITH VEGETATION WITHIN 30 DAYS.


ARLINGTON **VIRGINIA**

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813

ARLINGTON, VA 22201

PHONE: 703.228.3629

FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE 01/18/22 Amy Pflaum QUALITY CONFROL ENGINEER CONSTRUCTION MANAGEMENT SUPERVISO

WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach TRANSPORTATION DIRECTOR John Mir PROJECT MANAGER **REVISIONS**

. ⊘ \triangle

0 0 0


DESIGNED: SEB DRAWN: SEB CHECKED: SWS

SCALE:

PLOTTED: JANUARY 6 2022

C032.

NORTHSIDE SALT STORAGE SITE SLT1



SOURCE: VA. DSWC

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
4B	Urban land-Sassafras- Neabsco complex, 3 to 8 percent slopes	6.0	53.6%
7C	Glenelg-Urban land complex, 8 to 15 percent slopes	0.9	7.7%
7D	Glenelg-Urban land complex, 15 to 25 percent slopes	0.8	7.3%
12	Urban land-Udorthents complex, 2 to 15 percent slopes	3.5	31.5%
Totals for Area of Interest		11.2	100.0%






PLATE. 3.07-2





SECTION B-B


Plate 3.02-1




REINFORCED CONCRETE









SEDIMENT CONTRO AND DETAILS EROSION AND S NORTHSIDE DESIGNED: SEB DRAWN: SEB CHECKED: SWS PLOTTED: JANUARY 6 2022 SCALE: **AS SHOWN**

SITE

STOR/

C032.2

DESIGNED: SEB

DRAWN: SEB CHECKED: SWS

PLOTTED: JANUARY 6 2022

SCALE:

C035.

STORMWATER POLLUTION PREVENTION PLAN

STORMWATER POLLUTION PREVENTION PLAN (SWPPP) **Arlington County Projects** (Linear Development / Stormwater Retrofit)

For Construction Activities At: Northside Salt Storage Site SE Corner of Old Dominion Dr. & 26th St. N. Arlington, VA, 22207

Latitude: 38.902942 N (decimal degrees)

Longitude: 77.126444 W (decimal degrees)

Construction Activity Operator:

Arlington County Department of Environmental Services 2100 Clarendon Blvd., Suite 813 Arlington, VA 22201 c/o Solomon Shikur, P.E. (703)228-3654 sshikur@arlingtonva.us (703)228-6555 (24-hour Emergency)

SWPPP Preparation Date:

October 25, 2021

CERTIFICATION

"I certify under penalty of law that I have read and understand this document and that this document and all attachments were prepared in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

Operator Name:	
Title:	
Signature:	
Date:	

5.0 Potential Sources of Pollution & Pollution Prevention Practices

Arlington County SWPPP 12/2016

1.0 SWPPP Documents Located Onsite & Available for Review

SWPPP Document Type	Located Onsite & Available for Review?
Registration Statement Notice of Coverage Letter Construction General Permit Pollution Prevention Plan Erosion & Sediment Control Plan Stormwater Management Plan LDA Permit	Yes

Required documents must be kept at a centralized location on the project site (i.e. in a mail box or other container)

2.0 Authorized Non-Stormwater Discharges

Type of Authorized Non-Stormwater Discharges	Likely Present at Your Project Site?
Uncontaminated excavation dewatering Landscape irrigation Others [describe]	 ✓ Yes ✓ Yes ✓ No ✓ Yes ✓ No

3.0 Pollution Prevention Awareness

Employees will be given a "walk through" of the site identifying areas of possible pollution and will be shown Erosion and Sediment Controls and Pollution Prevention Practices (identified in Sections 4.0 and 5.0 of this SWPPP) that are applicable to their assigned job duties. A refresher meeting and "walk through" will be conducted on an as needed

4.0 Erosion & Sediment Controls

Select all that apply	Erosion & Sediment Control	Erosion & Sediment Control Estimated Estimated Removal Date Date				
	Construction Entrance (Std. & Spec. 3.02)					
	Silt Fence (Std. & Spec. 3.05)					
	Culvert Inlet Protection (Std. & Spec. 3.08)					
\boxtimes	Outlet Protection (Std. & Spec. 3.18)		NA			
	Temporary Seeding (Std. & Spec. 3.31)	B.31) Peding B.32) NA		Construction Activity Operator (See Cover		
	Permanent Seeding (Std. & Spec. 3.32)			Page)		
	Sodding (Std. & Spec. 3.33)					
	Mulching (Std. & Spec. 3.35)		NA			
	Safety Fence (Std. & Spec 3.01)					
	Storm Drain Inlet Protection					

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

MANUAL: 2.4 POLLUTION PREVENTION PLAN (P2 PLAN)

INLETS, OR

STREAM NETWORK.

Dewatering (Std. & Spec 3.26 and/or Arlington ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED County Std. & Spec from approved BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL ESC plan) BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), Turbidity Curtain OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT (Std. & Spec 3.27 and/or Arlington County Std. & Spec from approved SOURCE OF POLLUTANTS TO SURFACE WATERS: ESC plan) Tree Protection WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; (Arlington County Std. & Spec from RISING GROUND WATERS; UNCONTAMINATED GROUND WATER approved ESC plan)

STORMWATER POLLUTION PREVENTION PLAN

(Std. & Spec 3.08 and/or Arlington

County Std. & Spec from approved

ESC plan)

Stream Crossing / Cofferdams

(Std. & Spec 3.25 or on plan)

Pump Around System

(detail on approved plan)

Rip Rap

(Std. & Spec. 3-19)

The following actions shall be taken <u>prior to storm events with predicted heavy and/or large volume</u> <u>rainfall</u> to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with

- Perimeter controls (silt fence, hay bales, stone berms) used to prevent sediment from leaving the site shall be
- Sediment that has accumulated against perimeter controls shall be removed if the depth exceeds more than 1/2 of
- Exposed soil or slopes shall be covered with straw, tarps, plastic sheeting, or erosion control matting. Covering material shall be properly secured/anchored.
- or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side). Stockpiled materials should not obstruct flow along the curb line.
- ☐ Inlet protection controls shall be inspected to ensure they are installed per approved ESC plan, are functioning properly, and maintained as needed.

Pre-Storm Erosion and Sediment Control Checklist

predicted heavy and/or large volume rainfall.

- checked for undermining, holes, or deterioration and repaired/replaced if needed.
- the silt fence height.
- Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting,

STORM SEWER SYSTEM OR STATE WATERS.

10/25/2021

I hereby certify that I accept the responsibilities of Responsible Land Disturber for the above referenced project. I understand

Conducting a pre-construction briefing with earth moving and site contractors to present the E&S plan and

4. Regularily inspecting the site during construction to ensure that all E&S controls are functioning and are adequate to address erosion and sedimentation. Inspect the site 48 hours after a runoff-generating storm, and

5. Reporting to the owner the presence inadequate or non functioning E&S controls when they are observed.

6. Ensuring that temporary soil stabilization is applied within 7 days to areas denuded that will remain

highlight the presence of critical areas, the limits of clearing and the required E&S controls and tree protection

undisturbed for longer than 14 days. Permanent stabilization shall be applied to areas that are to be left dormant

1. Reviewing the erosion and sedimentation (E&S) plan for the project.

7. Calling (703) 228-0760 at least 80 hours before demolishing any structure.

measures to be installed. Call 703-228-0760 to schedule pre-construction meeting.

I may be reached at ________ with questions about this plan or my execution of the duties of

Walking the site prior to construction to identify critical areas.

provide a copy of the inspection findings to the county.

INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED

PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES;

FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION

WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS;

LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM

DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER

ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF

NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G.,

PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL

STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE

OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE

CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER,

ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN

FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE

RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL

ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.

APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY

DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO

Arlington County SWPPP 12/2016

STORMWATER POLLUTION PREVENTION PLAN

7.0 Spill Prevention & Response

Most spills can be cleaned up using a spill kit. Absorbent/oil dry, sealable containers, plastic bags, and shovels/brooms are suggested minimum spill response items that should be available at the project site.

1st Priority: Protect all people 2nd Priority: Protect equipment and property 3rd Priority: Protect the environment

- 1. Check for hazards (flammable material, noxious fumes, cause of spill) if flammable liquid, turn off engines and nearby electrical equipment. If serious hazards are present leave the area and call 911. LARGE SPILLS
- ARE LIKELY TO PRESENT A HAZARD. 2. Ensure the spill area is safe to enter and that it does not pose an immediate threat to health or safety of any
- 3. Stop the spill source.

VA Dept. of Emergency Management

24 Hour Reporting Service

Location(s) of spill kit:

- 4. Call co-workers and supervisor for assistance and to make them aware of the spill and potential dangers. 5. If possible, stop spill from spreading and/or entering storm drains (use absorbent or other materials as
- necessary). 6. If spilled material has entered a storm drain; contact Arlington County Fire Department and project manager.
- 7. Clean up spilled material according to manufacturer specifications, for liquid spills use absorbent materials and do not flush area with water.

804-674-2400

8. Properly dispose of cleanup materials and used absorbent material according to manufacturer specifications.

Emergency Contacts:

Local Contacts 703-558-2222 Arlington County Fire & Police DES Water, Sewer, Streets 24-Hour Emergency 703-228-6555 Washington Gas Emergency 703-750-1400 Nights, Holidays & Weekends

Spill kit on site: ☐ Yes ☐ No

Pollutant-Generating Activity	Likely Present at your Project Site?	Sediment	Nutrients	Heavy Metals	pH (acids and bases)	Pesticides & Herbicides	Oil & Grease	Bacteria & Viruses	Trash, Debris, Solids	Other Toxic Chemicals	Pollution Prevention Practice	Responsible Party
Clearing, grading, excavating, and un-stabilized areas	⊠ Yes □ No	x	Х						x		(1)	
Paving and saw cutting operations	⊠ Yes □ No	х					х		х		(2)	
Concrete operations, washout, and cement waste	⊠ Yes □ No			Х	Х				х		(3)	
Washing / cleaning	☐ Yes ⊠ No	X	X	X	Х		х		х	х	(4)	
Dewatering operations	⊠ Yes □ No	X	X						x		(5)	Construction Activity
Material / chemical use and storage	☐ Yes ⊠ No	Х	Х	Х	Х	Х	Х		Х	x	(6)	Operator (See Cover Page of this SWPPP)
Equipment and vehicle maintenance	☐ Yes ⊠ No				Х		Х		Х	x	(7)	
Waste management / disposal	⊠ Yes □ No								х	х	(8)	
Sanitary waste	⊠ Yes □ No		Х		Х			Х			(9)	

Arlington County SWPPP 11/2016

Nutrient management

SOLOMON W. SHIKUR 44276

Responsible Land Disturber.

for more than one year.

telephone number

Qiangian Li, P.E.

street address

permit number

Dear Mrs. Li:

ESC Program Administrator

Arlington, Virginia 22201

Department of Environmental Sevices

2100 Clarendon Boulevard, Suite 813

4753 Old Dominion Drive

lot, block, section subdivision


that these responsibilities include:


Re: Erosion and Sediment Control Permit Application for:


SE Corner of Old Dominion Dr. and 26th St N.

professional registration (type and number)

Arlington County SWPPP 12/2016







GRAPHIC SCALE

CONTROL DATA:

Northing(Y)

7014794.9500

7014626.2080

7014662.9233 7014738.1634

7014688.1514

7014865.8504

Easting(X) 11873604.6660

11873835.3460

11873813.7663

11873942.8377

11873842.3807 427.21

11873850.1155 427.36

429.73

428.13

428.46


424.98


TRV 101

TRV 102

TFLY

C045.1





DOME FACILITY

OUTFALL FROM SALT

DOME FACILITY

													Sto	orm	Inle	t Co	mp	utatio	ns S	She	et												
	Ir	ilet					Flo	w		-							Cı	ırb Inlet								Grate Inlets		s	-	Yard In	lets	Op	peration
Number	Туре	Length (Pt)	Station	Drainage Area (Acres)	C	CA	I (In/H	Q Inc	Carryove (CFS)	QT (CFS)	S Gutter Slope (Pt/Pt)	Crossslope	T (Spread)	W (Pt)	T Sw (Rt/Rt	Sw/S	EO	Local Depression (in)	a (in)	S'w	Se (ft/ft)	n Value	LT (Pt)	L/LT d(FT)	T Spread @ Sag (Pt)	Perimeter (Pt)	AFEA	H Flow Depth (ft)		h Throat Height (Rt)		E(%)	Q; Intercepted (CFS)
22529	CB-2B	8.00		0.09	0.30	0.03	3 5.70	0.18	0.00		0.025	0.010	4.55	1.50 0.	33 0.083	8.30	1.00	2.5	3.81	0.21	0.22	0.013	3.23	2.48 0.31	1		W. T. B.	1 m 1 m 1 m		1 0 1		100%	0.18
2388	CB-3			0.28	0.76	0.2	1 5.70	1.44	0.00	1.44												-				4.00	4.00	0.37	11			100%	1.44
2388A	MH-1								Ĭ m																								
2388B	MH-1																															1	
2388C	MH-1																																
2388C 2388D	MH-1								Y																								
2388E	MH-1								7				1													1							
2388G	DI-3C						Î		1													1											
	CB-3			0.12	0.61	0.0	7 5.70	0.50	0.00	0.50																3.00	2.25	0.22	ligg of			100%	0.50
2388I	CB-3			0.11	0.79	0.09	9 5.70	0.59	0.00	0.59			1							10.00					1		0.56					100%	
2388J	CB-3			0.37	0.35	0.13	3 5.70	0.88	0.00	0.88																4.77	0.56	0.21				100%	
2388K	CB-3			0.22	0.60		3 5.70	0.90	0.00	0.90																	6.25					100%	
2388L	CB-3			0.11	0.50	_	5 5.70	0.37	0.00	0.37				-					-								4.00			-		100%	
	CB-3			0.39	0.85	0.33	3 5.70	2.25	0.00	2.25																	6.25		11			100%	

								-					Junction	n Loss								
Inlet Structure	Upstream Structure	Outlet Water Surface Elev. (Pt)	Do (In)	Qo (CPS)	Lo (Pt)	Sfo (%)	Hf (Ft)	Vo (Pt/S)	Ho (Ft)	Qi	Vi (Rt/s)	QiVi	Vi2/2g			H Del	Ht (Ft)	1.3 Ht (Pt)	0.5 Ht (Rt)	Final H (Ft)	Inlet Water Surface Elev. (Rt)	Rim Elev. (Pt)
2417																					411.36	,
2529		413.45	18	5.25	31.701	0.25%	0.08	3.46	0.05			1		0.17		0.09			0.15	0.23	413.45	419.47
	2388		18)			5.13	5.51	28.27	0.47	0.17	15.76							
388		413.87		5.13	32.872	0.24%	0.08	5.51	0.12					0.11		0.07	0.30		0.15	0.23	414.11	420.75
	2388A		18							4.08	4.45	18.16	0.31	0.11	18.95	_	0.24					
388A		414.11		4.08	24.490	0.13%	0.03	4.45	0.08					0.15		0.14			0.19	0.22	414.73	421.53
	2388B		18			10000000				4.08	5.31	21.66	0.44	0.15	27.61	0.14			T 4 1			11000
388B		414.73		4.08	4.614	0.13%	0.01	5.31	0.11					0.05		0.01	0.18		0.09	0.09	414.82	421.62
2022	2388C		48		71.001	0.000		0.45		4.40	3.15	13.86	0.15	0.05	5.53	_	0.08		0.14		*****	100.70
2388C	22005	414.65		4.40	71.901	0.00%	0.00	3.15	0.04			25.40	0.56	0.20		0.05	0.29	_	0.14	0.14	414.90	423.78
2000	2388D	447.70	18	4.40	40.007	0.450/	0.00	6.00	_	4.40	6.00	26.40	0.56	0.20	6.93		0.09	_	0.47	0.40	447.00	424.00
388D	22005	417.79		4.40	10.097	0.15%	0.02	6.00	0.14	2.44	C 00	26.04	0.57	0.20	0.64	0.01	0.35	0.00	0.17	0.19	417.98	424.00
2005	2388E	417.00	18	4.41	12.000	0.150/	0.02	C 00		4.41	6.08	26.81	0.57	0.20	0.64	0.01	0.01	0.00	0.00	0.11	410.50	124 21
2388E	2388G	417.98		4.41	13.696	0.15%	0.02	6.08	0.17	2.68	3.29	8.82	0.17	0.06	4.75	0.01	0.17		0.09	0.11	418.58	424.31
	2388F		18 15							2.25	2.58	5.81		0.00	107.14						-	_
388G	23001	418.58		2.68	118.520	0.06%	0.07	3 20	0.05	2.23	2.30	3.01	0.10	0.04	107.14	0.00	0.05		0.03	0.09	419.81	426.95
.5000	2388H	110.50	15	2.00	110.520	0.0070	0.07	5.25	0.03	1.79	4.78	8.56	0.35	0.12	109.52	0.27	0.77		0.03	0.05	115.01	120,55
	2388K		15							1.06	4.47	4.74		0.11	3.28		0.05					
2388H		419.81	15	1.79	109.701	0.07%	0.07	4.78	0.09		1	1	5.51	0.07	5.20	0.16			0.21	0.28	421.63	423.75
	2388I	1,57,62	15							1.38	3.69	5.09	0.21	0.07	103.88						,,	
2388I		421.63		1.38	79.767	0.04%	0.03	3.69	0.05					0.05	1	0.01	0.11	_	0.07	0.10	422.79	425.90
	2388J		15	7 7 1						0.88	2.95	2.60	0.14	0.05	4.59		0.06	_				-
388K		419.89	15	1.06	24.436	0.02%	0.01	4.47	0.08					0.01		0.00	0.09	0.12	0.06	0.07	420.68	426.51
	2388L		15			11-6-11			11 - 11	0.37	1.61	0.60	0.04	0.01	1.78	0.00	0.03					100

STORM SEWER DESIGN COMPUTATIONS - PRE-IMPROVEMENT CONDITIONS PRIOR TO CONSTRUCTION OF SALT STORAGE STRUCTURE STORM SEWER DESIGN COMPUTATIONS Project: NORTHERN SALT STORAGE SITE - PHASE II (SALT) Inlet Rain Runoff Invert Elev. Length Slope Dia. Capacity VEL. Flow Area Factor Increment Cumm. Time Fall Q Upper Lower Q Time Min. In/Hr C.F.S. End End FT. % IN C.F.S. F.P.S. MIN. 1.08 0.84 0.91 0.91 5.00 6.79 6.16 423.20 422.29 33.3 2.74% 15 10.71 9.03 0.06 0.00 0.91 5.00 6.79 6.16 421.59 421.53 13.7 0.44% 15 4.28 3.49 0.07 0.73 | 0.15 | 1.05 | 5.00 | 6.79 | 7.15 | 421.48 | 420.75 | 52.1 | 1.40% | 15 | 7.67 | 7.10 | 0.12 0.69 | 0.69 | 5.00 | 6.79 | 4.67 | 422.70 | 422.28 | 15.9 | 2.64% | 15 | 10.52 | 8.32 | 0.03 0.00 0.69 5.00 6.79 4.67 421.95 420.96 46.9 2.11% 15 9.42 7.66 0.10 0.00 1.74 5.00 6.79 11.82 420.46 420.44 33.8 0.06% 15 1.57 1.28 0.44 0.9 0.35 0.35 5.00 6.79 2.38 420.85 420.60 23.5 1.06% 15 6.68 4.98 0.08 0.00 0 0.00 2.09 5.00 6.79 14.21 420.54 415.00 80.8 6.85% 15 16.96 15.48 0.09

OFFSITE FLOW (FROM OLD DOMINION DRIVE & 25TH STREET NORTH) TO PIPE (2417 TO 2376) = 20.94 CFS - 5.83 CFS = 15.11 CFS

OFFSITE FLOW (FROM OLD DOMINION DRIVE & 25TH STREET NORTH) TO PIPE (2417 TO 2376) = 21.08 CFS - 5.97 CFS = 15.11 CFS

POST-IMPROVEMENT CONDITIONS PRIOR TO PROPOSED STORMWATER MANAGEMENT IMPROVEMENTS

 2417
 1.00
 0.4
 0.40
 0.86
 5.00
 6.79
 5.83
 416.45
 416.01
 35.1
 1.25%
 15
 7.25
 6.57
 0.09

 2376
 0.16
 0.83
 0.13
 3.08
 5.00
 6.79
 20.94
 412.16
 411.36
 100.3
 0.80%
 18
 9.40
 5.32
 0.31

Project: N	NORTHERN S	SALT STORA	AGE SITE	- PHASE II	(SALT)	1	POS	CONDIT								
From	To	Drainage	С	Cx	A	Inlet	Rain	Runoff	Invert	Elev.	Length	Slope	Dia.	Capacity	VEL.	Flo
Point	Point	Area	Factor	Increment	Cumm.	Time Min.	Fall In/Hr	Q C.F.S.	Upper End	Lower End	FT.	%	IN.	Q C.F.S.	F.P.S.	Tin
22533	2471	1.08	0.84	0.91	0.91	5.00	6.79	6.16	423.20	422.29	33.3	2.74%	15	10.71	9.03	0.0
2471	2480	0.00	0	0.00	0.91	5.00	6.79	6.16	421.59	421.53	13.7	0.44%	15	4.28	3.49	0.0
2480	2465	0.20	0.73	0.15	1.05	5.00	6.79	7.15	421.48	420.75	52.1	1.40%	15	7.67	7.10	0.1
25271	2439	1.11	0.62	0.69	0.69	5.00	6.79	4.67	422.70	422.28	15.9	2.64%	15	10.52	8.32	0.0
2439	2465	0.00	0	0.00	0.69	5.00	6.79	4.67	421.95	420.96	46.9	2.11%	15	9.42	7.66	0.1
2465	2456	0.00	0	0.00	1.74	5.00	6.79	11.82	420.46	420.44	33.8	0.06%	15	1.57	1.28	0.4
2377	2456	0.39	0.9	0.35	0.35	5.00	6.79	2.38	420.85	420.60	23.5	1.06%	15	6.68	4.98	0.0
2456	2417	0.00	0	0.00	2.09	5.00	6.79	14.21	420.54	415.00	80.8	6.85%	15	16.96	15.48	0.0
2388	22529	1.08	0.64	0.69	0.69	5.00	6.79	4.69	419.27	417.64	32.8	4.97%	10	4.90	10.23	0.0
22529	2417	0.13	0.35	0.05	0.88	5.00	6.79	5.97	416.45	416.01	35.1	1.25%	15	7.25	6.19	0.0
2417	2376	0.16	0.83	0.13	3.10	5.00	6.79	21.08	412.16	411.36	100.3	0.80%	18	9.40	5.32	0.3
BASIN1	STR 1	0.17	0.84	0.14	0.14	5.00	6.79	0.97	423.00	422.50	22.2	2.26%	10	4.77	6.86	0.0
STR 1	BASIN2	0.00	0	0.00	0.14	5.00	6.79	0.97	422.00	419.22	102.9	2.70%	10	5.22	7.31	0.2
BASIN2	STR 2	0.00	0	0.00	0.14	5.00	6.79	0.97	418.80	417.20	176.6	0.91%	12	4.91	4.87	0.6
STR 2	22529	0.00	0	0.00	0.14	5.00	6.79	0.97	417.00	416.80	36.6	0.55%	12	3.82	4.06	0.1

OUTFALL FROM SALT DOME FACILITY

From Point	10 15 15 V	Area Drain "A"	Runoff Coefficient		CA	Inlet Time	Rainfall	Runoff Q	Invert El	evations	Length	Slope	Dia	Capacity	Velocity	How Time	Remarks
		Acres	С	Incremental	Accumulative	Min	In/Hr	CFS	Upper End	Lower End	Rt	%	In	CFS	FPS	Min	
22529	2417	0.09	0.30	0.03	1.05	5.0	6.79	5.25 *	412.57	412.25	31.701	1.00%	18	10.55	4.16	0.14	
2388	22529	0.28	0.76	0.21	1.02	5.0	6.79	5.13	413.00	412.67	32.872	1.00%	18	10.52	5.17	0.15	
2388A	2388	0.00	0.00	0.00	0.81	5.0	6.79	4.08	413.34	413.10	24.490	1.00%	18	11.26	4.45	0.14	
2388B	2388A	0.00	0.00	0.00	0.81	5.0	6.79	4.08	413.49	413.44	4.614	1.00%	18	11.84	4.88	0.03	
2388D	2388C	0.00	0.00	0.00	0.81	5.0	6.79	4.40	414.10	414.00	10.097	1.00%	18	11.32	5.28	0.06	
2388E	2388D	0.00	0.00	0.00	0.81	5.0	6.79	4.41	417.29	417.15	13.696	1.00%	18	11.50	5.32	0.08	
2388G	2388E	0.00	0.00	0.00	0.48	5.0	6.79	2.68	418.58	417.39	118.520	1.00%	18	11.40	3.59	1.13	
2388H	2388G	0.12	0.61	0.07	0.29	5.0	6.79	1.79	420.42	418.77	109.701	1.50%	15	8.58	4.19	1.17	
2388I	2388H	0.11	0.79	0.09	0.22	5.0	6.79	1.38	421.72	420.52	79.767	1.50%	15	8.58	3.51	1.13	
2388J	2388I	0.37	0.35	0.13	0.13	5.0	6.79	0.88	423.00	421.82	78.621	1.50%	15	8,57	2.94	1.83	
2388K	2388G	0.22	0.60	0.13	0.19	5.0	6.79	1.06	419.62	418.89	24.436	3.00%	15	12.09	3.78	0.40	
2388L	2388K	0.11	0.50	0.06	0.06	5.0	6.79	0.37	422.90	419.72	106.074	3.00%	15	12.11	1.96	5.81	
2388F	2388E	0.39	0.85	0.33	0.33	5.0	6.79	2.25	419.65	417.45	68.430	3.21%	15	13.07	3.23	0.62	

FLOW FROM 22529 - 2417: 5.25 CFS* PROPOSED FLOW IN EX. PIPE (2417 TO 2376) = PROPOSED OUTFALL FLOW FROM SALT DOME FACILITY + OFFSITE FLOW = 5.25 CFS + 15.11 CFS = 20.36 CFS PROPOSED FLOW IN PIPE (2417 TO 2376) < EXISTING FLOW IN PIPE (2417 TO 2376) 20.36 CFS < 20.94 CFS

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED

SOLOMON W SHIKUR

APPROVALS DATE

Amy Pflaum 01/18/22 QUALITY CONTROL ENGINEER CONSTRUCTION MANAGEMENT SUPERVISOR

MATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach 01/27/22 TRANSPORTATION DIRECTOR

Oohn Wir PROJECT MANAGER

REVISIONS

DESIGNED: SEB DRAWN: SEB CHECKED: SWS

PLOTTED: JANUARY 6 2022

SCALE:

C075.1

Company Name Address

Stormwater Specialist Department of Environmental Services 2100 Clarendon Blvd Suite 705 Arlington, VA 22201

RE: Stormwater Management Facility (SWMF) As-Built Certification [PROJECT NAME] [PROJECT ADDRESS] Arlington, VA [BUILDING PERMIT #], [LDA#], [SWM#]

Dear Sir or Madam,

We have inspected the [TYPE OF SWMF FACILITY] facility that was constructed as part of the above referenced project and determined that it has been installed in accordance to the County approved plan dated [INSERT DATE OF ENGINEER'S STAMP ON APPROVED PLANS]. The approved [TYPE OF SWMF FACILITY] facility is comprised of [INSERT DESCRIPTION OF STRUCTURE INCLUDING SIZE/DIMENSIONS AND MODEL #] with [NUMBER, SIZE AND TYPE OF CARTRIDGES] that treats stormwater runoff for this project.

Based on the as-built conditions of the site, facility [X] treats [TOTAL AREA TREATED] of which [AMOUNT OF IMPERVIOUS AREA TREATED] is impervious. Facility [Y] treats [TOTAL AREA TREATED] of which [AMOUNT OF IMPERVIOUS AREA TREATED] is impervious, therefore the facility meets the requirements of the Arlington County's Stormwater Ordinance.

For reference, the as-built drawings are attached showing the sizing of the facility along with the activation letter from the manufacturer. As required, the as-built drawings include the inverts for all inflow/outfall pipes connected to the facility. Therefore, it is our professional opinion that the facility was installed in accordance to the County approved plan and that the facility is functioning as designed.

If you have any questions regarding the above-mentioned facility, please do not hesitate to call me.


Respectfully,

Attachments:

1. As-built drawings 2. Activation Letter from manufacturer



Proprietary BMP | November 2016




MANUFACTURED FILTERING DEVICE DETAIL


SELECTED MANUFACTURED FILTERING DEVICE SHALL BE CONTECH STORMFILTER OR APPROVED EQUAL, SHALL HAVE A 50% PHOSPHORUS REMOVAL EFFICIENCY, AND SHALL BE ON THE VIRGINIA STORMWATER BMP CLEARINGHOUSE APPROVED LIST OF FILTERING DEVICES AWARDED 50% TP REMOVAL EFFICIENCY.

MAINTENANCE NOTE

THE MAINTENANCE SCHEDULE AND LIST OF MAINTENANCE TASKS AND METHODS WILL DEPEND ON THE MANUFACTURER SELECTED BY THE CONTRACTOR. AT A MINIMUM, INSPECTION OF THE FILTERING DEVICE SHALL TAKE PLACE TWICE A YEAR. SEDIMENT ACCUMULATION OF 4" OR MORE AT THE BOTTOM OF THE VAULT SHOULD BE CLEANED. OTHER MAINTENANCE WORKS SUCH AS FILTER CLEANING AND/OR REPLACEMENT SHALL FOLLOW MANUFACTURER'S RECOMMENDATIONS.

EL. = 421.33── 6" WEIR WALL SEE **DETAIL THIS SHEET** — 30" RECTANGULAR 10-YR WSE = 417.11 WEIR −EL. = 416.54 RECTANGULAR WEIR _____ ~1-YR WSE = 415.25 — TOP EL. = 414.35 -BOTTOM EL. = 413.54 18" HP PIPE FROM 2388B L_{9.75"} ORIFICE └ 9.75" ORIFICE 18" HP PIPE TO 2388 OUTLET CONTROL STRUCTURE (2388A) PLAN VIEW INV. IN = 413.54 INV. OUT = 413.44SEE OUTLET CONTROL STRUCTURE (OCS) LOCATION ON SHEET C083.1 SEE OUTLET CONTROL STRUCTURE CALCULATIONS ON SHEET C085.2 OUTLET CONTROL STRUCTURE (2388A) SECTION A-A OUTLET CONTROL STRUCTURE (2388A) SECTION B-B





INSTALLED STORAGE VOLUME = 4,100 CF

FACILITY LENGTH = 77.5 FT

FACILITY WIDTH = 25.5 FT

ARLINGTON VIRGINIA

DEPARTMENT OF **ENVIRONMENTAL SERVICES FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

18" HP PIPE

TO 2388

6" WEIR WALL SEE

RECTANGULAR WEIR

ONCE A YEAR, RECOMMENDED DURING A DRY SEASON. MAINTENANCE SHALL BE DONE

THROUGH THE TWO MAINTENANCE RISERS. CLEANING SHOULD BE DONE TO MAINTAIN

OTHER MAINTENANCE WORKS SHALL FOLLOW MANUFACTURER'S RECOMMENDATIONS.

PROPER STORAGE AND FLOW.


DETAIL THIS SHEET

ORIFICE

18" HP PIPE

FROM 2388B

COPYRIGHT © 2021 ARLINGTON COUNTY VIRGINIA - ALL RIGHTS RESERVED



APPROVALS DATE

Amy Pflaum
QUALITY CONFROL ENGINEER CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach
TRANSPORTATION DIRECTOR

Oohn Mir PROJECT MANAGER 1/27/22

REVISIONS

NORTHSID


DESIGNED: SEB DRAWN: SEB CHECKED: SWS


PLOTTED: JANUARY 6 2022

SCALE:

NORTHSIDE SALT STORAGE SITE SLT1

C082.





DATE

1/27/22

CALCULATIONS

SWM

Pond Summary

PONDPACK REPORT SUMMARY - PEAK FLOWS											
atchments Sumn	nary										
Label	Scenario	Return Event (years)	Hydrograph Volume (ft³)	Time to Peak (hours)	Peak Flow (ft³/s)						
EX. AREA	1 year	1	8,067.000	11.950	3.35						
EX. AREA	10 year	10	20,537.000	11.950	8.28						
PROP. AREA TO FAC	1 year	1	7,397.000	11.950	3.04						
PROP. AREA TO FAC	10 year	10	17,632.000	11.950	6.97						
PROP. AREA BYPASS FAC	1 year	1	2,196.000	11.950	0.89						
PROP. AREA BYPASS FAC	10 year	10	5,015.000	11.950	1.95						

Node Summary					
Label	Scenario	Return Event (years)	Hydrograph Volume (ft³)	Time to Peak (hours)	Peak Flow (ft³/s)
22529 (EX)	1 year	1	8,067.000	11.950	3.35
22529 (EX)	10 year	10	20,537.000	11.950	8.28
22529 (PROP)	1 year	1	9,574.000	12.000	2.77
22529 (PROP)	10 year	101	22,608,000	12.050	5.72

Label	Scenario	Return Event (years)	Hydrograph Volume (ft³)	Time to Peak (hours)	Peak Flow (ft³/s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storag (ft³)
UG DET. (IN)	1 year	1	7,397.000	11.950	3.04	(N/A)	(N/A
UG DET. (OUT)	1 year	1	7,377.000	12.050	2.06	415.01	1,244.000
UG DET. (IN)	10 year	10	17,632.000	11.950	6.97	(N/A)	(N/A
UG DET. (OUT)	10 year	10	17,593.000	12.050	4.45	417.15	3,540.000

- * POST-DEVELOPMENT PEAK FLOW FOR 1-YEAR STORM: 2.06CFS = 2.06CFS (QALLOWABLE) (SEE ENERGY BALANCE EQUATION ON SHEET C085.1, CHANNEL PROTECTION)
- ** POST-DEVELOPMENT PEAK FLOW FOR 10-YEAR STORM: 4.45CFS < 4.48CFS (QALLOWABLE) (SEE ENERGY BALANCE EQUATION ON SHEET C085.1, FLOOD CONTROL)

SLT1 Pondpack report
Subsection: Unit Hydrograph Summary
Label: EX. AREA
Scenario: 1 year

Flow (Peak, Computed)

Output Increment

Time to Flow (Peak

Interpolated Output)

Output)

Drainage Area SCS CN (Composite)

(Pervious)

(Pervious)

Volume

Area (User Defined)

Maximum Retention

Maximum Retention

Cumulative Runoff

(Pervious, 20 percent)

Cumulative Runoff Depth

Runoff Volume (Pervious)

Time of Concentration

Unit Hydrograph Shape

Receding/Rising, Tr/Tp

Computational Time

(Composite)

Increment

K Factor

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54 413.54 413.54 413.54 413.54 413.54 413.54 413.54 413.55 413.55 413.55 413.55 413.55 413.55 413.56 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.57 413.61 413.62 413.65 413.70 414.07 414.94 414.43 414.04 413.84 413.77 413.73 413.70 413.65 413.65 413.65 413.65 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.60 413.60 413.59 413.59 413.59 413.59 413.59 413.59 413.59 413.59 413.59 413.59 413.59 413.58

5.500
5.750
6.000
6.250
6.500
6.750
7.000
7.250
7.500
8.000
8.250
8.500
8.750
9.000
9.250
9.500
10.250
10.500
10.750
11.000
11.250
11.500
11.750
12.000
12.250
12.500
12.750
13.000
13.250
14.000
14.250
14.500
14.500
14.750
15.500
15.550
16.000
16.250
16.500
16.750
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250
17.500
17.250

413.54 413.54 413.54 413.54 413.54 413.54 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.56 413.57 413.58 413.58 413.66 413.72 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.66 413.72 413.70 413.60 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.60 413.60 413.60 413.59 413.58

413.54 413.54 413.54 413.54 413.54 413.54 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.57 413.57 413.57 413.57 413.58 413.60 413.61 413.61 413.63 413.75 413.80 413.63 413.65 413.60 413.60 413.60 413.60 413.60 413.60 413.60 413.60 413.59 413.58

413.54

Subsection: Time vs. Elevation

Label: UG DET. (OUT)

Scenario: 1 year

0.500 0.750

1.000

1.500 1.750 2.000

2.250 2.500

2.750 3.000 3.250

3.500 3.*7*50

4.000

4.500

4.750

SCS Unit Hydrograph Parameters

Hydrograph Volume (Area under Hydrograph curve)

Flow (Peak Interpolated

lydrograph Summary	
Storm Event	1-year
Return Event	1 years
Duration	24.000 hours
Depth	2.6 in
Time of Concentration (Composite)	0.100 hours
Area (User Defined)	1.679 acres
Computational Time Increment	0.013 hours
Time to Peak (Computed)	11.933 hours

3.39 ft³/s

0.050 hours

11.950 hours

3.35 ft³/s

1.679 acres

1.6 in

0.3 in

1.3 in

0.100 hours

0.013 hours

483.432

0.749

1.670

SLT1 Pondpack report

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54 413.54 413.54 413.54 413.54 413.54 413.55 413.55 413.55 413.55 413.55 413.55 413.57 413.57 413.58 413.60 413.60 413.60 413.60 413.61 413.61 413.61 413.61 413.63 413.63 413.63 413.63 413.64 413.65 413.65 413.65 413.65 413.60 413.60 413.60 413.60 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.60 413.60 413.60 413.60 413.60 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.60 413.60 413.60 413.60 413.60 413.60 413.60 413.59 413.58

413.54 413.54 413.54 413.54 413.54 413.54 413.55 413.55 413.55 413.55 413.55 413.55 413.55 413.56 413.57 413.57 413.57 413.57 413.60 413.60 413.62 413.64 413.68 413.71 413.60 413.74 413.71 413.60 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.62 413.63 413.63 413.64 413.65 413.65 413.67 413.61 413.61 413.61 413.61 413.61 413.61 413.61 413.60 413.59 413.58

Time vs. Elevation (ft)

Output Time increment = 0.050 hours

Time on left represents time for first value in each row.

Elevation Elevation Elevation Elevation

413.54

413.54

413.54

413.54

413.54

413.54

413.54

413.54

8,079.444 ft³

8,067.000 ft³

86.000

Return Event Duration Depth Time of Concentration (Composite) Area (User Defined)	10 yea 24.000 hou 4.9 in 0.100 hou 1.679 acr
Computational Time Increment	0.013 hou
Time to Peak (Computed)	11.933 hou
Flow (Peak, Computed)	8.48 ft³/
Output Increment	0.050 hou
Time to Flow (Peak Interpolated Output)	11.950 hou
Flow (Peak Interpolated Output)	8.28 ft³/
Drainage Area	
SCS CN (Composite)	86.000
Area (User Defined)	1.679 acr
Maximum Retention	4.6 :

Cumulative Runoff Depth

Runoff Volume (Pervious)

Time of Concentration

Computational Time

Unit Hydrograph Shape

Receding/Rising, Tr/Tp

(Composite)

Increment

Factor

K Factor

SCS Unit Hydrograph Parameters

Hydrograph Volume (Area under Hydrograph curve)

(Pervious)

Volume

Subsection: Unit Hydrograph Summary

Storm Event

Label: EX. AREA

Scenario: 10 year

Return Event	10 years	
Duration	24.000 hours	
Depth	4.9 in	
Time of Concentration (Composite)	0.100 hours	
Area (User Defined)	1.679 acres	
Computational Time Increment	0.013 hours	
Time to Peak (Computed)	11.933 hours	
Flow (Peak, Computed)	8.48 ft³/s	
Output Increment	0.050 hours	
Time to Flow (Peak Interpolated Output)	11.950 hours	
Flow (Peak Interpolated Output)	8.28 ft³/s	
Drainage Area		
SCS CN (Composite)	86.000	
Area (User Defined)	1.679 acres	
Maximum Retention (Pervious)	1.6 in	
Maximum Retention (Pervious, 20 percent)	0.3 in	

3.4 in

0.100 hours

0.013 hours

20,562.710 ft³

20,537.000 ft³

483.432

0.749

SLT1 Pondpack report

			Edben Trott Miles
Scenario: 1 year			Scenario: 10 year
	Storm Event	1-year	=
	Return Event	1 years	
	Duration	24.000 hours	
	Depth	2.6 in	
	Time of Concentration (Composite)	0.100 hours	
	Area (User Defined)	0.356 acres	
			=
	Computational Time Increment	0.013 hours	_
	Time to Peak (Computed)	11.933 hours	
	Flow (Peak, Computed)	0.91 ft³/s	
	Output Increment	0.050 hours	
	Time to Flow (Peak Interpolated Output)	11.950 hours	
	Flow (Peak Interpolated Output)	0.89 ft³/s	
	Drainage Area		=
	SCS CN (Composite)	91.000	_
	Area (User Defined)	0.356 acres	
	Maximum Retention (Pervious)	1.0 in	
	Maximum Retention (Pervious, 20 percent)	0.2 in	
	Cumulative Runoff		=

1.7 in

2,199.001 ft³

2,196.000 ft³

0.100 hours

0.013 hours

16.750 17.000 17.250 17.500 17.750 18.000 18.250 18.500 19.500 19.250 19.500 20.250 20.500 20.750 21.000 21.250 21.500 21.750 22.000 22.250 22.500 22.500 22.500 23.500 23.750 23.500 23.750 24.000

16.000 16.000 15.000 15.000 14.000 14.000 13.000 12.000 12.000 12.000 11.000 10.000 10.000 10.000 9.000

483.432

0.749

Cumulative Runoff Depth

Runoff Volume (Pervious)

SCS Unit Hydrograph Parameters

Time of Concentration

Computational Time

Unit Hydrograph Shape

Receding/Rising, Tr/Tp

Hydrograph Volume (Area under Hydrograph curve)

(Pervious)

Volume

(Composite)

Increment

Factor

K Factor

SLT1 Pondpack report

Subsection: Unit Hydrograph Summary

Label: PROP. AREA BYPASS FAC

Increment	
Time to Peak (Computed)	11.933 hours
Flow (Peak, Computed)	2.01 ft³/s
Output Increment	0.050 hours
Time to Flow (Peak Interpolated Output)	11.950 hours
Flow (Peak Interpolated Output)	1.95 ft³/s
Drainage Area	
SCS CN (Composite)	91.000
Area (User Defined)	0.356 acres
Maximum Retention (Pervious)	1.0 in
Maximum Retention (Pervious, 20 percent)	0.2 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	3.9 in
Runoff Volume (Pervious)	5,020.641 ft³
Hydrograph Volume (Area ur	nder Hydrograph curve)
Volume	5,015.000 ft ³
000111111111111111111111111111111111111	
SCS Unit Hydrograph Param	eters
Time of Concentration (Composite)	0.100 hours
	0.100 hours 0.013 hours

SLT1 Pondpack report

10-year

24.000 hours

4.9 in

0.100 hours

0.356 acres

0.013 hours

0.749

1.670

Subsection: Unit Hydrograph Summary

Storm Event

Return Event

Time of Concentration

Area (User Defined)

Computational Time

Increment

K Factor

SLT1 Pondpack report

Receding/Rising, Tr/Tp

Duration

Label: PROP. AREA BYPASS FAC

SLT1 Pondpack report **SLT1 Pondpack report** Subsection: Unit Hydrograph Summary Subsection: Unit Hydrograph Summary Label: PROP. AREA TO FAC Label: PROP. AREA TO FAC Scenario: 1 year Scenario: 10 year Storm Event

Storm Event	1-year
Return Event	1 years
Duration	24.000 hours
Depth	2.6 in
Time of Concentration (Composite)	0.100 hours
Area (User Defined)	1.323 acres
Community in a little of	
Computational Time Increment	0.013 hours
Time to Peak (Computed)	11.933 hours
Flow (Peak, Computed)	3.10 ft³/s
Output Increment	0.050 hours
Time to Flow (Peak Interpolated Output)	11.950 hours
Flow (Peak Interpolated Output)	3.04 ft³/s
Drainage Area	
SCS CN (Composite)	89.000
Area (User Defined)	1.323 acres
Maximum Retention (Pervious)	1.2 in
Maximum Retention (Pervious, 20 percent)	0.2 in
Cumulative Runoff	
Cumulative Runoff Depth (Pervious)	1.5 in
Runoff Volume (Pervious)	7,406.885 ft³
Hydrograph Volume (Area ur	nder Hydrograph curve)
,3	

SLT1 Pondpack report

Time of Concentration

Computational Time

Unit Hydrograph Shape

Receding/Rising, Tr/Tp

(Composite)

K Factor

7,406.885 113	Runoff Volume (Pervious)	17,652.757 ft³
Hydrograph curve)	Hydrograph Volume (Area und	er Hydrograph curve)
7,397.000 ft³	Volume	17,632.000 ft³
	SCS Unit Hydrograph Parame	ters
0.100 hours	Time of Concentration (Composite)	0.100 hours
0.013 hours	Computational Time Increment	0.013 hours
483.432	Unit Hydrograph Shape Factor	483.432
0.749	K Factor	0.749
1.670	Receding/Rising, Tr/Tp	1.670

ARLINGTON VIRGINIA

10-year

10 years

24.000 hours

4.9 in

0.100 hours

1.323 acres

0.013 hours

11.933 hours

7.16 ft³/s

0.050 hours

11.950 hours

6.97 ft³/s

1.323 acres

1.2 in

0.2 in

3.7 in

17,652.757 ft³

89.000

Return Event

Time of Concentration

Area (User Defined)

Computational Time

Time to Peak (Computed)

Flow (Peak, Computed)

Output Increment

Time to Flow (Peak

SCS CN (Composite)

Area (User Defined)

Maximum Retention

Maximum Retention

Cumulative Runoff

(Pervious, 20 percent)

Cumulative Runoff Depth

(Pervious)

(Pervious)


Output)

Interpolated Output)

Flow (Peak Interpolated

Duration

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606 COPYRIGHT © 2021 ARLINGTON COUNTY



SOLOMON W SHIKU Lic. No. 44276 1/6/2022	R A HARD
APPROVALS	DATE
Amy Pflaum	01/18/22

QUALITY CONTROL ENGINEER Oldam & Kulaury CONSTRUCTION MANAGEMENT SUPERVISOR WATER, SEWER, STREETS BUREAU CHIEF

Dennis M. Leach
TRANSPORTATION DIRECTOR John Mir 1/27/22 PROJECT MANAGER

REVISIONS

DETENTION CALCULATIONS

STORMWATER

SITE

STORAGE

NORTHSIDE

DESIGNED: SEB DRAWN: SEB CHECKED: SWS

PLOTTED: JANUARY 6 2022

SCALE:

C085.2 NORTHSIDE SALT STORAGE SITE SLT1

Structure ID: Riser - 1	
Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	18.0 in
Length	24.50 ft
Length (Computed Barrel)	24.50 ft
Slope (Computed)	0.018 ft/ft
Structure ID: Orifice - 1 Structure Type: Orifice-Circular	
Number of Openings	1
Elevation	413.54 ft
Orifice Diameter	9.8 in
Orifice Coefficient	0.600
Structure ID: Weir - 1 Structure Type: Rectangular Weir	
Number of Openings	1
Elevation	417.04 ft
Weir Length	2.50 ft
Weir Coefficient	3.00 (ft^0.5)/s

Label: Composite Outlet Structure - 1

Scenario: 1 year

414.54	1.4/	(N/A) [0.00
415.04	2.10	(N/A)	0.00
415.54	2.63	(N/A)	0.00
416.04	3.08	(N/A)	0.00
416.54	3.49	(N/A)	0.00
417.04	3.86	(N/A)	0.00
417.54	6.59	(N/A)	0.00
78.0000.00	SUSPRESE I	***************************************	ESPO CORE
Label: Composite Outl	et Structure - 1		
Scenario: 10 year	ct Structure 1		
Scenario. 10 year			
Composite Outflow Sumn	nary		
Composite Outflow Sumn Water Surface	Flow	Tailwater Elevation	Convergence Error
Water Surface Elevation	•	Tailwater Elevation (ft)	Convergence Error (ft)
Water Surface Elevation (ft)	Flow (ft³/s)	(ft)	(ft)
Water Surface Elevation (ft) 413.54	Flow (ft³/s)	(ft) (N/A)	(ft)
Water Surface Elevation (ft) 413.54 414.04	Flow (ft³/s) 0.00 0.48	(ft) (N/A) (N/A)	(ft) 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04 414.54	Flow (ft³/s) 0.00 0.48 1.47	(ft) (N/A) (N/A) (N/A)	0.00 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04	Flow (ft³/s) 0.00 0.48	(ft) (N/A) (N/A)	(ft) 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04 414.54	Flow (ft³/s) 0.00 0.48 1.47	(ft) (N/A) (N/A) (N/A)	0.00 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04 414.54 415.04	Flow (ft³/s) 0.00 0.48 1.47 2.10	(ft) (N/A) (N/A) (N/A) (N/A)	0.00 0.00 0.00 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04 414.54 415.04 415.54	Flow (ft³/s) 0.00 0.48 1.47 2.10 2.63	(ft) (N/A) (N/A) (N/A) (N/A) (N/A) (N/A)	0.00 0.00 0.00 0.00 0.00 0.00
Water Surface Elevation (ft) 413.54 414.04 414.54 415.04 415.54 416.04	Flow (ft³/s) 0.00 0.48 1.47 2.10 2.63 3.08	(ft) (N/A) (N/A) (N/A) (N/A) (N/A) (N/A) (N/A)	0.00 0.00 0.00 0.00 0.00 0.00 0.00

SLT1 Pondpack report Subsection: Time vs. Elevation Label: UG DET. (OUT) Scenario: 10 year

7	ime vs. Elevation (ft)	
Output T	ime increment = 0.050 ho	ur

		Outnut	Time increm	ont - 0.050	haura	
		ne on left rep		ent = 0.050 for first valu	e in each rov	
	Time (hours)	Elevation (ft)	(ft)	Elevation (ft)	Elevation (ft)	Elevation (ft)
	0.000 0.250	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54
	0.500	413.54	413.54	413.54	413.54	413.54
	0.750	413.54	413.54	413.54	413.54	413.54
	1.000	413.54	413.54	413.54	413.54	413.54
	1.250	413.54	413.54	413.54	413.54	413.54
	1.500	413.54	413.54	413.54	413.54	413.54
	1.750 2.000	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54
	2.250	413.54	413.54	413.54	413.54	413.54
	2.500	413.54	413.54	413.54	413.54	413.54
	2.750	413.54	413.54	413.54	413.54	413.54
	3.000	413.54	413.54	413.54	413.54	413.54
	3.250	413.54	413.54	413.54	413.54	413.54
	3.500	413.54	413.54	413.54	413.54	413.54
	3.750 4.000	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54	413.54 413.54
	4.250	413.54	413.54	413.54	413.54	413.54
	4.500	413.54	413.54	413.54	413.54	413.54
	4.750	413.54	413.54	413.55	413.55	413.55
	5.000	413.55	413.55	413.55	413.55	413.55
	5.250	413.55	413.55	413.55	413.55	413.55
	5.500	413.55	413.55	413.56	413.56	413.56
	5.750 6.000	413.56 413.56	413.56 413.56	413.56 413.56	413.56 413.56	413.56 413.56
	6.250	413.56	413.57	413.57	413.57	413.57
	6.500	413.57	413.57	413.57	413.57	413.57
	6.750	413.57	413.57	413.57	413.57	413.58
	7.000	413.58	413.58	413.58	413.58	413.58
	7.250	413.58	413.58	413.58	413.58	413.58
	7.500	413.58	413.59	413.59	413.59	413.59
	7.750 8.000	413.59	413.59	413.59	413.59	413.59
	8.000 8.250	413.59 413.60	413.59 413.60	413.60 413.60	413.60 413.60	413.60 413.61
	8.500	413.61	413.61	413.61	413.62	413.62
	8.750	413.62	413.62	413.62	413.63	413.63
	9.000	413.63	413.63	413.64	413.64	413.64
	9.250	413.64	413.64	413.64	413.65	413.65
	9.500	413.65	413.65	413.65	413.65	413.65
ļ	9.750	413.66	413.66	413.66	413.67	413.67
	10.000 10.250	413.67 413.70	413.68 413.70	413.68 413.71	413.69 413.71	413.69 413.72
	10.500	413.73	413.73	413.74	413.75	413.76
	10.750	413.76	413.77	413.78	413.79	413.80
	11.000	413.81	413.82	413.84	413.85	413.87
	11.250	413.89	413.91	413.93	413.96	413.98
	11.500	414.01	414.05	414.11	414.20	414.36
	11.750	414.57	414.82	415.17	415.69	416.30
	12.000	416.85 415.92	417.15	416.96 415.37	416.61	416.25
	12.250 12.500	415.92	415.63 414.57	415.37	415.14 414.30	414.93 414.22
	12.750	414.16	414.12	414.09	414.07	414.05
	13.000	414.03	414.00	413.98	413.97	413.95
	13.250	413.94	413.92	413.91	413.90	413.89
	13.500	413.88	413.87	413.86	413.86	413.85
	13.750	413.84	413.83	413.83	413.82	413.81
	14.000 14.250	413.81	413.80	413.79 413.77	413. <i>7</i> 9 413. <i>7</i> 7	413. <i>7</i> 8 413. <i>7</i> 7
	14.250	413.78 413.76	413.78 413.76	413.77	413.77	413.76
	14.750	413.75	413.75	413.75	413.75	413.74
	15.000	413.74	413.74	413.74	413.74	413.73
	15.250	413.73	413.73	413.73	413.72	413.72
	15.500	413.72	413.72	413.72	413.71	413.71
	15.750	413.71	413.71	413.70	413.70	413.70
	16.000	413.70	413.70	413.69	413.69	413.69
	16.250 16.500	413.69 413.68	413.69 413.68	413.69 413.68	413.69 413.68	413.68 413.68
	16.750	413.68	413.68	413.68	413.68	413.68
	17.000	413.68	413.67	413.67	413.67	413.67
	17.250	413.67	413.67	413.67	413.67	413.67
	17.500	413.67	413.67	413.67	413.67	413.66
	17.750	413.66	413.66	413.66	413.66	413.66
	18.000	413.66	413.66	413.66	413.66	413.66
	18.250 18.500	413.66 413.65	413.65 413.65	413.65 413.65	413.65 413.65	413.65 413.65
	18.750	413.65	413.65	413.65	413.65	413.64
	19.000	413.64	413.64	413.64	413.64	413.64
	19.250	413.64	413.64	413.64	413.64	413.64
	19.500	413.64	413.63	413.63	413.63	413.63
	19.750	413.63	413.63	413.63	413.63	413.63
ļ	20.000	413.63	413.63	413.63	413.63	413.63
	20.250	413.62	413.62	413.62	413.62	413.62
	20.500 20.750	413.62 413.62	413.62 413.62	413.62 413.62	413.62 413.62	413.62 413.62
	20.750	413.62	413.62	413.62	413.62	413.62
	21.250	413.62	413.62	413.62	413.62	413.62
	21.500	413.62	413.62	413.62	413.62	413.62
	21.750	413.62	413.62	413.62	413.62	413.62
	22.000	413.62	413.62	413.62	413.62	413.62
	22.250	413.62	413.62	413.62	413.62	413.62
	22.500	413.62	413.62	413.62	413.62	413.62
	22.750	413.62	413.62	413.62	413.62	413.62
	23.000 23.250	413.62 413.61	413.62 413.61	413.61 413.61	413.61 413.61	413.61 413.61
	23.250	413.61	413.61	413.61	413.61	413.61
	23.750	413.61	413.61	413.61	413.61	413.61
	24.000	413.61	(N/A)	(N/A)	(N/A)	(N/A)

		Time vs. Vol	ume (ft³)							
Output Time increment = 0.050 hours Time on left represents time for first value in each row.										
Time	Volume	Volume	Volume	Volume	Volume					
(hours)	(ft³)	(ft³)	(ft³)	(ft³)	(ft³)					
0.000	0.000	0.000	0.000	0.000	0.000					
0.250	0.000	0.000	0.000	0.000	0.000					
0.500 0. <i>7</i> 50	0.000	0.000	0.000	0.000	0.000					
1.000	0.000	0.000	0.000	0.000	0.000					
1.250	0.000	0.000	0.000	0.000	0.000					
1.500	0.000	0.000	0.000	0.000	0.000					
1.750	0.000	0.000	0.000	0.000	0.000					
2.000	0.000	0.000	0.000	0.000	0.000					
2.250	0.000	0.000	0.000	0.000	0.000					
2.500	0.000	0.000	0.000	0.000	0.000					
2. <i>7</i> 50	0.000	0.000	0.000	0.000	0.000					
3.000	0.000	0.000	0.000	0.000	0.000					
3.250	0.000	0.000	0.000	0.000	0.000					
3.500	0.000	0.000	0.000	0.000	0.000					
3.750	0.000	0.000	0.000	0.000	0.000					
4.000	0.000	0.000	0.000	0.000	0.000					
4.250	0.000	0.000	0.000	0.000	0.000					
4.500	0.000	0.000	0.000	0.000	0.000					
4.750	0.000	0.000	0.000	0.000	0.000					
5.000	0.000	0.000	0.000	0.000	0.000					
5.250	0.000	0.000	0.000	0.000	0.000					
5.500	0.000	0.000	0.000	0.000	0.000					
5.750 6.000	0.000	0.000	0.000	0.000	0.000					
6.250	0.000	0.000	0.000	0.000	0.000					
6.500	0.000	0.000	0.000	0.000	0.000					
6.750	0.000	0.000	0.000	0.000	0.000					
7.000	0.000	0.000	0.000	0.000	0.000					
7.250	0.000	0.000	0.000	1.000	1.000					
7.500	1.000	1.000	1.000	1.000	1.000					
7.750	1.000	1.000	1.000	1.000	1.000					
8.000	1.000	2.000	2.000	2.000	2.000					
8.250	2.000	2.000	2.000	2.000	2.000					
8.500	3.000	3.000	3.000	3.000	3.000					
8. <i>7</i> 50	3.000	3.000	4.000	4.000	4.000					
9.000	4.000	4.000	5.000	5.000	5.000					
9.250	5.000	5.000	5.000	6.000	6.000					
9.500	6.000	6.000	6.000	6.000	6.000					
9.750	7.000	7.000	7.000	8.000	8.000					
10.000	8.000	8.000	9.000	9.000	10.000					
10.250	10.000	10.000	11.000 14.000	11.000	12.000					
10.500 10.750	12.000 16.000	13.000 16.000	17.000	14.000 18.000	15.000 19.000					
11.000	21.000	22.000	24.000	26.000	29.000					
11.250	32.000	35.000	38.000	41.000	45.000					
11.500	49.000	57.000	78.000	118.000	188.000					
11.750	293.000	389.000	537.000	758.000	989.000					
12.000	1,172.000	1,244.000	1,161.000	977.000	794.000					
12.250	621.000	494.000	405.000	349.000	305.000					
12.500	270.000	225.000	192.000	166.000	146.000					
12.750	130.000	117.000	106.000	97.000	91.000					
13.000	85.000	79.000	74.000	70.000	66.000					
13.250	63.000	60.000	57.000	54.000	52.000					
13.500	50.000	49.000	47.000	46.000	44.000					
13.750	43.000	42.000	40.000	39.000	38.000					
14.000	37.000	36.000	35.000	34.000	33.000					
14.250	32.000	32.000	31.000	30.000	30.000					
14.500	30.000	29.000	29.000	28.000	28.000					
14.750	27.000	27.000	27.000	26.000	26.000					
15.000	25.000	25.000	25.000	24.000	24.000					
15.250 15.500	23.000 21.000	23.000	23.000 21.000	22.000 20.000	22.000 20.000					
15.500	19.000	21.000 19.000	19.000	19.000	18.000					
16.000	18.000	19.000	19.000	17.000	17.000					
16.250	17.000	17.000	17.000	17.000	17.000					
16.500	16.000	16.000	16.000	16.000	16.000					
		_0.000	_0.000	_0.000	10.000					

, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Output Time increment = 0.050 hours Time on left represents time for first value in each row.								
Time	Volume	Volume	Volume	Volume	Volume				
(hours) 0.000	(ft³) 0.000	(ft³) 0.000	(ft³) 0.000	(ft³)	(ft³) 0.000				
0.250	0.000	0.000	0.000	0.000	0.000				
0.500 0. <i>7</i> 50	0.000	0.000	0.000	0.000	0.000				
1.000	0.000	0.000	0.000	0.000	0.000				
1.250	0.000	0.000	0.000	0.000	0.000				
1.500 1.750	0.000	0.000	0.000	0.000	0.000				
2.000	0.000	0.000	0.000	0.000	0.000				
2.250	0.000	0.000	0.000	0.000	0.000				
2.500 2. <i>7</i> 50	0.000	0.000	0.000	0.000	0.000				
3.000	0.000	0.000	0.000	0.000	0.000				
3.250	0.000	0.000	0.000	0.000	0.000				
3.500 3. <i>7</i> 50	0.000	0.000	0.000	0.000	0.000				
4.000	0.000	0.000	0.000	0.000	0.000				
4.250	0.000	0.000	0.000	0.000	0.000				
4.500 4.750	0.000 1.000	0.000 1.000	1.000 1.000	1.000 1.000	1.000 2.000				
5.000	2.000	2.000	2.000	2.000	2.000				
5.250	2.000	3.000	3.000	3.000	3.000				
5.500 5. <i>7</i> 50	3.000 4.000	3.000 4.000	4.000 4.000	4.000 5.000	4.000 5.000				
6.000	5.000	5.000	5.000	5.000	6.000				
6.250	6.000	6.000	6.000	6.000	7.000				
6.500 6.750	7.000 8.000	7.000 8.000	7.000 8.000	7.000 8.000	7.000 8.000				
7.000	9.000	9.000	9.000	9.000	9.000				
7.250	10.000	10.000	10.000	10.000	10.000				
7.500 7. <i>7</i> 50	11.000 12.000	11.000 12.000	11.000 12.000	11.000 12.000	11.000 12.000				
8.000	13.000	13.000	13.000	13.000	14.000				
8.250	14.000	15.000	15.000	15.000	16.000				
8.500 8. <i>7</i> 50	16.000 19.000	17.000 20.000	17.000 21.000	18.000 22.000	18.000 23.000				
9.000	23.000	24.000	25.000	26.000	27.000				
9.250	27.000	28.000	29.000	29.000	29.000				
9.500 9.750	30.000 33.000	30.000 35.000	31.000 36.000	32.000 37.000	32.000 39.000				
10.000	40.000	41.000	43.000	45.000	47.000				
10.250	49.000	51.000	53.000	56.000	59.000				
10.500 10.750	63.000 83.000	66.000 88.000	70.000 94.000	74.000 99.000	78.000 106.000				
11.000	113.000	120.000	128.000	138.000	149.000				
11.250	1 61.000	175.000	189.000	205.000	224.000				
11.500 11.750	244.000 764.000	278.000 1,033.000	326.000 1,440.000	406.000 2,047.000	555.000 2 <i>,</i> 749.000				
12.000	3,304.000	3,540.000	3,400.000	3,080.000	2,696.000				
12.250	2,323.000	1,986.000	1,677.000	1,402.000	1,154.000				
12.500 12.750	939.000 3 <i>7</i> 3.000	767.000 339.000	611.000 313.000	500.000 293.000	422.000 277.000				
13.000	260.000	242.000	226.000	212.000	201.000				
13.250	192.000	184.000	177.000	170.000	164.000				
13.500 13.750	157.000 130.000	151.000 125.000	145.000 121.000	140.000 116.000	135.000 112.000				
14.000	108.000	104.000	100.000	97.000	94.000				
14.250	92.000	90.000	88.000	87.000	85.000				
14.500 14.750	84.000 77.000	82.000 76.000	81.000 75.000	80.000 74.000	79.000 72.000				
15.000	71.000	70.000	69.000	68.000	66.000				
15.250	65.000	64.000	63.000	61.000	60.000				
15.500	59.000	58.000	57.000	55.000	54.000				
15.750 16.000	53.000 49.000	52.000 48.000	51.000 47.000	51.000 47.000	50.000 46.000				
16.250	45.000	45.000	45.000	44.000	44.000				
16.500	43.000	43.000	43.000	42.000	42.000				
16.750 17.000	42.000 40.000	41.000 40.000	41.000 40.000	41.000 39.000	41.000 39.000				
17.250	39.000	38.000	38.000	38.000	38.000				
17.500	37.000	37.000	37.000	36.000	36.000				
17.750 18.000	36.000 34.000	35.000 34.000	35.000 34.000	35.000 33.000	35.000 33.000				
18.250	33.000	32.000	32.000	32.000	31.000				
18.500	31.000	31.000	31.000	30.000	30.000				
18.750 19.000	30.000 28.000	29.000 28.000	29.000 27.000	29.000 27.000	28.000 27.000				
19.000	28.000	26.000	26.000	26.000	25.000				
19.500	25.000	25.000	24.000	24.000	24.000				
19.750 20.000	24.000 22.000	23.000 22.000	23.000 21.000	23.000 21.000	22.000 21.000				
20.250	22.000	22.000	21.000	20.000	20.000				
20.500	20.000	20.000	20.000	20.000	20.000				
20.750 21.000	20.000 20.000	20.000 20.000	20.000 19.000	20.000 19.000	20.000 19.000				
21.000	19.000	19.000	19.000	19.000	19.000				
21.500	19.000	19.000	19.000	19.000	19.000				
21.750	19.000	19.000	19.000	19.000	19.000				
22.000 22.250	19.000 18.000	19.000 18.000	19.000 18.000	19.000 18.000	18.000 18.000				
22.500	18.000	18.000	18.000	18.000	18.000				
22.750	18.000	18.000	18.000	18.000	18.000				
23.000 23.250	18.000 18.000	18.000 18.000	18.000 18.000	18.000 18.000	18.000 18.000				
		17.000	17.000	17.000	17.000				
23.500	18.000	17.000	17.000	17.000	•				

= 0.050 hours first value in each row.					Subsection: Ti Label: UG DET	Г.	e			
	ie (ft³)				Scenario: 10 y	ear	Time vs. Vo	lume (ft³)		
Control Cont	/olume	Volume	Volume		Time	Volume	Volume	Volume	Volume	Volume
0.000	0.000	0.000	0.000		0.000	0.000	0.000	0.000	0.000	0.000
1.000	0.000	0.000	0.000			I	0.000	I	0.000	0.000
1.000						I				
1.000					1.250	0.000	0.000	0.000	0.000	0.000
1.000	0.000	0.000	0.000			I		I		
						I				
0.000	0.000	0.000	0.000		2.500	0.000	0.000	0.000	0.000	0.000
0.000						I				
0.000					I I	I				
0.000	0.000	0.000	0.000		3.750	II	0.000	0.000	0.000	0.000
	I .					II				
0.000					4.500	I	0.000		1.000	1.000
0.000	0.000	0.000	0.000		I I	II				2.000
0.000	I .					II				
0.000	0.000	0.000	0.000		5. <i>7</i> 50	4.000	4.000	4.000	5.000	5.000
0.000	0.000	0.000	0.000		I I	II				
0.000						I		I		7.000
1.000	0.000	0.000	0.000		7.000	9.000	9.000	9.000	9.000	9.000
1.000	1.000	1.000	1.000			I				
2.000	1.000	1.000	1.000		7. <i>7</i> 50	12.000	12.000	12.000	12.000	12.000
4.000	2.000	2.000	2.000			I				
5.000										
6.000					9.000	23.000	24.000	25.000	26.000	27.000
9,000 9,000 10,000 10,000 10,000 40,000 41,000 45,000 47,000 14,000 14,000 14,000 15,000 53,000 59,000 59,000 14,000 14,000 15,000 15,000 15,000 53,000 59,000 59,000 16,000 24,	6.000	6.000	6.000							
11.000		j j	j j							
17.000	11.000	11.000	12.000		10.250	49.000	51.000	53.000	56.000	59.000
18.000	17.000	18.000								
78,000	I .									
	78.000	118.000	188.000		11.500	244.000	278.000	326.000	406.000	555.000
495,000	1,161.000									
106.000 97.000 91.000 91.000 12.750 373.000 339.000 313.000 223.000 277.000 277.000 54.000 52.000 13.200 13.200 122.000 117.000 170.000 164.000 13.250 132.000 151.000 177.000 170.000 164.000 13.500 13.500 135.000 122.000 116.000 135.0		I			12.250	2,323.000	1,986.000	1,677.000	1,402.000	1,154.000
17,000 54,000 52,000 13,250 192,000 184,000 177,000 170,000 164,000 135,000 137,000 137,000 135,000 135,000 135,000 135,000 135,000 135,000 135,000 135,000 140,000 135,000 140,000 135,000 140,000 135,000 140,000 130,000 140,000 130,000 140,000 130,000 140,000 100,000 97,000 94,000 31,000 30,000 30,000 30,000 34,000 32,000 30,000	106.000	97.000	91.000					1		
47,000 46,000 44,000 135,000 137,000 151,000 145,000 146,000 135,000 30,000 33,000 33,000 14,000 136,000 125,000 125,000 126,000 37,000 34,000 33,000 30,000 34,000 30,000 34,000 30,000 34,000 30,000 34,000 30,000 34,000 30,000 34,000 34,000 36,000 37,000 38,000 38,000	I .									
14.000 33.000 33.000 14.000 109.000 87.000 85.000 87.000 85.000 29.000 28.000 28.000 28.000 14.250 92.000 92.000 88.000 87.000 85.000 27.000 28.000 28.000 28.000 14.250 94.000 82.000 81.000 87.000 79.000 27.000 28.000 28.000 28.000 14.750 77.000 76.000 75.000 79.000	47.000	46.000	44.000		13.500	157.000	151.000	145.000	140.000	135.000
29.000 28.000 28.000 28.000 26.000 14.500 84.000 82.000 81.000 79.000 77.000 72.000 26.000 26.000 26.000 14.750 77.000 76.000 75.000 76.000 68.000 66.000 68.000 66.000 68.000 6		34.000	33.000							
27.000 26.000 26.000 24.000 15.000 77.000 76.000 76.000 76.000 68.000 6	I .									
22,000 22,000 22,000 15,250 65,000 64,000 63,000 61,000 60,000 21,000 20,000 19,000 15,550 59,000 58,000 51,000 51,000 55,000 36,000 19,000 17,000 17,000 16,000 49,000 48,000 47,000 47,000 46,000 37,000 17,000 17,000 16,250 48,000 45,000 44,000 44,000 44,000 38,000 17,000 17,000 16,000 16,500 44,000 45,000 43,000 43,000 42,000 42,000 38,000 16,000 16,000 16,500 44,000 44,000 44,000 44,000 39,000 39,000 39,000 39,000 39,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 38,000 35,000 35,000 35,000 38,000 38,000 35,000 35,000 35,000 35,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 39,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 39,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,000 30,	27.000	26.000	26.000		14.750	77.000	76.000	75.000	74.000	72.000
19.000 19.000 19.000 15.000 15.500 59.000 58.000 57.000 55.000 54.000 18.000 17.000 17.000 17.000 17.000 17.000 17.000 17.000 16.000 49.000 48.000 47.000 47.000 46.000 17.000 17.000 17.000 16.000 16.500 45.000 45.000 45.000 44.000 44.000 44.000 16.000 16.000 16.000 16.500 43.000 43.000 43.000 42.000 44.000 16.000 15.000 15.000 15.000 17.000 40.000 40.000 40.000 40.000 39.000 39.000 15.000 15.000 15.000 17.000 40.000 40.000 40.000 38.000 3		22.000	22.000							
18,000	I .				15.500	59.000	58.000	57.000	55.000	54.000
16.000	18.000	17.000	17.000		16.000	49.000	48.000	47.000	47.000	46.000
15.000		I								
15.000	16.000	16.000	16.000		16.750	42.000	41.000	41.000	41.000	41.000
14.000 14.000 14.000 14.000 17.750 36.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 35.000 33.000 33.000 33.000 33.000 33.000 33.000 33.000 33.000 33.000 32.000 32.000 33.000 30.000 20.000 20.000 20.000 20.000 20.000 20.000 20.000 20.000 20.000 20.000 20.000<	15.000	15.000	15.000		17.250	39.000	38.000	38.000	38.000	38.000
14,000 14,000 13,000 13,000 34,000 34,000 33,000 33,000 33,000 33,000 33,000 33,000 33,000 32,000 32,000 32,000 32,000 32,000 30,000 31,000 31,000 31,000 31,000 31,000 31,000 30,000 20,000 20,000 20,000 20,000 20,000 20,000 20,000 20,000 20,000<		I						1		
13.000 13.000 13.000 13.000 31.000 31.000 30.000 30.000 30.000 30.000 29.000 29.000 29.000 29.000 28.000 28.000 29.000 29.000 29.000 28.000 28.000 28.000 29.000 29.000 29.000 29.000 29.000 28.000 28.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 27.000 27.000 27.000 27.000 27.000 27.000 27.000 27.000 21.000 29.000<	14.000	14.000	13.000		18.000	34.000	34.000	34.000	33.000	33.000
12.000 12.000 12.000 12.000 12.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 29.000 27.000<	13.000	13.000	13.000		18.500	31.000	31.000	31.000	30.000	30.000
11.000 11.000 11.000 11.000 26.000 26.000 26.000 25.000 11.000 11.000 11.000 11.000 25.000 25.000 24.000 24.000 24.000 10.000 10.000 10.000 10.000 20.000 22.000 21.000 20.000					18.750	30.000				28.000
10.000 10.000 10.000 10.000 23.000 23.000 23.000 23.000 23.000 23.000 22.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 21.000 20.000<	11.000	11.000	11.000		19.250	27.000	26.000	26.000	26.000	25.000
10.000 10.000 10.000 10.000 20.000 22.000 22.000 21.000 21.000 21.000 21.000 20.000 2	10.000	10.000								
10.000 10.000 10.000 20.500 20.000 19.000<					20.000	22.000	22.000	21.000	21.000	21.000
9.000 9.000 9.000 20.000 20.000 19.000 19.000 19.000 9.000 9.000 9.000 18.000 18.000	10.000	10.000	10.000		20.500	20.000	20.000	20.000	20.000	20.000
9.000 9.000 9.000 18.000 18.000 18.000 18.000 18.000 <td></td> <td></td> <td></td> <td></td> <td></td> <td>I .</td> <td></td> <td></td> <td></td> <td></td>						I .				
9.000 9.000 9.000 18.000 18.000 <td>9.000</td> <td>9.000</td> <td>9.000</td> <td></td> <td>21.250</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td>19.000</td>	9.000	9.000	9.000		21.250	19.000	19.000	19.000	19.000	19.000
9.000 9.000 9.000 19.000 19.000 19.000 19.000 19.000 19.000 19.000 18.000 <td>9.000</td> <td>9.000</td> <td>9.000</td> <td></td> <td>21.750</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td></td>	9.000	9.000	9.000		21.750	19.000	19.000	19.000	19.000	
9.000 9.000 9.000 18.000 <td></td> <td></td> <td></td> <td></td> <td>22.000</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td>19.000</td> <td>18.000</td>					22.000	19.000	19.000	19.000	19.000	18.000
9.000 9.000 9.000 18.000 17.000 <td>9.000</td> <td>9.000</td> <td>9.000</td> <td></td> <td>22.500</td> <td>18.000</td> <td>18.000</td> <td>18.000</td> <td>18.000</td> <td>18.000</td>	9.000	9.000	9.000		22.500	18.000	18.000	18.000	18.000	18.000
9.000 9.000 9.000 18.000 18.000 18.000 18.000 18.000 18.000 18.000 18.000 18.000 18.000 17.000 <td></td>										
8.000 8.000 8.000 23.750 17.000 17.000 17.000 17.000	9.000	9.000	9.000		23.250	18.000	18.000	18.000	18.000	18.000
	8.000	8.000	8.000		23.750	17.000	17.000	17.000	17.000	17.000
	(N/A)	(N/A)	(N/A)		24.000	17.000	(N/A)	(N/A)	(N/A)	(N/A)

GENERAL MOT NOTES:

- PROJECT IS A "TYPE A" TMP PROJECT. THIS PROJECT SUPPORTS FOR THE IMPROVEMENT OF THE NORTHSIDE SALT STORAGE SITE.
- THE DESIGN FOR THE NORTHSIDE SALT STORAGE PROJECT INCLUDES STORMWATER IMPROVEMENTS, SUCH AS QUALITY AND QUANTITY DESIGN, AND A PROPOSED STORM PIPE NETWORK WHICH WILL CONNECT TO AN EXISTING STORM PIPE
- THE WORKING HOURS WITHIN ARLINGTON COUNTY RIGHT-OF-WAY ARE AS FOLLOWS:

9:00 AM TO 4:00 PM *Not Allowed *Not Allowed

- BEFORE AND AFTER WORKING HOURS, ALL TRAVEL LANES SHALL BE OPENED TO THE MOTORISTS.
- NO LANE CLOSURES WILL BE ALLOWED FROM NOON ON THE DAY BEFORE A HOLIDAY UNTIL NOON ON THE WORKDAY FOLLOWING THE HOLIDAY. HOLIDAYS INCLUDE ALL STATE AND FEDERAL HOLIDAYS.
- MAINTENANCE OF TRAFFIC (MOT) PLAN WHICH INCLUDES THE SEQUENCE OF CONSTRUCTION (SOC) WAS REVIEWED AND
- APPROVED BY THE ARLINGTON COUNTY TRANSPORTATION ENGINEERING AND OPERATION (TE&O) BUREAU. THE CONTRACTOR SHALL COORDINATE WITH ARLINGTON COUNTY TRANSIT BUREAU (703-228-3049) AT LEAST 4 WEEKS
- PRIOR TO COMMENCEMENT OF WORK FOR APPROVAL, IF TRANSIT IS AFFECTED THE CONTRACTOR SHALL RETAIN PEDESTRIAN ACCESS TO THE BUS STOPS LOCATED WITHIN THE CONSTRUCTION ZONE
- FOR THE DURATION OF THE PROJECT. THE CONTRACTOR SHALL
- DESIGNATE A PERSON ASSIGNED TO THE PROJECT WHO WILL HAVE THE PRIMARY RESPONSIBILITY, WITH SUFFICIENT AUTHORITY, FOR IMPLEMENTING THE TMP/MOT/SOC AND OTHER SAFETY AND MOBILITY ASPECTS OF THE PERMIT WORK. THIS PERSON SHALL COORDINATE WITH THE ARLINGTON COUNTY CONSTRUCTION MANAGER FOR THE DURATION OF THE PROJECT.
- ENSURE THAT PERSONNEL ASSIGNED TO THE PROJECT ARE TRAINED IN TRAFFIC CONTROL TO A LEVEL COMMENSURATE WITH THEIR RESPONSIBILITIES IN ACCORDANCE WITH VDOT'S WORK ZONE TRAFFIC CONTROL
- PERFORM REVIEWS OF THE CONSTRUCTION AREA TO ENSURE COMPLIANCE WITH CONTRACT DOCUMENTS AT REGULARLY SCHEDULED INTERVALS AT THE DIRECTION OF THE ENGINEER. CONTRACTORS SHALL MAINTAIN AN APPROVED COPY OF THE TEMPORARY TRAFFIC CONTROL PLAN AT THE WORK SITE AT ALL TIMES.
- $11.\quad$ THIS TMP/MOT/SOC PLAN IS INTENDED AS A GUIDE. IT IS NOT TO ENUMERATE EVERY DETAIL WHICH MUST BE CONSIDERED IN THE CONSTRUCTION OF EACH PHASE, BUT ONLY TO TO SHOW THE GENERAL HANDLING OF EXISTING TRAFFIC. IF THE CONTRACTOR IS TO DEVIATE FROM THE APPROVED TMP, A NEW OR REVISED TMP MUST BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL
- ALL AREAS EXCAVATED BELOW THE EXISTING PAVEMENT SURFACE AND WITHIN THE CLEAR ZONE AT THE CONCLUSION OF EACH WORKDAY, SHALL BE BACKFILLED UP TO EXISTING PAVEMENT OR NEWLY CONSTRUCTED PAVEMENT SURFACE
- FOR THE SAFETY AND PROTECTION OF VEHICULAR TRAFFIC. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE FOR THE DURATION OF THE PROJECT. CONTRACTOR SHALL ADD ANY ADDITIONAL TEMPORARY MEASURES NECESSARY TO FACILITATE PROPER, POSITIVE DRAINAGE FOR THE DURATION OF
- EACH PHASE OF CONSTRUCTION SHALL BE COMPLETED PRIOR TO THE START OF THE NEXT PHASE UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

FIRE DEPARTMENT NOTES:


- ALL EXISTING FIRE HYDRANTS AND FIRE DEPARTMENT CONNECTIONS SHALL BE MAINTAINED UNOBSTRUCTED AND ACCESSIBLE AT ALL TIMES IN ACCORDANCE WITH SECTIONS 508.5.4 AND 508.5.5 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- ACCESS TO BUILDINGS FOR FIREFIGHTING SHALL BE MAINTAINED AT ALL TIMES. EXISTING FIRE APPARATUS ACCESS ROADS (FIRE LANES) SHALL BE KEPT CLEAR OF OBSTRUCTIONS IN ACCORDANCE WITH SECTION 503.4 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE. ACCESS TO CONSTRUCTION SITES SHALL BE PROVIDED AND MAINTAINED IN ACCORDANCE WITH SECTION 1410 OF THE ARLINGTON COUNTY FIRE PREVENTION CODE.
- IN THE EVENT THAT EXISTING FIRE DEPARTMENT CONNECTIONS OR FIRE APPARATUS ACCESS ROADS (FIRE LANES) MUST BE OBSTRUCTED TO FACILITATE CONSTRUCTION ACTIVITIES, CONTACT THE ARLINGTON COUNTY FIRE DEPARTMENT FIRE PREVENTION OFFICE AT 703-228-4644 TO COORDINATE REVIEW AND APPROVAL OF TEMPORARY FIRE DEPARTMENT CONNECTIONS AND/OR FIRE APPARATUS ACCESS ROADS PRIOR TO CREATING THE OBSTRUCTION

GENERAL SEQUENCE OF CONSTRUCTION:

- TRAFFIC CONTROL DEVICES AND SAFETY MEASURES SHALL COMPLY WITH THE LATEST EDITION OF THE VIRGINIA WORK AREA PROTECTION MANUAL, VDOT'S GUIDELINES FOR TEMPORARY TRAFFIC CONTROL, FEDERAL HIGHWAY ADMINISTRATION MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, ARLINGTON COUNTY STANDARDS, THE TRAFFIC
- CONTROL PLANS INCLUDED IN THE CONSTRUCTION DRAWINGS, AND/OR AS DIRECTED BY THE PROJECT OFFICER. THE CONTRACTOR SHALL SUBMIT A DETAILED SCHEDULE WHICH INDICATES START AND FINISH DATES FOR EACH SEGMENT OF THE WORK. THE SCHEDULE SHALL INDICATE THE DURATION OF ALL LANE OR SHOULDER CLOSURES. THE CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER A MINIMUM OF 3 BUSINESS DAYS IN ADVANCE OF PROCEEDING TO
- THE CONTRACTOR SHALL NOTIFY THE PROJECT OFFICER OF PARKING RESTRICTION NEEDS A MINIMUM OF 3 BUSINESS DAYS PRIOR TO COMMENCEMENT OF WORK FOR EACH SEGEMENT. COUNTY PROJECT OFFICER SHALL RESTRICT PARKING BY CONTACTING DES - PERMITTING SECTION, 703-228-4798.
- PORTABLE VARIABLE MESSAGE SIGNS WITH CLOSURE INFORMATION MUST BE INSTALLED AHEAD OF WORK AREA 3 WEEKS PRIOR TO CLOSURE.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL EITHER MAINTAIN APPROPRIATE SIGHT DISTANCE TO ALL TRAFFIC
- SIGNS OR PROVIDE FOR TEMPORARY SIGNAGE OR FLAGGERS TO GUIDE TRAFFIC THROUGH WORK ZONES. THE CONTRACTOR SHALL MINIMIZE THE DURATION OF ANY BLOCKAGE TO PRIVATE ENTRANCES AND DRIVEWAYS. THE CONTRACTOR SHALL SUBMIT A SCHEDULE OF DRIVEWAY CLOSURE FOR APPROVAL BY THE PROJECT OFFICER. THE PROJECT OFFICER SHALL BE NOTIFIED A MINIMUM OF 3 BUSINESS DAYS IN ADVANCE OF SUCH ACTIVITIES. THE CONTRACTOR SHALL NOTIFY THE PROPERTY OWNER AT LEAST 24 HOURS IN ADVANCE OF THE START OF ANY WORK THAT WILL REQUIRE TEMPORARY CLOSURE OF ACCESS TO THE PROPERTY. THE CONTRACTOR SHALL MAKE ALL PRIVATE
- ENTRANCES AND DRIVEWAYS ACCESSIBLE AT THE CONCLUSION OF EACH WORKDAY. ANY EXCAVATIONS WHICH ARE SPECIFICALLY APPROVED BY THE PROJECT OFFICER TO REMAIN OPEN PAST NORMAL WORKING HOURS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE PROTECTED IN ACCORDANCE
- WITH THE VIRGINIA WORK AREA PROTECTION MANUAL AND AS APPROVED BY THE PROJECT OFFICER. PEDESTRIAN TRAFFIC SHALL BE MAINTAINED AT ALL TIMES, INCLUDING ACCESS TO BUS STOP SHELTERS, UNLESS OTHERWISE APPROVED IN THE PLANS.
- PEDESTRIAN TRAFFIC SHALL BE SEPARATED FROM WORK ZONES WITH APPROPRIATE MEASURES IN ACCORDANCE WITH ADEQUATE PROVISIONS FOR PERSONS WITH DISABILITIES SHALL BE PROVIDED AT ALL TIMES PER ADA REQUIREMENTS.
- WHEN NECESSARY, PEDESTRIANS SHALL BE APPROPRIATELY DIRECTED WITH ADVANCED WARNING SIGNS PLACED AT INTERSECTIONS, TO CROSS TO THE OPPOSITE SIDE OF THE ROADWAY IN ORDER TO PREVENT CONFLICT WITH MIDBLOCK WORK SITES.
- PEDESTRIANS SHALL NOT BE LED INTO CONFLICT WITH WORK SITE EQUIPMENT, OPERATIONS, AND/OR VEHICLES MOVING THROUGH OR AROUND THE WORK SITE.
- THE CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY TRANSIT BUREAU, 703-228-3049, A MINIMUM OF 4 WEEKS PRIOR
- TO COMMENCEMENT OF WORK, IF TRANSIT IS AFFECTED. IF WORK DONE AT SIGNALIZED INTERSECTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING VEHICLE DETECTION AT ALL TIMES DURING THE PROJECT. CONTACT SIGNAL ITS TEAM DONALD CUNNINGHAM AT 703-228-6655 72 HOURS PRIOR TO COMMENCEMENT OF WORK.
- THE CONTRACTOR SHALL COMPLY WITH "RESTRICTED" WORKING HOURS AS DEFINED BY VDOT AND AS NOTED ON THE APPROVED VDOT PERMIT WHEN WORKING WITHIN THE VDOT RIGHT-OF-WAY. THE CONTRACTOR IS RESPONSIBLE FOR SATISFYING ALL VDOT PERMIT REQUIREMENTS.
- MAINTENANCE OF TRAFFIC PLANS AND DETAILS SHOWN HERE SHALL BE FOLLOWED BY THE CONTRACTOR DURING CONSTRUCTION. SHOULD THE CONTRACTOR DESIRE TO FOLLOW AN ALTERNATE PLAN, HE SHALL SUBMIT THE PLAN PRIOR TO CONSTRUCTION FOR REVIEW AND APPROVAL. ALTERNATIVE PLAN PREPARATION SHALL BE NO COST TO THE
- DIRECTIONAL ARROWS SHOWN ON THE MAINTENANCE OF TRAFFIC PLANS ARE FOR INFORMATION ONLY AND ARE NOT TO BE PLACED AS PAVEMENT MARKINGS. THE CONTRACTOR SHALL COVER ANY EXISTING SIGNS WHICH ARE NOT APPLICABLE OR ARE IN CONFLICT WITH THIS
- 19. THE CONTRACTOR SHALL ERADICATE AND RE-STRIPE AS NECESSARY ANY EXISTING PAVEMENT MARKINGS THAT ARE IN
- CONFLICT WITH OR DO NOT ALIGN WITH THE TEMPORARY PAVEMENT MARKINGS OR NEW TRAFFIC PATTERNS.
- 20. THE CONTRACTOR SHALL ERADICATE ALL TEMPORARY PAVEMENT MARKINGS, INCLUDING TEMPORARY MARKED CROSSWALKS ONCE THE WORK AREA(S) ASSOCIATED WITH THE MARKINGS HAS BEEN COMPLETED.
- CONTRACTOR SHALL NOTIFY ARLINGTON COUNTY PUBLIC SCHOOLS TWO WEEKS PRIOR TO STARTING CONSTRUCTION.

CONSTRUCTION NOTES:

. CONTRACTOR SHALL KEEP LOCAL PEDESTRIAN AND VEHICULAR ACCESS TO THE PROPERTIES ALONG 25TH RD. N. AT ALL TIMES DURING CONSTRUCTION.



MAINTENANCE OF TRAFFIC PLAN								
ZONE TABLE								
ZONE #	TT	C#	COMMENTS	MAXIMUM DURATION	WORK HOURS			
ZOINL #	VEHICULAR	PEDESTRIAN	COMMENTS	MAXIMUM DURATION	WORK HOOKS			
Α	TTC 23.2	N/A	- STORMWATER PIPE CONSTRUCTION IN ROADWAY	5 DAYS	9:00 A.M 4:00 P.M. (M-F)			
В	TTC 23.2	N/A	- STORMWATER STRUCTURE REMOVAL AND REPLACEMENT	5 DAYS	9:00 A.M 4:00 P.M. (M-F)			

September 2019

PTRS SEE NOTE 4 & 14

2: Revision 2 – 9/1/2019

3: Revision 2.1 - 11/1/2020

Page 6H-54 Page 6H-55 **Typical Traffic Control** Lane Closure on a Two-Lane Roadway Using Flaggers Lane Closure on a Two-Lane Roadway Using Flaggers (Figure TTC-23.2) (Figure TTC-23.2) **NOTES**

1. Sign spacing distance should be 350'-500' where the posted speed limit is 45 mph or less, and 500'-800' where the posted speed limit is greater than 45 mph. 2. Care should be exercised when establishing the limits of the work zone to insure maximum possible sight distance in advance of the flagger station and transition, based on the posted speed limit and at least equal to or greater than the values in Table 6H-3. Generally speaking, motorists should have a clear line of sight from the graphic flagger symbol sign to the flagger. 3. To maintain efficient traffic flow in a flagging operation on a two-lane roadway, the maximum time motorists should be stopped at a flagger station is 8 minutes for high volume roadways (average daily traffic of 500 or more vehicles per day) to a maximum of 12 minutes for low volume roadways (less than **- 500 +** 500 vehicles per day). For additional information see Section 6E.07.2 4. Portable Temporary Rumle Strips (PTRS) shall be used as noted in Section 6F.99. FLAGGER STATION SEE NOTES 2, 3, 5 & 6 5. Flagging stations shall be located far enough in advance of the work space to permit approaching traffic to reduce speed and/or stop before passing the work space and allow sufficient distance for BUFFER SEE TABLE 6H-3 departing traffic in the left lane to return to the right lane before reaching opposing traffic (see Table 6H-3 on Page 6H-5). PTRS SPACING 6. All flaggers shall be state certified and have their certification card in their possession when performing flagging duties (see Section 6E.01, Qualifications for Flaggers). ≤40 MPH 7. Cone spacing shall be based on the posted speed and the values in Table 6H-4 on Page 6H-6.1 8. A shadow vehicle with at least one high intensity amber rotating, flashing, or oscillating light shall SHADOW VEHICLE be parked 80'-120' in advance of the first work crew. REQUIRED Option: BUFFER SEE TABLE 6H-3 PTRS OPTIONAL 8. A SLOW (W21-V10) sign² may be required in this area to give advance warning of the operation ahead by slowing approaching traffic prior to reaching the flagger station or queued traffic. _ 50' - 100' FLAGGER STATION 9. If the queue of traffic reaches the BE PREPARED TO STOP (W3-4) sign then the signs, and if used the SEE NOTES 2, 3, 5 & 6 PTRS¹ should be readjusted at greater distances. 10. When a highway-rail crossing exists within or upstream of the transition area and it is anticipated that queues resulting from the lane closure might extend through the highway-rail grade crossing, the temporary traffic control zone should be extended so that the transition area precedes the highway-rail crossing (see Figure TTC-56 for additional information on highway-rail crossings). SEE NOTE 10 W20-V26 SEE NOTE 15

11. At night, flagger stations shall be illuminated, except in emergencies (see Section 6E.08). 12. Cones may be eliminated when using a pilot vehicle operation or when the total roadway width is 20 feet

13. For low-volume situations with short work zones on straight roadways where the flagger is visible to road users approaching from both directions, a single flagger, positioned to be visible to road users approaching from both directions, may be used (see Chapter 6E).

14. When used², three portable temporary rumble (PTRS) strips shall be installed across the entire travel lane adjacent to the BE PREPARED TO STOP (W3-4) sign. The portable temporary rumble strips shall be monitored and adjusted as necessary during the work shift to ensure proper placement on the roadway. When the PTRS are installed, the RUMBLE STRIPS AHEAD (W20-V26) sign shall also be utilized. 1: Revision 1 – 4/1/2015

2: Revision 2 – 9/1/2019

MOT ZONE LEGEND


September 2019

VIRGINIA

ARLINGTON

DEPARTMENT OF ENVIRONMENTAL SERVICES **FACILITIES & ENGINEERING DIVISION** ENGINEERING BUREAU 2100 CLARENDON BOULEVARD, SUITE 813 ARLINGTON, VA 22201 PHONE: 703.228.3629 FAX: 703.228.3606

COPYRIGHT © 2021 ARLINGTON COUNT VIRGINIA - ALL RIGHTS RESERVED



APPROVALS

Amy Pflaum QUALITY CONTROL ENGINEER CONSTRUCTION MANAGEMENT SUPERVISOR

WATER, SEWER, STREETS BUREAU CHIEF Dennis M. Leach TRANSPORTATION DIRECTOR

John Mir ROJECT MANAGER

REVISIONS

THSID NOR

DESIGNED: SEB DRAWN: SEB CHECKED: SWS

S

ш

0

S

Ш

PLOTTED: JANUARY 6 2022

SCALE:

GRAPHIC SCALE

C121.