

APPENDIX "A" – SCHEDULE OF VALUES

BID FORM

The following Base Bid Form is presented to assist the Village in evaluating the Bid. This Bid Form reflects estimated quantities for the Total Bid as described above. After award, the Village reserves the right to modify estimated quantities subject to the unit price, and eliminate line items if necessary. In the event of discrepancy or approved quantity change, the Unit Price for each item will govern. Payment shall be made for the items listed on the Bid Form on the basis of the Work actually performed and completed.

<u>Bid Item No.</u>	<u>DESCRIPTION</u>	<u>Estimated Quantity</u>	<u>UNIT</u>	<u>Unit Price</u>	<u>Total</u>
101-1	MOBILIZATION	LS	1		
102-1	MAINTENANCE OF TRAFFIC	LS	1		
110-1-1	CLEARING AND GRUBBING	LS/AC	1/0.80		
110-2-2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.04		
110-4-10	REMOVAL OF EXISTING CONCRETE	SY	52		
120-1	REGULAR EXCAVATION	CY	187		
160-4	TYPE B STABILIZATION	SY	285		
285-706	OPTIONAL BASE, BASE GROUP 06	SY	285.00		
327-70-1	MILLING EXIST. ASPH. PAVT. 1" AVG. DEPTH	SY	1,180		
334-1-13	SUPERPAVE ASPHALTIC CONC. TRAFFIC C	TN	115		
425-6	VALVE BOXES, ADJUST	EA	5		
520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	95		
520-2-4	CONCRETE CURB, TYPE D	LF	96		
522-1	CONCRETE SIDEWALK AND DRIVEWAYS. 4" THICK	SY	944		
522-2	CONCRETE SIDEWALK AND DRIVEWAYS. 6" THICK	SY	289		
527-2	DETECTABLE WARNINGS	SF	280		
570-1-2	PERFORMANCE TURF - SOD	SY	1,975		
630-2-12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	60		
635-2-11	PULL & SPLICE BOX, F&I, 13" X 24" COVER SIZE	EA	3		
639-1-122	ELECTRICAL POWER SERVICE, F&I UNDERGROUND METER PURCHASED BY CONTRACTOR	AS	1		
639-2-1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	60		

654-2-21	RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR POWERED, COMPLETE ASSEMBLY- SINGLE DIRECTION	AS	2		
700-1-11	SINGLE POST SIGN, F&I GM, UP TO 12 SF	AS	11		
700-1-12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1		
700-1-50	SINGLE POST SIGN, RELOCATE	AS	8		
700-1-60	SINGLE POST SIGN, REMOVE	AS	12		
706-3	REFLECTIVE PAVEMENT MARKERS (Y/Y)	EA	111		
711-11-123	THERMOPLASTIC, STD, WHITE, SOLID, 12" FOR CROSSWALK & ROUNDABOUT	LF	2,027		
711-11-125	THERMOPLASTIC, STD, WHITE, SOLID, 24" FOR STOP LINE & CROSSWALK	LF	422		
711-11-160	THERMOPLASTIC, STD, WHITE, MESSAGE OR SYMBOL	EA	1		
711-11-224	THERMOPLASTIC, STD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	20		
711-15-101	THERMOPLASTIC, STD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 6"	GM	0.133		
711-15-201	THERMOPLASTIC, STD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.522		

PAY ITEM NOTES:

- 110-1-1 INCLUDES REMOVAL AND DISPOSAL OF EXISTING ROCK AT APPROX. STATION 45+40 TO 45+98.
- 102-1 INCLUDES REMOVAL AND DISPOSAL OF EXISTING CONFLICTING MARKINGS AND RESTORATION OF EXISTING PAVEMENT.
- 425-6 VALVE BOXES AND MANHOLES SHALL BE ADJUSTED WHENEVER THEY ARE ¼" OR MORE ABOVE OR BELOW THE SIDEWALK FINAL GRADE ELEVATION. THE CONTRACTOR IS RESPONSIBLE FOR PERFORMING MEASUREMENTS ON ALL MANHOLES/VALVE BOXES WITHIN PAVING LIMITS. COST OF THE MEASURING IS INCLUDED IN THE MANHOLE/VALVE BOX ADJUSTMENT PAY ITEMS. COORDINATE WITH MIAMI-DADE WATER & SEWER

BASE BID AMOUNT \$ _____

BASE BID AMOUNT (IN WORDS) _____

Bidder: _____

By: _____

Title: _____