

**SPALDING COUNTY  
LOCAL MAINTENANCE AND IMPROVEMENT GRANT (LMIG)  
RESURFACING PROJECT  
CONTRACT SUMMARY  
2019-0118**

Item	Ref #	Description	Estimated Quantity	Unit	Unit Price	Item Total
1		PAYMENT & PERFORMANCE BONDS	1	LS		
2		MOBILIZATION	1	LS		
3	150-1000	TRAFFIC CONTROL	1	LS		
4	402-1802	RECYCLED ASPH CONC PATCHING, INCL BITUM MATL & H LIME (330 LBS/SY)	6,910	TN		
5	402-1812	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME, TP 1 (85 LBS/SY)	800	TN		
6	402-3100	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TP 1, GP 1, INCL BITUM MATL & H LIME (135 LBS/SY)	11,200	TN		
7	413-1000	BITUMINOUS TACK COAT	8,216	GAL		
8	652-2401	SOLID TRAFFIC STRIPE, 5 INCH WHITE	21.53	LM		
9	652-2402	SOLID TRAFFIC STRIPE, 5 INCH YELLOW	18.96	LM		
10	652-6402	SKIP TRAFFIC STRIPE, 5 INCH YELLOW	4.52	GLM		
11	653-0400	THERMOPLASTIC PAVEMENT MARKING, 24" WHITE STOP BAR	249	LF		
12		ADJUST WATER MAIN VALVE BOX TO GRADE (RISERS PROVIDED BY OWNER)	5	EA		
13		ADJUST SANITARY SEWER MANHOLE TO GRADE (RISERS PROVIDED BY OWNER)	2	EA		
					<b>TOTAL COST =</b>	