

LaGRANGE THREAD-PATHER PARK RTP - BID FORM PROPOSAL

Section A: Roadway / Trail					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE (INCLUDING DEMOLITION, & TREE REMOVAL)		
402-1802	1	LS	ASHPALT PAVEMENT CUT & PATCH - ROADWAY AND PARKING LOT MODIFICATIONS (PER GDOT STD. 1401)		
310-5060	460	SY	GR AGGR SUBBASE CRS, 6 IN, INCL MATL		
402-3910	38	TN	1 1/2 IN RECYCLED ASPH CONC 12.5MM SUPERPAVE GP 2 ONLY, INCL BITUM MTL & H LIME		
402-4012	51	TN	2 IN RECYCLED ASPH CONC 19MM SUPERPAVE GP 1 OR 2, INCL BITUM MTL & H LIME		
441-0018	37	SY	DRIVEWAY - 3000 psi CONCRETE, 8 IN TK (Labor, form, finish only) Materials furnished by city		
441-5002	178	LF	CONCRETE HEADER CURB, 6" TP. 2 (Labor, form, finish only) Concrete furnished by City		
441-6012	413	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2		
444-1000	3,168	LF	SAWED JOINTS IN EXISTING PAVEMENTS, (Space btw joint to equal trail width)		
500-3101	4355	SY	CONCRETE TRAIL, SIDEWALK, INCL ADA RAMPS (Labor,form,finish only) Concrete finished by City		
500-3800	10	SY	CLASS B CONCRETE INCL STEEL - STAIRS		
516-0001	350	LF	1.5" I.D TUBULAR PIPE (ALUMINUM) POST & HANDRAIL FOR STAIRS, POWDER COATED BLACK		
611-5360	2	EA	RESET HWY SIGN (STA 0+00, STA 101+35)		
611-8120		EA	ADJUST UTILITY TO GRADE (WATER, GAS, ELECTRIC, ETC.)		not in contract- city responsibility
636-1014	75	SF	MUTCD HIGHWAY SIGNS		
636-1042		SF	THREAD TRAIL SQUARE MATL 0.125 ALUM, DIRECT PRINT		not in contract- city responsibility
636-1043		LF	THREAD TRAIL SQUARE 3"X3" POST		not in contract- city responsibility
636-2070	9	EA	GALV STEEL SQUARE HIGHWAY POSTS, 14 FT PER GDOT		
652-5301		LF	THERMO SOLID TRAFFIC STRIPE, 8 IN WHITE, 12' WIDE (GDOT CROSSWALKS)		not in contract- city responsibility
653-0095		EA	THERMOPLASTIC PAVEMENT MARKING, HANDICAP SYMBOL		
653-1500		LF	THERMO SOLID TRAFFIC STRIPE (HATCH), 5 IN, WHITE (NEW MACEDONIA BAPTIST CHURCH PARKING LOT)		not in contract- city responsibility
653-1704		LF	THERMO SOLID TRAFFIC STRIPE, 24" WHITE (STOP BARS)		not in contract- city responsibility
652-6502	3168	LF	PAINTED SKIP STRIPING (YELLOW) (TRAIL CL) , 4 IN, STRIPE LENGTH AND GAP TO EQUAL TRAIL WIDTH		
900-0526	12	EA	FIXED STEEL BOLLARDS		
900-0527	6	EA	STEEL REMOVABLE BOLLARDS		
999-5200	232	SF	4"X8" DETECTABLE ADA PAVERS (RED),		
754-4000	4	EA	WASTE RECEPTACLE UNIT		
754-5000	8	EA	METAL BENCH		
754-6000	3	EA	BIKE RACK		
Section A Sub Total					

Section B: Bridges/Retaining Walls					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
445-1002	1	LS	29" TALL RETAINING WALL 1 COMPLETE AS SHOWN INC. PRECAST CAP AND BRICK VENEER (STA 12+26 TO STA 15+75)		
445-1003	1	LS	10' X 12' STRUCTURAL SLAB		
TOTAL ON SECTION 2					

Section C: Miscellaneous					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
446-0000	1	LS	ROOT BRIDGING		
TOTAL ON SECTION 3					

Section D: Erosion Control / Storm Drainage					
---	--	--	--	--	--

Item Number	Quantity	Units	Item Description	Unit Price	Cost
163-0300	6	EA	CONSTRUCTION EXIT		
163-0301	1	LS	EROSION CONTROL INSPECTIONS, WEEKLY AND MONTHLY		
	1	LS	TEMPORARY REFUELING AREA		
	1	LS	TEMPORARY CONC. WASHDOWN		
	120	LF	CONSTRUCT, MAINTAIN, & REMOVE 18" FILTER MEDIA SOCK CHECK DAMS		
163-0529	5200	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE NS		
	300	LF	CONSTRUCT, MAINTAIN, & REMOVE TEMPORARY SEDIMENT BARRIER J-HOOKS		
163-0550A	8	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
163-0550B	1	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE P		
165-0105	1	LS	MAINTENANCE OF INLET SEDIMENT TRAP		
165-0010	1	LS	MAINTENANCE OF TEMPORARY SEDIMENT BARRIER		
165-0101	1	LS	MAINT OF CONSTRUCTION EXIT		
167-1000	1	LS	WATER QUALITY MONITORING AND SAMPLING		
	1	EA	RECONSTR EXIST C.B. - REPLACE TOP WITH GDOT 1034D C.B.		
	4	EA	PEDESTAL TOP D.I., INCL MANHOLE & TOP		
	3	EA	DROP INLET, INCL MANHOLE, FRAME & GRATE (EJ 1205 Z FRAME & 1205 02 GRATE, OR APPROVED EQUAL)		
	3	EA	GADOT 1011A J.B., INCL MANHOLE, RING & COVER		
	1	EA	RECONSTR EXIST D.I. - REPLACE TOP WITH (EJ 1205 Z FRAME & 1205 02 GRATE, OR APPROVED EQUAL)		
	1	EA	TIE PROPOSED 15" HDPE TO EXISTING STRUCTURE		
	1	EA	TIE EXISTING 24" HDPE TO PROPOSED STRUCTURE		
	1	EA	TIE EXISTING 15" CLAY TO PROPOSED STRUCTURE		
	1	EA	TIE PROPOSED 36" HDPE TO EXISTING STRUCTURE		
550-1150	120	LF	STORM DRAIN PIPE, 15 IN, HDPE, H 1-10		
550-1180	190	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10		
550-1240	120	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		
550-1300	190	LF	STORM DRAIN PIPE, 30 IN, HDPE, H 1-10		
550-1360	200	LF	STORM DRAIN PIPE, 36 IN, HDPE, H 1-10		
603-1012	60	SY	ROCK RIPRAP, GADOT TYPE 3 EQUIVALENT RIVER ROCK (12" THICK)		
603-2997	300	SY	FILTER BLANKET		
700-6910	2.5	AC	PERMANENT GRASSING		
700-8000	2.5	AC	FERTILIZER MIX GRADE		
716-2000	10000	SY	EROSION CONTROL MATS, SLOPES		

Section D Sub Total

Section E: Allowances

Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9900		ALLOW	LANDSCAPE (TREES, PLANTS, +1 YR MAINT)		not in contract- city responsibility
999-1000	1	ALLOW	MISCELLANEOUS CONSTRUCTION	\$100,000.00	\$100,000.00

Section G Sub Total

Section A Sub Total	
Section B Sub Total	
Section C Sub Total	
Section D Sub Total	
Section E Sub Total	
TOTAL ESTIMATED CONSTRUCTION COST	

LS	LUMP SUM
SY	SQUARE YARD
CY	CUBIC YARD
LF	LINEAR FOOT
EA	EACH
ALLOW	ALLOWANCE
SF	SQUARE FOOT
GLF	GALLON PER LINEAR FOOT