


PROJECT MANUAL

Myrtle Beach Intermediate School Renovations

Myrtle Beach, South Carolina



D3G Architects LLC

March 4, 2020

TABLE OF CONTENTS

DIVISION 0	PROCUREMENT AND CONTRACTING
00 01 01	Project Title Page
00 01 15	List of Drawing Sheets
00 43 21	Allowance Form
DIVISION 1	GENERAL REQUIREMENTS
01 21 00	Allowances
01 22 00	Unit Prices
01 25 00	Substitution Procedures
01 26 00	Contract Modification Procedures
01 29 00	Payment Procedures
01 31 00	Project Management and Coordination
01 32 00	Photographic Documentation
01 33 00	Submittal Procedures
01 40 00	Quality Requirements and Special Inspections
01 42 00	References
01 50 00	Temporary Facilities and Controls
01 60 00	Product Requirements
01 73 00	Execution
01 74 19	Construction Waste Management
01 77 00	Closeout Procedures
01 78 23	Operation and Maintenance Data
01 78 39	Project Record Documents
01 79 00	Demonstration and Training
DIVISION 2	EXISTING CONDITIONS
02 41 19	Selective Demolition
DIVISION 3	CONCRETE
03 30 00	Cast in Place Concrete
DIVISION 4	MASONRY
04 21 13	Brick Masonry
04 22 00	Concrete Unit Masonry
DIVISION 5	METALS
05 05 20	Post-installed Structural Anchors
05 12 00	Structural Steel Framing
05 41 00	Engineered Cold-formed Metal Framing
05 50 00	Metal Fabrications
DIVISION 6	WOOD, PLASTICS & COMPOSITES
06 10 53	Miscellaneous Rough Carpentry
DIVISION 7	THERMAL AND MOISTURE PROTECTION
07 62 00	Sheet Metal Flashing & Trim
07 84 13	Penetration Firestopping
DIVISION 8	OPENINGS
08 11 13	Hollow Metal Doors and Frames
08 14 16	Flush Wood Doors
08 22 10	Fiberglass Reinforced Polyester Doors

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

08 31 13	Access Doors & Frames
08 41 13	Aluminum-framed Entrances and Storefronts
08 71 00	Door Hardware
08 80 00	Glazing

DIVISION 9 FINISHES

09 22 16	Non-structural Metal Framing
09 29 00	Gypsum Board
09 65 13	Resilient Base and Accessories
09 65 19	Resilient Tile Flooring
09 91 23	Painting

DIVISION 10 SPECIALTIES

10 14 24	Identifying Devices
10 21 13	Toilet Compartments
10 28 00	Toilet Accessories

DIVISION 31 EARTHWORK

31 10 00	Site Clearing
31 20 00	Earth Moving

DIVISION 32 EXTERIOR IMPROVEMENTS

32 12 16	Asphalt Paving
32 13 13	Concrete Paving
32 17 23	Pavement Markings
32 92 00	Turf and Grasses

DIVISION 33 UTILITIES

32 41 00	Storm Utility Drainage Piping
----------	-------------------------------

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

DOCUMENT 00 01 01 - PROJECT TITLE PAGE

Project Name: Myrtle Beach intermediate School Conversion

Dated: March 4, 2020

Owner's name: Horry County Schools
335 Four Mile Road
Conway, SC 29526

Architect Project No. 1917

Architect: D3G Architects LLC
350 Hilton Road Suite 101
Myrtle Beach, SC 29572

Phone: 843.427.4450

END OF DOCUMENT 00 01 01

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

DOCUMENT 00 01 15 - LIST OF DRAWING SHEETS AND TECHNICAL SPECIFICATIONS

1.1 INDEX OF TECHNICAL SPECIFICATIONS

- A. Technical Specifications: See Table of Contents for specification sections.

1.2 LIST OF DRAWINGS

- A. Drawings: See plan set cover for list of drawings.

END OF DOCUMENT 00 01 15

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

DOCUMENT 00 43 21 - ALLOWANCE FORM

- A. Project Name: Myrtle Beach Intermediate School Renovations
- B. Project Location: 3301 Oak St., Myrtle Beach, SC 29577
- C. Owner: Horry County Schools
- D. Architect: D3G Architects LLC
- E. Architect Project Number: 1917

1.2 BID FORM SUPPLEMENT

- A. This form is required to be attached to the Bid Form.
- B. The undersigned Bidder certifies that Base Bid submission to which this Bid Supplement is attached includes those allowances described in the Contract Documents and scheduled in Section 01 21 00 "Allowances."

1.3 SUBMISSION OF BID SUPPLEMENT

- A. Respectfully submitted this ____ day of _____, 2016.

Submitted By: _____
(Insert name of bidding firm or corporation)

Authorized Signature: _____
(Handwritten signature)

Signed By: _____
(Type or print name)

Title: _____
(Owner/Partner/President/Vice President)

END OF DOCUMENT 00 43 21

SECTION 01 21 00 - ALLOWANCES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements governing allowances.
- B. Types of allowances include the following:
 - 1. Lump-sum allowances.
- C. Related Requirements:
 - 1. Section 01 22 00 "Unit Prices" for procedures for using unit prices.

1.2 SELECTION AND PURCHASE

- A. At the earliest practical date after award of the Contract, advise Architect of the date when final selection and purchase of each product or system described by an allowance must be completed to avoid delaying the Work.
- B. At Architect's request, obtain proposals for each allowance for use in making final selections. Include recommendations that are relevant to performing the Work.
- C. Purchase products and systems selected by Architect from the designated supplier.

1.3 ACTION SUBMITTALS

- A. Submit proposals for purchase of products or systems included in allowances, in the form specified for Change Orders.

1.4 INFORMATIONAL SUBMITTALS

- A. Submit invoices or delivery slips to show actual quantities of materials delivered to the site for use in fulfillment of each allowance.
- B. Submit time sheets and other documentation to show labor time and cost for installation of allowance items that include installation as part of the allowance.
- C. Coordinate and process submittals for allowance items in same manner as for other portions of the Work.

1.5 COORDINATION

- A. Coordinate allowance items with other portions of the Work. Furnish templates as required to coordinate installation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.6 LUMP-SUM ALLOWANCES

- A. Allowance shall include cost to Contractor of specific products materials and installation ordered by Owner or selected by Architect under allowance and shall include taxes, freight and delivery to Project site.
- B. Unless otherwise indicated, Contractor's costs for receiving and handling at Project site, overhead and profit, taxes, and similar costs related to products and materials under allowance shall be included as part of the Contract Sum and not part of the allowance.
- C. Unused Materials: Return unused materials purchased under an allowance to manufacturer or supplier for credit to Owner, after installation has been completed and accepted.
 - 1. Retain and prepare unused material for storage by Owner. Deliver unused material to Owner's storage space as directed.

1.7 ADJUSTMENT OF ALLOWANCES

- A. Allowance Adjustment: To adjust allowance amounts, prepare a Change Order proposal based on the difference between purchase amount and the allowance, multiplied by final measurement of work-in-place where applicable. If applicable, include reasonable allowances for cutting losses, tolerances, mixing wastes, normal product imperfections, and similar margins.
 - 1. Include installation costs in purchase amount only where indicated as part of the allowance.
 - 2. If requested, prepare explanation and documentation to substantiate distribution of overhead costs and other margins claimed.
 - 3. Submit substantiation of a change in scope of work, if any, claimed in Change Orders related to unit-cost allowances.
 - 4. Owner reserves the right to establish the quantity of work-in-place by independent quantity survey, measure, or count.
- B. Submit claims for increased costs because of a change in scope or nature of the allowance described in the Contract Documents, whether for the purchase order amount or Contractor's handling, labor, installation, overhead, and profit.
 - 1. Do not include Contractor's or subcontractor's indirect expense in the Change Order cost amount unless it is clearly shown that the nature or extent of work has changed from what could have been foreseen from information in the Contract Documents.
 - 2. No change to Contractor's indirect expense is permitted for selection of higher- or lower-priced materials or systems of the same scope and nature as originally indicated.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine products covered by an allowance promptly on delivery for damage or defects. Return damaged or defective products to manufacturer for replacement.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.2 PREPARATION

- A. Coordinate materials and their installation for each allowance with related materials and installations to ensure that each allowance item is completely integrated and interfaced with related work.

3.3 SCHEDULE OF ALLOWANCES

- A. Allowance No. 1: Include the sum of \$10,000.00 for the furnishing and installation of replacement storefront glazing in Room B101 Storage.
- B. Allowance No. 2: Include the sum of \$110,000.00 for door hardware, materials only.
- C. Allowance No. 3: Include the sum of \$20,000.00 for contingencies.

END OF SECTION 01 21 00

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

SECTION 01 22 00 - UNIT PRICES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for unit prices.
- B. Related Requirements:
 - 1. Section 01 26 00 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.2 DEFINITIONS

- A. Unit price is a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.
- B. PROCEDURES
- C. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.
- D. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- E. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- F. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

- A. Unit Price No. 1: removal of unsuitable soil, measured in cubic yards.
- B. Unit price No. 2: replacement of unsuitable soil, measured in cubic yards.

END OF SECTION 01 22 00

SECTION 01 25 00 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
 - 1. Section 01 60 00 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.3 ACTION SUBMITTALS

- A. Substitution Requests: Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use CSI Form 13.1A
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project, from ICC-ES.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.

- k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: Architect will notify Contractor of acceptance or rejection of proposed substitution within 5 days of receipt of request.
- a. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause during Construction: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution provides sustainable design characteristics that specified product provided.
 - c. Requested substitution will not adversely affect Contractor's construction schedule.
 - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - e. Requested substitution is compatible with other portions of the Work.
 - f. Requested substitution has been coordinated with other portions of the Work.
 - g. Requested substitution provides specified warranty.
 - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Architect will consider requests for substitution if received within 6 days after the Notice to Proceed.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - b. Requested substitution does not require extensive revisions to the Contract Documents.
 - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - d. Requested substitution provides sustainable design characteristics that specified product provided.
 - e. Requested substitution will not adversely affect Contractor's construction schedule.
 - f. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - g. Requested substitution is compatible with other portions of the Work.
 - h. Requested substitution has been coordinated with other portions of the Work.
 - i. Requested substitution provides specified warranty.
 - j. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 25 00

SECTION 01 26 00 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Work Change Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.

4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 01 25 00 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.

1.4 ADMINISTRATIVE CHANGE ORDERS

- A. Allowance Adjustment: See Section 01 21 00 "Allowances" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect actual costs of allowances.
- B. Unit-Price Adjustment: See Section 01 22 00 "Unit Prices" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect measured scope of unit-price work.

1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 26 00

SECTION 01 29 00 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Section 01 21 00 "Allowances" for procedural requirements governing the handling and processing of allowances.
 - 2. Section 01 26 00 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 3. Section 01 32 00 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - b. Submittal schedule.
 - c. Items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section. Additional line items may be required at the discretion of the Architect.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.
 - 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.

- a. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
4. Round amounts to nearest whole dollar; total shall equal the Contract Sum. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
5. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
6. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
7. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.
8. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: Submit Application for Payment to Architect by the tenth day of the month. The period covered by each Application for Payment is one month, ending on the last day of the month.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

- E. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 - 2. When an application shows completion of an item, submit conditional final or full waivers.
 - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 - 4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- G. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - 1. List of subcontractors.
 - 2. Schedule of values.
 - 3. Contractor's construction schedule (preliminary if not final).
 - 4. Schedule of unit prices.
 - 5. Submittal schedule (preliminary if not final).
 - 6. List of Contractor's staff assignments.
 - 7. List of Contractor's principal consultants.
 - 8. Copies of building permits.
 - 9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 - 10. Initial progress report.
 - 11. Report of preconstruction conference.
 - 12. Certificates of insurance and insurance policies.
- H. Typical Applications for Payment shall include the past two construction progress reports.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 3. Updated final statement, accounting for final changes to the Contract Sum.
 - 4. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
 - 5. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
 - 6. AIA Document G707-1994, "Consent of Surety to Final Payment."

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

7. Evidence that claims have been settled.
8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 29 00

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 CONTRACT DOCUMENT

- A. The **Contract Agreement** with referenced attachments, technical specifications and drawings including all project addenda constitute the Scope of the Work.
- B. Specific project requirements are included in the Contract Agreement and contain, but may include more than the following:
 - 1. Pre-Construction Meeting
 - 2. Construction Management
 - 3. Conformance to applicable Codes and Laws
 - 4. Project Schedule
 - 5. SLED Background checks
 - 6. Submittals
 - 7. Record Drawings
 - 8. Quality Control
 - 9. Cut and Patching
 - 10. Jobsite Supervision
 - 11. Work site control and clean-up.
 - 12. Material testing and Inspections
 - 13. Warranties and Guarantees
 - 14. Traffic Control and Safety
- C. **Important safety and specific Horry County School requirements are contained in the Contract Agreement and specifically Section 83 "Mandatory Safety and Conduct Requirements."**

1.2 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Requirements:
 - 1. Those work restrictions and limitations listed on the **Scope of Work (Exhibit A)** and the **Contract Agreement**.

1.3 UTILITY USE AND CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless specifically noted otherwise within the Scope of Work (Exhibit A) to the Contract Agreement. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, testing agencies, and authorities having jurisdiction.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

B. Requirement for temporary utilities if paid for by the Contractor:

1. Sewer Service: **Pay** sewer-service use charges for sewer usage by all entities for construction operations.
2. Water Service: **Pay** water-service use charges for water used by all entities for construction operations.
3. Electric Power Service: **Pay** electric-power-service use charges for electricity used by all entities for construction operations.

C. Requirement for temporary utilities if paid for by the Owner:

1. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations at no cost to the Owner.
2. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations at no cost to the Owner.
 - a. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
 - b. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.5 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

1.6 DEFINITIONS

- A. Included within the **Contract agreement** and within each specific specification section.

PART 2 - PRODUCTS

2.1 TEMPORARY FENCING

- A. Chain-Link Fencing: Minimum 2-inch, 0.148-inch- thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet high with galvanized-steel pipe posts; minimum 2-3/8-inch- OD line posts and 2-7/8-inch- OD corner and pull posts, with 1-5/8-inch- OD top rails.
- B. Portable Chain-Link Fencing: Minimum 2-inch, 0.148-inch- thick, galvanized-steel, chain-link fabric fencing; minimum 6 feet high with galvanized-steel pipe posts; minimum 2-3/8-inch- OD line posts and 2-7/8-inch- OD corner and pull posts, with 1-5/8-inch- OD top and bottom rails. Provide galvanized-steel bases for supporting posts.

2.2 TEMPORARY FACILITIES

- A. Field Offices, General: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.
- B. Common-Use Field Office: Of sufficient size to accommodate needs of Owner, Architect, and construction personnel office activities and to accommodate Project meetings specified in **Contract agreement**. Keep office clean and orderly.
- C. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.
 - 1. Store combustible materials apart from building.

2.3 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
 - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.
 - 3. Permanent HVAC System: If Owner authorizes use of permanent HVAC system for temporary use during construction, provide filter with MERV of 8 at each return-air grille in system and remove at end of construction and clean HVAC system as required in Section 017700 "Closeout Procedures".

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
 - 1. Locate facilities to limit site disturbance.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
 - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Water Service: Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Heating: Provide temporary heating required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.
- E. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.
- F. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
 - 1. Install electric power service overhead unless otherwise indicated.
 - 2. Connect temporary service to Owner's existing power source, as directed by Owner.
- G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
 - 2. Install lighting for Project identification sign.
- H. Telephone Service: Provide temporary telephone service in common-use facilities for use by all construction personnel

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Provide superintendent with cellular telephone or portable two-way radio for use when away from field office.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
- B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate for construction operations. Locate temporary roads and paved areas within construction limits indicated on Drawings.
 1. Provide dust-control treatment that is nonpolluting and nontracking. Reapply treatment as required to minimize dust.
- C. Traffic Controls: Comply with requirements of authorities having jurisdiction.
 1. Protect existing site improvements to remain including curbs, pavement, and utilities.
 2. Maintain access for fire-fighting equipment and access to fire hydrants.
- D. Parking: Provide temporary parking areas for construction personnel.
- E. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.
 1. Identification Signs: Provide Project identification signs as indicated on Drawings.
 2. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.
 - a. Provide temporary, directional signs for construction personnel and visitors.
 3. Maintain and touchup signs so they are legible at all times.
- F. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- C. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- D. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.
- F. Site Enclosure Fence: Prior to commencing earthwork, furnish and install site enclosure fence in a manner that will prevent people and animals from easily entering site except by entrance gates.
 - 1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations and / or as indicated on Drawings.
 - 2. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Furnish one set of keys to Owner.
- G. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- H. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.
- I. Temporary Egress: Maintain temporary egress from existing occupied facilities as indicated and as required by authorities having jurisdiction.
- J. Covered Walkway: Erect protective, covered walkway for passage of individuals through or adjacent to Project site. Coordinate with entrance gates, other facilities, and obstructions. Comply with regulations of authorities having jurisdiction and requirements indicated on Drawings.
 - 1. Construct covered walkways using scaffold or shoring framing.
 - 2. Provide overhead decking, protective enclosure walls, handrails, barricades, warning signs, exit signs, lights, safe and well-drained walkways, and similar provisions for protection and safe passage.
 - 3. Paint and maintain appearance of walkway for duration of the Work.
- K. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.
 - 1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.
- L. Temporary Partitions: Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate areas occupied by Owner from fumes and noise.
 - 1. Construct dustproof partitions with gypsum wallboard with joints taped on occupied side, and fire-retardant-treated plywood on construction operations side.
 - 2. Construct dustproof partitions with two layers of 6-mil polyethylene sheet on each side. Cover floor with two layers of 6-mil polyethylene sheet, extending sheets 18 inches up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.
 - a. Construct vestibule and airlock at each entrance through temporary partition with not less than 48 inches between doors. Maintain water-dampened foot mats in vestibule.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
4. Insulate partitions to control noise transmission to occupied areas.
5. Seal joints and perimeter. Equip partitions with gasketed dustproof doors and security locks where openings are required.
6. Protect air-handling equipment.
7. Provide walk-off mats at each entrance through temporary partition.

3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Operate Project-identification-sign lighting daily from dusk until 12:00 midnight.
- D. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- E. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 2. Remove temporary roads and paved areas not intended for or acceptable for integration into permanent construction. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
 3. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 017700 "Closeout Procedures."

END OF SECTION 01 31 00

SECTION 01 32 33 - PHOTOGRAPHIC DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Preconstruction photographs.
 - 2. Periodic construction photographs.
 - 3. Final completion construction photographs.

1.3 INFORMATIONAL SUBMITTALS

- A. Key Plan: Submit key plan of Project site and building with notation of vantage points marked for location and direction of each photograph. Indicate elevation or story of construction. Include same information as corresponding photographic documentation.
- B. Digital Photographs: Submit image files within three days of taking photographs.
 - 1. Digital Camera: Minimum sensor resolution of 8 megapixels.
 - 2. Format: Minimum 3200 by 2400 pixels, in unaltered original files, with same aspect ratio as the sensor, uncropped, date and time stamped, in folder named by date of photograph, accompanied by key plan file.

1.4 QUALITY ASSURANCE

- A. Photographer Qualifications: An individual experienced in using the photographic equipment to produce new professional looking pictures and experienced in storing and transferring electronic documents. Photographer must be approved by the owner, and must be replaced if directed by the owner due to unsatisfactory services being provided.

- 1.5 Retain "Photographer Qualifications" Paragraph below when project circumstances warrant services of a professional photographer in lieu of ordinary documentation by Contractor's project staff.

1.6 USAGE RIGHTS

- A. Obtain and transfer copyright usage rights from photographer to Owner for unlimited reproduction of photographic documentation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 2 - PRODUCTS

2.1 PHOTOGRAPHIC MEDIA

- A. Digital Images: Provide images in JPG format, produced by a digital camera with minimum sensor size of 8 megapixels, and at an image resolution of not less than 3200 by 2400 pixels.

PART 3 - EXECUTION

3.1 CONSTRUCTION PHOTOGRAPHS

- A. Photographer: Engage a qualified photographer to take construction photographs.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
 - 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
 - 1. Date and Time: Include date and time in file name for each image.
 - 2. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Architect and Owner.
- D. Preconstruction Photographs: Before starting construction, take photographs of Project site and surrounding properties, including existing items to remain during construction, from different vantage points, as directed by Architect and Owner.
 - 1. Flag construction limits before taking construction photographs.
 - 2. Take minimum of 20 photographs to show existing conditions adjacent to property before starting the Work.
 - 3. Take minimum of 20 photographs of existing buildings either on or adjoining property to accurately record physical conditions at start of construction.
 - 4. Take additional photographs as required to record settlement or cracking of adjacent structures, pavements, and improvements.
- E. Periodic Construction Photographs: Take 20 photographs monthly, coinciding with the cutoff date associated with each Application for Payment. Select vantage points to show status of construction and progress since last photographs were taken.
- F. Final Completion Construction Photographs: Take color photographs (as directed by Architect and owner) after date of Substantial Completion for submission as project record documents. Architect will inform photographer of desired vantage points.
 - 1. Do not include date stamp.

END OF SECTION 01 32 33

SECTION 01 33 00 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Requirements:
 - 1. Section 01 32 00 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
 - 2. Section 01 78 23 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
 - 3. Section 01 78 39 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
 - 4. Section 01 79 00 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action.
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements.

1.3 ACTION SUBMITTALS

- A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- B. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 1. Initial Review: Allow [7] seven days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 - 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 - 3. Resubmittal Review: Allow [7] seven days for review of each resubmittal.
- C. Options: Identify options requiring selection by Architect.
- D. Deviations: Identify deviations from the Contract Documents on submittals.
- E. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
 - 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- F. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- G. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements:
 - 1. The General Contractor shall submit electronic submittals as PDF electronic files to the Architect.
 - a. Subcontractors and suppliers are to provide PDF files of their submittals to the General Contractor. The GC shall review the subcontractor's submittal and apply a stamp certifying that it complies with the requirements of the Contract Documents, including verification of manufacturer/product, dimensions, and coordination with other parts of the work. The Contractor shall then transmit each submittal to the Architect. Only the General Contractor may post submittals to the Architect.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- b. The Architect or his consultant will mark the submittal with his comments and stamp, and return it to the Contractor, with a copy sent to the Owner.
 - c. Distribution of the reviewed submittals to subcontractors and suppliers is the responsibility of the General Contractor.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 - 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
 - 2. Mark each copy of each submittal to show which products and options are applicable.
 - 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 - 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams showing factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 - 5. Submit Product Data before or concurrent with Samples.
 - 6. Submit Product Data in the following format: as stated above.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data[, unless submittal based on Architect's digital data drawing files is otherwise permitted].
 - 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.
 - 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches (215 by 280 mm), but no larger than 30 by 42 inches (750 by 1067 mm).

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 2. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of applicable Specification Section.
 3. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
 4. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit three sets of Samples. Architect retain two Sample sets; remainder will be returned.
 - 1) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- E. Contractor's Construction Schedule: Comply with requirements specified in Section 01 32 00 "Construction Progress Documentation."
- F. Application for Payment and Schedule of Values: Comply with requirements specified in Section 01 29 00 "Payment Procedures".
- G. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 01 40 00 "Quality Requirements."
- H. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 01 77 00 "Closeout Procedures."
- I. Maintenance Data: Comply with requirements specified in Section 01 78 23 "Operation and Maintenance Data."
- J. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- K. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.

- L. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- M. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- N. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- O. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- P. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- Q. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- R. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project.
- S. Schedule of Tests and Inspections: Comply with requirements specified in Section 014000 "Quality Requirements."
- T. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- U. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- V. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- W. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file and three paper copies of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
 - 1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Section 01 77 00 "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 01 33 00

SECTION 01 40 00 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 2. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
 - 3. Specific test and inspection requirements are not specified in this Section.

1.2 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.
 - 1. Laboratory Mockups: Full-size physical assemblies constructed at testing facility to verify performance characteristics.
- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.

- F. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- H. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.3 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.4 INFORMATIONAL SUBMITTALS

- A. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:
 - 1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system quality-assurance plan prepared by Architect.
 - 2. Main wind-force-resisting system or a wind-resisting component listed in the wind-force-resisting system quality-assurance plan prepared by Architect.
- B. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

1.5 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
1. Date of issue.
 2. Project title and number.
 3. Name, address, and telephone number of testing agency.
 4. Dates and locations of samples and tests or inspections.
 5. Names of individuals making tests and inspections.
 6. Description of the Work and test and inspection method.
 7. Identification of product and Specification Section.
 8. Complete test or inspection data.
 9. Test and inspection results and an interpretation of test results.
 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 12. Name and signature of laboratory inspector.
 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Field Reports: Prepare written information documenting tests and inspections specified in other Sections. Include the following:
1. Name, address, and telephone number of representative making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 4. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 5. Other required items indicated in individual Specification Sections.
- C. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products that are similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
 - 1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
 - 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 - 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Manufacturer's Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
 - 1. Contractor responsibilities include the following:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Build laboratory mockups at testing facility using personnel, products, and methods of construction indicated for the completed Work.
 - d. When testing is complete, remove test specimens, assemblies, mockups; do not reuse products on Project.
 - 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- J. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
 - 1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
 - 2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
 - 3. Demonstrate the proposed range of aesthetic effects and workmanship.

4. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
 - a. Allow seven days for initial review and each re-review of each mockup.
 5. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 6. Demolish and remove mockups when directed unless otherwise indicated.
- K. Laboratory Mockups: Comply with requirements of preconstruction testing and those specified in individual Specification Sections.

1.7 QUALITY CONTROL

- A. Contractor Responsibilities: The sole Owner-provided testing and inspections consists of IBC Chapter 17 Special Inspections, as described in Paragraph 1.8 below. All other tests and inspections are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
1. Except as called for in paragraph 1.8 below, Contractor shall engage a qualified testing agency to perform quality-control services. The testing agency may be the same as that used by the Owner for Chapter 17 Special Inspections.
 2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
 3. Submit a certified written report, in duplicate, of each quality-control service.
 4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- B. Manufacturer's Field Services: Where indicated, engage a manufacturer's representative to observe and inspect the Work. Manufacturer's representative's services include examination of substrates and conditions, verification of materials, inspection of completed portions of the Work, and submittal of written reports.
- C. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- D. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 6. Do not perform any duties of Contractor.

- E. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
 - 1. Access to the Work.
 - 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 - 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 - 4. Facilities for storage and field curing of test samples.
 - 5. Delivery of samples to testing agencies.
 - 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 - 7. Security and protection for samples and for testing and inspecting equipment at Project site.
- F. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
 - 1. Schedule times for tests, inspections, obtaining samples, and similar activities.

1.8 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage a qualified special inspector to conduct special tests and inspections required by Chapter 17 of the International Building Code as the responsibility of Owner, and as follows:
 - 1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
 - 2. Notifying Architect and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
 - 3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect with copy to Contractor and to authorities having jurisdiction.
 - 4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
 - 5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
 - 6. Retesting and reinspecting corrected work.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
 - 1. Date test or inspection was conducted.
 - 2. Description of the Work tested or inspected.
 - 3. Date test or inspection results were transmitted to Architect.

4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
 1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 01 73 00 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01 40 00

SECTION 01 42 00 - REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.3 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

AABC	Associated Air Balance Council
AAMA	American Architectural Manufacturers Association
AASHTO	American Association of State Highway and Transportation Officials
AATCC	American Association of Textile Chemists and Colorists
ABMA	American Bearing Manufacturers Association
ACI	American Concrete Institute (Formerly: ACI International)
ACPA	American Concrete Pipe Association
AEIC	Association of Edison Illuminating Companies, Inc. (The)
AF&PA	American Forest & Paper Association
AGA	American Gas Association
AHAM	Association of Home Appliance Manufacturers
AHRI	Air-Conditioning, Heating, and Refrigeration Institute (The)
AI	Asphalt Institute
AIA	American Institute of Architects (The)
AISC	American Institute of Steel Construction
AISI	American Iron and Steel Institute
AITC	American Institute of Timber Construction
AMCA	Air Movement and Control Association International, Inc.
ANSI	American National Standards Institute
AOSA	Association of Official Seed Analysts, Inc.
APA	APA - The Engineered Wood Association

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

APA	Architectural Precast Association
API	American Petroleum Institute
ARI	Air-Conditioning & Refrigeration Institute (See AHRI)
ARI	American Refrigeration Institute (See AHRI)
ARMA	Asphalt Roofing Manufacturers Association
ASCE	American Society of Civil Engineers
ASCE/SEI	American Society of Civil Engineers/Structural Engineering Institute (See ASCE)
ASHRAE	American Society of Heating, Refrigerating and Air-Conditioning Engineers
ASME	ASME International (American Society of Mechanical Engineers)
ASSE	American Society of Safety Engineers (The)
ASSE	American Society of Sanitary Engineering
ASTM	ASTM International (American Society for Testing and Materials International)
ATIS	Alliance for Telecommunications Industry Solutions
AWEA	American Wind Energy Association
AWI	Architectural Woodwork Institute
AWMAC	Architectural Woodwork Manufacturers Association of Canada
AWPA	American Wood Protection Association (Formerly: American Wood-Preservers' Association)
AWS	American Welding Society
AWWA	American Water Works Association
BHMA	Builders Hardware Manufacturers Association
BIA	Brick Industry Association (The)
BICSI	BICSI, Inc.
BIFMA	BIFMA International (Business and Institutional Furniture Manufacturer's Association)
BISSC	Baking Industry Sanitation Standards Committee
BOCA	BOCA (Building Officials and Code Administrators International Inc.) (See ICC)
BWF	Badminton World Federation (Formerly: International Badminton Federation)
CDA	Copper Development Association

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

CEA	Canadian Electricity Association
CEA	Consumer Electronics Association
CFFA	Chemical Fabrics & Film Association, Inc.
CFSEI	Cold-Formed Steel Engineers Institute
CGA	Compressed Gas Association
CIMA	Cellulose Insulation Manufacturers Association
CISCA	Ceilings & Interior Systems Construction Association
CISPI	Cast Iron Soil Pipe Institute
CLFMI	Chain Link Fence Manufacturers Institute
CPA	Composite Panel Association
CRI	Carpet and Rug Institute (The)
CRRC	Cool Roof Rating Council
CRSI	Concrete Reinforcing Steel Institute
CSA	Canadian Standards Association
CSA	CSA International (Formerly: IAS - International Approval Services)
CSI	Construction Specifications Institute (The)
CSSB	Cedar Shake & Shingle Bureau
CTI	Cooling Technology Institute (Formerly: Cooling Tower Institute)
CWC	Composite Wood Council (See CPA)
DASMA	Door and Access Systems Manufacturers Association
DHI	Door and Hardware Institute
ECA	Electronic Components Association
ECAMA	Electronic Components Assemblies & Materials Association (See ECA)
EIA	Electronic Industries Alliance (See TIA)
EIMA	EIFS Industry Members Association
EJMA	Expansion Joint Manufacturers Association, Inc.
ESD	ESD Association (Electrostatic Discharge Association)
ESTA	Entertainment Services and Technology Association (See PLASA)

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

EVO	Efficiency Valuation Organization
FIBA	Federation Internationale de Basketball (The International Basketball Federation)
FIVB	Federation Internationale de Volleyball (The International Volleyball Federation)
FM Approvals	FM Approvals LLC
FM Global	FM Global (Formerly: FMG - FM Global)
FRSA	Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.
FSA	Fluid Sealing Association
FSC	Forest Stewardship Council U.S.
GA	Gypsum Association
GANA	Glass Association of North America
GS	Green Seal
HI	Hydraulic Institute
HI/GAMA	Hydronics Institute/Gas Appliance Manufacturers Association (See AHRI)
HMMA	Hollow Metal Manufacturers Association (See NAAMM)
HPVA	Hardwood Plywood & Veneer Association
HPW	H. P. White Laboratory, Inc.
IAPSC	International Association of Professional Security Consultants
IAS	International Approval Services (See CSA)
ICBO	International Conference of Building Officials (See ICC)
ICC	International Code Council
ICEA	Insulated Cable Engineers Association, Inc.
ICPA	International Cast Polymer Alliance
ICRI	International Concrete Repair Institute, Inc.
IEC	International Electrotechnical Commission
IEEE	Institute of Electrical and Electronics Engineers, Inc. (The)
IES	Illuminating Engineering Society (Formerly: Illuminating Engineering Society of North America)
IESNA	Illuminating Engineering Society of North America (See IES)
IEST	Institute of Environmental Sciences and Technology

IGMA	Insulating Glass Manufacturers Alliance
IGSHPA	International Ground Source Heat Pump Association
ILI	Indiana Limestone Institute of America, Inc.
Intertek	Intertek Group (Formerly: ETL SEMCO; Intertek Testing Service NA)
ISA	International Society of Automation (The) (Formerly: Instrumentation, Systems, and Automation Society)
ISAS	Instrumentation, Systems, and Automation Society (The) (See ISA)
ISFA	International Surface Fabricators Association (Formerly: International Solid Surface Fabricators Association)
ISO	International Organization for Standardization
ISSFA	International Solid Surface Fabricators Association (See ISFA)
ITU	International Telecommunication Union
KCMA	Kitchen Cabinet Manufacturers Association
LMA	Laminating Materials Association (See CPA)
LPI	Lightning Protection Institute
MBMA	Metal Building Manufacturers Association
MCA	Metal Construction Association
MFMA	Maple Flooring Manufacturers Association, Inc.
MFMA	Metal Framing Manufacturers Association, Inc.
MHIA	Material Handling Industry of America
MIA	Marble Institute of America
MMPA	Moulding & Millwork Producers Association (Formerly: Wood Moulding & Millwork Producers Association)
MPI	Master Painters Institute
MSS	Manufacturers Standardization Society of The Valve and Fittings Industry Inc.
NAAMM	National Association of Architectural Metal Manufacturers
NACE	NACE International (National Association of Corrosion Engineers International)
NADCA	National Air Duct Cleaners Association
NAIMA	North American Insulation Manufacturers Association

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

NBGQA	National Building Granite Quarries Association, Inc.
NCAA	National Collegiate Athletic Association (The)
NCMA	National Concrete Masonry Association
NEBB	National Environmental Balancing Bureau NECA National Electrical Contractors Association
NeLMA	Northeastern Lumber Manufacturers Association
NEMA	National Electrical Manufacturers Association
NETA	InterNational Electrical Testing Association
NFHS	National Federation of State High School Associations
NFPA	NFPA (National Fire Protection Association)
NFPA	NFPA International (See NFPA)
NFRC	National Fenestration Rating Council
NHLA	National Hardwood Lumber Association
NLGA	National Lumber Grades Authority
NOFMA	National Oak Flooring Manufacturers Association (See NWFA)
NOMMA	National Ornamental & Miscellaneous Metals Association
NRCA	National Roofing Contractors Association
NRMCA	National Ready Mixed Concrete Association
NSF	NSF International (National Sanitation Foundation International)
NSPE	National Society of Professional Engineers
NSSGA	National Stone, Sand & Gravel Association
NTMA	National Terrazzo & Mosaic Association, Inc. (The)
NWFA	National Wood Flooring Association
PCI	Precast/Prestressed Concrete Institute
PDI	Plumbing & Drainage Institute
PLASA	PLASA (Formerly: ESTA - Entertainment Services and Technology Association)
RCSC	Research Council on Structural Connections
RFCI	Resilient Floor Covering Institute

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

RIS	Redwood Inspection Service
SAE	SAE International (Society of Automotive Engineers)
SBCCI	Southern Building Code Congress International, Inc. (See ICC)
SCTE	Society of Cable Telecommunications Engineers
SDI	Steel Deck Institute
SDI	Steel Door Institute
SEFA	Scientific Equipment and Furniture Association
SEI/ASCE	Structural Engineering Institute/American Society of Civil Engineers (See ASCE)
SIA	Security Industry Association
SJI	Steel Joist Institute
SMA	Screen Manufacturers Association
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association
SMPTE	Society of Motion Picture and Television Engineers
SPFA	Spray Polyurethane Foam Alliance
SPIB	Southern Pine Inspection Bureau
SPRI	Single Ply Roofing Industry
SRCC	Solar Rating and Certification Corporation
SSINA	Specialty Steel Industry of North America
SSPC	SSPC: The Society for Protective Coatings
STI	Steel Tank Institute
SWI	Steel Window Institute
SWPA	Submersible Wastewater Pump Association
TCA	Tilt-Up Concrete Association
TCNA	Tile Council of North America, Inc.
TEMA	Tubular Exchanger Manufacturers Association, Inc.
TIA	Telecommunications Industry Association (Formerly: TIA/EIA - Telecommunications Industry Association/Electronic Industries Alliance)
TIA/EIA	Telecommunications Industry Association/Electronic Industries Alliance (See TIA)
TMS	The Masonry Society

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

TPI	Truss Plate Institute
TPI	Turfgrass Producers International
TRI	Tile Roofing Institute
UBC	Uniform Building Code (See ICC)
UL	Underwriters Laboratories Inc.
UNI	Uni-Bell PVC Pipe Association
USAV	USA Volleyball
USGBC	U.S. Green Building Council
USITT	United States Institute for Theatre Technology, Inc.
WASTEC	Waste Equipment Technology Association
WCLIB	West Coast Lumber Inspection Bureau
WCMA	Window Covering Manufacturers Association
WDMA	Window & Door Manufacturers Association
WI	Woodwork Institute (Formerly: WIC - Woodwork Institute of California)
WMMPA	Wood Moulding & Millwork Producers Association (See MMPA)
WSRCA	Western States Roofing Contractors Association
WWPA	Western Wood Products Association

- C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

DIN	Deutsches Institut für Normung e.V.
IAPMO	International Association of Plumbing and Mechanical Officials
ICC	International Code Council
ICC-ES	ICC Evaluation Service, LLC

- D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

COE	Army Corps of Engineers
CPSC	Consumer Product Safety Commission

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

DOC	Department of Commerce National Institute of Standards and Technology
DOD	Department of Defense
DOE	Department of Energy
EPA	Environmental Protection Agency
FAA	Federal Aviation Administration
FG	Federal Government Publications
GSA	General Services Administration
HUD	Department of Housing and Urban Development
LBL	Lawrence Berkeley National Laboratory Environmental Energy Technologies Division
OSHA	Occupational Safety & Health Administration
SD	Department of State
TRB	Transportation Research Board National Cooperative Highway Research Program
USDA	Department of Agriculture Agriculture Research Service U.S. Salinity Laboratory
USDA	Department of Agriculture Rural Utilities Service
USDJ	Department of Justice Office of Justice Programs National Institute of Justice
USP	U.S. Pharmacopeia USPS United States Postal Service

- E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list.

CFR	Code of Federal Regulations Available from Government Printing Office
DOD	Department of Defense Military Specifications and Standards Available from Department of Defense Single Stock Point
DSCC	Defense Supply Center Columbus (See FS)

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

FED-STD	Federal Standard (See FS)
FS	Federal Specification Available from Department of Defense Single Stock Point Available from Defense Standardization Program Available from General Services Administration Available from National Institute of Building Sciences/Whole Building Design Guide
MILSPEC	Military Specification and Standards (See DOD)
USAB	United States Access Board
USATBCB	U.S. Architectural & Transportation Barriers Compliance Board (See USAB)

- F. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

CBHF	State of California Department of Consumer Affairs Bureau of Home Furnishings and Thermal Insulation
CCR	California Code of Regulations Office of Administrative Law California Title 24 Energy Code
CDHS	California Department of Health Care Services (Formerly: California Department of Health Services) (See CCR)
CDPH	California Department of Public Health Indoor Air Quality Program
CPUC	California Public Utilities Commission
SCAQMD	South Coast Air Quality Management District
TFS	Texas Forest Service Forest Resource Development and Sustainable Forestry

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 42 00

SECTION 01 50 00 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

1.2 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, testing agencies, and authorities having jurisdiction.

1.3 INFORMATIONAL SUBMITTALS

- A. Site Plan: Show temporary facilities, utility hookups, staging areas, and parking areas for construction personnel.
- B. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
- C. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire prevention program.

1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.5 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 TEMPORARY FACILITIES

- A. Field Offices, General: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.
- B. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.

2.2 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
 - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Obtain Architect's approval prior to installation of facilities. Relocate and modify facilities as required by progress of the Work when approved by Architect.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service.
- B. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Heating: Provide temporary heating required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.

- E. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.
- F. Electric Power Service: Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
 - 1. Install temporary electric power service overhead unless otherwise indicated.
- G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- H. Telephone Service:
 - 1. Provide superintendent with cellular telephone or portable two-way radio for use when away from field office.
- I. Electronic Communication Service: Provide a desktop computer in the primary field office adequate for use by Architect and Owner to access project electronic documents and maintain electronic communications.
 - 1. Printer: "All-in-one" unit equipped with printer, combining color printing, photocopying, scanning, and faxing, or separate units for each of these functions.
 - 2. Internet Service: Broadband modem, router and ISP, equipped with hardware firewall, providing minimum 384 Kbps upload and 1 Mbps download speeds at each computer.
 - 3. Internet Security: Integrated software, providing software firewall, virus, spyware, phishing, and spam protection in a combined application.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
 - 1. Provide construction for temporary offices, shops, and sheds located within construction area or within 30 feet (9 m) of building lines that is noncombustible according to ASTM E 136. Comply with NFPA 241.
 - 2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Temporary Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate for construction operations. Locate temporary roads and paved areas within construction limits indicated on Drawings.
 - 1. Provide dust-control treatment that is nonpolluting and nontracking. Reapply treatment as required to minimize dust.
- C. Temporary Use of Permanent Roads and Paved Areas: Locate temporary roads and paved areas in same location as permanent roads and paved areas. Construct and maintain temporary roads and paved areas adequate for construction operations. Extend temporary roads and paved areas, within construction limits indicated, as necessary for construction operations.

1. Coordinate elevations of temporary roads and paved areas with permanent roads and paved areas.
 2. Prepare subgrade and install subbase and base for temporary roads and paved areas according to Section 31 20 00 "Earth Moving."
 3. Recondition base after temporary use, including removing contaminated material, regrading, proofrolling, compacting, and testing.
 4. Delay installation of final course of permanent hot-mix asphalt pavement until immediately before Substantial Completion. Repair hot-mix asphalt base-course pavement before installation of final course according to Section 32 12 16 "Asphalt Paving."
- D. Traffic Controls: Comply with requirements of authorities having jurisdiction.
1. Protect existing site improvements to remain including curbs, pavement, and utilities.
 2. Maintain access for fire-fighting equipment and access to fire hydrants.
- E. Parking: Provide temporary parking areas for construction personnel.
- F. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction. Maintain Project site, excavations, and construction free of water.
1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining properties or endanger permanent Work or temporary facilities.
 2. Remove snow and ice as required to minimize accumulations.
- G. Project Signs: Provide Project signs as indicated.
1. Provide other signs as required to inform public and individuals seeking entrance to Project.
 - a. Provide temporary, directional signs for construction personnel and visitors.
 2. Maintain and touchup signs so they are legible at all times.
- H. Waste Disposal Facilities: Comply with requirements specified in Section 01 74 19 "Construction Waste Management and Disposal."
- I. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of authorities having jurisdiction. Comply with progress cleaning requirements in Section 01 73 00 "Execution."
- J. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.
- K. Temporary Stairs: Until permanent stairs are available, provide temporary stairs where ladders are not adequate.
- L. Temporary Use of Permanent Stairs: Use of new stairs for construction traffic will be permitted, provided stairs are protected and finishes restored to new condition at time of Substantial Completion.
- 3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION
- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.

- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- C. Temporary Erosion and Sedimentation Control: Provide measures to prevent soil erosion and discharge of soil-bearing water runoff and airborne dust to undisturbed areas and to adjacent properties and walkways.
- D. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- E. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.
- F. Pest Control: Engage pest-control service to recommend practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.
- G. Temporary Egress: Maintain temporary egress from existing occupied facilities as indicated and as required by authorities having jurisdiction.
- H. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities.
 - 1. Where heating or cooling is needed and permanent enclosure is not complete, insulate temporary enclosures.
- I. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire prevention program.
 - 1. Prohibit smoking in construction areas.
 - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
 - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
 - 4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

3.5 MOISTURE AND MOLD CONTROL

- A. Contractor's Moisture Protection Plan: Avoid trapping water in finished work. Document visible signs of mold that may appear during construction.
- B. Exposed Construction Phase: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect materials from water damage and keep porous and organic materials from coming into prolonged contact with concrete.
- C. Partially Enclosed Construction Phase: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:

1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
2. Keep interior spaces reasonably clean and protected from water damage.
3. Discard or replace water-damaged and wet material.
4. Discard, replace, or clean stored or installed material that begins to grow mold.
5. Perform work in a sequence that allows any wet materials adequate time to dry before enclosing the material in drywall or other interior finishes.

D. Controlled Construction Phase of Construction: After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Remove materials that cannot be completely restored to their manufactured moisture level within 48 hours.

3.6 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
2. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 01 77 00 "Closeout Procedures."

END OF SECTION 01 50 00

SECTION 01 60 00 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Requirements:
 - 1. Section 00 26 00 "Procurement Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a specific manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of additional manufacturers named in the specification.

1.3 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

- a. Form of Approval: As specified in Section 01 33 00 "Submittal Procedures."
 - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 01 33 00 "Submittal Procedures." Show compliance with requirements.

1.4 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
 - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.
- C. Storage:
 - 1. Store products to allow for inspection and measurement of quantity or counting of units.
 - 2. Store materials in a manner that will not endanger Project structure.
 - 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
 - 4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
 - 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
 - 6. Protect stored products from damage and liquids from freezing.

1.6 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
 2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
 3. Refer to other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 01 77 00 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 4. Where products are accompanied by the term "as selected," Architect will make selection.
 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Product Selection Procedures:
1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 3. Products:
 - a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 4. Manufacturers:

- a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
5. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
- C. Visual Matching Specification: Where Specifications require "match Architect's sample", provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 01 25 00 "Substitution Procedures" for proposal of product.
- D. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
 1. Evidence that the proposed product does not require revisions to the Contract Documents that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 3. Evidence that proposed product provides specified warranty.
 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 60 00

SECTION 01 73 00 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Field engineering and surveying.
 - 3. Installation of the Work.
 - 4. Cutting and patching.
 - 5. Coordination of Owner-installed products.
 - 6. Progress cleaning.
 - 7. Starting and adjusting.
 - 8. Protection of installed construction.

1.2 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For **land surveyor**.
- B. Certificates: Submit certificate signed by **land surveyor** certifying that location and elevation of improvements comply with requirements.
- C. Certified Surveys: Submit **two** copies signed by **land surveyor**.
- D. Final Property Survey: Submit **2** copies showing the Work performed and record survey data.

1.3 QUALITY ASSURANCE

- A. Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.
 - 1. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety
 - 2. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.
- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, **mechanical and electrical systems**, and other construction affecting the Work.
 - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
 - 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
 - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to **local utility and to Owner** that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Owner.

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey and existing benchmarks. If discrepancies are discovered, notify Engineer **and Owner** promptly.
- B. General: Engage a **land surveyor** to lay out the Work using accepted surveying practices.
 - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
 - 2. Establish limits on use of Project site.
 - 3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 4. Inform installers of lines and levels to which they must comply.
 - 5. Check the location, level and plumb, of every major element as the Work progresses.
 - 6. Notify Engineer **and Owner** when deviations from required lines and levels exceed allowable tolerances.
 - 7. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.
- C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and rim and invert elevations.
- D. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Engineer **and Owner**.

3.4 FIELD ENGINEERING

- A. Identification: Owner will identify existing benchmarks, control points, and property corners.
- B. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
 - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect **or Owner**. Report lost or destroyed permanent benchmarks or control points promptly.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.
- C. Final Property Survey: Engage a **land surveyor** to prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by **land surveyor** that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.
1. Show boundary lines, monuments, streets, site improvements and utilities, existing improvements and significant vegetation, adjoining properties, acreage, grade contours, and the distance and bearing from a site corner to a legal point.
 2. Recording: At Substantial Completion, have the final property survey recorded by or with authorities having jurisdiction as the official "property survey."

3.5 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

END OF SECTION 01 73 00

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for the following:
 - 1. Recycling nonhazardous demolition and construction waste.
 - 2. Disposing of nonhazardous demolition and construction waste.
- B. Related Requirements:
 - 1. Section 024119 "Selective Demolition" for disposition of waste resulting from partial demolition of buildings, structures, and site improvements.
 - 2. Section 042000 "Unit Masonry" for disposal requirements for masonry waste.
 - 3. Section 311000 "Site Clearing" for disposition of waste resulting from site clearing and removal of above- and below-grade improvements.

1.3 DEFINITIONS

- A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.
- C. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.
- E. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.
- F. Salvage and Reuse: Recovery of demolition or construction waste and subsequent incorporation into the Work.

1.4 PERFORMANCE REQUIREMENTS

- A. General: Achieve end-of-Project rates for salvage/recycling of 75 percent by weight of total non-hazardous solid waste generated by the Work. Practice efficient waste management in the use of materials in the course of the Work. Use all reasonable means to divert construction and

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

demolition waste from landfills and incinerators. Facilitate recycling and salvage of materials, including the following:

1. Demolition Waste:

- a. Asphalt paving.
- b. Concrete.
- c. Concrete reinforcing steel.
- d. Brick.
- e. Concrete masonry units.
- f. Wood studs.
- g. Wood joists.
- h. Plywood and oriented strand board.
- i. Wood paneling.
- j. Wood trim.
- k. Structural and miscellaneous steel.
- l. Rough hardware.
- m. Roofing.
- n. Insulation.
- o. Doors and frames.
- p. Door hardware.
- q. Windows.
- r. Glazing.
- s. Metal studs.
- t. Gypsum board.
- u. Acoustical tile and panels.
- v. Carpet.
- w. Carpet pad.
- x. Demountable partitions.
- y. Equipment.
- z. Cabinets.
- aa. Plumbing fixtures.
- bb. Piping.
- cc. Supports and hangers.
- dd. Valves.
- ee. Sprinklers.
- ff. Mechanical equipment.
- gg. Refrigerants.
- hh. Electrical conduit.
- ii. Copper wiring.
- jj. Lighting fixtures.
- kk. Lamps.
- ll. Ballasts.
- mm. Electrical devices.
- nn. Switchgear and panelboards.
- oo. Transformers.

2. Construction Waste:

- a. Masonry and CMU.
- b. Lumber.
- c. Wood sheet materials.
- d. Wood trim.
- e. Metals.
- f. Roofing.
- g. Insulation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- h. Carpet.
- i. Gypsum board.
- j. Piping.
- k. Electrical conduit.
- l. Packaging: Regardless of salvage/recycle goal indicated in "General" Paragraph above, salvage or recycle 100 percent of the following uncontaminated packaging materials:
 - 1) Paper.
 - 2) Cardboard.
 - 3) Boxes.
 - 4) Plastic sheet and film.
 - 5) Polystyrene packaging.
 - 6) Wood crates.
 - 7) Plastic pails.

1.5 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Waste Management Conference: Conduct conference at Project site. Review methods and procedures related to waste management including, but not limited to, the following:
 - 1. Review and discuss waste management plan.
 - 2. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
 - 3. Review waste management requirements for each trade.

PART 2 - EXECUTION

2.1 PLAN IMPLEMENTATION

- A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
- B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.
 - 1. Distribute waste management plan to everyone concerned within three days of submittal return.
 - 2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.
- C. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged, recycled, reused, donated, and sold.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Comply with Section 015000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.

2.2 RECYCLING DEMOLITION AND CONSTRUCTION WASTE, GENERAL

- A. General: Recycle paper and beverage containers used by on-site workers.
- B. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall accrue to Owner.
- C. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.
- D. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.
 1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.
 - a. Inspect containers and bins for contamination and remove contaminated materials if found.
 2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
 3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
 4. Store components off the ground and protect from the weather.
 5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor.

2.3 RECYCLING DEMOLITION WASTE

- A. Asphalt Paving: Grind asphalt to maximum 4-inch (100-mm) size.
- B. Concrete: Remove reinforcement and other metals from concrete and sort with other metals.
 1. Pulverize concrete to maximum 4-inch (100-mm) size.
- C. Masonry: Remove metal reinforcement, anchors, and ties from masonry and sort with other metals.
 1. Pulverize masonry to maximum 4-inch (100-mm) size.
- D. Metals: Separate metals by type.
 1. Structural Steel: Stack members according to size, type of member, and length.
 2. Remove and dispose of bolts, nuts, washers, and other rough hardware.
- E. Acoustical Ceiling Panels and Tile: Stack large clean pieces on wood pallets and store in a dry location.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- F. Metal Suspension System: Separate metal members including trim, and other metals from acoustical panels and tile and sort with other metals.
- G. Carpet: Roll large pieces tightly after removing debris, trash, adhesive, and tack strips.
 - 1. Store clean, dry carpet in a closed container or trailer provided by Carpet Reclamation Agency or carpet recycler.
- H. Carpet Tile: Remove debris, trash, and adhesive.
 - 1. Stack tile on pallet and store clean, dry carpet in a closed container or trailer provided by Carpet Reclamation Agency or carpet recycler.
- I. Piping: Reduce piping to straight lengths and store by type and size. Separate supports, hangers, valves, sprinklers, and other components by type and size.
- J. Conduit: Reduce conduit to straight lengths and store by type and size.

2.4 RECYCLING CONSTRUCTION WASTE

- A. Packaging:
 - 1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
 - 2. Polystyrene Packaging: Separate and bag materials.
 - 3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
 - 4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.
- B. Wood Materials:
 - 1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
 - 2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.
 - a. Comply with requirements in Section 329300 "Plants" for use of clean sawdust as organic mulch.
- C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.
 - 1. Clean Gypsum Board: Grind scraps of clean gypsum board using small mobile chipper or hammer mill. Screen out paper after grinding.
 - a. Comply with requirements in Section 329300 "Plants" for use of clean ground gypsum board as inorganic soil amendment.

2.5 DISPOSAL OF WASTE

- A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn waste materials.
- C. Disposal: Remove waste materials from Owner's property and legally dispose of them.

END OF SECTION 01 74 19

SECTION 01 77 00 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
 - 5. Repair of the Work.

1.2 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

1.4 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 5 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
 - 1. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 3. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of **5** days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 2. Complete final cleaning requirements, including touchup painting.
 3. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of **5** days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Engineer and Owner will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Engineer, that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 2. Results of completed inspection will form the basis of requirements for final completion.

1.5 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 2. Certified List of Incomplete Items: .
 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 5 days prior to date the work will be completed and ready for final inspection and tests. Engineer will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.6 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Owner for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
- C. Construction Waste Disposal: Comply with waste disposal requirements specified.

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.

END OF SECTION 01 77 00

SECTION 017823 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance documentation directory.
 - 2. Emergency manuals.
 - 3. Operation manuals for systems, subsystems, and equipment.
 - 4. Product maintenance manuals.
 - 5. Systems and equipment maintenance manuals.

1.3 CLOSEOUT SUBMITTALS

- A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Architect **and Commissioning Authority** will comment on whether content of operations and maintenance submittals are acceptable.
 - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operations and maintenance manuals in the following format:
 - 1. PDF electronic file. Assemble each manual into a composite electronically indexed file. Submit on digital media acceptable to Architect.
 - a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.
 - b. Enable inserted reviewer comments on draft submittals.
- C. Initial Manual Submittal: Submit draft copy of each manual at least **30** days before commencing demonstration and training. Architect **and Commissioning Authority** will comment on whether general scope and content of manual are acceptable.
- D. Final Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least **15** days before commencing demonstration and training. Architect **and Commissioning Authority** will return copy with comments.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Correct or revise each manual to comply with Architect's **and Commissioning Authority's** comments. Submit copies of each corrected manual within **15** days of receipt of Architect's **and Commissioning Authority's** comments and prior to commencing demonstration and training.

PART 2 - PRODUCTS

2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Directory: Prepare a single, comprehensive directory of emergency, operation, and maintenance data and materials, listing items and their location to facilitate ready access to desired information. Include a section in the directory for each of the following:
 1. List of documents.
 2. List of systems.
 3. List of equipment.
 4. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

2.2 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 1. Title page.
 2. Table of contents.
 3. Manual contents.
- B. Title Page: Include the following information:
 1. Subject matter included in manual.
 2. Name and address of Project.
 3. Name and address of Owner.
 4. Date of submittal.
 5. Name and contact information for Contractor.
 6. Name and contact information for Construction Manager.
 7. Name and contact information for Architect.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

8. Name and contact information for Commissioning Authority.
 9. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
 10. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
 2. File Names and Bookmarks: Enable bookmarking of individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.
- F. Manuals, Paper Copy: Submit manuals in the form of hard copy, bound and labeled volumes.
1. Binders: Heavy-duty, three-ring, vinyl-covered, **loose-leaf** binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.
 - a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
 - b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, **and** subject matter of contents, **and indicate Specification Section number on bottom of spine.** Indicate volume number for multiple-volume sets.
 2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
 3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment.
 4. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
 5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
- b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.3 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
 2. Performance and design criteria if Contractor has delegated design responsibility.
 3. Operating standards.
 4. Operating procedures.
 5. Operating logs.
 6. Wiring diagrams.
 7. Control diagrams.
 8. Piped system diagrams.
 9. Precautions against improper use.
 10. License requirements including inspection and renewal dates.
- B. Descriptions: Include the following:
1. Product name and model number. Use designations for products indicated on Contract Documents.
 2. Manufacturer's name.
 3. Equipment identification with serial number of each component.
 4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include the following, as applicable:
1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.4 PRODUCT MAINTENANCE MANUALS

- A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Product Information: Include the following, as applicable:
 - 1. Product name and model number.
 - 2. Manufacturer's name.
 - 3. Color, pattern, and texture.
 - 4. Material and chemical composition.
 - 5. Reordering information for specially manufactured products.
- D. Maintenance Procedures: Include manufacturer's written recommendations and the following:
 - 1. Inspection procedures.
 - 2. Types of cleaning agents to be used and methods of cleaning.
 - 3. List of cleaning agents and methods of cleaning detrimental to product.
 - 4. Schedule for routine cleaning and maintenance.
 - 5. Repair instructions.
- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

2.5 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:
 - 1. Standard maintenance instructions and bulletins.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
 3. Identification and nomenclature of parts and components.
 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
1. Test and inspection instructions.
 2. Troubleshooting guide.
 3. Precautions against improper maintenance.
 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 5. Aligning, adjusting, and checking instructions.
 6. Demonstration and training video recording, if available.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
1. Include procedures to follow and required notifications for warranty claims.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

- A. Operation and Maintenance Documentation Directory: Prepare a separate manual that provides an organized reference to emergency, operation, and maintenance manuals.
- B. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- C. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- D. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- E. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- F. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
1. Do not use original project record documents as part of operation and maintenance manuals.
 2. Comply with requirements of newly prepared record Drawings in Section 017839 "Project Record Documents."
- G. Comply with Section 01 77 00 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 01 78 23

SECTION 01 78 39 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
 - 1. Record Drawings.
 - 2. Record Specifications.
 - 3. Record Product Data.
 - 4. Miscellaneous record submittals.

1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit **one** set(s) of marked-up record prints.
 - 2. Number of Copies: Submit copies of record Drawings as follows:
 - a. Initial Submittal:
 - 1) Submit **one** paper-copy set(s) of marked-up record prints.
 - 2) Engineer will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.
 - b. Final Submittal:
 - 1) Submit PDF electronic files of scanned record prints and one set of prints.
 - 2) Print each drawing, whether or not changes and additional information were recorded.
- B. Record Specifications: Submit **one paper copy** of Project's Specifications, including addenda and contract modifications.
- C. Record Product Data: Submit **one paper copy and annotated PDF electronic files and directories** of each submittal.
 - 1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.
- D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit **one paper copy and annotated PDF electronic files** of each submittal.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an acceptable drawing technique.
 - c. Record data as soon as possible after obtaining it.
 - d. Record and check the markup before enclosing concealed installations.
 2. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 3. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 4. Mark important additional information that was either shown schematically or omitted from original Drawings.
 5. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

2.2 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 4. For each principal product, indicate whether record Product Data has been submitted in operation and maintenance manuals instead of submitted as record Product Data.
 5. Note related Change Orders, **record Product Data**, and record Drawings where applicable.
- B. Format: Submit record Specifications as **scanned PDF electronic file(s) of marked-up paper copy of Specifications**.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Engineer's **and Owner's** reference during normal working hours.

END OF SECTION 01 78 39

SECTION 01 79 00 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Demonstration of operation of systems, subsystems, and equipment.
 - 2. Training in operation and maintenance of systems, subsystems, and equipment.
 - 3. Demonstration and training video recordings.

1.3 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
 - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.
- B. Attendance Record: For each training module, submit list of participants and length of instruction time.
- C. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

1.4 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Submit **two** copies within **seven** days of end of each training module.
 - 1. Identification: On each copy, provide an applied label with the following information:
 - a. Name of Project.
 - b. Name and address of videographer.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Date of video recording.
 - 2. At completion of training, submit complete training manual(s) for Owner's use **in PDF electronic file format on compact disc**.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.5 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Architect.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Operations manuals.
 - b. Maintenance manuals.
 - c. Project record documents.
 - d. Identification systems.
 - e. Warranties and bonds.
 - f. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.
 - f. Safety procedures.
 - g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
5. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
6. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
7. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
8. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 3 - EXECUTION

3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."
- B. Set up instructional equipment at instruction location.

3.2 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
 - 1. Architect will furnish an instructor to describe basis of system design, operational requirements, criteria, and regulatory requirements.
 - 2. Owner will furnish an instructor to describe Owner's operational philosophy.
 - 3. Owner will furnish Contractor with names and positions of participants.
- C. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.

3.3 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

- A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.
 - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Video: Provide minimum 640 x 480 video resolution converted to **format file type acceptable to Owner**, on electronic media.
 - 1. Electronic Media: Read-only format compact disc acceptable to Owner, with commercial-grade graphic label.
 - 2. File Names: Utilize file names based upon name of equipment generally described in video segment, as identified in Project specifications.
 - 3. Contractor and Installer Contact File: Using appropriate software, create a file for inclusion on the Equipment Demonstration and Training DVD that describes the following for each Contractor involved on the Project, arranged according to Project table of contents:
 - a. Name of Contractor/Installer.
 - b. Business address.
 - c. Business phone number.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- d. Point of contact.
 - e. E-mail address.
- C. Recording: Mount camera on tripod before starting recording, unless otherwise necessary to adequately cover area of demonstration and training. Display continuous running time.
 - 1. Film training session(s) in segments not to exceed 15 minutes.
 - a. Produce segments to present a single significant piece of equipment per segment.
 - b. Organize segments with multiple pieces of equipment to follow order of Project Manual table of contents.
 - c. Where a training session on a particular piece of equipment exceeds 15 minutes, stop filming and pause training session. Begin training session again upon commencement of new filming segment.
- D. Light Levels: Verify light levels are adequate to properly light equipment. Verify equipment markings are clearly visible prior to recording.
 - 1. Furnish additional portable lighting as required.
- E. Preproduced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

END OF SECTION 01 79 00

SECTION 02 41 19 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Demolition and removal of selected portions of building or structure.
2. Demolition and removal of selected site elements.
3. Salvage of existing items to be reused.

1.2 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to Owner.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.3 INFORMATIONAL SUBMITTALS

- A. Predemolition Photographs or Video: Submit before Work begins.

1.4 CLOSEOUT SUBMITTALS

- A. Landfill Records: Indicate receipt and acceptance of hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.5 FIELD CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
1. Before selective demolition, Owner will remove the following items:
 - a. Smart boards.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
 - 1. Hazardous materials will be removed by Owner before start of the Work.
 - 2. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain fire-protection facilities in service during selective demolition operations.

1.6 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSE A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- D. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.

3.3 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
- C. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

3.4 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
 - 2. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 3. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
 - 4. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 - 5. Dispose of demolished items and materials promptly.
- B. Reuse of Building Elements: Do not demolish building elements beyond what is indicated on Drawings without Architect's approval.
- C. Removed and Salvaged Items:
 - 1. Clean salvaged items.
 - 2. Store items in a secure area until delivery to Owner.
 - 3. Protect items from damage during transport and storage.
- D. Removed and Reinstalled Items:
 - 1. Clean and repair items to functional condition adequate for intended reuse.
 - 2. Pack or crate items after cleaning and repairing. Identify contents of containers.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3. Protect items from damage during transport and storage.
 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- E. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

3.5 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Except for items or materials indicated to be recycled, reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site.
1. Do not allow demolished materials to accumulate on-site.
 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

3.6 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

END OF SECTION 02 41 19

SECTION 04 21 13 - BRICK MASONRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Face brick.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For each type and color of brick.

1.3 INFORMATIONAL SUBMITTALS

- A. Material Certificates: For each type and size of product indicated.

1.4 QUALITY ASSURANCE

- A. Masonry Standard: Comply with ACI 530.1/ASCE 6/TMS 602 unless modified by requirements in the Contract Documents.
- B. Sample Panels: Build sample panels to verify selections made under sample submittals and to demonstrate aesthetic effects. Comply with requirements in Section 01 40 00 "Quality Requirements" for mockups.
 - 1. Build sample panels for each type of exposed unit masonry construction in sizes approximately 60 inches (1500 mm) long by 48 inches (1200 mm) high by full thickness. Sample may become part of final construction if approved.

1.5 PROJECT CONDITIONS

- A. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.
 - 1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F (4 deg C) and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.
- B. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 MASONRY UNITS, GENERAL

- A. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated in the standard. Do not use units where such defects will be exposed in the completed Work.

2.2 BRICK

- A. Regional Materials: Brick shall be manufactured within 500 miles (800 km) of Project site from materials that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles (800 km) of Project site.
- B. General: Provide shapes indicated and as follows.
 - 1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.
 - 2. Provide special shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.
- C. Face Brick: Facing brick complying with ASTM C 216.
 - 1. Products: Subject to compliance with requirements, provide the following:
 - a. Brick to match existing as close as possible. Provide sample to architect for approval.
 - 2. Size (Actual Dimensions): 3-1/2 inches (89 mm) wide by 3-1/2 inches (89 mm) high by 11-1/2 inches (292 mm) long or 3-5/8 inches (92 mm) wide by 3-5/8 inches (92 mm) high by 11-5/8 inches (295 mm) long.

2.3 MORTAR MATERIALS

- A. Regional Materials: Aggregate for mortar shall be extracted, harvested, or recovered, as well as manufactured, within 500 miles (800 km) of Project site.
- B. Portland Cement: ASTM C 150, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.
- C. Hydrated Lime: ASTM C 207, Type S.
- D. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.
- E. Masonry Cement: ASTM C 91.
- F. Aggregate for Mortar: ASTM C 144.
 - 1. White-Mortar Aggregates: Natural white sand or crushed white stone.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- G. Cold-Weather Admixture: Nonchloride, noncorrosive, accelerating admixture complying with ASTM C 494/C 494M, Type C, and recommended by manufacturer for use in masonry mortar of composition indicated.
- H. Water-Repellent Admixture: Liquid water-repellent mortar admixture intended for use with concrete masonry units, containing integral water repellent by same manufacturer.

2.4 REINFORCEMENT

- A. Masonry Joint Reinforcement, General: ASTM A 951/A 951M.
- B. Masonry Joint Reinforcement for Veneers Anchored with Seismic Masonry-Veneer Anchors: Single 0.187-inch- (4.76-mm-) diameter, hot-dip galvanized, carbon-steel continuous wire.

2.5 TIES AND ANCHORS

- 1. See Section 04 22 00 for requirements.

2.6 EMBEDDED FLASHING MATERIALS

- A. Metal Flashing: Provide metal flashing complying with Section 07 62 00 "Sheet Metal Flashing and Trim" and as follows:
 - 1. Metal Drip Edge: Fabricate from stainless steel. Extend at least 3 inches (76 mm) into wall and 1/2 inch (13 mm) out from wall, with outer edge bent down 30 degrees and hemmed.
 - 2. Metal Sealant Stop: Fabricate from stainless steel. Extend at least 3 inches (76 mm) into wall and out to exterior face of wall. At exterior face of wall, bend metal back on itself for 3/4 inch (19 mm) and down into joint 1/4 inch (6 mm) to form a stop for retaining sealant backer rod.
- B. Flexible Flashing: Use[one of] the following unless otherwise indicated:
 - 1. Copper-Laminated Flashing: As shown on plans.
- C. Solder and Sealants for Sheet Metal Flashings: As specified in Section 07 62 00 "Sheet Metal Flashing and Trim."]
- D. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer's standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates.

2.7 MISCELLANEOUS MASONRY ACCESSORIES

- A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; formulated from neoprene, urethane or PVC.
- B. Bond-Breaker Strips: Asphalt-saturated, organic roofing felt complying with ASTM D 226, Type I (No. 15 asphalt felt).
- C. Weep/Vent Products: Use the following unless otherwise indicated:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Mesh Weep/Vent: Free-draining mesh; made from polyethylene strands, full height and width of head joint and depth 1/8 inch (3 mm) less than depth of outer wythe; in color selected from manufacturer's standard.
 - a. Products: Subject to compliance with requirements, provide the following:
 - 1) Mortar Net USA, Ltd.; Mortar Net Weep Vents.

2.8 MASONRY CLEANERS

- A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Diedrich Technologies, Inc.
 - b. EaCo Chem, Inc.
 - c. ProSoCo, Inc.

2.9 MORTAR MIXES

- A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures unless otherwise indicated.
 1. See Section 04 22 00 for requirements.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.
- B. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures.
- C. Wetting of Brick: Wet brick before laying if initial rate of absorption exceeds 30 g/30 sq. in. (30 g/194 sq. cm) per minute when tested per ASTM C 67. Allow units to absorb water so they are damp but not wet at time of laying.

3.2 TOLERANCES

- A. Dimensions and Locations of Elements:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. For dimensions in cross section or elevation do not vary by more than plus 1/2 inch (12 mm) or minus 1/4 inch (6 mm).
2. For location of elements in plan do not vary from that indicated by more than plus or minus 1/2 inch (12 mm).
3. For location of elements in elevation do not vary from that indicated by more than plus or minus 1/4 inch (6 mm) in a story height or 1/2 inch (12 mm) total.

B. Lines and Levels:

1. For bed joints and top surfaces of bearing walls do not vary from level by more than 1/4 inch in 10 feet (6 mm in 3 m), or 1/2 inch (12 mm) maximum.
2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2 inch (12 mm) maximum.
3. For vertical lines and surfaces do not vary from plumb by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2 inch (12 mm) maximum.
4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet (3 mm in 3 m), 1/4 inch in 20 feet (6 mm in 6 m), or 1/2 inch (12 mm) maximum.
5. For lines and surfaces do not vary from straight by more than 1/4 inch in 10 feet (6 mm in 3 m), 3/8 inch in 20 feet (9 mm in 6 m), or 1/2 inch (12 mm) maximum.

C. Joints:

1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm), with a maximum thickness limited to 1/2 inch (12 mm); do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch (3 mm).
2. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch (3 mm).

3.3 LAYING MASONRY WALLS

- A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.
- B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in running bond; do not use units with less than nominal 4-inch (100-mm) horizontal face dimensions at corners or jambs.
- C. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.
- D. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.

3.4 MORTAR BEDDING AND JOINTING

- A. Lay hollow brick as follows:
 1. With face shells fully bedded in mortar and with head joints of depth equal to bed joints.
 2. With entire units, including areas under cells, fully bedded in mortar at starting course on footings.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.
- C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

3.5 ANCHORING MASONRY VENEERS

- A. Anchor masonry veneers to [wall framing] [and] [concrete backup] with[seismic] masonry-veneer anchors to comply with the following requirements:
 - 1. See Section 04 22 00 for requirements.

3.6 FLASHING, WEEP HOLES, CAVITY DRAINAGE, AND VENTS

- A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated.
- B. Install flashing as follows unless otherwise indicated:
 - 1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.
 - 2. At lintels and shelf angles, extend flashing a minimum of 6 inches (150 mm) into masonry at each end. At heads and sills, extend flashing 6 inches (150 mm) at ends and turn up not less than 2 inches (50 mm) to form end dams.
 - 3. Install metal drip edges beneath flexible flashing at exterior face of wall. Stop flexible flashing 1/2 inch (13 mm) back from outside face of wall and adhere flexible flashing to top of metal drip edge.
 - 4. Install metal flashing termination beneath flexible flashing at exterior face of wall. Stop flexible flashing 1/2 inch (13 mm) back from outside face of wall and adhere flexible flashing to top of metal flashing termination.
- C. Install weep holes in head joints in exterior wythes of first course of masonry immediately above embedded flashing and as follows:
 - 1. Use specified weep/vent products to form weep holes.
 - 2. Space weep holes 24 inches (600 mm) o.c. unless otherwise indicated.
- D. Place cavity drainage material in cavities to comply with configuration requirements for cavity drainage material in "Miscellaneous Masonry Accessories" Article.
- E. Install vents in head joints in exterior wythes at spacing indicated. Use specified weep/vent products to form vents.
 - 1. Close cavities off vertically and horizontally with blocking in manner indicated. Install through-wall flashing and weep holes above horizontal blocking.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.7 FIELD QUALITY CONTROL

- A. Testing and Inspecting: Owner will engage special inspectors to perform tests and inspections and prepare reports. Allow inspectors access to scaffolding and work areas, as needed to perform tests and inspections. Retesting of materials that fail to meet specified requirements shall be done at Contractor's expense.
- B. Inspections: Level 1 special inspections according to the "International Building Code."
 - 1. Begin masonry construction only after inspectors have verified proportions of site-prepared mortar.
- C. Mortar Aggregate Ratio Test (Proportion Specification): For each mix provided, according to ASTM C 780.

3.8 CLEANING

- A. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.
- B. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:
 - 1. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes
 - 2. Protect adjacent surfaces from contact with cleaner.
 - 3. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
 - 4. Clean brick by bucket-and-brush hand-cleaning method described in "BIA Technical Notes 20."
 - 5. Clean masonry with a proprietary acidic cleaner applied according to manufacturer's written instructions.
 - 6. Clean concrete masonry by cleaning method indicated in NCMA TEK 8-2A applicable to type of stain on exposed surfaces.

3.9 MASONRY WASTE DISPOSAL

- A. Waste Disposal as Fill Material: Dispose of clean masonry waste, including excess or soil-contaminated sand, waste mortar, and broken masonry units, by crushing and mixing with fill material as fill is placed.
 - 1. Do not dispose of masonry waste as fill within 18 inches (450 mm) of finished grade.
- B. Excess Masonry Waste: Remove excess clean masonry waste that cannot be used as fill, as described above, and other masonry waste, and legally dispose of off Owner's property.

END OF SECTION 04 21 13

SECTION 04 22 00 - CONCRETE UNIT MASONRY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Concrete masonry units including architectural veneer units.
2. Mortar
3. Grout.
4. Steel reinforcing bars.
5. Masonry joint reinforcement.
6. Ties and anchors.
7. Miscellaneous masonry accessories.

B. Products furnished, but not installed, under this Section include the following:

C. Products installed, but not furnished, under this Section include the following:

1. Steel brick shelf angles, brick relieving angles and hung lintels anchored to masonry walls, furnished under Division 05 Section "Structural Steel Framing"
2. Loose steel lintels, furnished under Division 05 Section "Structural Steel Framing"
3. Anchor rods and embed plates indicated to be built into masonry, furnished under Division 05 Section "Structural Steel Framing"

D. Related Sections:

1. Division 01 Section "Quality Requirements" for independent testing agency procedures and administrative requirements.
2. Division 03 Section Division 05 Section "Cast-in-Place Concrete" for reinforcing steel dowels for anchoring concrete unit masonry to cast-in-place concrete.
3. Division 05 Section "Structural Steel Framing" for furnishing loose lintels.
4. Division 07 Section "Water Repellents" for water repellents applied to unit masonry.
5. Division 07 Section "Sheet Metal Flashing and Trim" for sheet metal flashing and for furnishing manufactured reglets installed in masonry joints.
6. Division 07 Section "Sheet Metal Flashing & Trim" for flashing
7. Division 04 Section "Brick Masonry" for clay masonry veneers

1.3 DEFINITIONS

- A. CMU(s): Concrete masonry unit(s).
- B. Reinforced Masonry: Masonry containing reinforcing steel in grouted cells.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.4 SUBMITTALS

A. Product Data:

1. Single Wythe Masonry Joint reinforcement
2. Mutliwythe Composite Masonry Joint reinforcement
3. Multiwythe Cavity Wall Joint Reinforcement
4. Veneer Joint Reinforcement
5. Partition Top Anchors
6. Rigid Anchors

B. Contractor's Statement of Responsibility Per Division 01 Section "Quality Control".

C. Shop Drawings: For the following:

1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes.
2. Reinforcing Steel: Detail bending and placement of unit masonry reinforcing bars. Comply with ACI 315, "Details and Detailing of Concrete Reinforcement."
 - a. Show elevations of all reinforced walls including reinforcing per typical details for all openings including but not limited to openings for ductwork and piping.
 - b. Dowels shall match typical wall reinforcing unless noted otherwise.
 - c. Dowels shall extend a lap distance above finished floor, unless top of footing is more than typical bar lift below finished floor. In such an instance dowel shall extend a lap distance out of footing.
 - d. Coordinate bar lift detailing with sequencing requirements of part 3 of this specification section.
 - e. Layout cmu control joints per contract documents and show associated typical reinforcing.
 - f. General Contractor shall coordinate all necessary openings in masonry walls with all subcontractors and shall provide information to reinforcing steel detailer for preparation of shop drawings.
 - g. Where above the ceiling coordination drawings are a project requirement the coordination drawings shall be provided to the reinforcing steel detailer to aid in developing elevation of reinforced walls.

D. Qualification Data:

1. Masonry Installer.
2. Post Installed Structural Anchor Installer

E. Material Test Reports: For the following, from a qualified testing agency, indicating compliance with requirements:

1. Concrete Masonry Units.
 - a. Submit material test reports for each type of mix to be use in production of block for the project.
 - b. Submit material test reports not more than 180 days old demonstrating compliance with the specified ASTM standards and project requirements.
2. Concrete Masonry Unit Aggregates: For concrete masonry units containing recycled material or post-industrial waste for aggregates provide test reports in accordance with the quality assurance requirements below.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3. Mortar Aggregates
 4. Mortar Cementitious Materials
 5. Grout Fine Aggregates (for field mixed grout only)
 6. Grout Course Aggregates (for field mixed grout only)
 7. Grout Cementitious Materials (for field mixed grout only)
- F. Material Certificates: For each of the following indicating compliance with the required standards and signed by manufacturers:
1. Concrete Masonry units (for each type and size):
 - a. Include material test reports substantiating compliance with requirements.
 - b. Include data and calculations establishing average net-area compressive strength of each size and profile of block to be used on the project.
 - c. Include a statement confirming that cmu produced for the project will use materials identical to those used in producing the block for which test reports are submitted.
 2. Grout Cementitious materials.
 - a. Submit material certificates not more than 90 days old demonstrating compliance with the specified ASTM standards.
 3. Mortar Cementitious materials.
 - a. Submit material certificates not more than 90 days old demonstrating compliance with the specified ASTM standards.
 4. Grout Coarse Aggregates
 - a. Submit material certificates not more than 90 days old demonstrating compliance with the specified ASTM standards.
 5. Grout Fine Aggregates.
 - a. Submit material certificates not more than 90 days old demonstrating compliance with the specified ASTM standards.
 6. Mortar Fine Aggregates
 - a. Submit material certificates not more than 90 days old demonstrating compliance with the specified ASTM standards.
 7. Preblended, dry mortar mixes. Include description of type and proportions of ingredients.
 8. Preblended Grout mixes. Include description of type and proportions of ingredients.
- G. Design Mixtures:
1. Grout: For each type of grout
 - a. Indicate amounts of mixing water to be withheld for later addition at Project site.
 - b. Mix design submittals shall include test results and/or trial batch data that meet or exceed the required average compressive strengths required by ACI 301. In accordance with ASTM C476 all testing shall be completed per ASTM C10119.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- c. Trial batches shall consist of identical cementitious materials, fine and coarse aggregates, and admixtures to be used for mix design.
 - d. Submit alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.
- 2. Mortar: For each type of mortar
 - a. Indicate materials to be used
 - b. Indicate proportioning of ingredients.
 - c. Indicate repeatable means of measuring ingredient proportions.
 - d. When using the ASTM C270 property specification include test reports. Test according to ASTM C 109/C 109M for compressive strength, ASTM C 1506 for water retention, and ASTM C 91 for air content.
- H. Research/Evaluation Reports:
 - 1. Post installed structural anchors: See specification section 050520
- I. Hot and Cold Weather Program: Describe in detail procedure for working in Hot and Cold Weather. Included detailed description of methods, materials, and equipment to be used to comply with requirements.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM C 1093 for testing indicated.
- B. Masonry Installer: A single, experienced firm, or an approved joint venture, specializing in masonry construction with a minimum five- year record of successful completion of projects of similar scope, capable of providing labor and material and performance bonds for its portion of the Work that are acceptable to the Owner. Installer shall furnish all required materials and equipment and perform the work of this Section with its own regular employees.
 - 1. The masonry supervisor/foreman shall have had at least 5 years of experience with at least 5 projects of similar size and nature; he shall not act as or become a production worker.
 - 2. The lead/crew chief masons shall have had at least 3 years of experience with at least 5 projects of similar size and nature;
 - 3. Installer shall have experienced masonry superintendent and crew chiefs on site supervising the work whenever work is in progress.
 - 4. Contractor's Own Forces: Contractor may utilize own forces for work of this Section when Contractor and Contractor's masonry superintendent and crew chiefs meet the above qualifications.
- C. Post Installed Structural Anchor Installer: See specification section 050520 for requirements
- D. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, from single source from single manufacturer for each product required.
- E. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from single manufacturer for each cementitious component and from single source or producer for each aggregate.
- F. Limitations on Aggregates: For concrete masonry units containing recycled material or post-industrial waste, provide units free of impurities that will cause rusting, staining or popouts and

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

with a record of successful in-service performance in conditions similar to those expected at Project site.

1. Ferrous material shall be removed by magnetic separation.
 2. Aggregates shall contain no combustible materials.
 3. Aggregates shall be graded and supplied in consist graduations from batch to batch.
 4. Material shall be tested according to the following:
 - a. ASTM C40: Organic Impurities in Fine Aggregates for Concrete.
 - b. ASTM C 136: Sieve Analysis of Fine and Coarse Aggregate.
 - c. ASTM C 641: Staining Materials in Lightweight Concrete Aggregates.
 - d. ASTM C 151: Autoclave Expansion of Hydraulic Cement (for popouts.)
- G. Masonry Standard: Comply with ACI 530.1/ASCE 6/TMS 602 unless modified by requirements in the Contract Documents.
- H. Grout Testing Service: Engage a qualified independent testing agency to perform material evaluation tests and to design grout mixtures.
- I. Daily Log: Maintain a daily log of masonry work in progress for inspection by Owner, Architect, Special Inspector or Authority Having Jurisdiction.
1. Indicate on small scale plans where masonry was erected.
 2. Indicate on small scale plans where masonry was grouted.
 3. Identify crew and assigned work area.
 4. Certify that the following tasks have been performed.
 - a. Inspection of construction and verification of compliance with requirements as indicated in schedule of special inspections.
 - b. Daily Cleaning.
- J. Fire-Resistance Ratings: Where indicated, provide materials and construction identical to those of assemblies with fire-resistance ratings determined per ASTM E 119 by a testing and inspecting agency, by equivalent concrete masonry thickness, or by other means, as acceptable to authorities having jurisdiction.
- K. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."
1. Review construction sequencing and required time allotted for inspections prior to grouting.
 2. Review ACI 530 tolerance for placement of reinforcing steel.
 3. Review hot and cold weather procedures.
 4. Review typical details for reinforcement requirements
 5. Review requirements for horizontal joint reinforcement
 6. Review reinforcement placement tolerance
 7. Review reinforcement anchorage requirements
 8. Review reinforcement lap requirements
 9. Review reinforced masonry construction sequence
 10. Review limits on embedded items in grouted masonry
 11. Review grouting procedures and requirement for mechanical vibration.
 12. Review requirements for masonry protection

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.
- B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.
- D. Deliver preblended, dry mortar mix in moisture-resistant containers designed for use with dispensing silos. Store preblended, dry mortar mix in delivery containers on elevated platforms, under cover, and in a dry location or in covered weatherproof dispensing silos.
- E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.7 PROJECT CONDITIONS

- A. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.
 - 1. Extend cover a minimum of 24 inches down both sides of walls and hold cover securely in place.
 - 2. Where one wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches down face next to unconstructed wythe and hold cover in place.
- B. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least three days after building masonry walls or columns.
- C. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed or painted. Immediately remove grout, mortar, and soil that come in contact with such masonry.
 - 1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
 - 2. Protect sills, ledges, and projections from mortar droppings.
 - 3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
 - 4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.
- D. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.
 - 1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and higher and will remain so until masonry has dried, but not less than seven days after completing cleaning.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 MASONRY UNITS, GENERAL

- A. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to contain chips, cracks, or other defects exceeding limits stated in the standard. Do not use units where such defects will be exposed in the completed Work.
- B. Fire-Resistance Ratings: Where indicated, provide units that comply with requirements for fire-resistance ratings indicated as determined by testing according to ASTM E 119, by equivalent masonry thickness, or by other means, as acceptable to authorities having jurisdiction.
- C. ARCHITECTURAL SPLIT-FACE CMU VENEER: Provide unit sizes nominal **4"x4"x16"**. Submit samples for color selection prior to ordering material.

2.2 CONCRETE MASONRY UNITS

- A. Shapes: Provide shapes indicated and as follows, with exposed surfaces matching exposed faces of adjacent units unless otherwise indicated.
 - 1. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, bond beams and other special conditions.
- B. Cell Layout:
 - 1. All block shall be of standard two cell or open end configuration.
 - 2. All block shall be configured such that it allows for both of the following:
 - a. Placement of reinforcing as indicated with not less than 1/2" clear grout cover between the bar and the block.
 - b. For the required bonding pattern the block will provide a minimum 3 inch by 3 inch continuous vertical column to receive grout.
- C. Integral Water Repellent: Provide units made with integral water repellent for exterior wall units.
 - 1. Integral Water Repellent: Liquid polymeric, integral water-repellent admixture that does not reduce flexural bond strength. Units made with integral water repellent, when tested according to ASTM E 514 as a wall assembly made with mortar containing integral water-repellent manufacturer's mortar additive, with test period extended to 24 hours, shall show no visible water or leaks on the back of test specimen.
- D. CMUs: ASTM C 90.

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

1. Unit Compressive Strength: Provide units with minimum average net-area compressive strength of 1900 psi.
2. Density Classification:
 - a. Lightweight unless otherwise indicated.
 - b. Blended medium weight block to be used at food preparation areas receiving epoxy finish and where indicated.
 - 1) Provide units made with graded aggregates to achieve smoother surface texture for the application of paint finish. Match Architect's sample for surface texture.
3. Size (Width): Manufactured to dimensions 3/8 inch less than nominal dimensions.
4. Exposed Faces: Provide color and texture matching the range represented by Architect's sample.

2.3 CONCRETE AND MASONRY LINTELS

- A. Concrete Lintels: Where specifically indicated provide formed-in-place concrete lintels complying with requirements in Division 03 Section "Cast-in-Place Concrete," and with reinforcing bars indicated.
- B. Masonry Lintels: Unless indicated otherwise provide built-in-place masonry lintels made from lintel or channel concrete masonry units for the bottom course, and bond beam units for additional courses indicated with reinforcing bars placed as indicated and filled with coarse grout. Temporarily support built-in-place lintels until cured.

2.4 MORTAR AND GROUT MATERIALS

- A. Portland Cement: ASTM C 150, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.
- B. Hydrated Lime: ASTM C 207, Type S.
- C. Portland Cement-Lime Mix: Packaged blend of portland cement and hydrated lime containing no other ingredients.
- D. Masonry Cement: Not Permitted
- E. Mortar Cement: ASTM C 1329.
- F. Mortar Pigments: Natural and synthetic iron oxides and chromium oxides, compounded for use in mortar mixes and complying with ASTM C 979. Use only pigments with a record of satisfactory performance in masonry mortar.
- G. Colored Cement Product: Packaged blend made from portland cement and hydrated lime mortar cement and mortar pigments, all complying with specified requirements, and containing no other ingredients.
 1. Formulate blend as required to produce color indicated or, if not indicated, as selected from manufacturer's standard colors.
 2. Pigments shall not exceed 10 percent of portland cement by weight.
 3. Pigments shall not exceed 5 percent of mortar cement by weight.

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

4. Pigments containing carbon black must be limited to 2 percent of portland cement by weight or 1 percent of mortar cement by weight
- H. Aggregate for Mortar: ASTM C 144.
1. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.
 2. For joints less than 1/4 inch thick, use aggregate graded with 100 percent passing the No. 16 sieve.
 3. White-Mortar Aggregates: Natural white sand or crushed white stone.
 4. Colored-Mortar Aggregates: Natural sand or crushed stone of color necessary to produce required mortar color.
- I. Aggregate for Grout: ASTM C 404.
- J. Cold-Weather Admixture: Nonchloride, noncorrosive, accelerating admixture complying with ASTM C 494/C 494M, Type C, and recommended by manufacturer for use in masonry mortar of composition indicated.
- K. Water-Repellent Admixture: Liquid water-repellent mortar admixture intended for use with CMUs containing integral water repellent by same manufacturer.
- L. Water: Potable.

2.5 REINFORCEMENT

- A. Steel Reinforcing Bars: ASTM A 615/A 615M or ASTM A 996/A 996M, Grade 60
- B. Masonry Joint Reinforcement, General: ASTM A 951/A 951M.
1. Finish: Hot Dip Galvanized
 2. Wire Size for Side Rods: W1.7 or 0.148-inch diameter.
 3. Wire Size for Cross Rods: W1.7 or 0.148-inch diameter.
 4. Wire Size for Veneer Ties: W1.7 or 0.148-inch diameter.
 5. Spacing of Cross Rods, Tabs, and Cross Ties: Not more than 16 inches o.c.
 6. Provide in lengths of not less than 10 feet, with prefabricated corner and tee units.
- C. Masonry Joint Reinforcement for Single-Wythe Masonry: Ladder type with single pair of side rods.
- D. Masonry Joint Reinforcement for Composite Masonry:
1. Ladder type
 2. One side rod at each face shell of hollow masonry units more than 4 inches wide
 3. One side rod at each wythe of masonry 4 inches wide or less.
- E. Masonry Joint Reinforcement for Multiwythe Cavity Wall Masonry:
1. Adjustable (two-piece) type, ladder design
 2. One side rod at each face shell of backing wythe
 3. Separate adjustable ties with pintle-and-eye connections having a maximum adjustment of 1-1/4 inches.

4. Tie Section:
 - a. Size ties to extend at least halfway through facing wythe but with at least 5/8-inch cover on outside face.
 - b. Provide rectangular units with closed ends and not less than 4 inches wide.
 - c. Ties have hooks or clips to engage a continuous horizontal wire in the facing wythe.

- F. Veneer Joint Reinforcement: Single W1.7 or 0.148-inch diameter, hot-dip galvanized, carbon-steel continuous wire.

2.6 TIES AND ANCHORS

- A. Materials: Provide ties and anchors specified in this article that are made from materials that comply with the following unless otherwise indicated.
 1. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A 82/A 82M; with ASTM A 153/A 153M, Class B-2 coating.
 2. Steel Sheet, Galvanized after Fabrication: ASTM A 1008/A 1008M, Commercial Steel, with ASTM A 153/A 153M, Class B coating.
 3. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M. Hot-dip galvanized to comply with ASTM A 153/A 153M
- B. Wire Ties, General: Unless otherwise indicated, size wire ties to extend at least halfway through veneer but with at least 5/8-inch cover on outside face. Outer ends of wires are bent 90 degrees and extend 2 inches parallel to face of veneer or anchored masonry.
- C. Partition Top anchors: 0.105-inch- thick metal plate with 3/8-inch diameter metal rod 6 inches long welded to plate and with closed-end plastic tube fitted over rod that allows rod to move in and out of tube. Fabricate from steel, hot-dip galvanized after fabrication.
- A. Rigid Anchors: Fabricate from ASTM A 36 steel bars 1-1/2 inches wide by 1/4 inch thick by length required, with ends turned up 2 inches in alternate directions
Corrosion Protection: Hot-dip galvanized to comply with ASTM A 153/A 153M

2.7 MISCELLANEOUS ANCHORS

- A. Post Installed Structural Anchors: See specification section 055020 for products

2.8 MISCELLANEOUS MASONRY ACCESSORIES

- A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene.
- B. Preformed Control-Joint Gaskets: Made from PVC, complying with ASTM D 2287, Type PVC-65406 and designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.
- A. Vertical Reinforcing Bar Positioners: Custom fabricated wire units designed to fit into mortar bed joints spanning masonry unit cells with loops for holding vertical reinforcing bars in proper location of cells. Units are formed from 0.142-inch steel wire, hot-dip galvanized after fabrication.

1. Provide units with two loops for masonry walls indicated to have a single vertical reinforcing bar at each grout spacing.
 - a. Loop layout shall allow for placement of vertical reinforcing in center of cmu wall thickness unless noted otherwise
 2. Provide units with four loops or a pair of units with two loops for masonry walls indicated to have two vertical reinforcing bars at each grout spacing.
 - a. Provide custom fabricated positioners with loop layout to allow for placement of vertical reinforcing as indicated in the contract documents.
- B. Horizontal Reinforcing Bar Positioners: Custom fabricated wire units designed to fit into mortar bed joints spanning masonry unit cells and bent down for holding horizontal reinforcing bars at proper height in lintels and bond beam. Units are formed from 0.142-inch steel wire, hot-dip galvanized after fabrication.
- a. Provide custom fabricated positioners to allow for placement of horizontal reinforcing in lintels as indicated in the contract documents.
 - b. Positioners for continuous bond beams shall center reinforcing in the depth of the bond beam unit unless noted otherwise.

2.9 MASONRY CLEANERS

- A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.

2.10 MORTAR AND GROUT MIXES

- A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures, unless otherwise indicated.
1. Do not use calcium chloride in mortar or grout.
 2. Use portland cement-lime or mortar cement mortar unless otherwise indicated.
 3. Add cold-weather admixture (if used) at same rate for all mortar that will be exposed to view, regardless of weather conditions, to ensure that mortar color is consistent.
- B. Preblended, Dry Mortar Mix: Furnish dry mortar ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.
- C. Preblended, Dry Grout Mix: Furnish dry grout ingredients in form of a preblended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.
- D. Mortar for Unit Masonry: Provide "Type S" mortar complying with ASTM C 270, Proportion or Property Specification unless indicated otherwise.

E. Grout for Unit Masonry: Comply with ASTM C 476.

1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with Table 1.15.1 in ACI 530.1/ASCE 6/TMS 602 for dimensions of grout spaces and pour height.
2. Proportion grout in accordance with ASTM C 476, paragraph 4.2.2 as follows:
 - a. 28-day compressive strength of 3000 psi unless noted otherwise.
 - b. Provide grout with a slump of 8 to 11 as measured according to ASTM C 143/C 143M.
3. Ready-Mixed Grout: Measure, batch, mix, and deliver grout according to ASTM C 476, and furnish batch ticket information.
 - a. Slump shall be adjusted on site as necessary, and grout shall be re-mixed at mixing speed for at least one minute before discharging to achieve the desired consistency.
4. Project-Site Mixed Grout: Mix preblended, dry grout mix according to ASTM C 476.
 - a. Mix in a mechanical mixer for a minimum of 5 minutes with sufficient water to achieve the desired consistency.
 - b. Hand mixing of grout is not permitted
 - c. Provide batch ticket for each batch discharged and used in the Work, indicating Project identification name and number, date, mixture time, quantity, and amount of water added. Record approximate location of final deposit in structure.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of work.
 2. Verify that foundations are within tolerances specified.

3. Verify that foundations are "broom" clean and free of debris or other laitance that may compromise mortar bond.
 4. Verify that reinforcing dowels are properly placed and extend to the proper elevation.
- B. Before installation, examine rough-in and built-in construction for electrical, mechanical, piping and other systems to identify locations of built in construction..
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.
- B. Build chases and recesses to accommodate items specified in this and other Sections.
- C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match the construction immediately adjacent to opening.
- D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed.
- E. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures.
1. Mix units from several pallets or cubes as they are placed.
- F. Matching Existing Masonry: Match coursing, bonding, color, and texture of existing masonry.

3.3 TOLERANCES

- A. Comply with the construction tolerances in ACI 5301.1 unless modified herein.
- B. Dimensions and Locations of Elements:
1. For dimensions in cross section or elevation do not vary by more than plus 1/2 inch or minus 1/4 inch.
 2. For location of elements in plan do not vary from that indicated by more than plus or minus 1/2 inch.
 3. For location of elements in elevation do not vary from that indicated by more than plus or minus 1/4 inch in a story height or 1/2 inch total.
- C. Lines and Levels:
1. For bed joints and top surfaces of bearing walls do not vary from level by more than 1/4 inch in 10 feet, or 1/2 inch maximum.
 2. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet , 1/4 inch in 20 feet, or 1/2 inch (12 mm) maximum.

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

3. For vertical lines and surfaces do not vary from plumb by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2 inch maximum.
4. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.
5. For lines and surfaces do not vary from straight by more than 1/4 inch in 10 feet, 3/8 inch in 20 feet, or 1/2 inch maximum.
6. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet, or 1/2 inch maximum.
7. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch except due to warpage of masonry units within tolerances specified for warpage of units.

D. Joints:

1. For bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch for typical bed joints.
2. For bed joints on foundations the minimum thickness shall be 1/4 inch and the maximum thickness shall be 3/4 inch.
3. For exposed bed joints, do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.
4. For head and collar joints, do not vary from thickness indicated by more than plus 3/8 inch or minus 1/4 inch.
5. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch. Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch.]
6. For exposed bed joints and head joints of stacked bond, do not vary from a straight line by more than 1/16 inch from one masonry unit to the next.

3.4 LAYING MASONRY WALLS

- A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.
- B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in running bond; do not use units with less than nominal 4-inch horizontal face dimensions at corners or jambs.
- C. Lay concealed masonry with all units in a wythe in running bond. Bond each course of each wythe at corners. Do not use units with less than nominal 4-inch horizontal face dimensions at corners or jambs.
- D. Reinforced Masonry: Keep vertical cells aligned to maintain continuous unobstructed cells not less than 3 inches by 3 inches to receive reinforcing steel and grout.
- E. Stopping and Resuming Work: Stop work by racking back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.
- F. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

MYRTLE BEACH INTERMEDIATE SCHOOL CONVERSION
Myrtle Beach, South Carolina

- G. Fill space between steel frames and masonry solidly with mortar unless otherwise indicated.
- H. Where built-in items are to be embedded in cores of hollow masonry units, place a layer of metal lath, wire mesh, or plastic mesh in the joint below and rod mortar or grout into core.
- I. Fill cores in hollow CMUs with grout 24 inches under bearing plates, beams, lintels, posts, and similar items unless otherwise indicated.
- J. Build non-load-bearing interior partitions full height of story to underside of solid floor or roof structure above, leaving a minimum 1" clearance between masonry and structure above unless otherwise indicated.
 - 1. Install compressible filler in joint between top of partition and underside of structure above.
 - 2. Fasten partition top anchors to structure above and build into top of partition. Grout cells of CMUs solidly around plastic tubes of anchors and push tubes down into grout to provide 1 inch clearance between end of anchor rod and end of tube. Space anchors 32 inches o.c. unless otherwise indicated.
 - 3. At fire-rated partitions, treat joint between top of partition and underside of structure above to comply with Division 07 Section "Fire-Resistive Joint Systems."

3.5 MORTAR BEDDING AND JOINTING

- A. General: Prepare mortar in accordance with current Portland Cement Association publications.
- B. Prepare fresh mortar at the rate it will be used, in order to maintain consistent color and workability. Do not use mortar that has stiffened because of hydration. Discard when not used within the time recommended by mortar manufacturer or PCA publications, whichever is shorter. Retemper mortar carefully to avoid color changes, no more than twice per batch.
- C. Measure mortar materials using cubic foot measuring box or other approved container of known volume, of size appropriate for operation. Use a consistent ratio of water to mortar materials, within the range recommended by the mortar manufacturer's written instructions.
- D. Lay hollow CMUs as follows:
 - 1. Only lay cmu on foundations after they have achieved a "broom" clean condition and are free of debris or other laitance that may compromise mortar bond.
 - 2. With face shells fully bedded in mortar and with head joints of depth equal to bed joints.
 - 3. With webs fully bedded in mortar in all courses of piers, columns, and pilasters.
 - 4. With webs fully bedded in mortar in grouted masonry, including starting course on footings.
 - 5. With entire units, including areas under cells, fully bedded in mortar at starting course on footings where cells are not grouted.
 - 6. With head joints filled to a minimum thickness equal to the face shell of the unit on both faces of the unit.
- E. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.
- F. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness unless otherwise indicated.

- G. Cut joints flush for masonry walls to receive plaster or other direct-applied finishes (other than paint) unless otherwise indicated.
- H. Immediately after placing a course of masonry clean mortar drippings and fins from cells to receive reinforcing. Care shall be taken to collect the loose material and remove it from the cell and not allowing it to collect at the bottom of the cell.

3.6 COMPOSITE MASONRY

- A. Bond wythes of composite masonry together as follows
 - 1. Masonry Joint Reinforcement: Install ladder-type reinforcement in horizontal mortar joints and extending across both wythes.
- B. Collar Joints:
 - 1. When collar joint is less than 1" thick solidly fill collar joints by parging face of first wythe that is laid and shoving units of other wythe into place.
 - 2. When collar joint is more than 1" thick grout collar joint solid as second wythe is laid. Comply with limitations of ACI 530 for height of grout pour in relation to collar joint width.
- C. Corners: Provide interlocking masonry unit bond in each wythe and course at corners unless otherwise indicated.
 - 1. Provide continuity with masonry joint reinforcement at corners by using prefabricated L-shaped units as well as masonry bonding.
- D. Intersecting and Abutting Walls: Unless vertical expansion or control joints are shown at juncture, bond walls together as follows:
 - 1. Provide rigid metal anchors not more than 16 inches o.c. If used with hollow masonry units, embed ends in mortar-filled cores.

3.7 CAVITY WALLS

- A. Bond wythes of cavity walls together as follows:
 - 1. Masonry Joint Reinforcement: Installed in horizontal mortar joints.
 - a. Use adjustable (two-piece) type reinforcement to allow for differential movement regardless of whether bed joints align.
 - b. Provide continuous horizontal wire in facing wythe attached to ties
- B. Keep cavities clean of mortar droppings and other materials during construction. Bevel beds away from cavity, to minimize mortar protrusions into cavity. Do not attempt to trowel or remove mortar fins protruding into cavity.
- C. Intersecting and Abutting Walls: Unless vertical expansion or control joints are shown at juncture, bond walls together as follows:
 - 1. Provide rigid metal anchors not more than 16 inches o.c. If used with hollow masonry units, embed ends in mortar-filled cores.

- D. Coat cavity face of backup wythe to comply with Division 07 Section "Bituminous Dampproofing."
- E. Apply air barrier to face of backup wythe to comply with Division 07 Section "**Modified Bituminous Sheet Air Barriers** or **Fluid-Applied Membrane Air Barriers** see architectural drawings and spec's."

3.8 MASONRY-CELL INSULATION

- A. Pour granular insulation into cavities to fill void spaces. Maintain inspection ports to show presence of insulation at extremities of each pour area. Close the ports after filling has been confirmed. Limit the fall of insulation to 1 story high, but not more than 20 feet.

3.9 MASONRY JOINT REINFORCEMENT

- A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch on exterior side of walls, 1/2 inch elsewhere. Lap reinforcement a minimum of 6 inches.
 - 1. Space reinforcement not more than 16 inches o.c.
 - 2. Space reinforcement not more than 8 inches o.c. in foundation walls and parapet walls.
 - 3. Provide reinforcement not more than 8 inches above and below wall openings and extending 24 inches beyond openings in addition to continuous reinforcement.
- B. Interrupt joint reinforcement at control and expansion joints unless otherwise indicated.
- C. Provide continuity at wall intersections by using prefabricated T-shaped units.
- D. Provide continuity at corners by using prefabricated L-shaped units.

3.10 CONTROL AND EXPANSION JOINTS

- A. General: Install control and expansion joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.
- B. Form control joints in concrete masonry as follows:
 - 1. Install preformed control-joint gaskets designed to fit standard sash block.

3.11 LINTELS

- A. Install loose steel lintels where indicated.
- B. Install shelf angles/hung lintels where indicated
- C. Built in Place Lintels:
 - 1. Provide lintels where shown and where openings of more than 12 inches for block-size units are shown without structural steel or other supporting lintels.

2. Construct from closed bottom lintel or channel concrete masonry units for the bottom course with reinforcing steel placed as indicated, supported on positioners and anchored in place. Bond beam units are not permitted for bottom course.
3. Provide bond beam units for additional courses indicated with reinforcing steel placed as indicated supported on positioners and anchored in place.
4. Fill the entire depth and length of the lintel grout in one grout pour. Grout joints are not permitted in lintels.
5. Temporarily support built-in-place lintels until cured.
6. Provide minimum bearing of 16 inches at each jamb unless otherwise indicated.

3.12 REINFORCED UNIT MASONRY INSTALLATION

- A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.
1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
 2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and other loads that may be placed on them during construction.
- B. Placing Reinforcement: Comply with requirements in ACI 530.1/ASCE 6/TMS 602 and as follows:
1. Center all vertical reinforcing steel on the thickness of the concrete masonry unit unless noted otherwise.
 2. Bar positioners must be anchored in place with mortar.
 3. Sequencing:
 - a. Reinforcing steel from previous grout lift extends a lap distance out of hardened grout.
 - b. No additional reinforcing is placed, and additional masonry is laid up, but not exceeded the grout pour height limit.
 - c. Reinforcing bar positioner is placed in the bed joint of the second course of additional masonry, and below the last bed joint of additional masonry with additional bar positioners installed such that spacing does not exceed 48 inches on center
 - d. The cells of additional masonry are cleaned of mortar droppings and mortar fins.
 - e. A lift of reinforcing steel is dropped into the previously laid masonry using the bar positioners to ensure proper location. The reinforcing steel shall extend above the proposed grout pour height by a minimum of one splice distance.
 - f. The grout lift is placed and consolidate.
 - g. The sequence is repeated.
 4. Where a reinforced cell is noted to have the vertical reinforcing offset from the center of the concrete masonry unit then provide special two loop bar positioners to locate each vertical bar and the associated splice bar per the contract documents.
 - a. Alternately a two loop bar positioner may be installed rotated parallel to the face shells to locate the vertical bar and the associated splice bar per the contract documents.

5. Where a reinforced cell is noted to have two vertical bars provide special four loop bar positioners to locate each vertical bar and the associated splice bar per the contract documents.
 - a. Alternately a pair of two loop bar positioners may be installed rotated parallel to the face shells to locate each vertical bar and the associate splice bar per the contract documents.
 6. A minimum of 1" clear shall be maintained between pairs of parallel bars occurring in the same vertical cell, lintel or bond beam.
 7. A minimum of 1" clear shall be maintained between vertical bars or pairs of vertical bars and , piping or other embeds occurring in the same vertical cell.
 8. A minimum of ½" shall be maintained between any reinforcing bar and the adjacent masonry unit.
 9. Wet setting of reinforcing steel into previously placed grout is not permitted.
- C. Conduits, Piping, Panels, Boxes and other Embedded Equipment
1. The maximum outside diameter of any vertical conduit or piping located in a grouted cell shall be as follows:
 - a. 1.5 inches for 12 inch cmu
 - b. 1.125 inches for 8 inch cmu
 - c. 1 inch for 6 inch cmu
 - d. Where vertically reinforced and grouted cells are not specifically located in the contract documents it is acceptable to relocate the vertically reinforced and grouted cell to the next adjacent cell to avoid a conduit or pipe of larger dimension than permitted. The typical center to center spacing of vertically reinforced and grouted cells shall be maintained.
 - e. Where vertically reinforced and grouted cells are specifically located in the contract documents, conduit or pipes of dimensions larger than permitted shall be routed to avoid the vertically reinforced and grouted cells. In the case that the conduit or piping cannot be routed to avoid the vertically reinforced and grouted cell the Engineer shall be contacted for resolution.
 2. Horizontal runs of conduit or pipe are not permitted in within lintels or bond beams
 3. Horizontal runs of conduit or pipe passing through vertically reinforced and grouted cells are not permitted.
 4. Piping containing either of the following shall not be located in grouted masonry:
 - a. Liquid, gas or vapors at temperatures higher than 150 degrees Farenheit
 - b. Under pressures in excess of 55 psi
 - c. Containing water or other liquids when they are subject to freezing
 5. Inset panels, boxes, fire extinguisher cabinets and other embedded items are not permitted in grouted cells.
 - a. Where vertically reinforced and grouted cells are not specifically located in the contract documents it is acceptable to relocate the vertically reinforced and grouted cell to the next adjacent cell to avoid conflict with embedded equipment. The typical center to center spacing of vertically reinforced and grouted cells shall be maintained.
 - b. Where vertically reinforced and grouted cells are specifically located in the contract documents and conflict with embedded equipment, the embedded equipment shall be surface mounted or relocated as allowed by the contract documents. Where

contract documents do not allow for surface mounting or relocating the equipment the Engineer shall be contacted for resolution.

- D. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure.
1. Prior to grouting all grouted cells shall be inspected to ensure cells are free of loose mortar droppings or debris.
 - a. All debris and mortar droppings shall be removed.
 - b. All hardened mortar or mortar fins protruding more than 1/2 inch into cell shall be removed.
 2. For grout pours of 60 inches or more, and other locations where specifically indicated provide cleanouts at the bottom of each grouted cell
 - a. Where cleanout will be located at location and elevation where the finished wall is exposed the cleanout shall be created by removing the face shell of a full block to allow for a seamless appearance by patching with a full face shell.
 - b. Where the cleanout will be concealed in finished construction the cleanout can be formed such that the grout will form the finished surface at the cleanout. Cleanout shall be a minimum of 4 inches by 4 inches.
 3. Comply with requirements in ACI 530.1/ASCE 6/TMS 602 for grout properties and minimum grout space.
 4. Limit height of vertical grout lifts and grout pours to not more than 60 inches.
 5. Grout all courses of lintels and beams in one continuous operation for the full height of the lintel or beam. Do not allow cold joints in lintels and beams.
 6. Grout lifts shall be terminated at top of walls shall be carefully consolidated to ensure grout is cured flush to top of masonry, and provides solid bearing beneath all bearing plates.
 7. Grout lifts terminating at bond beams, except at top of wall shall be stopped 1/2" down from top of bond beam
 8. Typical grout lifts, not terminating at bond beam or top of wall shall be terminated a minimum of 1 1/2", but not more than 3" below a bed joint.
 9. All grout lift terminations shall be coordinate with reinforcing steel layout to ensure proper lap distance of reinforcing steel. Grout pours shall not be terminated anywhere along the length of the splice.
 10. All grout shall be consolidated using internal vibration with a pencil type vibrator.
 - a. Consolidate grout in each cell or bond beam immediately after placement. Top of bond beam or cell to desired height after initial consolidation.
 - b. Reconsolidate grout in each cell or bond beam after initial water loss and settlement has occurred approximately 10 minutes after initial consolidation. Top of bond beam or cell to desired height after reconsolidation.

3.13 FIELD QUALITY CONTROL

- A. Testing and Inspection: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports in accordance with the schedule of special inspections.
- B. Correct deficiencies in Work that test reports and inspections indicate does not comply with the Contract Documents.

- C. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.14 REPAIRING, POINTING, AND CLEANING

- A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.
- B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, where indicated.
- C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.
- D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:
 - 1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
 - 2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect's approval of sample cleaning before proceeding with cleaning of masonry.
 - 3. Protect adjacent stone and nonmasonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.
 - 4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
 - 5. Clean masonry with a proprietary acidic cleaner applied according to manufacturer's written instructions.
 - 6. Clean concrete masonry by cleaning method indicated in NCMA TEK 8-2A applicable to type of stain on exposed surfaces.

3.15 MASONRY WASTE DISPOSAL

- A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

END OF SECTION 042200

SECTION 05 50 00 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Miscellaneous steel framing and supports.
2. Shelf angles.
3. Metal ladders.
4. Miscellaneous steel trim.
5. Metal bollards.
6. Loose bearing and leveling plates.

B. Products furnished, but not installed, under this Section:

1. Loose steel lintels.
2. Anchor bolts, steel pipe sleeves, slotted-channel inserts, and wedge-type inserts indicated to be cast into concrete or built into unit masonry.
3. Steel weld plates and angles for casting into concrete.

1.2 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design ladders, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes acting on exterior metal fabrications by preventing buckling, opening of joints, overstressing of components, failure of connections, and other detrimental effects.

1. Temperature Change: 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

1.3 ACTION SUBMITTALS

A. Product Data: For the following:

1. Paint products.
2. Grout.

B. Shop Drawings: Show fabrication and installation details for metal fabrications.

1. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items.

C. Delegated-Design Submittal: For installed products indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 2 - PRODUCTS

2.1 METALS, GENERAL

- A. Metal Surfaces, General: Provide materials with smooth, flat surfaces without blemishes.

2.2 FERROUS METALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
- C. Steel Tubing: ASTM A 500, cold-formed steel tubing.
- D. Steel Pipe: ASTM A 53/A 53M, standard weight (Schedule 40) unless otherwise indicated.
- E. Cast Iron: Either gray iron, ASTM A 48/A 48M, or malleable iron, ASTM A 47/A 47M.

2.3 NONFERROUS METALS

- A. Aluminum Extrusions: ASTM B 221 (ASTM B 221M), Alloy 6063-T6.
- B. Aluminum Castings: ASTM B 26/B 26M, Alloy 443.0-F.

2.4 FASTENERS

- A. General: Unless otherwise indicated, provide Type 304 stainless-steel fasteners for exterior use and zinc-plated fasteners with coating complying with ASTM B 633 or ASTM F 1941 (ASTM F 1941M), Class Fe/Zn 5, at exterior walls.
 - 1. Provide stainless-steel fasteners for fastening aluminum.
 - 2. Provide stainless-steel fasteners for fastening stainless steel.
- B. Cast-in-Place Anchors in Concrete: Either threaded type or wedge type unless otherwise indicated; galvanized ferrous castings, either ASTM A 47/A 47M malleable iron or ASTM A 27/A 27M cast steel. Provide bolts, washers, and shims as needed, all hot-dip galvanized per ASTM F 2329.
- C. Post-Installed Anchors: Torque-controlled expansion anchors.
 - 1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B 633 or ASTM F 1941 (ASTM F 1941M), Class Fe/Zn 5, unless otherwise indicated.

2.5 MISCELLANEOUS MATERIALS

- A. Low-Emitting Materials: Paints and coatings shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

- B. Shop Primers: Provide primers that comply with Section 099123 "Painting."
- C. Galvanizing Repair Paint: High-zinc-dust-content paint complying with SSPC-Paint 20 and compatible with paints specified to be used over it.
- D. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D 1187.
- E. Nonshrink, Nonmetallic Grout: Factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107. Provide grout specifically recommended by manufacturer for interior and exterior applications.
- F. Concrete: Comply with requirements in Section 033000 "Cast-in-Place Concrete" for normal-weight, air-entrained, concrete with a minimum 28-day compressive strength of 3000 psi (20 MPa).

2.6 FABRICATION, GENERAL

- A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Use connections that maintain structural value of joined pieces.
- B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges. Remove sharp or rough areas on exposed surfaces.
- C. Weld corners and seams continuously to comply with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. At exposed connections, finish exposed welds and surfaces smooth and blended.
- D. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Locate joints where least conspicuous.
- E. Fabricate seams and other connections that will be exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.
- F. Where units are indicated to be cast into concrete or built into masonry, equip with integrally welded steel strap anchors not less than 24 inches (600 mm) o.c.

2.7 MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.
- B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.8 SHELF ANGLES

- A. Fabricate shelf angles from steel angles of sizes indicated and for attachment to concrete framing. Provide horizontally slotted holes to receive 3/4-inch (19-mm) bolts, spaced not more than 6 inches (150 mm) from ends and 24 inches (600 mm) o.c., unless otherwise indicated.
- B. For cavity walls, provide vertical channel brackets to support angles from backup masonry and concrete.
- C. Galvanize shelf angles located in exterior walls.
- D. Furnish wedge-type concrete inserts, complete with fasteners, to attach shelf angles to cast-in-place concrete.

2.9 METAL LADDERS

- A. General:
 - 1. Comply with ANSI A14.3 unless otherwise indicated.
 - 2. For elevator pit ladders, comply with ASME A17.1.
- B. Steel Ladders:
 - 1. Space siderails 18 inches (457 mm) apart unless otherwise indicated.
 - 2. Space siderails of elevator pit ladders 1'-8" inches (300 mm) apart.
 - 3. Siderails: Continuous, 1/2-by-2-1/2-inch (12.7-by-64-mm) steel flat bars, with eased edges.
 - 4. Rungs: 3/4-inch- (19-mm-) steel bars.
 - 5. Fit rungs in centerline of siderails; plug-weld and grind smooth on outer rail faces.
 - 6. Provide nonslip abrasive surfaces on top of each rung.

2.10 MISCELLANEOUS STEEL TRIM

- A. Unless otherwise indicated, fabricate units from steel shapes, plates, and bars of profiles shown with continuously welded joints and smooth exposed edges. Miter corners and use concealed field splices where possible.
- B. Provide cutouts, fittings, and anchorages as needed to coordinate assembly and installation with other work.
- C. Galvanize exterior miscellaneous steel trim.

2.11 METAL BOLLARDS

- A. Fabricate metal bollards from Schedule 80 steel pipe.
- B. Prime bollards with zinc-rich primer.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.12 LOOSE BEARING AND LEVELING PLATES

- A. Provide loose bearing and leveling plates for steel items bearing on masonry or concrete construction. Drill plates to receive anchor bolts and for grouting.

2.13 LOOSE STEEL LINTELS

- A. Fabricate loose steel lintels from steel angles and shapes of size indicated for openings and recesses in masonry walls and partitions at locations indicated.
- B. Galvanize loose steel lintels located in exterior walls.

2.14 STEEL WELD PLATES AND ANGLES

- A. Provide steel weld plates and angles not specified in other Sections, for items supported from concrete construction as needed to complete the Work. Provide each unit with no fewer than two integrally welded steel strap anchors for embedding in concrete.

2.15 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Finish metal fabrications after assembly.

2.16 STEEL AND IRON FINISHES

- A. Galvanizing: Hot-dip galvanize items as indicated to comply with ASTM A 153/A 153M for steel and iron hardware and with ASTM A 123/A 123M for other steel and iron products.
- B. Shop prime iron and steel items not indicated to be galvanized unless they are to be embedded in concrete, sprayed-on fireproofing, or masonry, or unless otherwise indicated.
 - 1. Shop prime with primers specified in Section 099123 "Painting".
 - 2. Preparation for Shop Priming: Prepare surfaces to comply with SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.
- B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.

- C. Field Welding: Comply with the following requirements:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. At exposed connections, finish exposed welds and surfaces smooth and blended.
- D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction.
- E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

3.2 INSTALLING METAL BOLLARDS

- A. Anchor bollards in concrete as shown on plans. Fill annular space around bollard solidly with nonshrink, nonmetallic grout.
- B. Anchor bollards in place with concrete footings. Place concrete and vibrate or tamp for consolidation. Support and brace bollards in position until concrete has cured.
- C. Fill bollards solidly with concrete, mounding top surface to shed water.

3.3 INSTALLING BEARING AND LEVELING PLATES

- A. Clean concrete and masonry bearing surfaces of bond-reducing materials, and roughen to improve bond to surfaces. Clean bottom surface of plates.
- B. Set bearing and leveling plates on wedges, shims, or leveling nuts. After bearing members have been positioned and plumbed, tighten anchor bolts. Do not remove wedges or shims but, if protruding, cut off flush with edge of bearing plate before packing with grout.
- C. Pack grout solidly between bearing surfaces and plates to ensure that no voids remain.

3.4 ADJUSTING AND CLEANING

- A. Touchup Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
- B. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing to comply with ASTM A 780.

END OF SECTION 05 50 00

SECTION 06 10 53 - MISCELLANEOUS ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
1. Framing with dimension lumber.
 2. Rooftop equipment bases and support curbs.
 3. Wood blocking, cants, and nailers.
 4. Plywood backing panels.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1.3 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
1. Preservative-treated wood.
 2. Fire-retardant-treated wood.
 3. Power-driven fasteners.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. Certified Wood: Lumber and plywood shall be produced from wood obtained from forests certified by an FSC-accredited certification body to comply with FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship."
- B. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.
1. Factory mark each piece of lumber with grade stamp of grading agency.
 2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece or omit grade stamp and provide certificates of grade compliance issued by grading agency.
 3. Provide dressed lumber, S4S, unless otherwise indicated.
- C. Maximum Moisture Content of Lumber: 19 percent unless otherwise indicated.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

- A. Preservative Treatment by Pressure Process: AWP A U1; Use Category UC2.
 - 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
- B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or does not comply with requirements for untreated material.
- C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.
- D. Application: Treat:
 - 1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
 - 2. Wood sills, sleepers, blocking, and similar concealed members in contact with masonry or concrete.

2.3 FIRE-RETARDANT-TREATED MATERIALS

- A. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame spread index of 25 or less when tested according to ASTM E 84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet (3.2 m) beyond the centerline of the burners at any time during the test.
 - 1. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D 3201 at 92 percent relative humidity. Use where exterior type is not indicated.
 - 2. Design Value Adjustment Factors: Treated lumber shall be tested according ASTM D 5664, and design value adjustment factors shall be calculated according to ASTM D 6841.
- B. Kiln-dry plywood after treatment to a maximum moisture content of 15 percent.
- C. Identify fire-retardant-treated wood with appropriate classification marking of testing and inspecting agency acceptable to authorities having jurisdiction.
- D. Application: Treat:
 - 1. Plywood backing panels.

2.4 MISCELLANEOUS LUMBER

- A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:
 - 1. Blocking.
 - 2. Nailers.
 - 3. Rooftop equipment bases and support curbs.
 - 4. Cants.
 - 5. Furring.
 - 6. Grounds.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

7. Utility shelving.

- B. For items of dimension lumber size, provide Construction or No. 2 grade lumber of any species.
- C. For concealed boards, provide lumber with 19 percent maximum moisture content and any of the following species and grades:
 - 1. Mixed southern pine, No. 2 grade; SPIB.
 - 2. Eastern softwoods, No. 2 Common grade; NELMA.
 - 3. Northern species, No. 2 Common grade; NLGA.
 - 4. Western woods, Construction or No. 2 Common grade; WCLIB or WWPA.

2.5 PLYWOOD BACKING PANELS

- A. Equipment Backing Panels: DOC PS 1, fire-retardant treated, not less than 3/4-inch (19-mm) nominal thickness.
 - 1. Plywood shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.6 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.
 - 1. Where carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M].
- B. Power-Driven Fasteners: NES NER-272.

2.7 MISCELLANEOUS MATERIALS

- A. Flexible Flashing: Self-adhesive butyl rubber or rubberized-asphalt compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch (0.6 mm).

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry to other construction; scribe and cope as needed for accurate fit.
- B. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.
- C. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels. Install fire-retardant treated plywood backing panels with classification marking of testing agency exposed to view.
- E. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.
- F. Securely attach carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
 - 1. NES NER-272 for power-driven fasteners.
 - 2. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
 - 3. Table R602.3(1), "Fastener Schedule for Structural Members," and Table R602.3(2), "Alternate Attachments," in ICC's International Residential Code for One- and Two-Family Dwellings.

3.2 PROTECTION

- A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 06 10 53

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

SECTION 07 62 00 - SHEET METAL FLASHING AND TRIM

PART 1 GENERAL

1.1 WORK INCLUDED

- A. Fabrication and installation of new sheet metal flashings and trim to provide a permanently watertight condition.
- B. Re-securement of fascia metal at existing standing seam metal roofs.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Specification Sections, apply to this Section, including but not limited to:

- 1. Section 061053 Miscellaneous Rough Carpentry.
- 2. Section 074100 Metal Roofing.
- 3. Section 075216 SBS Modified Bituminous Membrane Roofing.

1.3 REFERENCES

- A. Refer to the following references for specification compliance:

- 1. South Carolina State Building Codes.
- 2. American Society for Testing and Materials (ASTM).
- 3. National Roofing Contractors Association (NRCA).
- 4. Sheet Metal and Air Conditioning Contractors National Association (SMACNA).
- 5. ANSI/SPRI ES-1.

1.4 SUBMITTALS

- A. Refer to Section 01 33 00 and Section 7 of the General Conditions for Submittals.
- B. Manufacturer's Product Data Sheets for all materials specified certifying material complies with all specified requirements.
- C. Pre-finished sheet metal color chart. Provide one set of original color samples.
- D. Shop Drawings for any transitions and/or terminations not depicted in Contract Drawings.

1.5 QUALITY ASSURANCE

- A. Installation shall comply with the current SMACNA Architectural Sheet Metal Manual.
- B. Fabricate metal edge (where no gutter is present) and coping in accordance with

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

ANSI/SPRI ES-1 requirements.

- C. Workmanship shall be first-class in every respect. The various sections shall be uniform with joints at corners and angles mitered and the different sections accurately fitted and rigidly secured. Completed work will be free of leaks under all weather conditions.

1.6 DELIVERY, STORAGE AND HANDLING

- A. Delivery: Deliver materials in the manufacturer's original sealed and labeled containers and in quantities required to allow continuity of application.
- B. Storage: Store materials within areas designated or approved by the Owner. Ensure materials remain dry, covered and not in contact with the ground.
- C. Handling: Handle material in such manner as to preclude damage and contamination with moisture or foreign matter.
 - 1. The Contractor shall handle pre-finished materials to prevent scratches, dents and other damages. Significantly scratched materials as judged by the Owner and Engineer and materials scratched through to the base steel shall be removed from the project, not to be installed.

1.7 PROJECT CONDITIONS

- A. Environmental: Protect building and its components from the elements at all times during the project.
- B. Coordination and Scheduling: Coordinate all phases of work to allow continuity of work without delays.

1.8 WARRANTY

- A. Manufacturer's Finish Warranty: Provide finish warranty on all pre-finished sheet metal materials covering color fade, chalking and film integrity. Salt water exclusion due to project's location shall be rejected.
 - 1. Warranty Period: Twenty (20) years from date of final acceptance.
- B. Installer's Warranty: Provide on Horry County Schools form HCS-CC41.
 - 1. Contractor will be required to attend an inspection prior to the five (5) year warranty end date and complete any corrective action requested by Engineer, Membrane Roof Manufacturer or Metal Roof Manufacturer at no additional cost to the Owner.
 - 2. Warranty Period: Five (5) years from date of Final Acceptance.

PART 2 PRODUCTS

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.1 PRE-FINISHED STEEL

- A. Aluminum sheet, factory pre-finished with Kynar® 500-based fluoropolymer coating, containing not less than 70% polyvinylidene fluoride resin by weight. Mask metal with protective plastic film. Thickness shall be .040 inches.
- 1. Color to be selected by Architect from manufacturer's standard color charts.
- B. Galvanized steel sheet, factory pre-finished with Kynar® 500-based fluoropolymer coating, containing not less than 70% polyvinylidene fluoride resin by weight. Mask metal with protective plastic film. Color to be selected by Architect from manufacturer's standard color charts. Thickness shall be minimum 22 gauge.
 - 1. Coping cap
 - 2. Counterflashing
 - 3. Edge metal extension
 - 4. Expansion joint metal
 - 5. Expansion joint cleatpo
 - 6. Fascia metal
 - 7. Inside panel corner
 - 8. Outside panel corner
 - 9. Multiple pipe enclosure
 - 10. Rake closure
 - 11. Receiver flashing
 - 12. Ridge closure
 - 13. Sheet metal closure
 - 14. Scupper trim plate
 - 15. Sill flashing
 - 16. Slip counterflashing/skirt, surface mounted and support curb counterflashing
 - 17. Termination closure
 - 18. Roof area divider

2.2 GALVANIZED STEEL

- A. ASTM A 653, G-90 zinc-coated sheets, 20 gauge.
 - 1. Continuous cleat
 - 2. Continuous eave cleat
- 3. Rake support
 - 4. Gutter Brackets: Prime and paint to match gutter, or clad in gutter material. If painting, form brackets prior to painting and paint prior to installation. Touch up paint after installation.
 - a. 1/4-inch x 1-1/2 inch for gutter girth of 20-inches to 24-inches
 - b. 1/8-inch x 1-inch for gutter girth up to 20-inches

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

5. Gutter Spacers/Downspout Hangers: 1/16-inch x 1-inch.

2.3 STAINLESS STEEL

- A. 24 gauge, Type 304 as tested in accordance with ASTM A 167.
 1. Scupper liner
 2. Roof mounted splash pans
- B. 16 Gauge
 1. Continuous zee

2.4 LEAD

- A. Four pound soft lead:
 1. Lead counter flashing wedges at saw cut joints.
 2. Roof Drain Flashing – utilize 30-inch x 30-inch sheet.

2.5 FASTENERS

- A. Provide fasteners that are rust-resistant and compatible with materials to be joined.
- B. All exposed fasteners for use with painted metals shall have factory painted heads to match the painted metal finish.
- C. Provide stainless steel fasteners at all locations where fastener will be used in lumber products.
- D. Fasteners for securing counterflashings to receivers: Self-piercing, hardened steel, corrosion resistant, hex washer screws; size and length as appropriate.
- E. Fasteners for securing sheet metal to structural steel (greater than 18 ga.): Self drilling fastener size, type and length required by manufacturer for metal type and thickness/gauge. Acceptable manufacturer, ITW Buildex, Itasca, IL, Powers Fasteners, Inc., Construction Fasteners, Inc., SFS Stadler, Inc.
- F. Fasteners for securing sheet metal to sheet metal: Self drilling, stainless steel fastener size and length required by fastener manufacturer for metal gauges being joined. Rivets, of equal, compatible material, color to match metal finish.
- G. Provide metal and EPDM washers on all exposed fasteners. Do not install exposed fasteners on horizontal surfaces.
- H. Roofing Nails: Eleven (11) or twelve (12) gauge stainless ring shank roofing nails with diamond point, minimum 3/8-inch diameter head and 1-1/4 inch length.
- I. Screws: #12 stainless steel hex or pan head screws with length as required to penetrate substrate a minimum of 1-1/2 inches.

- J. Concrete and Masonry Anchors:

SHEET METAL FLASHING AND TRIM

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. 1/4-inch diameter metal based expansion anchor with EPDM washers and with stainless steel pin of length as required to penetrate substrate a minimum of 1-1/2 inch.
2. Masonry screws, approved by membrane manufacturer, 1/4-inch minimum diameter, corrosion resistant, with Phillips flat head. Length as required to provide minimum 1-1/2 inch embedment into substrate, or as required by the fastener manufacturer to achieve required withdrawal load.
3. All exposed fasteners into masonry shall be metal based expansion anchor with stainless steel pin fastened through EPDM washers with stainless steel backing, and fastened through oversized or slotted holes.

K. Washers: Shall be stainless steel with neoprene gasket backing. Shall be 9/16 inch diameter for use with #12 screws and 5/8-inch diameter for use with 1/4-inch diameter concrete and masonry anchors.

L. Rivets: #44 stainless steel rivets with stainless steel mandrel. Length of rivet as required to properly fasten particular sheet metal components. Rivets shall be factory painted to match adjacent sheet metal.

2.6 RELATED MATERIALS

A. Underlayment Membrane: High temperature underlayment specifically formulated to resist temperatures up to 300⁰F without degradation of the butyl adhesive; composed of two waterproofing materials – an aggressive butyl rubber based adhesive backed by a layer of high density cross laminated polyethylene. Minimum 30 mil; slip-resistant surface, with release paper backing; cold-applied, suitable for metal roofs. Provide primer for adjoining concrete or masonry surfaces and other surfaces to receive underlayment as recommended by manufacturer. Acceptable Product:

1. GRACE – Ultra.

B. Flashing Envelope Membrane: 20 mil corrosion resistant, waterproof PVC flashing such as Nuflex Plastic Flashing as manufactured by Sandell Mfr. Co., Inc., or Engineer accepted equivalent.

C. Compressible Insulation: Un-faced friction-fit fiberglass building insulation, cut to fit from 3-1/2 inch x 15-inch x 48-inch batts.

D. Sealant: One-component elastomeric gun grade polyurethane sealant conforming to ASTM C 920, Type S, Grade NS, Class 25, and use NT, M, A, G, or O as required by substrate conditions.. Color to match adjacent materials.

E. Continuous Sealant Tape: Minimum 1/2-inch wide non-skinning butyl sealant tape.

F. Solder: 20-80 tin-lead alloy conforming to ASTM B32.

G. Flux: Muriatic acid killed with zinc or an accepted brand of commercial soldering flux designed for use with 20-80 solder.

H. Metal Primer: ASTM D 41.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

- I. SBS Mastic: Asbestos-free, VOC compliant, SBS modified asphalt mastic prepackaged in caulking tubes, such as 19 ULTRA as manufactured by Karnak Corporation, or as recommended by modified bitumen roofing manufacturer.
- J. Roof Cement: An asphalt cutback mastic, reinforced with non-asbestos fibers, used as a base for setting metal flanges and conforming to ASTM D 4586, Type II and Fed Spec No. SS-C-153, Type I requirements.
- K. Termination Bar: Extruded aluminum bar, 1-inch wide by 1/8 inch thick, with pre-punched holes at 6-inches on center.
- L. Non-Shrink Grout: High early strength, non-rusting non-shrink grout conforming to ASTM C 1107 Grade C (modified for rapid-setting grout) such as 747 Rapid Setting Grout as manufactured by ThoRoc (ChemRex), Multi Purpose Non- Shrink Grout as manufactured by US Mix, or Sikagrout 212 as manufactured by Sika.
- M. Gutter Shim: 1/8-inch x 1-inch square painted steel tubing, as indicated on Contract Drawings.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Coordinate with other work for correct sequencing of items which make up the entire system.
- B. Ensure substrates are installed, secured and modified to accommodate sheet metal flashings.
- C. Deficiencies associated with the sheet metal substrates shall be reported to Engineer before beginning sheet metal work. All such deficiencies shall be corrected before installing sheet metal flashings.
- D. Contractor shall inspect pre-finished sheet metal components before installation.
Materials with scratches through the paint finish shall be repaired or replaced as determined by the Engineer. Damaged and dented materials, and materials scratched through to the steel base material shall be removed from the project, not to be installed.

3.2 INSTALLATION

- A. General:
 - 1. All joints to be locked and sealed or soldered as required.
 - 2. Provide for thermal movement (expansion and contraction) of all exposed sheet metal.
 - 3. Where dissimilar metals contact, galvanic action shall be prevented by means of heavy coat of asphalt paint.
 - 4. Prime all metal surfaces (top and bottom) to receive bituminous materials. Allow primer to dry thoroughly before application of bituminous materials.
 - 5. All metal flanges shall be installed on top of membrane and adhered as

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

indicated in Contract Drawings. Metal flanges connected to the roof shall be installed per membrane manufacturer's specifications and the requirements herein.

6. Various sheet metal sections shall be uniform with corners, joints and angles mitered, sealed and secured.
7. Exposed edges shall be returned (hemmed); both for strength and appearance, and sheet metal shall be fitted closely and neatly.
8. Provide all necessary cleats or stiffeners and other reinforcements as required to make all sections rigid and substantial.
9. Sheet metal shall be fabricated, supported, cleated, fastened and joined to prevent warping, "oil canning", and buckling.
10. All sheet metal details shall provide for redundancy including but not limited to sheet metal underlayment and/or sealants. This secondary protection shall be installed, sealed, lapped, etc. to ensure a redundant layer of protection will shed moisture infiltration in the sheet metal fails.

B. Fasteners: Shall be size and type required.

1. Replacement of Fasteners: All ridge cap flashing fasteners at the existing standing seam metal roofs shall be replaced. Fasteners shall be replaced with larger diameter fasteners, and the area re-secured by adding a new oversized fastener at the existing fastener location. All missing fasteners shall be replaced with new oversized fasteners.
2. All fasteners to be rust resistant and compatible with materials to be joined.
3. All exposed fasteners shall be stainless steel screws with washers fastened through 5/16-inch predrilled oversized holes.
4. All exposed fasteners into concrete or masonry shall be metal based expansion anchor with stainless steel pin with washers fastened through 11/32" predrilled oversized holes.

5. color. All exposed fasteners shall have factory painted heads to match the sheet metal

6. Exposed horizontal surface fasteners are not acceptable.

C. Parapet Wall

1. Fabricate coping cap in 8-foot or 10-foot lengths. Refer to SMACNA Architectural Sheet Metal Manual Figure 3-4A.
2. Install tapered edge strip mechanically attached or set in foam adhesive to top of wood blocking.
3. Install sheet metal underlayment membrane up and over parapet extending a minimum of 1 inch below wood blocking.
4. Install continuous cleat fastened to substrate 6 inches on center in vertical leg. Locate fasteners no greater than 2 inches from the bottom hem.
5. Lock outside face of coping cap onto continuous cleat and secure inside face as follows:
 - a. Secure inside face with continuous cleats. Secure cleat through vertical face of cleat to blocking with fasteners at 6 inches on center. Locate fasteners no greater than 2 inches from the bottom hem.

6. Provide standing seams at adjoining coping cap sections. Refer to

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

SMACNA Architectural Sheet Metal Manual Figure 3-3, type 22.

7. Provide seams located between 12 inches and 18 inches from each direction of the coping corners measured on the interior side.
8. Turn coping cap ends up a minimum of 2 inches at elevation walls and cover termination as shown in Contract Drawings.

D. Roof to Wall Expansion Joint

1. Fabricate expansion joint cover, cleat and receiver as indicated in Contract Drawings in 8 foot or 10 foot lengths. Refer to SMACNA Architectural Sheet Metal Manual Figure 5-5A.
2. Prior to installation of expansion joint cover, install compressible insulation in flashing envelope membrane.
3. Install underlayment membrane adhered to vertical substrate and extending a minimum of 2 inches down below the top of the expansion joint curb.
4. Provide continuous cleat fastened to the expansion joint curb 8 inches on center.
5. Lock expansion joint cover onto cleat and fasten to wall substrate 12 inches on center.
6. Apply sealant tape between receiver flashing and wall substrate and surface mount counterflashing 12 inches on center.
7. Install sealant in kick-out and manually tool concave to ensure proper adhesion and slope to shed water.
8. Notch and lap ends of adjoining expansion joint cleat and counterflashing sheet metal sections not less than 4 inches; apply sealant tape between sections.
9. Notch and lap ends of adjoining expansion joint cover sheet metal sections not less than 6 inches and apply two beads of sealant between sections. Center 8 inch wide cover plate over exposed edge of sheet metal and apply sealant to each side of lap. Rivet cover plate at 2 inches on center to one side of lap only.

E. Roof Drain

1. Provide roof drain flashings as indicated in detail drawing. Install lead flashing in full bed of roof cement over modified bitumen roof membrane. Form flashing with a rubber mallet to conform to substrate and extend a minimum of 1-inch beyond clamping ring. Strip-in lead flashing as specified.
2. Provide new stainless steel clamping ring bolts for all drain clamping rings.
3. Clamping rings shall be secured in place with all bolts at the end of each work day. Contractor shall water test roof drains after every instance the clamping ring is removed and reinstalled. The Contractor shall notify the Owner of the water test schedule.

F. Curb Flashing

1. Fabricate slip flashing at curbs as indicated in Contract Drawings in 8 foot or 10 foot lengths.
2. Slip flashing shall extend a minimum of 2 inches below base flashing termination and shall fit tightly against curb.
3. Secure flashing 8 inches on center of a minimum of two (2) fasteners per side of the curb.
4. Notch and lap ends of adjoining sections not less than 4 inches; apply sealant tape between sections.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

5. Lap miters at corners a minimum of 1-inch and apply sealant between laps. Rivet at 2 inches on center.

G. Equipment Support

1. Wrap top of equipment support with sheet metal underlayment to extend 2 inches below base flashing termination.
2. Fabricate equipment support cap at curbs as indicated in Contract Drawings in one continuous piece of sheet metal and secure at eighteen inches on center.

H. Reglet Mounted Counterflashing

1. Fabricate counterflashing in 8 foot or 10 foot lengths.
2. Install counter flashing into saw-cut reglet and secure with lead wedges at 18 inches on center set deep into joint.
3. Install sealant properly tooled to ensure adhesion and slope to shed water in saw-cut reglet. Sealant shall completely cover lead wedges.
4. Counterflashing shall extend a minimum of 1-1/2 inches below rake closure termination.
5. Notch and lap ends of adjoining sheet metal sections not less than 4 inches; apply sealant tape between sections.
6. Lap miters at corners a minimum of 1-inch and apply sealant between laps. Rivet at 2 inches on center.

I. Through-Wall Overflow Scupper

1. Fabricate thru-wall scupper flange, liner, and faceplate as indicated in Contract Drawings. Scuppers shall be 4 inches high by 8 inches wide.
2. Clean and solder all seams of the flange and liner.
3. Install base ply through scupper opening prior to installing new scupper to seal wall cavity.
4. Provide flange which extends a minimum of 4 inches on top and sides of scupper, and extends a minimum of 4 inches out onto the horizontal membrane. Set all flanges in a full bead of roof cement and mechanically fasten the horizontal flange into structural deck 8 inches on center or a minimum of two fasteners per scupper with approved fasteners.
5. Strip-in flange as specified.
6. Provide faceplate which extends 1-1/2 inches around the entire scupper and secure to wall substrate with four fasteners through EPDM washers. Fasteners shall be factory painted to match adjacent pre-finished sheet metal. Set faceplate in a bead of sealant.
7. Scupper Liner shall extend 1-inch beyond the exterior wall face and lock onto faceplate.

J. Edge Metal Extension

1. Fabricate in 8 or 10 foot lengths. Refer to SMACNA Manual Figure 2-2A and 3-4E for similar cleated installations.
2. Extend vertically a minimum of 3 inches behind the outside vertical leg of edge metal and coping cap. Refer to SMACNA Manual Figure 2-2A.
3. Leave a 1/4-inch opening between metal edge sections. Center back-up plates

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- under opening, set in 2 beads of the specified sealant, one on each side of the opening. Refer to SMACNA Manual Figure 2-5C
4. Secure vertical flange of metal extension to wood blocking 16 inches on center.

K. Gutters

1. Fabricate to profile indicated in the Contract Drawings. Refer to SMACNA Manual Figure 1.2 Style A.
2. Gutters shall be continuous, roll formed from coil stock on site or formed in 10 foot lengths.
 - a. Joints in gutters must be lapped a minimum of 1 inch, riveted 1 inch on center. Install sealant tape between gutter sections and sealant at exposed inside edge and on rivets. Lap joints in the direction of water flow if possible.
3. Provide sheet metal underlayment to cover fascia as indicated in the Contract Drawings. Allow base ply membrane to extend down the outside vertical face of wall a minimum of 2 inches.
4. Provide butt type expansion joints in gutters at spacing appropriate for the type material used to fabricate gutters. Refer to SMACNA Manual Figure 1-7. Maximum length of gutters shall be 50 feet.
5. Provide downspout outlets in downspout locations. Refer to SMACNA Manual Figure 1-33B. Gutter outlet tubes to be tabbed a minimum of 1 inch, set in a full bead of sealant and secured to gutter with a minimum of two (2) rivets per tab.
6. Provide brackets and spacers as indicated in the Contract Drawings. Evenly stagger the placement of brackets and spacers. Spacing shall be 36 inches on center for both brackets and spacers unless otherwise indicated in the Contract Drawings.
7. Spacers shall be riveted to both sides of the gutter only.
8. Brackets shall be secured with two (2) stainless steel fasteners to the wood blocking.
9. Leading edge of gutter to be a minimum of 1 inch below the back edge as indicated in the Contract Drawing.
10. Hang gutters level.
11. Downspouts:
 - a. Fabricate 10 foot lengths. Refer to SMACNA Architectural Sheet Metal Manual Figure 1-32B.
 - b. Downspouts shall tie into existing below grade storm drainage system or if no below grade system is applicable downspouts shall kick-out above grade onto a new concrete splash blocks. Fill in soil as necessary to provide slope away from building.
 - c. Each downspout shall be secured to the structure with one-piece hangers spaced no more than 8 feet apart with a minimum of two (2) hangers per downspout with a hanger located within 12 inches from bottom. Hangers shall be primed and painted to match downspouts. Refer to SMACNA Architectural Sheet Metal Manual Figure 1-35G.
 - d. Downspouts are to be fashioned so as to run back to (at overhangs) and parallel to the facility walls.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- e. Provide discharge elbow at the base of downspout.
- f. Where downspouts terminate at lower roof levels, including any roofs Not In Contract, provide sheet metal splash pan cemented to walkpad adhered over membrane with membrane Manufacturer's approved mastic. Fabricate splash pan in accordance with SMACNA Architectural Sheet Metal Manual Figure 1-36, Second Alternate Section.

L. Metal Fascia

- 1. Fabricate in 8 foot or 10 foot lengths. Install formed fascia metal to conform to profile of fascia sheathing as indicated on Contract Drawings.
- 2. Not used
- 3. Extend vertically a minimum of 3 inches behind the outside vertical leg of edge metal extension. Refer to SMACNA Manual Figure 2-2A.
- 4. Install gutter shim where indicated on Contract Drawings.
- 5. Leave a 1/4-inch opening between metal edge sections. Center back-up plates under opening, set in two (2) beads of the specified sealant, one on each side of the opening. Refer to SMACNA Manual Figure 2-5C.
- 6. Secure vertical flange of metal extension to wood blocking 16 inches on center.

L. Multiple Pipe Enclosure

- 1. Fabricate pan, pipe enclosure flashing, and cap as indicated in the Contract Drawings. Refer to SMACNA Architectural Sheet Metal Manual Figure 4-14A.
- 2. Size pan minimum 2" larger than the penetration on all sides. Provide a 4" minimum flange and double walls with minimum depth of 6".
- 3. Set flange of pan in full bead of roof cement and strip-in flange of metal edge as specified.
- 4. Secure pipe enclosure flashing and cap as indicated in the Contract Drawings.
- 5. Clean and solder all seams.

M. Inside Corner Gutter Piece

- 1. Fabricate to match profile and color of existing gutter. Install as indicated in Contract Drawings.

N. Roof Area Divider

- 1. Fabricate area divider cover and cleat as shown in detail drawing in 8- or 10-foot lengths. Refer to SMACNA Architectural Sheet Metal Manual Figure 3-7B.
- 2. Prior to area divider installation, install self adhered membrane underlayment over top of curb, extending vertically the approximate length of the area divider cover sections. Seal all laps.
- 3. Install continuous cleat on one outside vertical surface of the wood curb. Secure through vertical face of cleat to blocking with fasteners at 6 inches on center. Locate fasteners no greater than 2 inches from the bottom hem.
- 4. Secure inside face with screws through waterproof washers and elongated holes at 18 inches on center.
- 5. Provide 1-inch standing seams at adjoining area divider cover sections. Install sealant between section seams. Fold cover from one section over standing

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

seam at adjacent section. Refer to SMACNA Architectural Sheet Metal Manual Figure 3-3 type 22.

6. Cover area divider cap terminations at elevation walls and edge metal transitions. Refer to SMACNA Architectural Sheet Metal Manual Figure 5- 3.

1.9 CLEANING AND PROTECTION

- A. Immediately remove all metal dust and cut debris produced by cutting, drilling and fastening.
- B. All sheet metal work shall be thoroughly cleaned of all asphalt, flux, scrapes and dust in accordance with manufacturer's recommendations.
- C. The Contractor shall protect work against damage until final acceptance. The Contractor shall replace or repair to the satisfaction of the Owner, any work that becomes damaged prior to final acceptance.
- D. Scratches through the metal finish shall be repaired or replaced to the Owner's satisfaction.

END OF SECTION 07 62 00

SECTION 077200 - ROOF ACCESSORIES

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Furnish and install roof accessory assemblies as indicated and required by the Contract Drawings.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Specification Sections, apply to this Section, including but not limited to:

- | | | |
|----|----------------|--------------------------------|
| 1. | Section 053100 | Steel Decking. |
| 2. | Section 061053 | Miscellaneous Rough Carpentry. |
| 3. | Section 072216 | Roof Board Insulation. |
| 4. | Section 076200 | Sheet Metal Flashing and Trim. |

1.3 SUBMITTALS

- A. Refer to Section 01 33 00 and Section 7 of the General Conditions for Submittals.
- B. Latest edition of the Manufacturer's current material specifications and installation instructions.
- C. Manufacturer's Product Data Sheets for all materials specified certifying material complies with all specified requirements.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Packing and Shipping: Deliver materials to site in Manufacturer's original unopened packaging with labels intact.
- B. Storage: Adequately protect against damage while stored at the site.
- C. Handling: Comply with Manufacturer's instructions.

1.5 PROJECT CONDITIONS

- A. Field Measurements: Verify all dimensions required.

1.6 WARRANTIES

- A. All roof accessories shall be included in the specified roof system manufacturer's warranty.

PART 2 PRODUCTS

2.1 MATERIALS

A. Access Ladder

1. Fixed Steel Ladder: Fixed ladder of appropriate length with walk-thru hand rails, welded one-piece construction, gray powder coat finish such as Model FW as manufactured by Cotterman Co. (800-5-LADDER, www.cotterman.com).
2. Fixed Steel Ladder Anchors: HIT HY 20 Adhesive Anchor System utilizing ½" by 3-1/8" HIT-A Rods and S12 Screens as manufactured by Hilti (800- 879-8000, www.hilti.com).

B. Roof Hatch: Basis of design is Bilco, 3'-0" x 3'-6". Aluminum and Galvanized steel, 11 gage cover & curb, 18 gage cover liner. 1 inch thick rigid insulation in curb and cover 12 inch high curb. Curb option shall be provided for modification for the specified standing seam metal roof profile. Fabricate base flanges of roof hatch to the configuration of the standing seam metal roof.

1. Provide heavy duty padlock hasp.
2. Provide vandal resistant features as available.
3. Provide built-in self-drainage to eliminate water accumulation on the up-slope side.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verification of Conditions: Examine subsurfaces to receive Work and report detrimental conditions in writing to Engineer. Commencement of Work will be construed as acceptance of subsurfaces.

B. Coordination: Coordinate with other Work which affects, connects with, or will be concealed by this Work.

3.2 INSTALLATION

A. Ladder:

1. Drill 5/8" diameter hole a minimum of 2-1/2" into masonry wall using the appropriate drill bit.
2. Use brush and/or compressed air to remove all dust and debris from hole.
3. Insert HIT-S Screen tube into hole and fill to front edge of screen with HY 20 adhesive (minimum 1 pump for S12 screen tube).
4. Insert HIT-A Rod into adhesive-filled screen, twisting slightly. Fastener may be adjusted during specified gel time. Do not disturb fastener between specified gel and cure time.
5. Install fixed steel ladder and secure to HIT-A Rods with washers and nuts.

Do not exceed maximum torque on anchors.

B. Roof Hatch

1. Install roof hatches at locations indicated, fastening securely to deck through curb flange per the manufacturer's specifications.

3.3 CLEANING

- A. During the course of the Work and on completion, remove and dispose of excess materials, equipment and debris away from premises.

END OF SECTION 07 72 00

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

SECTION 07 84 13 - PENETRATION FIRESTOPPING

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Section, apply to work specified in this section.

1.02 DEFINITIONS

- PART 1 - Firestopping: Material or combination of materials used to retain integrity of fire-rated construction by maintaining an effective barrier against the spread of flame, smoke, water and hot gases through penetrations in fire rated wall and floor assemblies.

1.03 GENERAL DESCRIPTION OF THE WORK OF THIS SECTION

Only tested firestop systems shall be used in specific locations as follows:

- A. Penetrations for the passage of duct, cable, cable tray, conduit, piping, electrical busways and raceways through fire-rated vertical barriers (walls and partitions), horizontal barriers (floor/ceiling assemblies), and vertical service shaft walls and partitions.
- B. Safing slot gaps between edge of floor slabs and curtain walls.
- C. Openings between structurally separate sections of wall or floors.
- D. Gaps between the top of walls and ceiling or roof assemblies.
- E. Expansion joints in walls and floors.
- F. Openings and penetrations in fire-rated partitions or walls containing fire doors.
- G. Openings around structural members which penetrate floors or walls.

1.04 RELATED WORK OF OTHER SECTIONS

- A. Coordinate work of this section with work of other sections as required to properly execute the work and as necessary to maintain satisfactory progress of the work of other sections, including:
 - 1. Section 033000 - Cast-In-Place Concrete
 - 2. Section 079200 - Joint Sealers

1.05 REFERENCES

- A. Test Requirements: ASTM E-814, "Standard Method of Fire Tests of Through Penetration Fire Stops" (July 1983).
- B. Underwriters Laboratories (UL) of Northbrook IL runs ASTM E-814 under their designation of UL 1479 and publishes the results in their "FIRE RESISTANCE DIRECTORY" that is updated annually with a midyear supplement.
 - 1. UL Fire Resistance Directory:
 - a. Through-Penetration Firestop Devices (XHCR)
 - b. Fire Resistance Ratings (BXUV)
 - c. Through-Penetration Firestop Systems (XHEZ)
 - d. Fill, Voids, or Cavity Materials (XHHW)
 - e. Forming Materials (XHKU)
- A. Test Requirements: UL 2079, "Tests for Resistance of Building Joint Systems" (November 1994).
- B. International Firestop Council Guidelines for Evaluating Firestop Systems Engineering Judgments.
- C. ASTM E-84, Standard Test Method for Surface Burning Characteristics of Building Materials.
- E. All major building codes: ICBO, SBCCI, BOCA, and IBC.
- F. NFPA 101 - Life Safety Code
- G. NFPA 70- National Electrical Code

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.06 QUALITY ASSURANCE

- A. A Manufacturer's direct representative (Not distributor or agent) to be on-site during initial installation of firestop systems to train appropriate contractor personnel in proper selection and installation procedures. This will be done per manufacturer's written recommendations published in their literature and drawing details.
- B. Firestop System installation must meet requirements of ASTM E-814, UL 1479 or UL 2079 tested assemblies that provide a fire rating equal to that of construction being penetrated.
- C. Proposed firestop materials and methods shall conform to applicable governing codes having local jurisdiction.
- D. Firestop Systems do not reestablish the structural integrity of load bearing partitions/assemblies, or support live loads and traffic. Installer shall consult the structural engineer prior to penetrating any load bearing assembly.
- E. For those firestop applications that exist for which no UL tested system is available through a manufacturer, a manufacturer's engineering judgment derived from similar UL system designs or other tests will be submitted to local authorities having jurisdiction for their review and approval prior to installation. Engineer judgment drawings must follow requirements set forth by the International Firestop Council (September 7, 1994).

1.07 SUBMITTALS

- A. Submit Product Data: Manufacturer's specifications and technical data for each material including the composition and limitations, documentation of UL firestop systems to be used and manufacturer's installation instructions to comply with Section 01300.
- B. Manufacturer' engineering judgment identification number and drawing details when no UL system is available for an application. Engineer judgment must include both project name and contractor's name who will install firestop system as described in drawing.
- C. Submit material safety data sheets provided with product delivered to job-site.

1.08 INSTALLER QUALIFICATIONS

- A. Engage an experienced installer who is certified, licensed, or otherwise qualified by the firestopping manufacturer as having the necessary experience, staff, and training to install manufacturer's products per specified requirements. A manufacturer's willingness to sell its firestopping products to the Contractor or to an installer engaged by the Contractor does not in itself confer qualification to the buyer.

1.09 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials undamaged in manufacturer's clearly labeled, unopened containers, identified with brand, type, and UL label where applicable.
- B. Coordinate delivery of materials with scheduled installation date to allow minimum storage time at job-site.
- C. Store materials under cover and protect from weather and damage in compliance with manufacturer's requirements.
- D. Comply with recommended procedures, precautions or remedies described in material safety data sheets as applicable.
- E. Do not use damaged or expired materials.

1.10 PROJECT CONDITIONS

- A. Do not use materials that contain flammable solvents.
- B. Schedule installation of firestopping after completion of penetrating item installation but prior to covering or concealing of openings.
- C. Verify existing conditions and substrates before starting work. Correct unsatisfactory conditions before proceeding.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Weather conditions: Do not proceed with installation of firestop materials when temperatures exceed the manufacturer's recommended limitation for installation printed on product label and product data sheet.
- E. During installation, provide masking and drop cloths to prevent firestopping materials from contaminating any adjacent surfaces.

PART 2 - PRODUCTS

2.01 FIRESTOPPING, GENERAL

- A. Provide firestopping composed of components that are compatible with each other, the substrates forming openings, and the items, if any, penetrating the firestopping under conditions of service and application, as demonstrated by the firestopping manufacturer based on testing and field experience.
- B. Provide components for each firestopping system that are needed to install fill materials. Use only components specified by the firestopping manufacturer and approved by the qualified testing agency for the designated fire-resistance-rated systems.

2.02 ACCEPTABLE MANUFACTURERS

- A. Subject to compliance with through penetration firestop systems (XHEZ) and joint systems (XHBN) listed in Volume II of the UL Fire Resistance Directory, provide products of the following manufacturers as identified below:
 - 1. Hilti, Inc., Tulsa, Oklahoma
(800) 879-8000
 - 2. Tremco Sealants & Coatings, Beechwood, Ohio
(216) 292-5000
 - 3. 3M Fire Protection Products, St. Paul, Minnesota
(612) 736-0203
 - 4. Other manufacturers listed in the UL Fire Resistance Directory - Volume 2

2.03 MATERIALS

- A. Use only firestop products that have been UL 1479, ASTM E-814, or UL 2079 tested for specific fire-rated construction conditions conforming to construction assembly type, penetrating item type, annular space requirements, and fire-rating involved for each separate instance.
- B. Sealants or caulking materials for use with non-combustible items including steel pipe, copper pipe, rigid steel conduit and electrical metallic tubing (EMT), the following products are acceptable:
 - 1. Hilti FS-ONE Intumescent Firestop Sealant
 - 2. 3M Fire Stop Sealant 2000
 - 3. 3M Fire Barrier CP25 WB
 - 4. Tremco Tremstop Fyre-Sil Sealant
 - 5. Equivalent products listed in the UL Fire Resistance Directory - Volume 2
- C. Sealants or caulking materials for use with sheet metal ducts, the following products are acceptable:
 - 1. Hilti CP 601s Elastomeric Firestop Sealant
 - 2. Hilti CP 606 Flexible Firestop Sealant
 - 3. Hilti FS-ONE Intumescent Firestop Sealant
 - 4. Equivalent products listed in the UL Fire Resistance Directory - Volume 2
- D. Sealants, caulking or spray materials for use with fire-rated construction joints and other gaps, the following products are acceptable:
 - 1. Hilti CP 672 Firestop Spray
 - 2. Hilti CP 601s Elastomeric Firestop Sealant
 - 3. Hilti CP 606 Flexible Firestop Sealant
 - 4. 3M Firestop Sealant 2000
 - 5. Tremco Tremstop Fyre-Sil Sealant

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- 6. Equivalent products listed in the UL Fire Resistance Directory - Volume 2
- E. Intumescent sealants or caulking materials for use with combustible items (penetrans consumed by high heat and flame) including insulated metal pipe, PVC jacketed, flexible cable or cable bundles and plastic pipe, the following products are acceptable:
 - 1. Hilti FS-ONE Intumescent Firestop Sealant
 - 2. 3M Fire Barrier CP25 WB
 - 3. Tremco Tremstop WBM Intumescent Firestop Sealant
 - 4. Equivalent products listed in the UL Fire Resistance Directory - Volume 2
- F. Intumescent sealants, caulking or putty materials for use with flexible cable or cable bundles, the following products are acceptable:
 - 1. Hilti FS-ONE Intumescent Firestop Sealant
 - 2. Hilti CP 618 Firestop Putty Stick
 - 3. 3M Fire Barrier CP25 WB
 - 4. Tremco Tremstop WBM Intumescent Firestop Sealant

END OF SECTION 07 84 13

SECTION 07 92 00 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Urethane joint sealants.
3. Latex joint sealants.
4. Preformed joint sealants.

1.2 PRECONSTRUCTION TESTING

- A. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates. Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.

1.3 SUBMITTALS

- A. Product Data: For each joint-sealant product indicated.
- B. Samples: For each kind and color of joint sealant required.
- C. Joint-Sealant Schedule: Include the following information:
1. Joint-sealant application, joint location, and designation.
 2. Joint-sealant manufacturer and product name.
 3. Joint-sealant formulation.
 4. Joint-sealant color.
- D. Product test reports.
- E. Preconstruction compatibility and adhesion test reports.
- F. Preconstruction field-adhesion test reports.
- G. Field-adhesion test reports.
- H. Warranties.

1.4 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.

1.5 WARRANTY

- A. Special Installer's Warranty: Manufacturer's standard form in which Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.
- B. Special Manufacturer's Warranty: Manufacturer's standard form in which joint-sealant manufacturer agrees to furnish joint sealants to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. VOC Content of Interior Sealants: Provide sealants and sealant primers for use inside the weatherproofing system that comply with the following limits for VOC content when calculated according to 40 CFR 59, Part 59, Subpart D (EPA Method 24):
 - 1. Architectural Sealants: 250 g/L.
 - 2. Sealant Primers for Nonporous Substrates: 250 g/L.
 - 3. Sealant Primers for Porous Substrates: 775 g/L.
- B. Liquid-Applied Joint Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.
 - 1. Suitability for Immersion in Liquids. Where sealants are indicated for Use I for joints that will be continuously immersed in liquids, provide products that have undergone testing according to ASTM C 1247. Liquid used for testing sealants is deionized water, unless otherwise indicated.
- C. Stain-Test-Response Characteristics: Where sealants are specified to be nonstaining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.
- D. Suitability for Contact with Food: Where sealants are indicated for joints that will come in repeated contact with food, provide products that comply with 21 CFR 177.2600.

2.2 SILICONE JOINT SEALANTS

- A. Mildew-Resistant Neutral-Curing Silicone Joint Sealant: ASTM C 920.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Building Systems.
 - b. Dow Corning Corporation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- c. GE Advanced Materials - Silicones.
 - d. Pecora Corporation.
 - e. Tremco Incorporated.
- 2. Type: Single component (S)
 - 3. Grade: Pourable (P) or nonsag (NS).
 - 4. Class: 100/50
 - 5. Uses Related to Exposure: Nontraffic (NT).

2.3 LATEX JOINT SEALANTS

- A. Latex Joint Sealant: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Building Systems.
 - b. Bostik, Inc.
 - c. May National Associates, Inc.
 - d. Pecora Corporation.
 - e. Schnee-Morehead, Inc.
 - f. Tremco Incorporated.

2.4 PREFORMED JOINT SEALANTS

- A. Preformed Foam Joint Sealant: Manufacturer's standard preformed, precompressed, open-cell foam sealant manufactured from urethane foam with minimum density of 10 lb/cu. ft. (160 kg/cu. m) and impregnated with a nondrying, water-repellent agent. Factory produce in precompressed sizes in roll or stick form to fit joint widths indicated; coated on one side with a pressure-sensitive adhesive and covered with protective wrapping.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Dayton Superior Specialty Chemicals.
 - b. EMSEAL Joint Systems, Ltd.
 - c. Sandell Manufacturing Co.
 - d. Schul International, Inc.
 - e. Willseal USA, LLC.

2.5 JOINT SEALANT BACKING

- A. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), or any type approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- B. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer.

2.6 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions.
 - 1. Remove laitance and form-release agents from concrete.
 - 2. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.2 INSTALLATION

- A. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- B. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 - 1. Do not leave gaps between ends of sealant backings.
 - 2. Do not stretch, twist, puncture, or tear sealant backings.
 - 3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- C. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
 - 1. Place sealants so they directly contact and fully wet joint substrates.
 - 2. Completely fill recesses in each joint configuration.
 - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- E. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 - 1. Remove excess sealant from surfaces adjacent to joints.
 - 2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
 - 3. Provide concave joint profile per Figure 8A in ASTM C 1193, unless otherwise indicated.
- F. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.3 FIELD QUALITY CONTROL

- A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:
 - 1. Extent of Testing: Test completed and cured sealant joints as follows:
 - a. Perform 10 tests for the first 1000 feet (300 m) of joint length for each kind of sealant and joint substrate.
 - b. Perform 1 test for each 1000 feet (300 m) of joint length thereafter or 1 test per each floor per elevation.
 - 2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
- B. Evaluation of Field-Adhesion Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.4 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces.
 - 1. Joint Locations:
 - a. Construction joints in cast-in-place concrete.
 - b. Control and expansion joints in unit masonry.
 - c. Joints in exterior insulation and finish systems.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- d. Joints between different materials listed above.
 - e. Perimeter joints between materials listed above and frames of doors, windows and louvers.
 - f. Control and expansion joints in ceilings and other overhead surfaces.
 - g. Other joints as indicated.
 - 2. Joint Sealant: Silicone.
 - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- B. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces.
- 1. Joint Locations:
 - a. Control and expansion joints on exposed interior surfaces of exterior walls.
 - b. Perimeter joints of exterior openings where indicated.
 - c. Tile control and expansion joints.
 - d. Vertical joints on exposed surfaces of interior unit masonry
 - e. Perimeter joints between interior wall surfaces and frames of interior doors and windows.
 - 2. Joint Sealant: Latex.
 - 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors

END OF SECTION 07 92 00

SECTION 08 11 13 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Standard hollow metal doors and frames.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Include elevations, door edge details, frame profiles, metal thicknesses, preparations for hardware, and other details.
- C. Schedule: Prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings.

1.3 QUALITY ASSURANCE

- A. Fire-Rated Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252.
 - 1. Temperature-Rise Limit: At vertical exit enclosures and exit passageways, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F (250 deg C) above ambient after 30 minutes of standard fire-test exposure.
- B. Fire-Rated, Borrowed-Light Frame Assemblies: Assemblies complying with NFPA 80 that are listed and labeled, by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated, based on testing according to NFPA 257 or UL 9. Label each individual glazed lite.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ceco Door Products; an Assa Abloy Group company.
 - 2. Curries Company; an Assa Abloy Group company.
 - 3. Steelcraft; an Ingersoll-Rand company.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.2 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, CS, Type B; suitable for exposed applications.
- B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, CS, Type B.
- C. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with minimum A40 (ZF120) metallic coating.
- D. Frame Anchors: ASTM A 591/A 591M, Commercial Steel (CS), 40Z (12G) coating designation; mill phosphatized.
 - 1. For anchors built into exterior walls, steel sheet complying with ASTM A 1008/A 1008M or ASTM A 1011/A 1011M, hot-dip galvanized according to ASTM A 153/A 153M, Class B.
- E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.
- F. Grout: ASTM C 476, except with a maximum slump of 4 inches (102 mm), as measured according to ASTM C 143/C 143M.
- G. Mineral-Fiber Insulation: ASTM C 665, Type I.
- H. Glazing: Division 8 Section "Glazing."
- I. Bituminous Coating: Cold-applied asphalt mastic, SSPC-Paint 12, compounded for 15-mil (0.4-mm) dry film thickness per coat.

2.3 STANDARD HOLLOW METAL DOORS

- A. General: Comply with ANSI/SDI A250.8.
 - 1. Design: Flush panel
 - 2. Core Construction: Manufacturer's standard kraft-paper honeycomb, polystyrene, polyurethane, polyisocyanurate, mineral-board, or vertical steel-stiffener core.
 - a. Fire Door Core: As required to provide fire-protection and temperature-rise ratings indicated.
 - 3. Vertical Edges for Single-Acting Doors: Beveled edge, 1/8 inch in 2 inches (3 mm in 50 mm).
 - 4. Top and Bottom Edges: Closed with flush or inverted 0.042-inch- (1.0-mm-) thick, end closures or channels of same material as face sheets.
 - 5. Tolerances: SDI 117, "Manufacturing Tolerances for Standard Steel Doors and Frames."
- B. Interior Doors: Face sheets fabricated from cold-rolled steel sheet. Provide doors complying with requirements indicated below by referencing ANSI/SDI A250.8 for level and model and ANSI/SDI A250.4 for physical performance level:
 - 1. Level 1 and Physical Performance Level C (Standard Duty).
 - a. Width: 1-3/4 inches (44.5 mm)

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Hardware Reinforcement: ANSI/SDI A250.6.

2.4 STANDARD HOLLOW METAL FRAMES

- A. General: Comply with ANSI/SDI A250.8.
- B. Interior Frames: Fabricated from cold-rolled steel sheet.
 - 1. Fabricate frames with mitered or coped corners.
 - 2. Fabricate frames as full profile welded unless otherwise indicated.
 - 3. Frames for Level 1 Steel Doors: 0.042-inch- (1.0-mm-) thick steel sheet.
 - 4. Frames for Wood Doors: 0.042-inch- (1.0-mm-) thick steel sheet.
- C. Hardware Reinforcement: ANSI/SDI A250.6.

2.5 FRAME ANCHORS

- A. Jamb Anchors:
 - 1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, not less than 0.042 inch (1.0 mm) thick, with corrugated or perforated straps not less than 2 inches (50 mm) wide by 10 inches (250 mm) long; or wire anchors not less than 0.177 inch (4.5 mm) thick.
 - 2. Postinstalled Expansion Type for In-Place Concrete or Masonry: Minimum 3/8-inch- (9.5-mm-) diameter bolts with expansion shields or inserts. Provide pipe spacer from frame to wall, with throat reinforcement plate, welded to frame at each anchor location.
- B. Floor Anchors: Formed from same material as frames, not less than 0.042 inch (1.0 mm) thick, and as follows:
 - 1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.

2.6 STOPS AND MOLDINGS

- A. Moldings for Glazed Lites in Doors: Minimum 0.032 inch (0.8 mm) thick, same material as door face sheet.
- B. Fixed Frame Moldings: Formed integral with hollow metal frames, a minimum of 5/8 inch (16 mm) high unless otherwise indicated.
- C. Loose Stops for Glazed Lites in Frames: Minimum 0.032 inch (0.8 mm) thick, same material as frames.
- D. Terminated Stops: Where indicated, terminate stops 6 inches (152 mm) above finish floor with a 45-degree angle cut, and close open end of stop with steel sheet closure. Cover opening in extension of frame with welded-steel filler plate, with welds ground smooth and flush with frame.

2.7 LOUVERS

- A. Provide sightproof heavy-duty aluminum louvers for interior doors, where indicated.

2.8 ACCESSORIES

- A. Mullions and Transom Bars: Join to adjacent members by welding or rigid mechanical anchors.
- B. Ceiling Struts: Minimum 1/4-inch-thick by 1-inch- (6.4-mm-thick by 25.4-mm-) wide steel.
- C. Grout Guards: Formed from same material as frames, not less than 0.016 inch (0.4 mm) thick.

2.9 FABRICATION

- A. Tolerances: Fabricate hollow metal work to tolerances indicated in SDI 117.
- B. Hollow Metal Doors:
 - 1. Exterior Doors: Provide weep-hole openings in bottom of exterior doors. Seal joints in top edges of doors against water penetration.
 - 2. Glazed Lites: Factory cut openings in doors.
 - 3. Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated.
- C. Hollow Metal Frames: Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
 - 1. Welded Frames: Weld flush face joints continuously; grind, fill, dress, and make smooth, flush, and invisible.
 - 2. Sidelight and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
 - 3. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 - 4. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
 - 5. Floor Anchors: Weld anchors to bottom of jambs and mullions with at least four spot welds per anchor.
 - 6. Jamb Anchors: Provide number and spacing of anchors as follows:
 - a. Masonry Type: Locate anchors not more than 18 inches (457 mm) from top and bottom of frame. Space anchors not more than 32 inches (813 mm) o.c. and as follows:
 - 1) Two anchors per jamb up to 60 inches (1524 mm) high.
 - 2) Three anchors per jamb from 60 to 90 inches (1524 to 2286 mm) high.
 - 3) Four anchors per jamb from 90 to 120 inches (2286 to 3048 mm) high.
 - 4) Four anchors per jamb plus 1 additional anchor per jamb for each 24 inches (610 mm) or fraction thereof above 120 inches (3048 mm) high.
 - b. Compression Type: Not less than two anchors in each jamb.
 - c. Postinstalled Expansion Type: Locate anchors not more than 6 inches (152 mm) from top and bottom of frame. Space anchors not more than 26 inches (660 mm) o.c.
 - 7. Door Silencers: Except on weather-stripped doors, drill stops to receive door silencers.
 - a. Single-Door Frames: Three door silencers.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- b. Double-Door Frames: Two door silencers.
- D. Hardware Preparation: Factory prepare hollow metal work to receive templated mortised hardware according to the Door Hardware Schedule and templates furnished as specified in Division 8 Section "Door Hardware."
 - 1. Locate hardware as indicated, or if not indicated, according to ANSI/SDI A250.8.
 - 2. Reinforce doors and frames to receive nontemplated, mortised and surface-mounted door hardware.
 - 3. Comply with applicable requirements in ANSI/SDI A250.6 and ANSI/DHI A115 Series specifications for preparation of hollow metal work for hardware.
 - 4. Coordinate locations of conduit and wiring boxes for electrical connections with Division 16 electrical Sections.
- E. Stops and Moldings: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with butted or mitered hairline joints.
 - 1. Single Glazed Lites: Provide fixed stops and moldings welded on secure side of hollow metal work.
 - 2. Multiple Glazed Lites: Provide fixed and removable stops and moldings so that each glazed lite is capable of being removed independently.
 - 3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames.
 - 4. Provide loose stops and moldings on inside of hollow metal work.
 - 5. Coordinate rabbet width between fixed and removable stops with type of glazing and type of installation indicated.

2.10 STEEL FINISHES

- A. Prime Finish: Apply manufacturer's standard primer immediately after cleaning and pretreating.
 - 1. Shop Primer: ANSI/SDI A250.10.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Hollow Metal Frames: Comply with ANSI/SDI A250.11.
 - 1. Set frames accurately in position, plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.
 - a. At fire-protection-rated openings, install frames according to NFPA 80.
 - b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
 - c. Install frames with removable glazing stops located on secure side of opening.
 - d. Install door silencers in frames before grouting.
 - e. Remove temporary braces necessary for installation only after frames have been properly set and secured.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- f. Check plumbness, squareness, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
 - g. Field apply bituminous coating to backs of frames that are filled with grout containing antifreezing agents.
 - 2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.
 - a. Floor anchors may be set with powder-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
 - 3. Masonry Walls: Coordinate installation of frames to allow for solidly filling space between frames and masonry with grout.
 - 4. Concrete Walls: Solidly fill space between frames and concrete with grout. Take precautions, including bracing frames, to ensure that frames are not deformed or damaged by grout forces.
 - 5. In-Place Concrete or Masonry Construction: Secure frames in place with postinstalled expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.
 - 6. Ceiling Struts: Extend struts vertically from top of frame at each jamb to overhead structural supports or substrates above frame unless frame is anchored to masonry or to other structural support at each jamb. Bend top of struts to provide flush contact for securing to supporting construction. Provide adjustable wedged or bolted anchorage to frame jamb members.
 - 7. Installation Tolerances: Adjust hollow metal door frames for squareness, alignment, twist, and plumb to the following tolerances:
 - a. Squareness: Plus or minus 1/16 inch (1.6 mm), measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
 - b. Alignment: Plus or minus 1/16 inch (1.6 mm), measured at jambs on a horizontal line parallel to plane of wall.
 - c. Twist: Plus or minus 1/16 inch (1.6 mm), measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - d. Plumbness: Plus or minus 1/16 inch (1.6 mm), measured at jambs at floor.
- B. Hollow Metal Doors: Fit hollow metal doors accurately in frames, within clearances specified below. Shim as necessary.
 - 1. Non-Fire-Rated Standard Steel Doors:
 - a. Jambs and Head: 1/8 inch (3 mm) plus or minus 1/16 inch (1.6 mm).
 - b. Between Edges of Pairs of Doors: 1/8 inch (3 mm) plus or minus 1/16 inch (1.6 mm).
 - c. Between Bottom of Door and Top of Threshold: Maximum 3/8 inch (9.5 mm).
 - d. Between Bottom of Door and Top of Finish Floor (No Threshold): Maximum 3/4 inch (19 mm).
 - 2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.
- C. Glazing: Comply with installation requirements in Division 8 Section "Glazing" and with hollow metal manufacturer's written instructions.
 - 1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches (230 mm) o.c. and not more than 2 inches (50 mm) o.c. from each corner.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.2 ADJUSTING AND CLEANING

- A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow metal work that is warped, bowed, or otherwise unacceptable.
- B. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

END OF SECTION 08 11 13

SECTION 08 14 16 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Solid-core doors with wood-veneer faces.
 - 2. Factory fitting flush wood doors to frames and factory machining for hardware.
- B. Related Sections include the following:
 - 1. Division 8 "Hollow Metal Doors and Frames"
 - 2. Division 8 Section "Glazing" for glass view panels in flush wood doors.
 - 3. Division 8 "Finish Hardware"

1.3 SUBMITTALS

- A. Product Data: For each type of door. Include details of core and edge construction and trim for openings.
- B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data; location and extent of hardware blocking; and other pertinent data.
 - 1. Indicate dimensions and locations of mortises and holes for hardware.
 - 2. Indicate dimensions and locations of cutouts.
 - 3. Indicate doors to be factory finished and finish requirements.
 - 4. Indicate fire ratings for fire doors.
- C. Samples for Initial Selection: Color charts consisting of actual materials in small sections for the following:
 - 1. Faces of Factory-Finished Doors: Show the full range of colors available for stained finishes.
- D. Samples for Verification:
 - 1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches (200 by 250 mm), for each material and finish. For each wood species and transparent finish, provide set of three samples showing typical range of color and grain to be expected in the finished work.

1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain flush wood doors through one source from a single manufacturer.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Quality Standard: Comply with AWI's "Architectural Woodwork Quality Standards Illustrated."
- C. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to NFPA 252.
 - 1. Test Pressure: After 5 minutes into the test, the neutral pressure level in furnace shall be established at 40 inches (1000 mm) or less above the sill.
 - 2. Temperature-Rise Rating: At exit enclosures, provide doors that have a temperature-rise rating of 450 deg F (250 deg C) maximum in 30 minutes of fire exposure.
- D. Accompany Owner's maintenance personnel for inspection of work at completion of project.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Package doors individually in plastic bags or cardboard cartons.
- C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install doors until building is enclosed, wet work is complete, and HVAC system is operating and will maintain temperature and relative humidity at occupancy levels during the remainder of the construction period.

1.7 WARRANTY

- A. Special Warranty: Manufacturer's standard form, signed by manufacturer, Installer, and Contractor, in which manufacturer agrees to repair or replace doors that are defective in materials or workmanship, have warped (bow, cup, or twist) more than 1/4 inch (6.4 mm) in a 42-by-84-inch (1067-by-2134-mm) section, or show telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch (0.25 mm in a 75-mm) span.
 - 1. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
 - 2. Warranty shall be in effect during the following period of time from date of Substantial Completion:
 - a. Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flush Wood Doors:
 - a. Algoma Hardwoods Inc.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- b. Eggers Industries; Architectural Door Division.
- c. Lambton Inc.

2.2 DOOR CONSTRUCTION, GENERAL

- A. Adhesives: Do not use adhesives containing urea formaldehyde.
- B. Doors for Transparent Finish:
 - 1. Grade: Premium, with Grade A faces
 - 2. Species and Cut: White birch, rotary cut.
 - 3. Match between Veneer Leaves: Pleasing match.
 - 4. Assembly of Veneer Leaves on Door Faces: Center balance match.
 - 5. Pair and Set Match: Provide for doors hung in same opening or separated only by mullions.

2.3 SOLID-CORE DOORS

- A. Interior Veneer-Faced Doors:
 - 1. Core: Laminated strand lumber.
 - 2. Construction: Five plies with stiles and rails bonded to core, then entire unit abrasive planed before veneering.
- B. Fire-Rated Doors:
 - 1. Construction: Construction and core specified above for type of face indicated or manufacturer's standard mineral-core construction as needed to provide fire rating indicated.
 - 2. Blocking: For mineral-core (if required for fire rating) doors, provide composite blocking with improved screw-holding capability approved for use in doors of fire ratings indicated:
 - a. 5-inch (125-mm) top-rail blocking.
 - b. 5-inch (125-mm) bottom-rail blocking, in doors indicated to have protection plates.
 - c. 5-inch (125-mm) midrail blocking, in doors indicated to have armor plates.
 - d. 4-1/2-by-10-inch (114-by-250-mm) lock blocks in doors indicated to have exit devices.
 - 3. Edge Construction: Provide edge construction with intumescent seals concealed by outer stile matching face veneer, and laminated backing at hinge stiles for improved screw-holding capability and split resistance.
 - 4. Pairs: Furnish formed-steel edges and astragals with intumescent seals for pairs of fire-rated doors, unless otherwise indicated.
 - a. Finish steel edges and astragals to match door hardware (locksets or exit devices).

2.4 LIGHT FRAMES

- A. Wood Beads for Light Openings in Wood Doors:
 - 1. Wood Species: Species compatible with door faces
 - 2. Profile: Manufacturer's standard shape.
 - 3. At 20-minute, fire-rated, wood-core doors, provide wood beads and metal glazing clips approved for such use.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Metal Frames for Light Openings in Fire Doors: Manufacturer's standard frame formed of 0.0478-inch- (1.2-mm-) thick, cold-rolled steel sheet; factory primed and approved for use in doors of fire rating indicated.

2.5 LOUVERS

- A. Provide sightproof heavy-duty aluminum louvers for interior doors, where indicated.

2.6 FABRICATION

- A. Fabricate doors in sizes indicated for Project-site fitting.
- B. Factory fit doors to suit frame-opening sizes indicated, with the following uniform clearances and bevels, unless otherwise indicated:
 - 1. Comply with clearance requirements of referenced quality standard for fitting. Comply with requirements in NFPA 80 for fire-rated doors.
- C. Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, DHI A115-W series standards, and hardware templates.
 - 1. Coordinate measurements of hardware mortises in metal frames to verify dimensions and alignment before factory machining.
 - 2. Metal Astragals: Premachine astragals and formed-steel edges for hardware for pairs of fire-rated doors.
- D. Openings: Cut and trim openings through doors to comply with applicable requirements of referenced standards for kind(s) of door(s) required.
 - 1. Light Openings: Trim openings with moldings of material and profile indicated.

2.7 FACTORY FINISHING

- A. General: Comply with AWI's "Architectural Woodwork Quality Standards Illustrated" for factory finishing.
- B. Finish doors at factory.
- C. Finish doors at factory that are indicated to receive transparent finish.
- D. Transparent Finish:
 - 1. Grade: Premium
 - 2. Finish: Manufacturer's standard finish with performance comparable to AWI System TR-4 conversion varnish
 - 3. Staining: As selected by Architect from manufacturer's full range.
 - 4. Effect: Filled finish.
 - 5. Sheen: Satin

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine doors and installed door frames before hanging doors.
 - 1. Verify that frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
 - 2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Hardware: For installation, see Division 8 "Door Hardware."
- B. Manufacturer's Written Instructions: Install doors to comply with manufacturer's written instructions, referenced quality standard, and as indicated.
 - 1. Install fire-rated doors in corresponding fire-rated frames according to NFPA 80.
- C. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or do not comply with requirements. Doors may be repaired or refinished if work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 08 14 16

SECTION 08 22 10 – FIBERGLASS REINFORCED POLYESTER DOORS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and General provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work specified in this section.

1.02 DESCRIPTION OF WORK

- A. The fiberglass doors and aluminum frames required for this work are indicated on the drawings and include, but is not necessarily limited to:
 - 1. Aluminum frames
 - 2. FRP Flush Doors
 - 3. FRP Panel
 - 4. The installation of opening systems that include aluminum frames, fiberglass doors, fiberglass panels and door hardware.

1.03 RELATED WORK SPECIFIED ELSEWHERE

- A. For Finish Hardware see Division 8.
- B. For Glazing see Division 8.

1.04 QUALITY ASSURANCE

- A. Standards: Comply with the requirements and recommendations in applicable specification and standards by AAMA, except to the extent where more stringent requirements are indicated here in.
- B. Performance: A minimum ten year record of production manufacturing of frames, doors and panels and completion of similar type and size projects is required.
- C. Instruction: The manufacturer or his representative will be available for consultation to all parties engaged in the project including instruction to installation personnel.
- D. Field Measurement: The supplier shall field verify all information prior to fabrication and furnishing of materials. Omitted details due to lack of verification shall be furnished at no additional cost to Owner.
- E. Accompany Owner's maintenance personnel for inspection of work at completion of project.
- F. Regulation and Codes: Comply with the current edition in force at the project location of all local, state, and federal codes and regulations, including the Americans with Disabilities Act of 1992.

1.05 SUBMITTALS

- A. Product Data: Submit manufacturer's product data, specifications and instructions for each type of door and frame required in accordance with Section 01340 and the following:
 - 1. Include details of core stile and rail construction, trim for lites and all other components.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Include details of finish hardware mounting.
 3. Include samples of each aluminum alloy to be used on this project. Where normal finish color and texture variations are expected, include two or more samples to show the range of such variations.
 4. Include one sample of typical fabricated section, showing joints, fastenings, quality of workmanship, hardware and accessory items before fabrication of the work proceeds.
- B. Submit shop drawings for the fabrication and installation of the doors and frames, and associated components. Details to be shown full scale. Include glazing details and finish hardware schedule.

1.06 PRODUCT DELIVERY, STORAGE AND HANDLING

- A. Deliver materials to job site in their original, unopened packages with labels intact. Each door and frame will be tagged with a mark or number, which correlates with designation system used for shop drawings. Inspect materials for damage and advise manufacturer immediately of any unsatisfactory materials.
- B. Package door assemblies in individual corrugated cartons so no portion of the door has contact with the outer shell of the container. Package and ship frames pre assembled to the greatest possible extent.
- C. Store material in a secure, weatherproof space.
- D. Handle doors and frames with care. Do not walk or place other material on top of stacked doors. Contractor shall use all means necessary to protect doors from damage prior to, during, and after installation. All damaged doors shall be repaired or replaced by the contractor at no cost to the owner.

1.07 PROJECT WARRANTY

- A. Provide a written warranty signed by manufacturer agreeing to replace at no cost to the Owner, any doors, frames, hardware, or factory hardware installation which fail in materials or workmanship, within the warranty period. Failure of materials or workmanship includes: excessive deflection; faulty operation of entrances; deterioration of finish, or construction, in excess of normal weathering; and defects in hardware installation.
1. FRP doors will carry a 25 year limited warranty on doors structural integrity, mainframe, and the lamination between face sheets and core.
 2. System manufacture will guarantee THE ENTIRE SYSTEM for a period of 10 years.

PART 2 - PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

- A. Manufacturer: Subject to compliance with requirements, provide products manufactured by:
1. Commercial Door Systems (CDS) – Philadelphia, PA – 215-244-9080
www.commercialdoorsystems.com
 2. Special-Lite, Inc., Decatur, MI 49045 (800)821-6531. Model SL-17.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3. or other manufacturers meeting these specifications and approved in writing by Owner prior to bid date.

2.02 MATERIALS AND ACCESSORIES

- A. Aluminum Members: Alloy and temper as recommended by manufacturer for strength, corrosion resistance, and application of required finish and control of color; ASTM B 221 for extrusions, ASTM B209 for sheet/plate with a minimum wall thickness of 0.125".
- B. Components: Furnish door and frame components from the same manufacturer. The use of a different manufacturer of door and frame components is not permitted.
- C. Fasteners: Provide Aluminum, non-magnetic stainless steel or other non-corrosive metal fasteners, guaranteed by the manufacturer to be compatible with the doors, frames, stops, panels, hardware, anchors and other items being fastened. For exposed fasteners (if any) provide Oval Phillips Head screws with finish matching the item to be fastened. The use of sex bolts or thru bolts will not be accepted.
- D. Glazing Gaskets: For glazing factory-installed glass, and for gaskets which are factory-installed in "captive" assembly of glazing stops, manufacturer's standard stripping of molded neoprene, complying with ASTM D 2000 (designation 2BC415 to 3BC620), or molded PVC complying with ASTM C 509 Grade 4.

2.03 FABRICATION

- A. Sizes and Profiles: The required sizes for door and frame units, and profiles requirements are shown on the drawings.
- B. Coordination of fabrication: Field measure before fabrication, and show recorded measurements on final shop drawings.
- C. Complete the cutting, fitting, forming, drilling and grinding of all metal work prior to assembly. Remove burrs from cut edges, and ease edges and corners to a radius of approximately 1/64".
- D. No welding of joinery of doors or frames will be provided except with owner request.
- E. Maintain continuity of line and accurate relation of planes and angles. Secure attachments and support at mechanical joints, with hairline fit at contacting members.

2.04 FIBERGLASS REINFORCED POLYESTER FRP FLUSH DOORS – F500HD

- A. Materials and Construction
 1. Construct 1-3/4 thick doors of 6063-T6 aluminum alloy with minimum stiles of 5-1/2" tube, top rails minimum of 6" and bottom rails minimum of 10". Provide joinery 3/8" diameter full width tie rods through extruded splines top and bottom as standard .125" tubular shaped stiles and rails reinforced to accept hardware as specified. Provide hex type aircraft nuts for joiner without welds, glues or other methods for securing internal door extrusions. Furnish reglets to accept face sheet to permit a flush appearance.

Main Frame Stile Wall Thickness:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- a. Side Stiles Minimum 3/16" thick hinge edge wall.
 - b. Bottom Rail Minimum 1/8" thick face walls.
 - c. Top Rail Minimum 1/8" thick all walls.
2. Door face sheeting .120" thickness fiberglass reinforced polyester. Provide Model F500HD doors with an abuse resistant engineered surface of the manufacturer's expanded line of colors.
3. Core of door assembly will be minimum 25 pound psi density polystyrene with a flame spread rating of no more than 25. Meeting stiles on pairs of doors top and bottom weather bar with FIN-SEAL wool pile brush weather stripping.
4. Manufacture doors with cutouts for vision lites, louvers, or panels as scheduled. Factory to furnish and install all glass, louvers and panels prior to shipment. All trim pieces shall match face panel color.
5. Pre-machine doors in accordance with templates from the specified hardware manufacturers and approved hardware schedule. Factory install hardware except door closers.
6. See glazing specification for glass requirements.

2.05 ARCHITECTURAL PANELS

A. FRP Panels

1. Model: P25 one quarter inch, P75 one inch or thickness as shown.
2. FRP face sheets with finish color throughout. Color to be selected by Architect.
3. FRP Option Construct insulated panels of two .120" minimum thickness sheets with core of minimum 2 ½ pound psi density polystyrene.
4. Class A option for flame spread and smoke developed rating on interior faces of exterior panels and both faces of interior panels as shown. Flame spread no greater than 25, smoke developed no greater than 450 per ASTM E-84.

2.06 ALUMINUM FRAMING SYSTEMS

A. Tubular Framing

1. Framing system shall be by the door manufacturer and of the size and type shown. Framing shall be type 6063-T6 aluminum alloy with minimum wall thickness of .125" and .625" high applied door stops with screws and weather-stripping. Frame members are to be box type with four (4) enclosed sides. Open back framing will not be acceptable.
2. Caulk joints before assembling from members. Secure joint with fasteners and provide a hairline butt joint appearance. Prefit doors using "stick" materials are not acceptable.
3. Applied stops for side, transom and borrowed lites and panels, with fasteners exposed on interior or unsecured portion only. Pre-machine and reinforced frame members for hardware in accordance with manufacturer's standards and the approved hardware schedule. Factory install hardware except closers.
4. Anchors appropriate for wall conditions to anchor framing to wall materials. A minimum of five anchors up to 7'4" on jamb members and one additional anchor for each foot over 7'4". Secure head and still members of transom, sidelites and similar conditions.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

5. Factory pre-assemble sidelite to the greatest extent possible, and mark frame assemblies according to location.
6. Provide framing in a knock-down condition and attached to door assembly. Mark frames members according to location.
7. See glazing specification for glass requirements.

2.07 GLAZING

- A. Design system for replacement of glass
 1. Manufacturer's standard flush glazing system of recessed channels and captive glazing gaskets or applied stops as shown.
 2. Allow for thermal expansion on exterior units.
 3. Glass as shown and factory glazed into doors

2.08 ALUMINUM FINISHES

- A. Special painted finish required.

PART 3 - EXECUTION

3.01 INSTALLATION

- A. Comply with manufacturer's recommendations and specifications for the installation of the doors and frames. Factory install hardware, glass and louvers in doors. Factory assemble side-lites and transoms to the greatest extent possible.
- B. Set units plumb, level and true to line, without harp or rack of doors or frames. Anchor securely in place. Separate aluminum and other metal surfaces with bituminous coatings or other means as approved by architect.
- C. Set thresholds in a bed of mastic and backseal.
- D. Clean surfaces promptly after installation doors and frames, exercising care to avoid damage to the protective coating.
- E. Ensure that the doors and frames will be without damage or deterioration (other than normal weathering) at the time of acceptance.
- F. Provide Owner with all adjustment tools and instruction sheets. Arrange an inservice session to Owner at Owner's convenience. Provide a minimum one-year written warranty on all labor related to this section. Any workmanship which is defective or deficient shall be corrected to the Owner's satisfaction and at no additional cost to the Owner.

END OF SECTION 08 22 10

SECTION 08 31 13 - ACCESS DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Access doors and frames for walls and ceilings.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
- C. Samples: For each door face material.
- D. Schedule: Types, locations, sizes, latching or locking provisions, and other data pertinent to installation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Rated Access Doors and Frames: Units complying with NFPA 80 tested according to the following test method:
 - 1. NFPA 252 or UL 10B for fire-rated access door assemblies installed vertically.
 - 2. NFPA 288 for fire-rated access door assemblies installed horizontally.

2.2 ACCESS DOORS AND FRAMES FOR WALLS AND CEILINGS

- A. Basis-of-Design Product: Subject to compliance with requirements, provide product indicated or comparable product by one of the following, or submit other product for approval:
 - 1. Access Panel Solutions.
 - 2. Babcock-Davis.
 - 3. Larsen's Manufacturing Company.
- B. Source Limitations: Obtain each type of access door and frame from single source from single manufacturer.
- C. Flush Access Doors with Exposed Flanges
 - 1. Assembly Description: Fabricate door to fit flush to frame. Provide manufacturer's standard-width exposed flange, proportional to door size.
 - 2. Locations: Wall and ceiling.
 - 3. Uncoated Steel Sheet for Door: Nominal 0.060 inch (1.52 mm), 16 gage.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

a. Finish: Factory finish.

4. Frame Material: Same material, thickness, and finish as door.
5. Hinges: Manufacturer's standard.
6. Hardware: Lock.
7. Provide fire-rated access doors where applicable.

2.3 MATERIALS

- A. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
- B. Rolled-Steel Floor Plate: ASTM A 786/A 786M, rolled from plate complying with ASTM A 36/A 36M or ASTM A 283/A 283M, Grade C or D.
- C. Steel Sheet: Uncoated or electrolytic zinc coated, ASTM A 879/A 879M, with cold-rolled steel sheet substrate complying with ASTM A 1008/A 1008M, Commercial Steel (CS), exposed.
- D. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with minimum G60 (Z180) or A60 (ZF180) metallic coating.
- E. Frame Anchors: Same type as door face.
- F. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel according to ASTM A 153/A 153M or ASTM F 2329.

2.4 FABRICATION

- A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.
- B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.
- C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish attachment devices and fasteners of type required to secure access doors to types of supports indicated.
- D. Latching Mechanisms: Furnish number required to hold doors in flush, smooth plane when closed.
 1. For cylinder locks, furnish two keys per lock and key all locks alike.

2.5 FINISHES

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- D. Steel and Metallic-Coated-Steel Finishes:
 - 1. Factory Prime: Apply manufacturer's standard, fast-curing, lead- and chromate-free, universal primer immediately after surface preparation and pretreatment.
 - 2. Factory Finish: Immediately after cleaning and pretreating, apply manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat, with a minimum dry-film thickness of 1 mil (0.025 mm) for topcoat.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with manufacturer's written instructions for installing access doors and frames.
- B. Install doors flush with adjacent finish surfaces or recessed to receive finish material.

3.2 ADJUSTING

- A. Adjust doors and hardware, after installation, for proper operation.
- B. Remove and replace doors and frames that are warped, bowed, or otherwise damaged.

END OF SECTION 08 31 13

SECTION 08 36 13 SECTIONAL OVERHEAD DOORS

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Aluminum Sectional Overhead Doors.
- B. Operating Hardware, tracks, and support.

1.2 RELATED SECTIONS

- A. Section 03300 - Cast-In-Place Concrete: Prepared opening in concrete. Execution requirements for placement of anchors in concrete wall construction.
- B. Section 04810 - Unit Masonry Assemblies: Prepared opening in masonry. Execution requirements for placement of anchors in masonry wall construction.
- C. Section 05500 - Metal Fabrications: Steel frame and supports.
- D. Section 06114 - Wood Blocking and Curbing: Rough wood framing and blocking for door opening.
- E. Section 07900 - Joint Sealers: Perimeter sealant and backup materials.
- F. Section 08710 - Door Hardware: Cylinder locks.
- G. Section 09900 - Paints and Coatings: Field painting.

1.3 REFERENCES

- A. ANSI/DASMA 102 - American National Standard Specifications for Sectional Overhead Type Doors.

1.4 DESIGN / PERFORMANCE REQUIREMENTS

- A. Wind Loads: Design and size components to withstand loads caused by pressure and suction of wind acting normal to plane of wall as calculated in accordance with applicable code.
 - 1. See structural plans for design pressure.

1.5 SUBMITTALS

- A. Submit under provisions of Section 01300.
- B. Shop Drawings: Indicate plans and elevations including opening dimensions and required tolerances, connection details, anchorage spacing, hardware locations, and installation details.
- C. Manufacturer's Certificates: Certify products meet or exceed specified requirements.
- D. Operation and Maintenance Data.

1.6 QUALITY ASSURANCE

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section with minimum (20) years documented experience.
- B. Installer Qualifications: Authorized representative of the manufacturer with minimum (10) years approved by manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store products in manufacturer's unopened labeled packaging until ready for installation.
- B. Protect materials from exposure to moisture until ready for installation.
- C. Store materials in a dry, ventilated weathertight location.

1.8 WARRANTY

- A. 20-year welded aluminum frame warranty. Standard one year warranty applies to the rest of the door: track, spring, hardware.
- A. Finish Warranty:
 - 1. 20-year warranty finish for clear anodized, dark bronze anodized, or black anodized finish, except on installations within 1 mile of salt water.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: For purposes of designating type and quality of work under this Section, Drawings and Specifications are based on products manufactured or Furnished by ARM-R-LITE DOOR MANUFACTURING CO. Toll Free: 800-554-5816 P:908-754-2600 ext 4016 Shannon McGrady F: 908-754-6522 email: smcgrady@arm-r-lite.com W: www.arm-r-lite.com.
- B. Requests for substitutions will be considered in accordance with provisions of Division 1.

2.2 ALUMINUM SECTIONAL OVERHEAD DOORS

- A. Sectional Overhead Doors: TITAN™ MODEL by Arm-R-Lite Door Manufacturing Co., Inc. Units shall have the following characteristics:
 - 1. Door Assembly: Stile and rail assembly secured with concealed heli-arch welds. Through rods, bolts, and self-tapping screw construction methods will not be accepted
 - a. Panel Thickness: 1-3/4 inches
 - b. Aluminum Panels
 - 1) .5 inch insulated aluminum panels
 - c. Stiles and Rails to be constructed of 4-sided .075 - .085 extruded 6063 - T6 aluminum alloy.
 - 1) Energy Efficiency Package: Polyurethane expanding foam filled insulated rails and stiles with water resistant feature. Not water proof.
 - d. Springs:
 - 1) 30,000 cycles
 - 2. Finish and Color:
 - a. Anodized Finish: dark bronze anodized
 - 3. Windload Design: Provide to meet the Design/Performance requirements specified.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

4. Hardware: All hinges and fixtures made of 14 gauge galvanized steel. Full floating, ball bearing rollers to have hardened steel races and roller sizes to be adequate for design requirements and limitations. Heavy-duty, fully adjustable roller brackets are attached to each end cap to provide an easy adjustment of the door to the job for proper seal. All hardware is heavy-duty and rust resistant with galvanized fasteners.
 - a. Powdercoat Corrosion Resistant Package: Powdercoated track and face hardware to provide added corrosion resistance to galvanized steel.
5. Lock: Interior galvanized single unit.
6. Weatherstripping:
 - a. Flexible bulb-type strip at bottom section.
 - b. Flexible Jamb seals.
 - c. Flexible Header seal.
7. Track: Provide track as recommended by manufacturer to suit loading required and clearances available.
 - a. High lift Track

PART 3 EXECUTION

3.1 EXAMINATION

- A. Verify that all openings are ready to receive work and opening dimensions and tolerances are within specified limits.
- B. Beginning of installation means acceptance of existing surfaces.

3.2 PREPARATION

- A. Prepare opening to permit correct installation of door unit.

3.3 INSTALLATION

- A. Install overhead doors and track in accordance with approved shop drawings and the manufacturer's printed instructions. Framing and opening preparation per submitted shops is the responsibility of the general contractor and not the sectional door installer.
- B. Coordinate installation with adjacent work to ensure proper clearances and allow for maintenance.
- C. Anchor assembly to wall construction and building framing without distortion or stress.
- D. Secure tracks to structural members only.
- E. Fit and align door assembly including hardware, level and plumb, to provide smooth operation.
- F. Install perimeter trim and closures

3.4 TOLERANCES

- A. Maintain dimensional tolerances and alignment with adjacent work
- B. Maximum variation from plumb: 1/8 inch
- C. Maximum variation from level: 1/8 inch
- D. Longitudinal or diagonal warp: plus or minus 1/8 inch from 10 ft. straight edge

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.5 CLEANING AND ADJUSTING

- A. Clean doors, frames and glass.

3.6 PROTECTION

- A. Do not permit construction traffic through overhead door openings after adjustment and cleaning.
- B. Protect installed products until completion of project.
- C. Touch-up, damaged coatings and finishes and repair minor damage before Substantial Completion.

END OF SECTION 08 36 13

SECTION 08 41 13 ALUMINUM-FRAMED ENTRANCES & STOREFRONTS

PART 1 GENERAL

Furnish all necessary materials, labor, and equipment for the complete installation of the aluminum storefront framing system as shown on the drawings and specified herein.

1.01 SUMMARY

- A. Section includes: Aluminum Storefront Systems
 - 1. YKK AP Series YHS 50 TU Impact Resistant Storefront System (Insulated Glazing)
- B. Related Sections:
 - 1. Glass: Contact YKK AP for approved glass types.
 - 2. Glazing: Dow Corning® 995 Structural Silicone Sealant.
 - 3. Single Source Requirement: All products listed below shall be by the same manufacturer.
 - a. Section 08 51 13 Aluminum Windows.
 - b. Section 08 44 13 Glazed Aluminum Curtain Walls.
 - c. Section 08 44 33 Sloped Glazing Assemblies.

1.02 SYSTEM DESCRIPTION

- A. Performance Requirements: Provide aluminum storefront systems that meet all requirements of South Florida Building Code Protocols TAS 201, TAS 202, and TAS 203 comply with the following specific performance requirements indicated.
 - 1. Air Infiltration: Completed storefront systems shall have 0.06 CFM/FT² (1.10 m³/h·m²) maximum allowable infiltration when tested in accordance with ASTM E 283 at differential static pressure of 6.24 psf (299 Pa).
 - 2. Water Infiltration: No uncontrolled water when tested in accordance with ASTM E 331 at test pressure differential of: 12 PSF (575 Pa) (or when required, field tested in accordance with AAMA 503). Fastener Heads must be seated and sealed against Sill Flashing on any fasteners that penetrate through the Sill Flashing.
 - 3. Wind Loads: Completed storefront system shall withstand wind pressure loads normal to wall plane indicated:
 - a. Exterior Walls:
 - 1) Positive Pressure: 70 psf.
 - 2) Negative Pressure: 70 psf.
 - 4. Deflection: Maximum allowable deflection in any member when tested in accordance with ASTM E 330 with allowable stress in accordance with AAMA Specifications for Aluminum Structures.
 - a. For spans less than 13'-6" (4.1m): L/175 or 3/4" (19.1mm) maximum.
 - b. For spans greater than 13'-6" (4.1m) but less than 40'-0" (12.2m): L/175 or L/240 + 1/4" (6.4mm).
 - 5. Thermal Movement: Provide for thermal movement caused by 180 degrees F. (82.2 degrees C.) surface temperature, without causing buckling stresses on glass, joint seal failure, undue stress on structural elements, damaging loads on fasteners, reduction of performance, or detrimental effects.
 - 6. Thermal Performance for YHS 50 TU shall be:
 - a. Condensation Resistance Factor (CRF): A minimum of 59 when tested in accordance with AAMA 1503.1.
 - b. Thermal Transmittance U-Factor: 0.45 BTU/HR/FT²/°F or less when tested in accordance with NFRC 102.
- Note: Thermal performance depends on glass specified. U-Factor shown for system when using a 1-5/16" insulating glass unit - 1/4" heat strengthened as required with 0.034 low emissivity coating on surface #2, 1/2" air space with aluminum spacer, 1/4" heat strengthened / 0.090 PVB interlayer / 1/4" heat strengthened. Size: 2000mm x 2000mm (78.7 inches x 78.7 inches).
- 7. Acoustical Performance: Acoustical Performance: When tested in accordance with ASTM E 1425:
 - a. Sound Transmission Class (STC) shall not be less than 39
 - b. Outdoor-Indoor Transmission Class (OITC) shall not be less than 33

1.03 SUBMITTALS

- A. General: Prepare, review, approve, and submit specified submittals in accordance with "Conditions of the Contract" and Division 1 Submittals Section. Product data, shop drawings, samples, and similar submittals are defined in "Conditions of the Contract".
- B. Product Data: Submit product data for each type storefront series specified.
- C. Substitutions: Whenever substitute products are to be considered, supporting technical data, samples and test reports must be submitted ten (10) working days prior to bid date in order to make a valid comparison.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Shop Drawings: Submit shop drawings showing layout, profiles, and product components, including anchorage, accessories, finish colors, and textures.
- E. Samples: Submit verification samples for colors on actual aluminum substrates indicating full color range expected in installed system.
- F. Quality Assurance / Control Submittals:
1. Test Reports: Submit certified test reports showing compliance with specified performance characteristics and physical properties.
 2. Installer Qualification Data: Submit installer qualification data.
- G. Close-out Submittals:
1. Warranty: Submit warranty documents specified herein.
 2. Project Record Documents: Submit project record documents for installed materials in accordance with Division 1
Project Close-out (Project Record Documents) Section.

1.04 QUALITY ASSURANCE

- A. Qualifications:
1. Installer Qualifications: Installer experienced (as determined by contractor) to perform work of this section who has specialized in the installation of work similar to that required for this project. If requested by Owner, submit reference list of completed projects.
 2. Manufacturer Qualifications: Manufacturer capable of providing field service representation during construction process.

1.05 PRODUCT CONDITIONS / SITE CONDITIONS

- A. Field Measurements: Verify actual measurements/openings by field measurements before fabrication; show recorded measurements on shop drawings. Coordinate field measurements, fabrication schedule with construction progress to avoid construction delays.

1.06 WARRANTY

- A. Project Warranty: Refer to "Conditions of the Contract" for project warranty provisions.
- B. Manufacturer's Warranty: Submit, for Owner's acceptance, manufacturer's standard warranty document executed by an authorized company official.
1. Warranty Period: Manufacturer's one (1) year standard warranty commencing on the substantial date of completion for the project provided that the warranty, in no event, shall start later than six (6) months from the date of shipment by YKK AP America Inc.

PART 2 PRODUCTS

It is the intent of this specification to have a single source responsibility for the supply of the aluminum doors and framing systems on this project. Any deviation from the acceptable manufacturers listed below must be approved in writing by the architect at least ten (10) days prior to bid date.

2.01 MANUFACTURERS (Acceptable Manufacturers/Products)

- A. Acceptable Manufacturers:
- YKK AP America Inc.
7680 The Bluffs, Suite 100
Austell, GA 30168
Telephone: (678) 838-6000; Fax: (678) 838-6001
1. Storefront System: YKK AP YHS 50 TU Impact Resistant Storefront System.
- B. Storefront Framing Systems:
1. Description: Center set, exterior flush glazed; jambs and vertical mullions continuous; head, sill, intermediate horizontal attached by screw spline joinery. Continuous and wept sill flashing.
 2. Components: Manufacturer's standard extruded aluminum mullions, entrance doors, framing, and indicated shapes, perimeter anchor fillers and steel reinforcing as required.
 3. Glazing: Manufacturer's standard glazing stops with EPDM glazing gaskets to prevent water infiltration at the exterior and Dow Corning® 995 Structural Silicone Sealant with fixed stops at the interior.
 4. Thermal Barrier: Provide continuous thermal barrier by means of a poured and debridged pocket consisting of a two-part, chemically curing high density polyurethane which is bonded to the aluminum by

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

YKK ThermaBond Plus®. Systems employing non structural thermal barriers are not acceptable.

2.02 MATERIALS

- A. Extrusions: ASTM B 221 (ASTM B 221M), 6063-T5 Aluminum Alloy.
- B. Aluminum Sheet:
 - 1. Anodized Finish: ASTM B 209 (ASTM B 209M), 5005-H14 Aluminum Alloy, 0.050" (1.27 mm) minimum thickness.
 - 2. Painted Finish: ASTM B 209 (ASTM B 209M), 3003-H14 Aluminum Alloy, 0.080" (1.95 mm) minimum thickness.

2.03 ACCESSORIES

- A. Manufacturer's Standard Accessories:
 - 1. Fasteners: Zinc plated steel concealed fasteners; Hardened aluminum alloys or AISI 300 series stainless steel exposed fasteners.
 - 2. Glazing: Setting blocks, edge blocks, and spacers in accordance with ASTM C 864, shore durometer hardness as recommended by manufacturer; Glazing gaskets in accordance with ASTM C 864.
 - 3. 0.050 Aluminum Sill Flashing End Dams featuring 3 point attachment.

2.04 RELATED MATERIALS (Specified in Other Sections)

- A. Aluminum swing doors: Section 08 41 13 35H Impact Resistant Heavy Duty Swing Doors.

2.05 FABRICATION

- A. Shop Assembly: Fabricate and assemble units with joints only at intersection of aluminum members with hairline joints; rigidly secure, and sealed in accordance with manufacturer's recommendations.

2.06 FINISHES AND COLORS

- A. High Performance Organic Coating Finish:
 - 1. Fluoropolymer Type: Factory applied two-coat 70% Kynar resin by Arkema or 70% Hylar resin by Solvay Solexis, fluoropolymer based coating system, Polyvinylidene Fluoride (PVF-2), applied in accordance with YKK AP procedures and meeting AAMA 2605 specifications.
 - 2. Colors: Selected by Architect from the following:
 - a. Standard coating color charts.
- D. Finishes Testing:
 - 1. Apply 0.5% solution NaOH, sodium hydroxide, to small area of finished sample area; leave in place for sixty minutes; lightly wipe off NaOH. Do not clean area further.
 - 2. Submit samples with test area noted on each sample.

PART 3 EXECUTION

3.01 MANUFACTURER'S INSTRUCTIONS / RECOMMENDATIONS

- A. Compliance: Comply with manufacturer's product data, including product technical bulletins, installation instructions, and product carton instructions. The latest installation instructions are available at www.ykkap.com.

3.02 EXAMINATION

- A. Site Verification of Conditions: Verify substrate conditions (which have been previously installed under other sections) are acceptable for product installation in accordance with manufacturer's instructions.

3.03 PREPARATION

- A. Adjacent Surfaces Protection: Protect adjacent work areas and finish surfaces from damage during product installation.
 - 1. Aluminum Surface Protection: Protect aluminum surfaces from contact with lime, mortar, cement, acids, and other harmful contaminants.

3.04 INSTALLATION

- A. General: Install manufacturer's system in strict accordance with shop drawings, and within specified tolerances.
 - 1. Shim and brace aluminum system before anchoring to structure.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Provide sill flashing at exterior storefront systems. Extend extruded flashing continuous with splice joints; set in continuous beads of sealant and wept.
3. Verify storefront system allows water entering system to be collected in gutters and wept to exterior. Verify metal joints are sealed in accordance with the manufacturer's instructions.
4. Seal metal to metal storefront system joints using sealant recommended by system manufacturer.

3.05 FIELD QUALITY CONTROL

- A. Manufacturer's Field Services: Upon request, provide manufacturer's field service consisting of site visit for inspection of product installation in accordance with manufacturer's instructions.
- B. Field Test: Conduct field test to determine watertightness of storefront system. Conduct test in accordance with AAMA 501.2.

3.06 ADJUSTING AND CLEANING

- A. Adjusting: Adjust operating items as recommended by manufacturer.
- B. Cleaning: The General Contractor shall clean installed products in accordance with manufacturer's instructions prior to Owner's acceptance, and remove construction debris from project site. Legally dispose of debris.
- C. Protection: The General Contractor shall protect the installed product's finish surfaces from damage during construction.

END OF SECTION 08 41 13

SECTION 08 71 00 DOOR HARDWARE

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Finish hardware for doors as specified and as listed in "Hardware Groups" and required by actual conditions. Work under this section includes furnishing and the installation of finish and security hardware specified herein and as noted on drawings for a complete and operational system.
- B.
 - 1. Include screws, special screws, bolts, special bolts, expansion shields, and other devices for proper application of hardware.
- C. Related Sections:
 - 1. Division 6: Carpentry
 - 2. Section 08 11 00, Section 08 12 00, and Section 08 21 00 - Certain hardware items installed with doors.
 - 3. Division 26: Electrical.

1.02 GENERAL REQUIREMENTS

- A. Provide items, articles, materials, operations and methods listed, mentioned or scheduled herein or on drawings, in quantities as required to complete project. Provide hardware that functions properly. Prior to furnishing hardware, advise Architect of items that will not operate properly, are improper for conditions, or will not remain permanently anchored. Where items of hardware are not specified or correctly specified, and are required for completion of the project, submit a written statement of each error, omission, or discrepancy to the Architect 14 days prior to the bid date for clarification to be included in an addendum

1.03 SUBMITTALS

- A. Hardware Schedule: Submit 6 copies of hardware schedule in vertical format as illustrated by the Sequence of Format for the Hardware Schedule as published by the Door and Hardware Institute. Schedules which do not comply will be returned for correction before checking.
- B. Hardware schedule shall clearly indicate architect's hardware group and manufacturer of each item proposed.
- C. The schedule shall be reviewed prior to submission by a certified Architectural Hardware Consultant (AHC), who shall affix his or her seal attesting to the completeness and correctness of the schedule.
 - 1. Provide 2 copies of illustrations from manufacturer's catalogs and data in brochure form.
 - 2. Check specified hardware for suitability and adaptability to details and surrounding conditions. Indicate unsuitable or incompatible items and proposed substitutions in hardware schedule.
 - 3. Provide listing of manufacturer's template numbers for each item of hardware in hardware schedule.
 - 4. Furnish the Owner- HCSD Facilities Department & Locksmith with a copy of submittal for District review. Furnish other Contractors and Subcontractors concerned with copies of final approved hardware schedule. Submit necessary templates and schedules as soon as possible to hollow metal, wood door, and aluminum door fabricators in accordance with schedule they require for fabrication.
 - 5. Samples: Lever design or finish sample: Provide 3 samples if requested by architect.
- D. Wiring Diagrams: Provide complete and detailed system operation and elevation diagrams specially developed for each opening requiring electrified hardware, except openings where only magnetic hold-opens or door position switches are specified. Provide these diagrams with hardware schedule submittal for approval. Provide detailed wiring diagrams with hardware delivery to jobsite.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

- E. Installation Instructions: Provide manufacturer's written installation and adjustment instructions for finish hardware. Send installation instructions to site with hardware.
- F. Templates: Submit templates and "reviewed Hardware Schedule" to door and frame supplier and others as applicable to enable proper and accurate sizing and locations of cutouts and reinforcing.
- G. Contract Closeout Submittals: Comply with Section 01700 including specific requirements indicated below.
 - 1. Operating and maintenance manuals: Submit 3 sets containing the following:
 - 2. Complete information in care, maintenance, and adjustment, and data on repair and replacement parts, and information on preservation of finishes.
 - 3. Catalog pages for each product.
 - 4. Name, address, and phone number of local representative for each manufacturer.
 - 5. Parts list for each product.
 - 6. Copy of final approved hardware schedule, edited to reflect "As installed".
 - 7. Copy of final keying schedule.
 - 8. As installed "Wiring Diagrams" for each opening connected to power, both low voltage and 110 volts.
 - 9. One complete set of special tools required for maintenance and adjustment of hardware, including changing of cylinders.

1.04 QUALITY ASSURANCE

- A. Manufacturer: Obtain each type of hardware (ie. latch and locksets, hinges, closers) from single manufacturer, although several may be indicated as offering products complying with requirements.
- B. Supplier: A recognized architectural door hardware supplier, with warehousing facilities, who has been providing hardware for period of not less than 4 years. The supplier shall be, or employ, a certified Architectural Hardware Consultant (AHC), who is registered in the continuing education program as administered by the Door and Hardware Institute, and who is available during the course of the project for consultation about the project's hardware requirements. The hardware schedule shall be prepared and signed by a certified AHC. The Hardware Supplier shall be responsible for proper coordination of all finish hardware items and access control items with related section to insure compatibility of the products and door function. The Hardware Supplier shall be an authorized, direct factory distributor of all door hardware products specified herein to insure compliance and service of these products.
- C. Installer: The hardware installer shall have documented experience in the installation of hardware of similar quantities and types as required for this project. The installer's qualifications shall be submitted to the GC, in writing, for approval by the GC & the Owner before any work shall commence. HCSD requires certified hardware installers. Certification demonstrates the installer has attended trainings provided by the approved manufacturers of locksets, exit devices, and door closers. Proof of certification shall be available in the form of a written certificate from the manufacturer of these products.
- D. Regulatory Label Requirements: Where UL requirements conflict with drawings or specifications, hardware conforming to UL requirements shall be provided. Conflicts and proposed substitutions shall be clearly indicated in hardware schedule.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

E. Pre-Installation Meetings: The Contractor shall initiate and conduct a jobsite meeting with the supplier and installer, and all related trades for mechanical hardware, and a meeting for electronic hardware. The Hardware Supplier shall schedule the Manufacturer's representatives of the following products to provide training for product installation: Closers, Exit Devices, and Locksets. These meetings shall convene at least one month prior to commencement of the related work. All approved shop drawings and schedules shall be made available to all related trades as required for work to be performed. Prior to installation of wiring and installation of power supplies for electronic hardware, arrange a conference between the supplier, the installers and all related trades to review materials, procedures, review door opening functions, and coordinating related work.. The Owner's Construction Project Manager and the Maintenance Department Hardware Representative shall attend all pre-install meetings. The Owner's Construction Project Manager and the Maintenance Department Hardware Representative shall attend all mechanical and electrical pre-installation meetings.

1.05 DELIVERY, STORAGE AND HANDLING

- A. Deliver hardware to jobsite in manufacturer's original packaging, marked to correspond with approved hardware schedule. Do not deliver hardware until suitable locked storage space is available. Check hardware against reviewed hardware schedule. Store hardware to protect against loss, theft or damage.
- B. Deliver hardware required to be installed during fabrication of hollow metal, aluminum, wood, or stainless steel doors prepaid to manufacturer.

1.06 WARRANTY

- A. Guarantee workmanship and material provided against defective manufacture. Repair or replace defective workmanship and material appearing within period of one year after Substantial Completion.
- B. Provide thirty-year factory warranty on door closer body against defects in material and workmanship from date of occupancy of Project. The following special warranties:
 - 1. Butt & Continuous Hinges: Life of the Door Opening (original installation)
 - 2. Mortise Locks: Three (3) year period.
 - 3. Exit Devices: Three (3) year period.
- C. Replace shortages and incorrect items with correct material at no additional cost to Owner.
- D. At completion of project, qualified factory representative shall inspect closer installations. After this inspection, letter shall be sent to Architect reporting on conditions, verifying that closers have been properly installed and adjusted.
- E. Refer to Section 01 – closeout procedures for additional warranty requirements.

PART 2 PRODUCTS

2.0 General Requirements:

- 1. Hardware shall be of best grade, entirely free of imperfections in manufacture and finish, and shall satisfactorily perform various functions needed.
- 2. Furnish necessary screws, bolts or others fastenings of suitable size and type to anchor hardware in position and match hardware as to material and finish. Provide Phillips flat-head screws except as otherwise indicated.
- 3. Verify use of through-bolts for closer/exit device installations where bolt head or nut opposite face is exposed in other work. Use of sex bolts shall be allowed, as required by the door manufacturer for compliance with fire door certification.
- 4. Drawings show direction of slide, swing or hand of each door leaf. Furnish each item of hardware for proper installation and operation of door movement as indicated. Items of hardware not definitely specified, but needed for satisfactory installation of hardware shall be provided. Such items shall be of type and quality suitable for service needed and comparable to adjacent hardware

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.1 BUTTS AND HINGES

A. Acceptable Manufacturers and Types:

Type	Ives	Hager	Stanley
Type 2	5BB1	BB1279	FBB179
Type 3	5BB1	BB1191	FBB191
Type 4	5BB1HW	BB1168	FBB168
Type 5	5BB1HW	BB1199	FBB199

B. Application:

- Exterior out-swinging doors Type 5 x NRP
- Exterior in-swinging doors and vestibule doors Type 4
- Interior doors with closers Type 2 or 4
- Interior doors over 36 inches wide Type 4
- Interior doors 36 inches or less without closer Type 2
- Provide NRP (non-removable pins) at out-swinging lockable doors.

C. Size:

- 2-1/4 inch Doors 5 inch by 5 inch
- 1-3/4 inch Doors 4-1/2 inch by 4-1/2 inch
- 1-3/8 inch Doors 3-1/3 inch by 3-1/2 inch

D. Quantity:

- Two hinges per leaf for openings through 60 inches high.
- One additional hinge per leaf for each additional 30 inches in height or fraction thereof.
- Four hinges for Dutch doors up to 90 inches in height.

E. Drill 5/32 inch hole and use No. 12, 1-1/4 inch steel threaded to the head wood screws for hinges on wood doors.

2.2 CONTINUOUS GEARED HINGES

A. Acceptable manufacturers:

Ives	Hager	Select
112HD	780-112HD	SL11HD

B. Provide one of the above two models of continuous hinges as specified. Coordinate hinge types with the door supplier.

C. Provide electric power transfer (EPT) cutouts, or electric through-wire options as specified in hardware groups.

2.3 FLUSH BOLTS AND DUSTPROOF STRIKES

A. Acceptable manufacturers:

Ives	Trimco	Door Controls
FB31P	3810	842
FB41P	3815	942
FB51P	3820 x 3810	845
FB61P	3825 x 3815	945
FB358	3913	790F
FB458	3915	780F
DP2	3910	82

B. Non-labeled Openings: Provide 2 flush bolts FB457 for inactive leaf of pairs of locked and latched doors. Locate centerline of top bolt not more than 78 inches from finished floor. Provide dustproof strike DP1 for bottom bolt.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Labeled Openings: Provide automatic flush bolt set FB31P or FB41P, as applicable, for inactive leaf of pairs of doors. Provide dustproof strike DP1 for bottom bolt.

2.4 LOCKSETS – MORTISE

- A. Acceptable Manufacturer and Series:

Manufacturer	Series
Schlage	L9000 03N
Corbin	ML2000 x LWM

- B. Provide lock functions specified in Hardware Groups, with following provisions:
1. Cylinders: Schlage small format 7-pin existing GMK system, as specified. Refer to Keying Section.
 2. Locksets shall meet the requirements of ANSI/BHMA A156.13-1994, Operational Grade 1, and Security Grade 1.
 3. Backsets: 2-3/4 inches with 3/4" throw latchbolt.
 4. Strikes: Provide wrought boxes and strikes with proper lip length to protect trim but not to project more than 1/8 inch beyond trim, frame or inactive leaf. Where required, provide open back strike and protected to allow practical and secure operation.
 5. Lock trim shall be thru-bolted to the door to assure correct alignment and proper operation.

2.5 EXIT DEVICES

- A. Acceptable Manufacturers:

Von Duprin		Precision
98/99 Series		2100 Apex Series

- B. Provide exit device series and functions as specified in Hardware Groups. Von Duprin product numbers are referenced in the Hardware Groups.
- C. All exit devices shall be UL listed for panic. Exit devices for labeled doors shall be UL listed as "Fire Exit Hardware".
- D. Where lever trim is specified, provide lever design to match lockset levers.
- E. Provide cylinders for exit devices with locking trim and cylinder dogging.
- F. Provide exit devices with stainless steel touch bars. Plastic parts are not acceptable.
- G. Provide exit devices with cast metal, flush end caps.
- H. Provide deadlocking latchbolt feature for exit devices.
- I. Provide cylinder dogging feature for non-rated exit devices.
- J. Provide keyed removable mullions, with cylinders, as specified in the Hardware Groups.

2.6 KEYING

- A. Provide Construction keyed cylinders as specified.
- B. Provide permanent keyed cores to match the school's existing Grand Masterkey system by Corbin-Russwin. Keyway: verify all keying directions with the HCSD locksmith prior to preparing the keying schedule for approval.
- C. Grand Masterkey and key in groups, unless otherwise specified. Factory key all locks with Corbin-Russwin, retaining the permanent keying records.
- D. Provide for 6 Masters for each masterkey set. Provide 3 change keys for each lock. Provide 2 control keys for core removal. Provide one extra key blank per cylinder. Stamp keys "DO NOT DUPLICATE." Keys and cores shall be marked with applicable blind code for identification. Visual key control marks or codes shall not include actual key cuts.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Meet with the Owner, GC, and Architect to review the project keying requirements. Prepare and submit a keying schematic and a proposed key schedule for review. No keying shall be performed without an approved key schedule.
- F. Provide the interchangeable core cylinders for each lock with keyed construction cores. Provide three each construction keys to the GC.
- G. Permanent cores and keys shall be furnished to the Owner's representative and installed by the installed by the GC/installer upon completion of the project per Architect/Owners instruction.
- H. Cylinders shall meet the requirements of UL437.
- I. Furnish 1 each bitting list to the HCSD Locksmith by registered mail.

2.7 DOOR TRIM

- A. Acceptable Manufacturers and Types:

Ives	Trimco	Burns
------	--------	-------

- B. Push Plates:
 - 1. Ives type 8200 4 inches by 16 inch unless otherwise indicated.
- C. Pull Plates:
 - 1. Ives type 8305 4 inches by 16 inches unless otherwise indicated.
- D. Push Bars:
 - 1. Von Duprin type 350, unless otherwise indicated.
- E. Pulls:
 - 1. Ives Series 8190, unless otherwise indicated.
 - 2. Where required, mount back to back with push bars.
- F. Kick Plates and Armor Plates: Ives 8400 Series, minimum of 0.050 inch thick, beveled 4 edges.
 - 1. At single doors provide width two inches less than door width on stop side and one inch less than door width on pull side.
 - 2. At pairs of doors provide width one inch less than door width on both sides.
 - 3. Height of 8 inches, unless otherwise indicated.
 - 4. Provide plates with countersunk screw holes.

2.8 DOOR CLOSERS

- A. Acceptable Manufacturers and Types of Exposed Closers:

LCN	Stanley-Ryoby
4040XP	D 4551 EDA

- B. Closers shall have fully hydraulic, full rack and pinion action with a high strength cast iron cylinder.
- C. Provide non-sized closers, continuously adjustable over the full range of closer sizes, and allow for reduced opening force to meet opening force requirements of ANSI A117.1
- D. Hydraulic regulation shall be by tamper-proof, non-critical valves. Closers shall have separate adjustment for latch speed, swing speed, and back check.
- E. Provide closers with solid forged steel main arms (and forearms for parallel arm closers) and where specified to have a cast-in solid stop on the closer shoe ("CUSH"). Parallel arm mounted closers shall have "EDA" type arms or, where specified, or "SCUSH" type arms.
- F. Surface closers shall be certified to exceed ten million full load cycles by a recognized independent testing laboratory.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- G. Provide drop plates, brackets, or adapters for arms as required to suit details and coordinate with overhead stops/holders as required..
- H. Mount closers on room side of corridor doors, inside of exterior doors, and stair side of stairway doors.
- I. Provide back-check for closers.
- J. Provide hold-open arms where indicated.
- K. Provide closers for doors as noted in Hardware Groups and, in addition, provide closers for labeled doors whether or not specifically noted in group.
- L. Provide closers meeting the requirements of UBC 7-2, 1997 and UL 10C positive pressure tests.
- M. Pressure relief valves (PRV's) will not be permitted.

2.9 OVERHEAD STOPS

- A. Acceptable Manufacturers

Glynn Johnson	Rixon
90	9 series

- B. Provide overhead stops for interior doors equipped with regular arm surface type closer for doors that open against equipment, casework, sidelights, other objects that would make wall stops inappropriate.
- C. Provide coordination as required with closers to suit function and application of opening.
- D. Provide 90 series overhead stops at exterior doors where specified.
- E. Provide sex bolt attachments for mineral core door application.

2.10 STOPS AND HOLDERS

- A. Acceptable Manufacturers and Types:

Ives	Trimco	Door Controls
WS406/407CVX	1270WXCP	3211
FS436	W1211	3267X
WS45		

- B. Provide wall stop for each door leaf unless otherwise specified, or where conditions require the use of an overhead stop.
- C. Floor or base stops shall be used only where definitely specified or absolutely unavoidable.

2.11 THRESHOLDS

- A. Except as otherwise indicated, provide standard threshold units of type, size, and profile as shown or scheduled in the HW Sets/Groups. Refer to drawings for any special sill details and notify the architect of any exceptions. Provide accessories, shims and fasteners as required for proper installation.
- B. Where thresholds occur at openings with one or more mullions, they shall be cut for the mullions and extended continuously for the entire opening.
- C. Metal: extruded aluminum. Finish: clear anodized, BHMA 628.
- D. Acceptable Manufactures: Zero; National Guard, Reese

2.12 WEATHERSTRIPPING

- A. Where weatherstripping is specified in hardware groups, provide as detailed otherwise.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Provide self-tapping fasteners for weatherstripping, being applied to hollow metal frames, as specified.
- C. Where sweeps are specified in hardware groups, provide 39A unless detailed otherwise.
- D. Where rain drips are specified in hardware groups, provide 142A x full frame width, unless detailed otherwise.

2.13 GASKETING

- A. Acceptable Manufacturers: Zero, National Guard, and Reese Enterprises. Refer to drawings for special details. Provide accessories, shims and fasteners.
- B. Where smoke gasket is specified in hardware groups, provide 488S, unless detailed otherwise.
- C. Provide gaskets for 20-minute doors and doors designated for smoke and draft control.
- D. Where frame applied intumescent seals are required by the manufacturer, provide gaskets that comply with UBC 7-2, 1997 and UL 10C positive pressure tests.

2.14 SOUND GASKETING

- A. Where sound gasketing is specified in hardware groups, provide 475AA unless detailed otherwise.
 - 1. Provide self-tapping fasteners being applied to hollow metal doors and frames.
 - 2. Cutting or notching of sound gasket for stop mounted hardware shall not be permitted.

2.15 MAGNETIC HOLDERS

- A. Acceptable Manufacturers and Types:

LCN	Dorma	Edwards
SEM 7850	EM504	1504

- B. Where magnetic holders are specified in the Hardware Groups, provide LCN SEM 7850, unless detailed otherwise.
 - 1. Verify voltage with Electrical Contractor.
- C. Provide magnetic holders made of cast metal material. Plastic or stamped material will not be accepted.

2.16 ACCESS CONTROLLED LOCKS/EXIT TRIM

Electronic Access Controlled Locks and Exit trim shall be as manufactured as Schlage Electronics. All locksets/exit trim shall have the ability for the Reader to be upgraded in the field from the multi-tech solution to a smartcard solution without the lock being removed from the door. All locksets/exit trim shall be capable of being managed by the HCSD existing software or for future networked software. All readers shall be programmed to the Owner's card database. Furnish all locksets and exit trim with a multi-tech reader module.

- 1. The HCSD Locksmith shall execute the programming and initiate the lock functionality by use of the HCSD's Hand Held Device.
- 2. The wall-mounted card readers shall be a hardwired application.
- 3. The access controlled locksets and exit device trim shall be prepared to receive a Schlage keyed SFIC, keyed per the Owner's existing Schlage key system. The access controlled locksets shall be furnished with a temporary keyed core.
- 4. Mortise Lock with proximity reader shall be as: AD-400-MS-70-MTK-TLR-BD- 626 (US26D) 8BB.
- 5. Exit Trim with proximity reader shall be as: AD-400-993R-70-MTK-TLR-BD - 626 8BB.
- 6. Furnish 200 each proximity cards: #7510 by Schlage Electronics.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.17 SILENCERS

- A. Acceptable Manufacturers and types:

Ives	Steelcraft	Don-Jo
SR64	Q146	1608

- B. Provide grey rubber silencers featuring pneumatic design that, once installed, forms an air pocket to absorb shock and reduce noise of door closing.
- C. Provide three (3) silencers per hollow metal strike jamb; two (2) per hollow metal double door head. Omit at doors scheduled to receive perimeter weatherstripping or smoke gasket.
- D. Silencers shall meet ANSI/BHMA A156.16, L03011

2.18 FASTENERS

- A. Including, but not limited to, wood or machine screws, bolts, bolts, nuts, anchors, etc. of proper type, material, and finish required for installation of hardware.
- B. Use phillips head for exposed screws. Do not use aluminum screws to attach hardware.
- C. Furnish only fasteners and/or brackets provided by the manufacturer of each hardware item. Any substitute fastener shall be approved by Horry County Schools Locksmith. Any unauthorized install fastener shall be removed and shall be replaced with the correct fastener at the Installer's expense.

2.19 TYPICAL FINISHES AND MATERIALS

- A. Finishes, unless otherwise specified:
1. Butts: Outswinging Exterior Doors
 - a. US32D (BHMA 630) on Stainless Steel
 2. Butts: Interior Doors and Inswinging Exterior Doors
 - a. US26D (BHMA 652) on Steel
 3. Continuous Hinges:
 - a. US28 (BHMA 628) on Aluminum
 4. Flush Bolts:
 - a. US26D (BHMA 626) on Brass or Bronze
 5. Exit Devices:
 - a. US26D (BHMA 626) on Brass or Bronze
 6. Locks and Latches:
 - a. US26D (BHMA 626) on Brass or Bronze
 7. Push Plates, Pulls and Push Bars:
 - a. US32D (BHMA 630) on Stainless Steel
 8. Coordinators:
 - a. USP (BHMA 600) on Steel
 9. Kick Plates, Armor Plates, and Edge Guards:
 - a. US32D (BHMA 630) on Stainless Steel
 10. Overhead Stops and Holders:
 - a. US26D (BHMA 626) on Brass or Bronze
 11. Closers: Surface mounted.
 - a. Sprayed Aluminum Lacquer.
 12. Latch Protectors:
 - a. US32D (BHMA 630) on Stainless Steel
 13. Miscellaneous Hardware:
 - a. US26D (BHMA 626) on Brass or Bronze

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

PART 3 EXECUTION

3.1 EXAMINATION

- A. Examine doors, frames, and related items for conditions that would prevent the proper application of finish hardware. Do not proceed until defects are corrected.

3.2 INSTALLATION

- A. Install finish hardware in accordance with reviewed hardware schedule and manufacturer's printed instructions. Pre-fit hardware before finish is applied, remove and reinstall after finish is completed. Install hardware so that parts operate smoothly, close tightly and do not rattle.
- B. Installation of hardware shall comply with NFPA 80 and NFPA 101 requirements.
- C. Set units level, plumb and true to line and location. Adjust and reinforce attachment to substrate as necessary for proper installation and operation.
- D. Drill and countersink units which are not factory-prepared for anchorage fasteners. Space fasteners and anchors in accordance with industry standards.
- E. Set thresholds for exterior doors in full bed of butyl-rubber or polyisobutylene mastic sealant, forming tight seal between threshold and surface to which set. Securely and permanently anchor thresholds, using countersunk non-ferrous screws to match color of thresholds (stainless steel screws at aluminum thresholds).
- F. Install each hardware item in compliance with the manufacturer's instructions and recommendations. Install only with fasteners and/or brackets furnished with each hardware item or exact match if additional fasteners are required. Any substitute fasteners shall be approved by Horry County Schools Maintenance Department.
- G. Certified installers: Contractor's personnel and Section 8710 supplier/installer shall be certified prior to installation of exit devices, computer- managed exit device trim, locksets, closers, and electrified hardware, including ADA operators, and electric door releases. Certification shall be obtained by attendance of manufacturer's training at the pre-install meeting. The manufacturer's representative shall provide written certification to the installers and a copy of the certification shall be provided to the Contractor, Horry County Schools Construction Representative and the Horry County Schools Maintenance Department Hardware Representative. Hardware Installers working on the project site not certified by attending the above specified training, shall be removed from the project site.
- H. Upon completion of the final installation of the Door Hardware the Hardware Supplier and the HCSD Locksmith shall jointly inspect the project openings to insure proper function/adjustment of the opening for correct installation and functionality requirements. This inspection shall take place prior to the installation of the final keyed cores. The Hardware Supplier shall submit a written report of the inspection, including any exceptions noted during the inspection.

3.3 FIELD QUALITY CONTROL

- A. After installation has been completed, provide services of qualified hardware consultant to check Project to determine proper application of finish hardware according to schedule. Also check operation and adjustment of hardware items.
- B. Adjust door control devices to compensate for final operation of heating and ventilating equipment.
- C. Door Hardware Supplier's Field Service

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

1. The Hardware Supplier/AHC shall inspect door hardware items for correct installation and adjustment prior to Owner's permanent core installation. The Hardware Installer shall be present for this inspection. The Owner shall give written notice to the Contractor five (5) days prior to inspection. The Hardware Supplier/AHC shall submit a written report of the inspection, including any exceptions noted during the inspection, and shall include the certified AHC stamp or seal, to the Contractor, Architect, the Horry County Schools Construction Representative, and the Horry County Schools Maintenance Department Hardware Representative. The inspection shall include:

- a. Fasteners
- b. Templating for correct latch/strike engagement, degree of opening/holding
- c. Operable Function: locks/exits
- d. Operation: closers, exits, locks, cylinders, hinges

3.4 ADJUSTING AND CLEANING

- A. At final completion, hardware shall be left clean and free from disfigurement. Make final adjustment to door closers and other items of hardware. Where hardware is found defective repair or replace or otherwise correct as directed.
- B. Adjust door closers to meet opening force requirements of Uniform Federal Accessibility Standards.
- C. Final Adjustment: Wherever hardware installation is made more than one month prior to acceptance or occupancy of space or area, return to work during week prior to acceptance or occupancy, and make final check and adjustment of hardware items in such space or area. Clean operating items as necessary to restore proper function and finish of hardware and doors.
- D. Instruct Owner's personnel in proper adjustment and maintenance of door hardware and hardware finishes.
- E. Clean adjacent surfaces soiled by hardware installation.

3.5 PROTECTION

- A. Provide for proper protection of items of hardware until Owner accepts Project as complete.

3.6 HARDWARE GROUPS

- A. The hardware supplier shall to refer to general conditions, special conditions, and the preamble to this section. It shall be the hardware supplier's responsibility to furnish all required hardware.
- B. Refer to the door schedule for hardware group required at each door opening.

END OF SECTION 08 71 00

SECTION 08 80 00 - GLAZING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes glazing for the following products and applications, including those specified in other Sections where glazing requirements are specified by reference to this Section:
 - 1. Windows.
 - 2. Doors.
 - 3. Curtain walls.
 - 4. Storefront framing.
 - 5. Glazed entrances.
 - 6. Interior borrowed lites and transoms.

1.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Design glass, including comprehensive engineering analysis according to ASTM E 1300 by a qualified professional engineer, using the following design criteria:
 - 1. Design Wind Pressures: As indicated on Drawings.
 - 2. Vertical Glazing: For glass surfaces sloped 15 degrees or less from vertical, design glass to resist design wind pressure based on glass type factors for short-duration load.

1.3 PRECONSTRUCTION TESTING

- A. Preconstruction Adhesion and Compatibility Testing: Test each glazing material type, tape sealant, gasket, glazing accessory, and glass-framing member for adhesion to and compatibility with elastomeric glazing sealants.
 - 1. Testing will not be required if data are submitted based on previous testing of current sealant products and glazing materials matching those submitted.

1.4 ACTION SUBMITTALS

- A. Product Data: For each glass product and glazing material indicated.
- B. Glass Samples: For each type of glass product other than clear monolithic vision glass; 12 inches (300 mm) square.
- C. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.
- D. Delegated-Design Submittal: For glass indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.5 INFORMATIONAL SUBMITTALS

- A. Preconstruction adhesion and compatibility test report.

1.6 QUALITY ASSURANCE

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.
 - 1. GANA Publications: GANA's "Laminated Glazing Reference Manual" and GANA's "Glazing Manual."
 - 2. AAMA Publications: AAMA GDSG-1, "Glass Design for Sloped Glazing," and AAMA TIR-A7, "Sloped Glazing Guidelines."
 - 3. IGMA Publication for Sloped Glazing: IGMA TB-3001, "Guidelines for Sloped Glazing."
 - 4. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."
- B. Safety Glazing Labeling: Where safety glazing labeling is indicated, permanently mark glazing with certification label of the manufacturer. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.
- C. Fire-Protection-Rated Glazing Labeling: Permanently mark fire-protection-rated glazing with certification label of a testing agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, test standard, whether glazing is for use in fire doors or other openings, whether or not glazing passes hose-stream test, whether or not glazing has a temperature rise rating of 450 deg F (250 deg C), and the fire-resistance rating in minutes.
- D. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of IGCC.

1.7 WARRANTY

- A. Manufacturer's Special Warranty on Insulating Glass: Manufacturer's standard form in which insulating-glass manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is the obstruction of vision by dust, moisture, or film on interior surfaces of glass.
 - 1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GLASS PRODUCTS, GENERAL

- A. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass lites in thicknesses as needed to comply with requirements indicated.
- B. Strength: Where float glass is indicated, provide annealed float glass, Kind HS heat-treated float glass, or Kind FT heat-treated float glass as needed to comply with "Performance

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

Requirements" Article. Where heat-strengthened glass is indicated, provide Kind HS heat-treated float glass or Kind FT heat-treated float glass as needed to comply with "Performance Requirements" Article. Where fully tempered glass is indicated, provide Kind FT heat-treated float glass.

- C. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:
1. U-Factors: Center-of-glazing values, according to NFRC 100 and based on LBL's WINDOW 5.2 computer program, expressed as Btu/sq. ft. x h x deg F (W/sq. m x K).
 2. Solar Heat-Gain Coefficient and Visible Transmittance: Center-of-glazing values, according to NFRC 200 and based on LBL's WINDOW 5.2 computer program.
 3. Visible Reflectance: Center-of-glazing values, according to NFRC 300.

2.2 GLASS PRODUCTS

- A. Float Glass: ASTM C 1036, Type I, Quality-Q3, Class I (clear) unless otherwise indicated.
- B. Heat-Treated Float Glass: ASTM C 1048; Type I; Quality-Q3; Class I (clear) unless otherwise indicated; of kind and condition indicated.
- C. Reflective-Coated Vision Glass (all glazing in exterior wall openings): ASTM C 1376, coated by vacuum deposition (sputter-coating) process, and complying with other requirements specified.
1. Basis-of-Design Product: Subject to compliance with requirements, provide PPG Solarban 70XL(2) Solexia + Clear, or submit a comparable product for approval by one of the following within the time permitted during the Bid process:
 - a. Cardinal
 - b. Pilkington

2.3 INSULATING GLASS

- A. Insulating-Glass Units (all glazing in exterior wall openings): Factory-assembled units consisting of sealed lites of glass separated by a dehydrated interspace, qualified according to ASTM E 2190, and complying with other requirements specified.
1. Sealing System: Dual seal.
 2. Spacer: Manufacturer's standard spacer material and construction.
- B. Low-e-coated, tinted, insulating laminated glass with the following characteristics:
1. Visible Light Transmittance: 54 percent minimum.
 2. Winter Nighttime U-Factor: .28 maximum.
 3. Summer Daytime U-Factor: .26 maximum.
 4. Solar Heat Gain Coefficient: .25 maximum.
 5. Shading coefficient: .29.
 6. Provide safety glazing labeling.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.4 GLAZING GASKETS

- A. Dense Compression Gaskets: Molded or extruded gaskets of profile and hardness required to maintain watertight seal, made from one of the following:
 - 1. Neoprene complying with ASTM C 864.
 - 2. EPDM complying with ASTM C 864.
 - 3. Silicone complying with ASTM C 1115.
 - 4. Thermoplastic polyolefin rubber complying with ASTM C 1115.
- B. Soft Compression Gaskets: Extruded or molded, closed-cell, integral-skinned gaskets complying with ASTM C 509, Type II, black; of profile and hardness required to maintain watertight seal.
 - 1. Application: Use where soft compression gaskets will be compressed by inserting dense compression gaskets on opposite side of glazing or pressure applied by means of pressure-glazing stops on opposite side of glazing.

2.5 GLAZING SEALANTS

- A. General:
 - 1. Compatibility: Provide glazing sealants that are compatible with one another and with other materials they will contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
 - 2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
 - 3. Sealants used inside the weatherproofing system, shall have a VOC content of not more than 250 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 4. Sealants used inside the weatherproofing system shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
 - 5. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.
- B. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 100/50, Use NT.
- C. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 50, Use NT.
- D. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 25, Use NT.

2.6 GLAZING TAPES

- A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C 1281 and AAMA 800 for products indicated below:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. AAMA 804.3 tape, where indicated.
 2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
 3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.
- B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:
1. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.
 2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.7 MISCELLANEOUS GLAZING MATERIALS

- A. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.
- B. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.
- C. Spacers: Elastomeric blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
- D. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).
- E. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

PART 3 - EXECUTION

3.1 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
- B. Adjust glazing channel dimensions as required by Project conditions during installation to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.
- C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.
- D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- G. Provide spacers for glass lites where length plus width is larger than 50 inches (1270 mm).
- H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.

3.2 TAPE GLAZING

- A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.
- B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.
- C. Cover vertical framing joints by applying tapes to heads and sills first and then to jambs. Cover horizontal framing joints by applying tapes to jambs and then to heads and sills.
- D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.
- E. Delete first paragraph below if not required, or qualify by adding "where indicated" and show locations on Drawings.
- F. Apply heel bead of elastomeric sealant.
- G. Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.
- H. Apply cap bead of elastomeric sealant over exposed edge of tape.

3.3 GASKET GLAZING (DRY)

- A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.
- B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.
- C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.
- E. Install gaskets so they protrude past face of glazing stops.

3.4 CLEANING AND PROTECTION

- A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer.
- C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains; remove as recommended in writing by glass manufacturer.
- D. Remove and replace glass that is broken, chipped, cracked, or abraded or that is damaged from natural causes, accidents, and vandalism, during construction period.

END OF SECTION 08 80 00

SECTION 09 22 16 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior gypsum board assemblies.
2. Suspension systems for interior gypsum ceilings and soffits.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: Provide materials and construction identical to those tested according to ASTM E 119.

2.2 FRAMING SYSTEMS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content is not less than 25 percent.
- B. Steel Studs and Runners: ASTM C 645.
1. Minimum Base-Metal Thickness: 0.027 inch (0.68 mm)
 2. Depth: As indicated on Drawings.
- C. Slip-Type Head Joints: Where indicated, provide[one of] the following in thickness not less than indicated for studs and in width to accommodate depth of studs:
1. Single Long-Leg Runner System: ASTM C 645 top runner with 2-inch- (51-mm-) deep flanges, installed with studs friction fit into top runner and with continuous bridging located within 12 inches (305 mm) of the top of studs to provide lateral bracing.

2.3 SUSPENSION SYSTEMS

- A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- (1.59-mm-) diameter wire, or double strand of 0.048-inch- (1.21-mm-) diameter wire.
- B. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch (4.12 mm) in diameter.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Flat Hangers: Steel sheet, 1 by 3/16 inch (25 by 5 mm).
- D. Carrying Channels: Cold-rolled, commercial-steel sheet with a base-metal thickness of 0.053 inch (1.34 mm) and minimum 1/2-inch- (13-mm-) wide flanges.
 - 1. Depth: 2-1/2 inches (64 mm).

2.4 AUXILIARY MATERIALS

- A. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C 754.
 - 1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.
- B. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- C. Install bracing at terminations in assemblies.
- D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

3.2 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
- B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- C. Install studs so flanges within framing system point in same direction.
- D. Install tracks (runners) at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions above ceiling.
 - 1. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
 - a. Install two studs at each jamb unless otherwise indicated.
 - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch (13-mm) clearance from jamb stud to allow for installation of control joint in finished assembly.
 - c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
- E. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch (3 mm) from the plane formed by faces of adjacent framing.

3.3 INSTALLING SUSPENSION SYSTEMS

- A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
 - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
 3. Do not attach hangers to steel roof deck.
 4. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
 5. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
 6. Do not connect or suspend steel framing from ducts, pipes, or conduit.
- D. Seismic Bracing: Sway-brace suspension systems with hangers used for support.
- E. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet (3 mm in 3.6 m) measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION 09 22 16

SECTION 09 29 00 - GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.
- B. Low Emitting Materials: For ceiling and wall assemblies, provide materials and construction identical to those tested in assembly and complying with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.2 GYPSUM BOARD, GENERAL

- A. Recycled Content of Gypsum Panel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Regional Materials: Gypsum panel products shall be manufactured within 500 miles (800 km) of Project site.

2.3 INTERIOR GYPSUM BOARD

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
 1. American Gypsum.
 2. Georgia-Pacific Gypsum LLC.
 3. USG Corporation.
- B. Gypsum Wallboard: ASTM C 1396/C 1396M.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Thickness: 5/8 inch (15.9 mm).
2. Long Edges: Tapered.

C. Gypsum Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch (15.9 mm).
2. Long Edges: Tapered.

2.4 TRIM ACCESSORIES

A. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.

B. Aluminum Trim: ASTM B 221 (ASTM B 221M), Alloy 6063-T5.

2.5 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:

1. Interior Gypsum Board: Paper.

C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.

2.6 AUXILIARY MATERIALS

A. Laminating Adhesive: Adhesive or joint compound recommended for directly adhering gypsum panels to continuous substrate.

1. Laminating adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

B. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.

C. Sound Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing).

1. Recycled Content of Blankets: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

D. Thermal Insulation: As specified in Section 07 21 00 "Thermal Insulation."

E. Vapor Retarder: As specified in Section 07 21 00 "Thermal Insulation."

PART 3 - EXECUTION

3.1 APPLYING AND FINISHING PANELS

- A. Comply with ASTM C 840.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- D. Install trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
 - 1. Control Joints: Install control joints according to ASTM C 840 and in specific locations approved by Architect for visual effect. Submit drawing of Dining Room wall for approval.
- E. Prefill open joints and damaged surface areas.
- F. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- G. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
 - 1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
 - 2. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.
 - a. Primer and its application to surfaces are specified in Section 09 91 23 "Interior Painting."
- H. Protect adjacent surfaces from drywall compound and texture finishes and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- I. Remove and replace panels that are wet, moisture damaged, and mold damaged.

END OF SECTION 09 29 00

SECTION 09 30 00 – CERAMIC TILE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Ceramic tile.
2. Crack isolation membrane.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

1.3 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering and identified with labels describing contents.

1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.

1.4 QUALITY ASSURANCE

A. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup of each type of floor tile installation.
2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

PART 2 - PRODUCTS

2.1 TILE PRODUCTS

- A. ANSI Ceramic Tile Standard: Provide Standard grade tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.
- B. Tile Type: match existing as close as possible. See plans.

2.2 SETTING MATERIALS

A. Water-Cleanable, Tile-Setting Epoxy: ANSI A118.3.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Bonsal American; an Oldcastle company.
 - b. Bostik, Inc.
 - c. Custom Building Products.

- d. Laticrete International, Inc.
- e. MAPEI Corporation.

2.3 GROUT MATERIALS

- A. Water-Cleanable Epoxy Grout: ANSI A118.3.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Bonsal American; an Oldcastle company.
 - b. Bostik, Inc.
 - c. Custom Building Products.
 - d. Laticrete International, Inc.
 - e. MAPEI Corporation.

2.4 ELASTOMERIC SEALANTS

- A. One-Part, Mildew-Resistant Silicone Sealant: ASTM C 920; Type S; Grade NS; Class 25; Uses NT, G, A, and, as applicable to nonporous joint substrates indicated, O; formulated with fungicide, intended for sealing interior ceramic tile joints and other nonporous substrates that are subject to in-service exposures of high humidity and extreme temperatures.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. DAP Inc.; 100 percent Silicone Kitchen and Bath Sealant.
 - b. Dow Corning Corporation; Dow Corning 786.
 - c. GE Silicones, a division of GE Specialty Materials; Sanitary 1700.
 - d. Laticrete International, Inc.; Latasil Tile & Stone Sealant.
 - e. Pecora Corporation; Pecora 898 Sanitary Silicone Sealant.
 - f. Tremco Incorporated; Tremsil 600 White.

2.5 MISCELLANEOUS MATERIALS

- A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of installed tile.
 - 1. Verify that substrates for setting tile are firm, dry, clean, free of coatings that are incompatible with tile-setting materials including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.

3.2 PREPARATION

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS

Myrtle Beach, South Carolina

- A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with adhesives or thin-set mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer. Install crack isolation membrane to comply with ANSI A108.17 and manufacturer's written instructions to produce membrane of uniform thickness and bonded securely to substrate.
- B. Blending: Blend tiles at Project site before installing.

3.3 INSTALLATION

- A. Comply with TCA's "Handbook for Ceramic Tile Installation" for TCA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 Series "Specifications for Installation of Ceramic Tile" that are referenced in TCA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.
 - 1. For the following installations, follow procedures in the ANSI A108 Series of tile installation standards for providing 95 percent mortar coverage:
 - a. Tile floors composed of tiles 8 by 8 inches (200 by 200 mm) or larger.
- B. Install tile completely to walls in kitchen and bathrooms prior to casework installation. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
- D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
- E. Jointing Pattern: Lay tile in grid pattern parallel to walls. Lay out tile work and center tile fields in both directions in each space. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths. Continue joint pattern into adjoining spaces where tile is scheduled for both spaces and no door interrupts the flooring.
- F. Joint Widths: Unless otherwise recommended by tile manufacturer, install tile with the following joint widths:
 - 1. Floor Tile: 3/16 inch.
- G. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.
 - 1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
 - 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."
- H. Stone Thresholds: Install stone thresholds in same type of setting bed as adjacent floor unless otherwise indicated.

END OF SECTION 09 30 00

SECTION 095113 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes acoustical panels and exposed suspension systems for ceilings.

1.3 DEFINITIONS

- A. AC: Articulation Class.
- B. CAC: Ceiling Attenuation Class.
- C. LR: Light Reflectance coefficient.
- D. NRC: Noise Reduction Coefficient.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
 - 1. Ceiling suspension system members.
 - 2. Method of attaching hangers to building structure.
 - a. Furnish layouts for cast-in-place anchors, clips, and other ceiling attachment devices whose installation is specified in other Sections.
 - 3. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
 - 4. Minimum Drawing Scale: 1/8 inch = 1 foot (1:96)
- C. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.
 - 1. Acoustical Panel: Set of 6-inch- (150-mm-) square Samples of each type, color, pattern, and texture.
 - 2. Exposed Suspension System Members, Moldings, and Trim: Set of 12-inch- (300-mm-) long Samples of each type, finish, and color.
- D. Maintenance Data: For finishes to include in maintenance manuals.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.5 QUALITY ASSURANCE

- A. Source Limitations: Obtain each type of acoustical ceiling panel and supporting suspension system through one source from a single manufacturer.
 - 1. Surface-Burning Characteristics: Provide acoustical panels with the following surface-burning characteristics complying with ASTM E 1264 for Class A materials as determined by testing identical products per ASTM E 84:
 - a. Smoke-Developed Index: 450 or less.
- B. Seismic Standard: Seismic Design Category D. Provide acoustical panel ceilings designed and installed to withstand the effects of earthquake motions according to the following:
- C. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

1.8 COORDINATION

- A. Coordinate layout and installation of acoustical panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

1.9 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Acoustical Ceiling Panels: Full-size panels equal to 2.0 percent of quantity installed.
 - 2. Suspension System Components: Quantity of each exposed component equal to 2.0 percent of quantity installed.
 - 3. Hold-Down Clips: Equal to 2.0 percent of quantity installed.

PART 2 - PRODUCTS

2.1 ACOUSTICAL PANELS, GENERAL

- A. Acoustical Panel Standard: Provide manufacturer's standard panels of configuration indicated that comply with ASTM E 1264 classifications as designated by types, patterns, acoustical ratings, and light reflectances, unless otherwise indicated.
 - 1. Mounting Method for Measuring NRC: Type E-400; plenum mounting in which face of test specimen is 15-3/4 inches (400 mm) away from test surface per ASTM E 795.
- B. Acoustical Panel Colors and Patterns: Match appearance characteristics indicated for each product type.
 - 1. Where appearance characteristics of acoustical panels are indicated by referencing pattern designations in ASTM E 1264 and not manufacturers' proprietary product designations, provide products selected by Architect from each manufacturer's full range that comply with requirements indicated for type, pattern, color, light reflectance, acoustical performance, edge detail, and size.
- C. Antimicrobial Fungicide Treatment: Provide acoustical panels with face and back surfaces coated with antimicrobial treatment consisting of manufacturer's standard formulation with fungicide added to inhibit growth of mold and mildew and showing no mold or mildew growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.

2.2 ACOUSTICAL PANELS FOR ACOUSTICAL PANEL CEILINGS

- A. Subject to compliance with requirements, provide products as follows. Submit requests for substitutions as required by General Conditions.
 - 1. APC 1: Armstrong #2822 with Prelude #7301 HD Grid and #7808 2" wall molding, OR, USG #88135 with Donn DX26 HD Grid and 2" M20SM wall molding.
- B. Antimicrobial Treatment: Fungicide based.

2.3 METAL SUSPENSION SYSTEMS, GENERAL

- A. Comply with CISCA 3-4 and IBC 2015 seismic installation requirements.
- B. Metal Suspension System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635.
- C. Finishes and Colors, General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Provide manufacturer's standard factory-applied finish for type of system indicated.
 - 1. High-Humidity Finish: Comply with ASTM C 635 requirements for "Coating Classification for Severe Environment Performance" where high-humidity finishes are indicated.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Attachment Devices: Size for five times the design load indicated in ASTM C 635, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.
- E. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
 - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
 - 2. Stainless-Steel Wire: ASTM A 580/A 580M, Type 304, nonmagnetic.
 - 3. Nickel-Copper-Alloy Wire: ASTM B 164, nickel-copper-alloy UNS No. N04400.
 - 4. Size: Select wire diameter so its stress at 3 times hanger design load (ASTM C 635, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- (2.69-mm.) diameter wire.
- F. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.
- G. Angle Hangers: Angles with legs not less than 7/8 inch (22 mm) wide; formed with 0.04-inch- (1-mm-) thick, galvanized steel sheet complying with ASTM A 653/A 653M, G90 (Z275) coating designation; with bolted connections and 5/16-inch- (8-mm-) diameter bolts.
- H. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- I. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.
- J. Seismic Clips: Manufacturer's standard seismic clips designed and spaced to secure acoustical panels in-place.
- K. Hold-Down Clips: Where indicated, provide manufacturer's standard hold-down clips spaced 24 inches (610 mm) o.c. on all cross tees.
- L. Impact Clips: Where indicated, provide manufacturer's standard impact-clip system designed to absorb impact forces against acoustical panels.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
 - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

3.3 INSTALLATION

- A. General: Install acoustical panel ceilings to comply with ASTM C 636 and seismic design Category D requirements, per manufacturer's written instructions and CISCA's "Ceiling Systems Handbook for Zones 3-4", and IBC 2006 seismic installation requirements.
- B. Suspend ceiling hangers from building's structural members and as follows:
 - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
 - 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 - 3. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 - 4. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
 - 5. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
 - 6. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both structure to which hangers are attached and type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
 - 7. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
 - 8. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
 - 9. Do not attach hangers to steel deck tabs.
 - 10. Do not attach hangers to steel roof deck. Attach hangers to structural members.
 - 11. Space hangers not more than 48 inches (1200 mm) o.c. along each member supported directly from hangers, unless otherwise indicated; provide hangers not more than 8 inches (200 mm) from ends of each member.
 - 12. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
 - 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
 - 2. Screw attach moldings to substrate at intervals not more than 16 inches (400 mm) o.c. and not more than 3 inches (75 mm) from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet (3.2 mm in 3.6 m). Miter corners accurately and connect securely.
 - 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fit accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
 - 1. Arrange directionally patterned acoustical panels as follows:
 - a. As indicated on reflected ceiling plans.
 - 2. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension system runners and moldings.
 - 3. For reveal-edged panels on suspension system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
 - 4. For reveal-edged panels on suspension system members with box-shaped flanges, install panels with reveal surfaces in firm contact with suspension system surfaces and panel faces flush with bottom face of runners.
 - 5. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
 - 6. Install hold-down clips in areas indicated, in areas required by authorities having jurisdiction, and for fire-resistance ratings; space as recommended by panel manufacturer's written instructions, unless otherwise indicated.
 - 7. Protect lighting fixtures and air ducts to comply with requirements indicated for fire-resistance-rated assembly.

3.4 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 09 51 13

SECTION 096513 - RESILIENT BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Resilient base.
 - 2. Resilient molding accessories.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples: For each exposed product and for each color and texture specified, not less than 12 inches (300 mm) long.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Low-Emitting Materials: Flooring system shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.2 THERMOSET-RUBBER BASE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Burke Mercer Flooring Products, Division of Burke Industries Inc.
 - 2. Johnsonite
 - 3. Roppe Corporation, USA.
 - 4. Armstrong World Industries
 - 5. Flexco
- B. Product Standard: ASTM F 1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).
 - 1. Style:
 - a. Cove base with toe
- C. Min. thickness: 0.125 inch (3.2 mm).
- D. Height: 4 inches (102 mm).
- E. Lengths: Coils in manufacturer's standard length.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- F. Outside Corners: Job formed
- G. Inside Corners: Job formed
- H. Colors: As selected by Architect from full range of industry colors.

2.3 RUBBER STAIR ACCESSORIES

- A. Fire-Test-Response Characteristics: As determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Armstrong World Industries, Inc.
 - 2. Burke Mercer Flooring Products, Division of Burke Industries Inc.
 - 3. Flexco.
 - 4. Johnsonite; A Tarkett Company.
 - 5. Roppe Corporation, USA.
- C. Colors and Patterns: As selected by Architect from full range of industry colors.

2.4 RUBBER MOLDING ACCESSORY

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Roppe Corporation, USA.
 - 2. VPI, LLC, Floor Products Division.
- B. Description: Rubber nosing for resilient flooring, reducer strip for resilient flooring, joiner for tile and carpet, and transition strips.
- C. Profile and Dimensions: As required.
- D. Locations: Provide rubber molding accessories at intersection of dissimilar flooring materials, or change of flooring material elevation.
- E. Colors and Patterns: As selected by Architect from full range of industry colors.

2.5 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.
 - 1. Adhesives shall have a VOC content of 50 g/L or less except that adhesive for rubber stair treads shall have a VOC content of 60 g/L or less.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Adhesives shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

PART 3 - EXECUTION

3.1 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates for Resilient Stair Accessories: Prepare horizontal surfaces according to ASTM F 710.
 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
 3. Alkalinity and Adhesion Testing: Perform tests recommended by manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
 4. Moisture Testing: Proceed with installation only after substrates pass testing according to manufacturer's written recommendations, but not less stringent than the following:
 - a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
 - b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have maximum 75 percent relative humidity level.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install resilient products until they are the same temperature as the space where they are to be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.2 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.
- G. Preformed Corners: Install preformed corners before installing straight pieces.
- H. Job-Formed Corners:
 - 1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches (76 mm) in length.
 - a. Form without producing discoloration (whitening) at bends.
 - 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches (76 mm) in length.

3.3 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 09 65 13

SECTION 096519 - RESILIENT TILE FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid vinyl floor tile.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Shop Drawings: For each type of floor tile. Include floor tile layouts, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.

1. Show details of special patterns.

C. Samples: Full-size units of each color and pattern of floor tile required.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance data.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Fire-Test-Response Characteristics: For resilient tile flooring, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.

1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.

B. FloorScore Compliance: Resilient tile flooring shall comply with requirements of FloorScore certification.

C. Low-Emitting Materials: Flooring system shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.2 SOLID VINYL FLOOR TILE

A. Products: Subject to compliance with requirements, provide the following:

1. Estrie Products International, American Biltrite, "Texas Granite".
2. Submit equal products for approval 21 days prior to bid date.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Tile Standard: ASTM F 1700.
 - 1. Class: Class I, monolithic vinyl tile
 - 2. Type: A, smooth surface
- C. Thickness: 0.125 inch (3.2 mm).
- D. Size: 24 by 24 inches (610 by 610 mm).
- E. Colors and Patterns: As selected by Architect from full range of industry colors.

2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated. Install Ardex Featherfinish as required to provide level, uniform substrate.
- B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.
 - 1. Adhesives shall comply with the following limits for VOC content:
 - a. Vinyl Composition Tile Adhesives: 50 g/L or less.
 - b. Rubber Floor Adhesives: 60 g/L or less.
 - 2. Adhesives shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

PART 3 - EXECUTION

3.1 PREPARATION

- A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates: Prepare according to ASTM F 710.
 - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
 - 3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
 - 4. Moisture Testing: Proceed with installation only after substrates pass testing according to floor tile manufacturer's written recommendations, but not less stringent than the following:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- a. Perform anhydrous calcium chloride test according to ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
- b. Perform relative humidity test using in situ probes according to ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level.

3.2 FLOOR TILE INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor tile.
- B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.
 1. Lay tiles square with room axis.
- C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.
 1. Lay tiles with grain direction alternating in adjacent tiles (basket-weave pattern).
- D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.
- E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Install floor tiles on covers for telephone and electrical ducts, building expansion-joint covers, and similar items in finished floor areas. Maintain overall continuity of color and pattern between pieces of tile installed on covers and adjoining tiles. Tightly adhere tile edges to substrates that abut covers and to cover perimeters.
- H. Adhere floor tiles to flooring substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.3 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.
- B. Cover floor tile until Substantial Completion.

END OF SECTION 09 65 19

SECTION 096813 - TILE CARPETING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes modular, fusion-bonded carpet tile.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show the following:
 - 1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet tiles.
 - 2. Type of subfloor.
 - 3. Type of installation.
 - 4. Pattern of installation.
 - 5. Pattern type, location, and direction.
 - 6. Pile direction.
- C. Samples: For each exposed product and for each color and texture specified.

1.4 INFORMATIONAL SUBMITTALS

- A. Product test reports.
- B. Sample warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance data.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is certified by the International Certified Floorcovering Installers Association at the Commercial II certification level.
- B. Fire-Test-Response Ratings: Where indicated, provide carpet tile identical to those of assemblies tested for fire response according to NFPA 253 by a qualified testing agency.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Comply with CRI 104.

1.8 FIELD CONDITIONS

- A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.

1.9 WARRANTY

- A. Special Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.
 - 1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
 - 2. Failures include, but are not limited to, more than 10 percent edge raveling, snags, runs, dimensional stability, excess static discharge, loss of tuft bind strength, loss of face fiber, and delamination.
 - 3. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 CARPET TILE

- A. Products:
 - 1. As listed on plans.
- B. Size: 24 by 24 inches (610 by 610 mm).
- C. Installation: Monolithic. Pattern direction by Architect.

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet tile manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet tile and is recommended by carpet tile manufacturer for releasable installation.
 - 1. Adhesives shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 2. Adhesives shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance. Examine carpet tile for type, color, pattern, and potential defects.
- B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710.
- C. Existing VCT floor areas to receive carpet: Clean, degrease, and strip wax from existing tile surface. Repair/replace any loose VCT prior to installation of carpet tile.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.
- E. Preparation: Comply with CRI 104, Section 6.2, "Site Conditions; Floor Preparation," and with carpet tile manufacturer's written installation instructions for preparing substrates indicated to receive carpet tile installation.
- F. Installation: Comply with CRI 104, Section 14, "Carpet Modules," and with carpet tile manufacturer's written installation instructions.
- G. Installation Method: As recommended in writing by carpet tile manufacturer.
- H. Maintain dye lot integrity. Do not mix dye lots in same area.
- I. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet tile manufacturer.
- J. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- K. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.
- L. Install pattern parallel to walls and borders.
- M. Perform the following operations immediately after installing carpet tile:
 - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet tile manufacturer.
 - 2. Remove yarns that protrude from carpet tile surface.
 - 3. Vacuum carpet tile using commercial machine with face-beater element.
- N. Protect installed carpet tile to comply with CRI 104, Section 16, "Protecting Indoor Installations."

END OF SECTION 09 68 13

SECTION 09 91 23 - PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes surface preparation and field painting of exposed interior and exterior items and surfaces.
 - 1. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.
- B. Paint exposed surfaces, except where these Specifications indicate that the surface or material is not to be painted or is to remain natural. If an item or a surface is not specifically mentioned, paint the item or surface the same as similar adjacent materials or surfaces. If a color of finish is not indicated, Architect will select from standard colors and finishes available.
 - 1. Painting includes field painting of exposed bare and covered pipes and ducts (including color coding), hangers, exposed steel and iron supports, and surfaces of mechanical and electrical equipment that do not have a factory-applied final finish.
- C. Do not paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels.
 - 1. Prefinished items include the following factory-finished components:
 - a. Architectural woodwork.
 - b. Acoustical wall panels.
 - c. Toilet enclosures.
 - d. Finished mechanical and electrical equipment.
 - e. Light fixtures.
 - 2. Concealed surfaces include walls or ceilings in the following generally inaccessible spaces:
 - a. Foundation spaces.
 - b. Furred areas.
 - c. Ceiling plenums.
 - d. Utility tunnels.
 - e. Pipe spaces.
 - f. Duct shafts.
 - g. Elevator shafts.
 - 3. Finished metal surfaces include the following:
 - a. Anodized aluminum.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- b. Stainless steel.
 - c. Chromium plate.
 - d. Copper and copper alloys.
 - e. Bronze and brass.
 - 4. Operating parts include moving parts of operating equipment and the following:
 - a. Valve and damper operators.
 - b. Linkages.
 - c. Sensing devices.
 - d. Motor and fan shafts.
 - 5. Labels: Do not paint over UL, FMG, or other code-required labels or equipment name, identification, performance rating, or nomenclature plates.
- D. Related Sections include the following:
- 1. Division 2 Section "Hot-Mix Asphalt Paving" for traffic-marking paint.
 - 2. Division 5 Section "Structural Steel" for shop priming structural steel.
 - 3. Division 5 Section "Metal Fabrications" for shop priming ferrous metal.
 - 4. Division 6 Section "Interior Architectural Woodwork" for shop priming interior architectural woodwork.
 - 5. Division 8 Section "Steel Doors and Frames" for factory priming steel doors and frames.
 - 6. Division 8 Section "Wood Windows" for shop priming unclad wood windows.
 - 7. Division 9 Section "Gypsum Board Assemblies" for surface preparation of gypsum board.

1.3 DEFINITIONS

- A. General: Standard coating terms defined in ASTM D 16 apply to this Section.
- 1. Flat refers to a lusterless or matte finish with a gloss range below 15 when measured at an 85-degree meter.
 - 2. Eggshell refers to low-sheen finish with a gloss range between 20 and 35 when measured at a 60-degree meter.
 - 3. Semigloss refers to medium-sheen finish with a gloss range between 35 and 70 when measured at a 60-degree meter.
 - 4. Full gloss refers to high-sheen finish with a gloss range more than 70 when measured at a 60-degree meter.

1.4 SUBMITTALS

- A. Product Data: For each paint system indicated. Include block fillers and primers.
- 1. Material List: An inclusive list of required coating materials. Indicate each material and cross-reference specific coating, finish system, and application. Identify each material by manufacturer's catalog number and general classification.
 - 2. Manufacturer's Information: Manufacturer's technical information, including label analysis and instructions for handling, storing, and applying each coating material.
- B. Samples for Initial Selection: For each type of finish-coat material indicated.
- C. Qualification Data: For Applicator.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.5 QUALITY ASSURANCE

- A. Applicator Qualifications: A firm or individual experienced in applying paints and coatings similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.
- B. Source Limitations: Obtain block fillers and primers for each coating system from the same manufacturer as the finish coats.
- C. Accompany Owner's maintenance personnel for inspection of work at completion of project.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to Project site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label and the following information:
 - 1. Product name or title of material.
 - 2. Product description (generic classification or binder type).
 - 3. Manufacturer's stock number and date of manufacture.
 - 4. Contents by volume, for pigment and vehicle constituents.
 - 5. Thinning instructions.
 - 6. Application instructions.
 - 7. Color name and number.
 - 8. VOC content.
- B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F (7 deg C). Maintain storage containers in a clean condition, free of foreign materials and residue.
 - 1. Protect from freezing. Keep storage area neat and orderly. Remove oily rags and waste daily.

1.7 PROJECT CONDITIONS

- A. Apply waterborne paints only when temperatures of surfaces to be painted and surrounding air are between 50 and 90 deg F (10 and 32 deg C).
- B. Apply solvent-thinned paints only when temperatures of surfaces to be painted and surrounding air are between 45 and 95 deg F (7 and 35 deg C).
- C. Do not apply paint in snow, rain, fog, or mist; or when relative humidity exceeds 85 percent; or at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.
 - 1. Painting may continue during inclement weather if surfaces and areas to be painted are enclosed and heated within temperature limits specified by manufacturer during application and drying periods.

1.8 EXTRA MATERIALS

- A. Furnish extra paint materials from the same production run as the materials applied and in the quantities described below. Package with protective covering for storage and identify with labels describing contents. Deliver extra materials to Owner.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Quantity: Furnish Owner with extra paint materials in quantities indicated below:
 - a. 2 gal. (7.5 L) of each color applied.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, products listed in other Part 2 articles.
- B. Products: Subject to compliance with requirements, provide one of the products listed in other Part 2 articles.
- C. Manufacturers:
 1. Sherwin-Williams
 2. Benjamin Moore
 3. PPG

2.2 PAINT MATERIALS, GENERAL

- A. Material Compatibility: Provide block fillers, primers, and finish-coat materials that are compatible with one another and with the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience. When painting a previously painted surface, thoroughly clean, degrease, and prime old surfaces as required to ensure paint compatibility and adhesion.
- B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified that are factory formulated and recommended by manufacturer for application indicated. Paint-material containers not displaying manufacturer's product identification will not be acceptable.
 1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.
- C. Chemical Components of Interior Paints and Coatings: Provide products that comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24) and the following chemical restrictions:
 1. Flat Paints and Coatings: VOC content of not more than 50 g/L.
 2. Non-Flat Paints and Coatings: VOC content of not more than 150 g/L.
 3. Anticorrosive Coatings: VOC content of not more than 250 g/L.
 4. Varnishes and Sanding Sealers: VOC content of not more than 350 g/L.
 5. Stains: VOC content of not more than 250 g/L.
 6. Aromatic Compounds: Paints and coatings shall not contain more than 1.0 percent by weight of total aromatic compounds (hydrocarbon compounds containing one or more benzene rings).
 7. Restricted Components: Paints and coatings shall not contain any of the following:
 - a. Acrolein.
 - b. Acrylonitrile.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- c. Antimony.
- d. Benzene.
- e. Butyl benzyl phthalate.
- f. Cadmium.
- g. Di (2-ethylhexyl) phthalate.
- h. Di-n-butyl phthalate.
- i. Di-n-octyl phthalate.
- j. 1,2-dichlorobenzene.
- k. Diethyl phthalate.
- l. Dimethyl phthalate.
- m. Ethylbenzene.
- n. Formaldehyde.
- o. Hexavalent chromium.
- p. Isophorone.
- q. Lead.
- r. Mercury.
- s. Methyl ethyl ketone.
- t. Methyl isobutyl ketone.
- u. Methylene chloride.
- v. Naphthalene.
- w. Toluene (methylbenzene).
- x. 1,1,1-trichloroethane.
- y. Vinyl chloride.

- D. Colors: As selected by Architect from manufacturer's full range.

2.3 CONCRETE UNIT MASONRY BLOCK FILLERS

- A. Concrete Unit Masonry Block Filler: Factory-formulated high-performance latex block fillers.

- 1. Sherwin-Williams; PrepRite Interior/Exterior Block Filler B25W25: Apply 3 coats except at food prep areas and toilet rooms, which shall receive 4 coats.

2.4 EXTERIOR PRIMERS

- A. Exterior Concrete and Masonry Primer: Factory-formulated alkali-resistant acrylic-latex primer for exterior application.

- 1. Sherwin-Williams; Loxon Exterior Masonry Acrylic Primer A24W300: Applied at a dry film thickness of not less than 3.0 mils (0.076 mm).
- 2. Sherwin-Williams; A-100 Latex Exterior Wood Primer B42W41: Applied at a dry film thickness of not less than 1.4 mils (0.036 mm).

- B. Exterior Wood Primer for Acrylic Enamels: Factory-formulated alkyd or latex wood primer for exterior application.

- 1. Sherwin-Williams; A-100 Exterior Latex Wood Primer B42W41: Applied at a dry film

- C. Exterior Wood Primer for Alkyd Enamels: Factory-formulated alkyd or latex wood primer for exterior application.

- 1. Sherwin-Williams; A-100 Exterior Latex Wood Primer B42W42: Applied at a dry film thickness of not less than 1.4 mils (0.036 mm).

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- D. Exterior Ferrous-Metal Primer: Factory-formulated rust-inhibitive metal primer for exterior application.
 - 1. Sherwin-Williams; Kem Kromik Universal Metal Primer B50NZ6/B50WZ1: Applied at a dry film thickness of not less than 3.0 mils (0.076 mm).
- E. Exterior Galvanized Metal Primer: Factory-formulated galvanized metal primer for exterior application.
 - 1. Sherwin-Williams; primer not required over this substrate.
 - 2. Sherwin-Williams; Galvite HS Paint B50WZ3: Applied at a dry film thickness of not less than 2.0 mils (0.051 mm).
- F. Exterior Aluminum Primer under Acrylic Finishes: Factory-formulated acrylic-based metal primer for exterior application.
 - 1. Sherwin-Williams; primer not required over this substrate.
 - 2. Sherwin-Williams; DTM Acrylic Primer/Finish B66W1: Applied at a dry film thickness of not less than 2.5 mils (0.064 mm).
- G. Exterior Aluminum Primer under Alkyd Finishes: Factory-formulated acrylic-based metal primer for exterior application.
 - 1. Sherwin-Williams; DTM Wash Primer B71Y1: Applied at a dry film thickness of not less than 2.5 mils (0.064 mm).

2.5 INTERIOR PRIMERS

- A. Interior Concrete and Masonry Primer: Factory-formulated alkali-resistant acrylic-latex interior primer for interior application.
 - 1. Sherwin-Williams; PrepRite Masonry Primer B28W300: Applied at a dry film thickness of not less than 3.0 mils (0.076 mm).
- B. Interior Gypsum Board Primer: Factory-formulated latex-based primer for interior application.
 - 1. Sherwin-Williams; PrepRite 200 Latex Wall Primer B28W200 Series: Applied at a dry film thickness of not less than 1.6 mils (0.041 mm).
- C. Interior Wood Primer for Acrylic-Enamel and Semigloss Alkyd-Enamel Finishes: Factory-formulated alkyd- or acrylic-latex-based interior wood primer.
 - 1. Sherwin-Williams; PrepRite Classic Interior Primer B28W101 Series: Applied at a dry film thickness of not less than 1.6 mils (0.041 mm).
- D. Interior Wood Primer for Full-Gloss Alkyd-Enamel Finishes: Factory-formulated alkyd- or acrylic-latex-based interior wood primer.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Sherwin-Williams; PrepRite Wall and Wood Primer B49W200 Series: Applied at a dry film thickness of not less than 1.6 mils (0.041 mm).
- E. Interior Ferrous-Metal Primer: Factory-formulated quick-drying rust-inhibitive alkyd-based metal primer.
 1. Sherwin-Williams; Kem Kromik Universal Metal Primer B50NZ6/B50WZ1: Applied at a dry film thickness of not less than 3.0 mils (0.076 mm).
- F. Interior Zinc-Coated Metal Primer: Factory-formulated galvanized metal primer.
 1. Sherwin-Williams; Galvite HS B50WZ30: Applied at a dry film thickness of not less than 3.0 mils (0.076 mm).

2.6 EXTERIOR FINISH COATS

- A. Exterior Low-Luster Acrylic Paint: Factory-formulated low-sheen (eggshell) acrylic-latex paint for exterior application.
 1. Sherwin-Williams; A-100 Exterior Latex Satin House & Trim Paint A82 Series: Applied at a dry film thickness of not less than 1.5 mils (0.038 mm), 2 coats minimum.
- B. Exterior Semigloss Acrylic Enamel: Factory-formulated semigloss waterborne acrylic-latex enamel for exterior application.
 1. Sherwin-Williams; A-100 Latex Gloss A8 Series: Applied at a dry film thickness of not less than 1.3 mils (0.033 mm), 2 coats minimum.
- C. Exterior Full-Gloss Acrylic Enamel for Ferrous and Other Metals: Factory-formulated full-gloss waterborne acrylic-latex enamel for exterior application.
 1. Sherwin-Williams; DTM Acrylic Coating Gloss (Waterborne) B66W100 Series: Applied at a dry film thickness of not less than 2.4 mils (0.061 mm), 2 coats minimum.
- D. Exterior Full-Gloss Alkyd Enamel: Factory-formulated full-gloss alkyd enamel for exterior application.
 1. Sherwin-Williams; Industrial Enamel B-54 Series: Applied at a dry film thickness of not less than 2.0 mils (0.051 mm), 2 coats minimum.

2.7 INTERIOR FINISH COATS

- A. Interior Flat Acrylic Paint: Factory-formulated flat acrylic-emulsion latex paint for interior application.
 1. Sherwin-Williams; ProMar 200 Interior Latex Flat Wall Paint B30W200 Series: Applied at a dry film thickness of not less than 1.4 mils (0.036 mm), 2 coats minimum.
- B. Interior Flat Latex-Emulsion Size: Factory-formulated flat latex-based interior paint.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Sherwin-Williams; ProMar 200 Interior Latex Flat Wall Paint B30W200 Series: Applied at a dry film thickness of not less than 1.4 mils (0.036 mm), 2 coats minimum.
 - C. Interior Low-Luster Acrylic Enamel: Factory-formulated eggshell acrylic-latex interior enamel.
 1. Sherwin-Williams; ProMar 200 Interior Latex Egg-Shell Enamel B20W200 Series: Applied at a dry film thickness of not less than 1.6 mils (0.041 mm), 3 coats minimum.
 - D. Interior Semigloss Acrylic Enamel: Factory-formulated semigloss acrylic-latex enamel for interior application.
 1. Sherwin-Williams; ProMar 200 Interior Latex Semi-Gloss Enamel B31W200 Series: Applied at a dry film thickness of not less than 1.3 mils (0.033 mm), 3 coats minimum.
 - E. Interior Full-Gloss Acrylic Enamel: Factory-formulated full-gloss acrylic-latex interior enamel.
 1. Sherwin-Williams; ProMar 200 Interior Latex Gloss Enamel B21W201: Applied at a dry film thickness of not less than 1.5 mils (0.038 mm), 3 coats minimum.
 - F. Interior Semigloss Alkyd Enamel: Factory-formulated semigloss alkyd enamel for interior application.
 1. Sherwin-Williams; ProMar 200 Interior Alkyd Semi-Gloss Enamel B34W200 Series: Applied at a dry film thickness of not less than 1.7 mils (0.043 mm), 3 coats minimum.
- 2.8 INTERIOR WOOD STAINS AND VARNISHES
- A. Open-Grain Wood Filler: Factory-formulated paste wood filler applied at spreading rate recommended by manufacturer.
 1. Sherwin-Williams; Sher-Wood Fast-Dry Filler.
 - B. Interior Wood Stain: Factory-formulated alkyd-based penetrating wood stain for interior application applied at spreading rate recommended by manufacturer.
 1. Minwax
 2. Sherwin-Williams; Wood Classics Interior Oil Stain A-48 Series.
 - C. Clear Sanding Sealer: Factory-formulated fast-drying alkyd-based clear wood sealer applied at spreading rate recommended by manufacturer.
 1. Sherwin-Williams; Wood Classics Fast Dry Sanding Sealer B26V43.
 - D. Interior Alkyd- or Polyurethane-Based Clear Satin Varnish: Factory-formulated alkyd- or polyurethane-based clear varnish.
 1. Sherwin-Williams; Wood Classics Fast Dry Oil Varnish, Satin A66-300 Series.
 - E. Interior Waterborne Clear Satin Varnish: Factory-formulated clear satin acrylic-based polyurethane varnish applied at spreading rate recommended by manufacturer.
 1. Sherwin-Williams; Wood Classics Waterborne Polyurethane Satin, A68 Series.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- F. Interior Waterborne Clear Gloss Varnish: Factory-formulated clear gloss acrylic-based polyurethane varnish applied at spreading rate recommended by manufacturer.
 - 1. Sherwin-Williams; Wood Classics Waterborne Polyurethane Gloss, A68 Series.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for paint application.
 - 1. Proceed with paint application only after unsatisfactory conditions have been corrected and surfaces receiving paint are thoroughly dry.
 - 2. Start of painting will be construed as Applicator's acceptance of surfaces and conditions within a particular area.
- B. Coordination of Work: Review other Sections in which primers are provided to ensure compatibility of the total system for various substrates. On request, furnish information on characteristics of finish materials to ensure use of compatible primers.
 - 1. Notify Architect about anticipated problems when using the materials specified over substrates primed by others.

3.2 PREPARATION

- A. General: Remove hardware and hardware accessories, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of size or weight of the item, provide surface-applied protection before surface preparation and painting.
 - 1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.
- B. Cleaning: Before applying paint or other surface treatments, clean substrates of substances that could impair bond of the various coatings. Remove oil and grease before cleaning.
 - 1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.
- C. Surface Preparation: Clean and prepare surfaces to be painted according to manufacturer's written instructions for each particular substrate condition and as specified.
 - 1. Provide barrier coats over incompatible primers or remove and reprime.
 - 2. Cementitious Materials: Prepare concrete, concrete unit masonry, cement plaster, and mineral-fiber-reinforced cement panel surfaces to be painted. Remove efflorescence, chalk, dust, dirt, grease, oils, and release agents. Roughen as required to remove glaze. If hardeners or sealers have been used to improve curing, use mechanical methods of surface preparation.
 - a. Use abrasive blast-cleaning methods if recommended by paint manufacturer.
 - b. Determine alkalinity and moisture content of surfaces by performing appropriate tests. If surfaces are sufficiently alkaline to cause the finish paint to blister and

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- burn, correct this condition before application. Do not paint surfaces if moisture content exceeds that permitted in manufacturer's written instructions.
 - c. Clean concrete floors to be painted with a 5 percent solution of muriatic acid or other etching cleaner. Flush the floor with clean water to remove acid, neutralize with ammonia, rinse, allow to dry, and vacuum before painting.
3. Wood: Clean surfaces of dirt, oil, and other foreign substances with scrapers, mineral spirits, and sandpaper, as required. Sand surfaces exposed to view smooth and dust off.
- a. Scrape and clean small, dry, seasoned knots, and apply a thin coat of white shellac or other recommended knot sealer before applying primer. After priming, fill holes and imperfections in finish surfaces with putty or plastic wood filler. Sand smooth when dried.
 - b. Prime, stain, or seal wood to be painted immediately on delivery. Prime edges, ends, faces, undersides, and back sides of wood, including cabinets, counters, cases, and paneling.
 - c. If transparent finish is required, backprime with spar varnish.
 - d. Backprime paneling on interior partitions where masonry, plaster, or other wet wall construction occurs on back side.
 - e. Seal tops, bottoms, and cutouts of unprimed wood doors with a heavy coat of varnish or sealer immediately on delivery.
4. Ferrous Metals: Clean ungalvanized ferrous-metal surfaces that have not been shop coated; remove oil, grease, dirt, loose mill scale, and other foreign substances. Use solvent or mechanical cleaning methods that comply with SSPC's recommendations.
- a. Blast steel surfaces clean as recommended by paint system manufacturer and according to SSPC-SP 6/NACE No. 3
 - b. Treat bare and sandblasted or pickled clean metal with a metal treatment wash coat before priming.
 - c. Touch up bare areas and shop-applied prime coats that have been damaged. Wire-brush, clean with solvents recommended by paint manufacturer, and touch up with same primer as the shop coat.
5. Galvanized Surfaces: Clean galvanized surfaces with nonpetroleum-based solvents so surface is free of oil and surface contaminants. Remove pretreatment from galvanized sheet metal fabricated from coil stock by mechanical methods.
- D. Material Preparation: Mix and prepare paint materials according to manufacturer's written instructions.
- 1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
 - 2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
 - 3. Use only thinners approved by paint manufacturer and only within recommended limits.
- E. Tinting: Tint each undercoat a lighter shade to simplify identification of each coat when multiple coats of same material are applied. Tint undercoats to match the color of the finish coat, but provide sufficient differences in shade of undercoats to distinguish each separate coat.

3.3 APPLICATION

- A. General: Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.
1. Paint colors, surface treatments, and finishes are indicated in the paint schedules.
 2. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
 3. Provide finish coats that are compatible with primers used.
 4. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, grilles, convector covers, covers for finned-tube radiation, and similar components are in place. Extend coatings in these areas, as required, to maintain system integrity and provide desired protection.
 5. Paint surfaces behind movable equipment and furniture the same as similar exposed surfaces. Before final installation of equipment, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
 6. Paint interior surfaces of ducts with a flat, nonspecular black paint where visible through registers or grilles.
 7. Paint back sides of access panels and removable or hinged covers to match exposed surfaces.
 8. Finish exterior doors on tops, bottoms, and side edges the same as exterior faces.
 9. Finish interior of wall and base cabinets and similar field-finished casework to match exterior.
 10. Sand lightly between each succeeding enamel or varnish coat.
- B. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.
1. The number of coats and film thickness required are the same regardless of application method. Do not apply succeeding coats until previous coat has cured as recommended by manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
 2. Omit primer over metal surfaces that have been shop primed and touchup painted.
 3. If undercoats, stains, or other conditions show through final coat of paint, apply additional coats until paint film is of uniform finish, color, and appearance. Give special attention to ensure that edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
 4. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, and does not deform or feel sticky under moderate thumb pressure, and until application of another coat of paint does not cause undercoat to lift or lose adhesion.
- C. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.
1. Brushes: Use brushes best suited for type of material applied. Use brush of appropriate size for surface or item being painted.
 2. Rollers: Use rollers of carpet, velvet-back, or high-pile sheep's wool as recommended by manufacturer for material and texture required.
 3. Spray Equipment: Use airless spray equipment with orifice size as recommended by manufacturer for material and texture required.
- D. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate to achieve dry film thickness indicated. Provide total dry film thickness of the entire system as recommended by manufacturer.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- E. Mechanical and Electrical Work: Painting of mechanical and electrical work is limited to items exposed in equipment rooms and occupied spaces, including exposed items in 2-story wing corridors which have no finished ceiling.
- F. Mechanical items to be painted include, but are not limited to, the following:
 - 1. Mechanical equipment that is indicated to have a factory-primed finish for field painting.
 - 2. Exposed ductwork in corridors of 2-story wing.
- G. Electrical items to be painted include, but are not limited to, the following:
 - 1. Electrical equipment that is indicated to have a factory-primed finish for field painting.
 - 2. Cable tray in corridors of 2-story wing corridors.
- H. Block Fillers: Apply block fillers to concrete masonry block at a rate to ensure complete coverage with pores filled. Apply minimum 3 coats block filler at all toilet room walls.
- I. Prime Coats: Before applying finish coats, apply a prime coat, as recommended by manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn-through or other defects due to insufficient sealing.
- J. Pigmented (Opaque) Finishes: Completely cover surfaces as necessary to provide a smooth, opaque surface of uniform finish, color, appearance, and coverage. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections will not be acceptable.
- K. Transparent (Clear) Finishes: Use multiple coats to produce a glass-smooth surface film of even luster. Provide a finish free of laps, runs, cloudiness, color irregularity, brush marks, orange peel, nail holes, or other surface imperfections.
 - 1. Provide satin finish for final coats.
- L. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.

3.4 CLEANING

- A. Cleanup: At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from Project site.
 - 1. After completing painting, clean glass and paint-spattered surfaces. Remove spattered paint by washing and scraping without scratching or damaging adjacent finished surfaces.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.5 PROTECTION

- A. Protect work of other trades, whether being painted or not, against damage from painting. Correct damage by cleaning, repairing or replacing, and repainting, as approved by Architect.
- B. Provide "Wet Paint" signs to protect newly painted finishes. After completing painting operations, remove temporary protective wrappings provided by others to protect their work.
 - 1. After work of other trades is complete, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

END OF SECTION 09 91 23

SECTION 10 14 24 – IDENTIFYING DEVICES

PART 1 - GENERAL

1.01 DESCRIPTION

- A. The "Bidding Documents", "General Conditions", "Special Conditions" and other pertinent Sections of the Project Documents are hereby declared to be part of this division, the same as if fully set forth herein.
- B. Scope of Work:
 - 1. Provide all labor, materials, transportation, equipment and all support brackets, standards, clips, bolts, etc., necessary for the installation of signs as required for the Work under this section for the following:
 - a. Interior signage

1.03 SUBMITTALS

- PART 1 - Submit shop drawings and product data to Architect for approval in accordance with the General conditions and General Requirements of the Contract.

PART 2 - PRODUCT

2.01 INTERIOR SIGNAGE

- A. Signage shall comply with all requirements of the Americans with Disabilities Act.
- B. Submit shop drawings for approved prior to fabrication. Approved manufacturers are National Signage Affiliates, Best Manufacturing Co., and Advance Corporation.
- C. See plans for signage sizes and features.
- D. Interior signage to be mechanically fastened and not reliant on adhesives or glues.

2.03 TEMPORARY JOB SIGN

Contractor shall relocate the existing job sign as shown on the plans, and replace the name of the site work contractor with his own company name. Use graphics matching those on the sign. No other sign shall be erected on the premises.

PART 3 - EXECUTION

3.01 PLACEMENT

- A. Inspect surfaces for application of signs to determine acceptability for placement of signs.
- B. Signs and letters shall be installed true and level in proper location as shown on plans.

END OF SECTION 10 14 24

SECTION 10 21 13 - TOILET COMPARTMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Solid-polymer toilet compartments configured as toilet enclosures.

1.2 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For toilet compartments. Include plans, elevations, sections, details, and attachments to other work.
- C. Samples for each exposed product and for each color and texture specified.
- D. Product certificates.
- E. Maintenance data.

1.3 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84, or another standard acceptable to authorities having jurisdiction, by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 75 or less.
 - 2. Smoke-Developed Index: 450 or less.
 - 3. Material Fire Ratings:
 - a. NFPA – Class B.
 - b. ICC – Class B.
- B. Regulatory Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA) and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities" and ICC/ANSI A117.1 for toilet compartments designated as accessible.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Zamac: ASTM B 86, commercial zinc-alloy die castings.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.2 SOLID-POLYMER UNITS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Bradley Corporation; Mills Partitions.
 - 2. Partition Systems Incorporated of South Carolina.
 - 3. Rockville Partitions Incorporated.
 - 4. Santana Products, Inc.
- B. Toilet-Enclosure Style: Overhead braced.
- C. Door, Panel, and Pilaster Construction: Solid, high-density polyethylene (HDPE) panel material, not less than 1 inch (25 mm) thick, seamless, with eased edges, and with homogenous color and pattern throughout thickness of material.
 - 1. Continuous aluminum hinges.
 - 2. Polymer Panel Finish: One color and pattern in each room.
 - a. Color and Pattern: As selected by Architect from manufacturer's full range
- D. Pilaster Shoes and Sleeves (Caps): Stainless steel.
- E. Brackets (Fittings):
 - 1. Full-Height (Continuous) Type: extruded aluminum.

2.3 ACCESSORIES

- A. Hardware and Accessories: Manufacturer's standard design, heavy-duty operating hardware and accessories.
 - 1. Material: Chrome-plated zamac
 - 2. Hinges: Continuous aluminum that swings to a closed or partially open position.
 - 3. Latch and Keeper: Manufacturer's standard surface-mounted latch unit designed for emergency access and with combination rubber-faced door strike and keeper. Provide units that comply with regulatory requirements for accessibility at compartments designated as accessible.
 - 4. Coat Hook: Manufacturer's standard combination hook and rubber-tipped bumper, sized to prevent in-swinging door from hitting compartment-mounted accessories.
 - 5. Door Bumper: Manufacturer's standard rubber-tipped bumper at out-swinging doors.
 - 6. Door Pull: Manufacturer's standard unit at out-swinging doors that complies with regulatory requirements for accessibility. Provide units on both sides of doors at compartments designated as accessible.
- B. Overhead Bracing: Manufacturer's standard continuous, extruded-aluminum head rail with antigrip profile and in manufacturer's standard finish.
- C. Anchorages and Fasteners: Manufacturer's standard exposed fasteners of stainless steel or chrome-plated steel or brass, finished to match the items they are securing, with theft-resistant-type heads. Provide sex-type bolts for through-bolt applications. For concealed anchors, use stainless steel, hot-dip galvanized steel, or other rust-resistant, protective-coated steel.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.4 FABRICATION

- A. Overhead-Braced Units: Provide manufacturer's standard corrosion-resistant supports, leveling mechanism, and anchors at pilasters to suit floor conditions. Provide shoes at pilasters to conceal supports and leveling mechanism.
- B. Door Size and Swings: Unless otherwise indicated, provide 24-inch- (610-mm-) wide, in-swinging doors for standard toilet compartments and 36-inch- (914-mm-) wide, out-swinging doors with a minimum 32-inch- (813-mm-) wide, clear opening for compartments designated as accessible.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Comply with manufacturer's written installation instructions. Install units rigid, straight, level, and plumb. Secure units in position with manufacturer's recommended anchoring devices.
- B. Clearances: Maximum 1/2 inch (13 mm) between pilasters and panels; 1 inch (25 mm) between panels and walls.

3.2 ADJUSTING

- A. Hardware Adjustment: Adjust and lubricate hardware according to hardware manufacturer's written instructions for proper operation. Set hinges on in-swinging doors to hold doors open approximately 30 degrees from closed position when unlatched. Set hinges on out-swinging doors to return doors to fully closed position.

END OF SECTION 10 21 13

SECTION 10 28 00 – TOILET ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Public-use washroom accessories.
 - 2. Warm-air dryers.
 - 3. Underlavatory guards.
 - 4. Custodial accessories.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.
 - 1. Identify locations using room designations indicated.
 - 2. Identify products using designations indicated.

1.3 INFORMATIONAL SUBMITTALS

- A. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

- A. Maintenance data.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

1.6 WARRANTY

- A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: 15 years from date of Substantial Completion.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 2 - PRODUCTS

2.1 PUBLIC-USE WASHROOM ACCESSORIES

- A. See plans for accessory schedule.

2.2 WARM-AIR DRYERS

- A. Manufacturers: Subject to compliance with requirements, provide product identified on plans.

2.3 UNDERLAVATORY GUARDS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Plumberex Specialty Products, Inc.
 - 2. Truebro by IPS Corporation.
- B. Underlavatory Guard:
 - 1. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
 - 2. Material and Finish: Antimicrobial, molded plastic, white.

2.4 FABRICATION

- A. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Grab Bars: Install to withstand a downward load of at least 250 lbf (1112 N), when tested according to ASTM F 446.

END OF SECTION 10 28 00

SECTION 31 10 00 - SITE CLEARING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Protecting existing vegetation to remain.
2. Removing existing vegetation.
3. Clearing and grubbing.
4. Stripping and stockpiling topsoil.
5. Removing above- and below-grade site improvements.
6. Disconnecting, capping or sealing site utilities.
7. Temporary erosion- and sedimentation-control measures.

1.2 MATERIAL OWNERSHIP

- A. Except for stripped topsoil and other materials indicated to be stockpiled or otherwise remain Owner's property, cleared materials shall become Contractor's property and shall be removed from Project site.

1.3 PROJECT CONDITIONS

- A. Traffic: Minimize interference with adjoining roads, streets, walks, and other adjacent occupied or used facilities during site-clearing operations.
1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction.
 2. Provide alternate routes around closed or obstructed traffic ways if required by Owner or authorities having jurisdiction.
- B. Salvable Improvements: Carefully remove items indicated to be salvaged and store on Owner's premises – Horry County School District Maintenance Office.
- C. Utility Locator Service: Notify utility locator service for area where Project is located before site clearing.
- D. Do not commence site clearing operations until temporary erosion- and sedimentation-control and plant protection measures are in place.
- E. The following practices are prohibited within protection zones:
1. Storage of construction materials, debris, or excavated material.
 2. Parking vehicles or equipment.
 3. Foot traffic.
 4. Erection of sheds or structures.
 5. Impoundment of water.
 6. Excavation or other digging unless otherwise indicated.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Satisfactory Soil Material: Requirements for satisfactory soil material are specified in Section 31 20 00 "Earth Moving."
 1. Obtain approved borrow soil material off-site when satisfactory soil material is not available on-site.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Protect and maintain benchmarks and survey control points from disturbance during construction.
- B. Locate and clearly identify trees, shrubs, and other vegetation to remain or to be relocated.
- C. Protect existing site improvements to remain from damage during construction.
 1. Restore damaged improvements to their original condition, as acceptable to Owner.

3.2 TEMPORARY EROSION AND SEDIMENTATION CONTROL

- A. Provide temporary erosion- and sedimentation-control measures to prevent soil erosion and discharge of soil-bearing water runoff or airborne dust to adjacent properties and walkways, according to erosion- and sedimentation-control Drawings and requirements of authorities having jurisdiction.
- B. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.
- C. Inspect, maintain, and repair erosion- and sedimentation-control measures during construction until permanent vegetation has been established.
- D. Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.

3.3 TREE AND PLANT PROTECTION

- A. General: Protect trees and plants remaining on-site according to requirements in Section 015639 "Temporary Tree and Plant Protection."
- B. Repair or replace trees, shrubs, and other vegetation indicated to remain or be relocated that are damaged by construction operations, in a manner approved by Owner representative.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.4 EXISTING UTILITIES

- A. Locate, identify, disconnect, and seal or cap utilities indicated to be removed or abandoned in place.
 - 1. Arrange with utility companies to shut off indicated utilities.
- B. Interrupting Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 - 1. Notify Owner representative not less than two days in advance of proposed utility interruptions.
 - 2. Do not proceed with utility interruptions without Owners written permission.

3.5 CLEARING AND GRUBBING

- A. Remove obstructions, trees, shrubs, and other vegetation to permit installation of new construction.
 - 1. Grind down stumps and remove roots, obstructions, and debris to a depth of 24 inches below exposed subgrade.
 - 2. Use only hand methods for grubbing within protection zones.
- B. Fill depressions caused by clearing and grubbing operations with satisfactory soil material unless further excavation or earthwork is indicated.
 - 1. Place fill material in horizontal layers not exceeding a loose depth of 8 inches, and compact each layer to a density equal to adjacent original ground.

3.6 TOPSOIL STRIPPING

- A. Remove sod and grass before stripping topsoil.
- B. Strip topsoil to a depth of 6 inches in a manner to prevent intermingling with underlying subsoil or other waste materials.
- C. Stockpile topsoil away from edge of excavations without intermixing with subsoil. Grade and shape stockpiles to drain surface water. Cover to prevent windblown dust and erosion by water.

3.7 SITE IMPROVEMENTS

- A. Remove existing above- and below-grade improvements as indicated and necessary to facilitate new construction.

3.8 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Remove surplus soil material, unsuitable topsoil, obstructions, demolished materials, and waste materials including trash and debris, and legally dispose of them off Owner's property.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Separate recyclable materials produced during site clearing from other nonrecyclable materials. Store or stockpile without intermixing with other materials and transport them to recycling facilities. Do not interfere with other Project work.

END OF SECTION 31 10 00

SECTION 31 20 00 - EARTH MOVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Preparing subgrades for sidewalk.
2. Subbase course for concrete sidewalk.
3. Subbase course and base course for asphalt paving.
4. Excavating and backfilling for utility & drainage trenches.

1.2 DEFINITIONS

A. Backfill: Soil material used to fill an excavation.

1. Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.
2. Final Backfill: Backfill placed over initial backfill to fill a trench.

B. Base Course: Aggregate layer placed between the subbase course and hot-mix asphalt paving.

C. Bedding Course: Aggregate layer placed over the excavated subgrade in a trench before laying pipe.

D. Borrow Soil: Satisfactory soil imported from off-site for use as fill or backfill.

E. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.

1. Authorized Additional Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions as directed by Owners representative. Authorized additional excavation and replacement material will be paid for according to Contract provisions for changes in the Work.
2. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions without direction by Owners representative. Unauthorized excavation, as well as remedial work directed by Architect and/or Engineer, shall be without additional compensation.

F. Fill: Soil materials used to raise existing grades.

G. Subbase Course: Aggregate layer placed between the subgrade and base course for hot-mix asphalt pavement, or aggregate layer placed between the subgrade and a cement concrete sidewalk.

H. Subgrade: Uppermost surface of an excavation or the top surface of a fill or backfill immediately below subbase, drainage fill, drainage course, or topsoil materials.

I. Utilities: On-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.3 QUALITY ASSURANCE

- A. Pre-excavation Conference: Conduct conference at project site.

1.4 PROJECT CONDITIONS

- A. Utility Locator Service: Notify utility locator service for area where Project is located before beginning earth moving operations.

PART 2 - PRODUCTS

2.1 SOIL MATERIALS

- A. General: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.
- B. Satisfactory Soils: Soil Classification [Groups GW, GP, GM, SW, SP, and SM according to ASTM D 2487], [Groups A-1, A-2-4, A-2-5, and A-3 according to AASHTO M 145], or a combination of these groups; free of rock or gravel larger than 3 inches (75 mm) in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter.
- C. Unsatisfactory Soils: Soil Classification [Groups GC, SC, CL, ML, OL, CH, MH, OH, and PT according to ASTM D 2487], [Groups A-2-6, A-2-7, A-4, A-5, A-6, and A-7 according to AASHTO M 145], or a combination of these groups.
 - 1. Unsatisfactory soils also include satisfactory soils not maintained within 2 percent of optimum moisture content at time of compaction.
- D. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2 inch sieve and not more than 12 percent passing a No. 200 sieve.
- E. Base Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 95 percent passing a 1-1/2 inch sieve and not more than 8 percent passing a No. 200 sieve.
- F. Engineered Fill: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2 inch sieve and not more than 12 percent passing a No. 200 sieve.
- G. Bedding Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; except with 100 percent passing a 1 inch sieve and not more than 8 percent passing a No. 200 sieve.
- H. Drainage Course: Narrowly graded mixture of washed stone, or crushed or uncrushed gravel; ASTM D 448; coarse-aggregate grading Size 57; with 100 percent passing a 1-1/2 inch sieve and 0 to 5 percent passing a No. 8 sieve.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.2 ACCESSORIES

- A. Detectable Warning Tape: Acid- and alkali-resistant, polyethylene film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches wide and 4 mils thick, continuously inscribed with a description of the utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 24 inches deep; colored to comply with local practice or requirements of authorities having jurisdiction.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earth moving operations.
- B. Protect and maintain erosion and sedimentation controls during earth moving operations.
- C. Protect subgrades and foundation soils from freezing temperatures and frost. Remove temporary protection before placing subsequent materials.

3.2 EXCAVATION, GENERAL

- A. Unclassified Excavation: Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in the Contract Sum or the Contract Time will be authorized for rock excavation or removal of obstructions.
 - 1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.

3.3 EXCAVATION FOR STRUCTURES

- A. Excavations at Edges of Tree- and Plant-Protection Zones:
 - 1. Excavate by hand to indicated lines, cross sections, elevations, and subgrades. Use narrow-tine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.
 - 2. Cut and protect roots according to requirements in Section 015639 "Temporary Tree and Plant Protection."

3.4 EXCAVATION FOR WALKS AND PAVEMENTS

- A. Excavate surfaces under walks and pavements to indicated lines, cross sections, elevations, and subgrades.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.5 EXCAVATION FOR UTILITY TRENCHES

- A. Excavate trenches to indicated gradients, lines, depths, and elevations.
- B. Excavate trenches to uniform widths to provide the following clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches higher than top of pipe or conduit unless otherwise indicated.
- C. Trench Bottoms: Excavate and shape trench bottoms to provide uniform bearing and support of pipes and conduit. Shape subgrade to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits. Remove projecting stones and sharp objects along trench subgrade.
 - 1. Excavate trenches 6 inches deeper than elevation required in rock or other unyielding bearing material, 4 inches deeper elsewhere, to allow for bedding course.
- D. Trenches in Tree- and Plant-Protection Zones:
 - 1. Hand-excavate to indicated lines, cross sections, elevations, and subgrades. Use narrow-tine spading forks to comb soil and expose roots. Do not break, tear, or chop exposed roots. Do not use mechanical equipment that rips, tears, or pulls roots.
 - 2. Do not cut main lateral roots or taproots; cut only smaller roots that interfere with installation of utilities.
 - 3. Cut and protect roots according to requirements in Section 015639 "Temporary Tree and Plant Protection."

3.6 SUBGRADE INSPECTION

- A. Proof-roll subgrade for concrete sidewalks and pavement areas with a pneumatic-tired dump truck to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
- B. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by Architect, without additional compensation.

3.7 UNAUTHORIZED EXCAVATION

- A. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill, with 28-day compressive strength of 2500 psi (17.2 MPa), may be used when approved by Architect.
 - 1. Fill unauthorized excavations under other construction, pipe, or conduit as directed by Architect.

3.8 STORAGE OF SOIL MATERIALS

- A. Stockpile borrow soil materials and excavated satisfactory soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
 - 1. Stockpile soil materials away from edge of excavations. Do not store within drip line of remaining trees.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.9 UTILITY TRENCH BACKFILL

- A. Place backfill on subgrades free of mud, frost, snow, or ice.
- B. Place and compact bedding course on trench bottoms and where indicated. Shape bedding course to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits.
- C. Trenches under Roadways: Provide 4 inch thick, concrete-base slab support for piping or conduit less than 24 inches (unless concrete culverts) below surface of roadways. Place and compact initial backfill of suitable fill, free of particles larger than 1 inch in any dimension, to a height of 12 inches over the pipe or conduit.
 - 1. Carefully compact initial backfill under pipe haunches and compact evenly up on both sides and along the full length of piping or conduit to avoid damage or displacement of piping or conduit. Coordinate backfilling with utilities testing.
- D. Place and compact final backfill of satisfactory soil to final subgrade elevation.
- E. Install warning tape directly above utilities, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

3.10 SOIL FILL

- A. Plow, scarify, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so fill material will bond with existing material.
- B. Place and compact fill material in layers to required elevations as follows:
 - 1. Under grass and planted areas, use satisfactory soil material.
 - 2. Under walks and pavements, use satisfactory soil material.

3.11 SOIL MOISTURE CONTROL

- A. Uniformly moisten or aerate subgrade and each subsequent fill or backfill soil layer before compaction to within 2 percent of optimum moisture content.
 - 1. Do not place backfill or fill soil material on surfaces that are muddy, frozen, or contain frost or ice.
 - 2. Remove and replace, or scarify and air dry, otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.

3.12 COMPACTION OF SOIL BACKFILLS AND FILLS

- A. Place backfill and fill soil materials in layers not more than 8 inches in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers.
- B. Place backfill and fill soil materials evenly on all sides of structures to required elevations, and uniformly along the full length of each structure.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Compact soil materials to not less than the following percentages of maximum dry unit weight according to ASTM 698:
 - 1. Under walkways, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 95 percent.
 - 2. Under turf or unpaved areas, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 90 percent.
 - 3. For utility trenches, compact each layer of initial and final backfill soil material at 90 percent.

3.13 GRADING

- A. General: Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.
- B. Site Rough Grading: Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to required elevations within the following tolerances:
 - 1. Turf or Unpaved Areas: Plus or minus 1 inch.
 - 2. Walks: Plus or minus 1 inch.
 - 3. Pavements: Plus or minus ½ inch.

3.14 SUBBASE AND BASE COURSES UNDER PAVEMENTS AND WALKS

- A. Place subbase course and base course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place subbase course and base courses under pavements and walks as follows:
 - 1. Shape subbase course and base course to required crown elevations and cross-slope grades.
 - 2. Place subbase course and base course that exceeds 6 inches in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches thick or less than 3 inches thick.
 - 3. Compact subbase course and base course at optimum moisture content to required grades, lines, cross sections, and thickness to not less than 95 percent of maximum dry unit weight according to ASTM D 698.

3.15 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified geotechnical engineering testing agency to perform tests and inspections.
- B. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earth moving only after test results for previously completed work comply with requirements.
- C. Footing Subgrade: At footing subgrades, at least one test of each soil stratum will be performed to verify design bearing capacities. Subsequent verification and approval of other footing

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

subgrades may be based on a visual comparison of subgrade with tested subgrade when approved by Architect.

- D. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil materials to depth required; recompact and retest until specified compaction is obtained.

3.16 PROTECTION

- A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.
- B. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.
- C. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.
 - 1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.17 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Remove surplus satisfactory soil and waste materials, including unsatisfactory soil, trash, and debris, and legally dispose of them off Owner's property.

END OF SECTION 31 20 00

SECTION 32 12 16 - ASPHALT PAVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cold milling of existing asphalt pavement.
2. Hot-mix asphalt patching.
3. Hot-mix asphalt paving.
4. Hot-mix asphalt overlay.
5. Asphalt curbs.

B. Related Requirements:

1. Section 312000 "Earth Moving" for subgrade preparation, fill material, unbound-aggregate subbase and base courses, and aggregate pavement shoulders.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at the project job trailer.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1.4 INFORMATIONAL SUBMITTALS

- A. Material Certificates: For each paving material, the contractor shall certify the use of asphalt mixes containing recycled materials will perform equal to mixes produced from all new materials.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A paving-mix manufacturer registered with and approved by SCDOT.
- B. Regulatory Requirements: Comply with materials, workmanship, and other applicable requirements of latest edition of the SCDOT specifications for asphalt paving work.
1. Measurement and payment provisions and safety program submittals included in standard specifications do not apply to this Section.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

PART 2 - PRODUCTS

2.1 AGGREGATES

- A. Coarse Aggregate: ASTM D 692/D 692M, sound; angular crushed stone, crushed gravel, or cured, crushed blast-furnace slag.
- B. Fine Aggregate: Per ASTM D 1073, sharp-edged natural sand or sand prepared from stone, gravel, cured blast-furnace slag, or combinations thereof.
- C. Mineral Filler: Per ASTM D 242/D 242M, rock or slag dust, hydraulic cement, or other inert material.

2.2 ASPHALT MATERIALS

- A. Asphalt Binder: AASHTO M 320, grade of binder to be PG 64-22.
- B. Tack Coat: ASTM D 977 and AASHTO M 140 emulsified asphalt, or ASTM D 2397 and AASHTO M 208 cationic emulsified asphalt, slow setting, diluted in water, of suitable grade and consistency for application.

2.3 AUXILIARY MATERIALS

- A. Recycled Materials for Hot-Mix Asphalt Mixes: Reclaimed asphalt pavement; reclaimed, unbound-aggregate base material; and recycled tires, asphalt shingles, or glass from sources and gradations that have performed satisfactorily in previous installations, equal to performance of required hot-mix asphalt paving produced from all new materials.
- B. Herbicide: Commercial chemical for weed control, registered by the EPA, and not classified as "restricted use" for locations and conditions of application. Provide in granular, liquid, or wettable powder form.

2.4 MIXES

- A. Recycled Content of Hot-Mix Asphalt: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 10/20/40 percent or more than 15/25/50 percent by weight.
 - 1. Surface Course Limit: Recycled content no more than 10 percent by weight.
- B. Hot-Mix Asphalt: Dense-graded, hot-laid, hot-mix asphalt plant mixes by the SCDOT; designed according to procedures in AI MS-2, "Mix Design Methods for Asphalt Concrete and Other Hot-Mix Types"; and complying with the following requirements:
 - 1. Provide mixes with a history of satisfactory performance in geographical area where Project is located.
 - 2. Base Course: SCDOT approved mix LO546.
 - 3. Surface Course: SCDOT approved mix LO546.

PART 3 - EXECUTION

3.1 COLD MILLING

- A. Clean existing pavement surface of loose and deleterious material immediately before cold milling. Remove existing asphalt pavement by cold milling to grades and cross sections indicated.
 - 1. Mill to a depth of 2 inches.
 - 2. Patch surface depressions deeper than 1 inch after milling, before wearing course is laid.

3.2 PATCHING

- A. Asphalt Pavement: Saw cut perimeter of patch and excavate existing pavement section to sound base. Excavate rectangular or trapezoidal patches, extending 24 inches into perimeter of adjacent sound pavement, unless otherwise indicated. Cut excavation faces vertically. Remove excavated material. Recompress existing unbound-aggregate base course to form new subgrade.
- B. Portland Cement Concrete Pavement: Break cracked slabs and roll as required to reseal concrete pieces firmly.
 - 1. Remove disintegrated or badly cracked pavement. Excavate rectangular or trapezoidal patches, extending into perimeter of adjacent sound pavement, unless otherwise indicated. Cut excavation faces vertically. Recompress existing unbound-aggregate base course to form new subgrade.
- C. Tack Coat: Before placing patch material, apply tack coat uniformly to vertical asphalt surfaces abutting the patch. Apply at a rate of 0.05 to 0.15 gal./sq. yd.
 - 1. Allow tack coat to cure undisturbed before applying hot-mix asphalt paving.
 - 2. Avoid smearing or staining adjoining surfaces, appurtenances, and surroundings. Remove spillages and clean affected surfaces.
- D. Placing Patch Material: Fill excavated pavement areas with hot-mix asphalt base mix for full thickness of patch and, while still hot, compact flush with adjacent surface.

3.3 SURFACE PREPARATION

- A. General: Immediately before placing asphalt materials, remove loose and deleterious material from substrate surfaces. Ensure that prepared subgrade is ready to receive paving.
- B. Proof-roll subgrade below pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
- C. Herbicide Treatment: Apply herbicide according to manufacturer's recommended rates and written application instructions. Apply to dry, prepared subgrade or surface of compacted-aggregate base before applying paving materials.
- D. Tack Coat: Apply uniformly to surfaces of existing pavement at a rate of 0.05 to 0.15 gal./sq. yd.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Allow tack coat to cure undisturbed before applying hot-mix asphalt paving.
2. Avoid smearing or staining adjoining surfaces, appurtenances, and surroundings. Remove spillages and clean affected surfaces.

3.4 PLACING HOT-MIX ASPHALT

- A. Machine place hot-mix asphalt on prepared surface, spread uniformly, and strike off. Place asphalt mix by hand in areas inaccessible to equipment in a manner that prevents segregation of mix. Place each course to required grade, cross section, and thickness when compacted.
 1. Spread mix at a minimum temperature of 250 deg F.
 2. Regulate paver machine speed to obtain smooth, continuous surface free of pulls and tears in asphalt-paving mat.
- B. Place paving in consecutive strips not less than 10 feet wide unless infill edge strips of a lesser width are required.
- C. Promptly correct surface irregularities in paving course behind paver. Use suitable hand tools to remove excess material forming high spots. Fill depressions with hot-mix asphalt to prevent segregation of mix; use suitable hand tools to smooth surface.

3.5 JOINTS

- A. Construct joints to ensure a continuous bond between adjoining paving sections. Construct joints free of depressions, with same texture and smoothness as other sections of hot-mix asphalt course.
 1. Clean contact surfaces and apply tack coat to joints.
 2. Offset longitudinal joints, in successive courses, a minimum of 6 inches.
 3. Offset transverse joints, in successive courses, a minimum of 24 inches.
 4. Construct transverse joints at each point where paver ends a day's work and resumes work at a subsequent time. Construct these joints using either "bulkhead" or "papered" method according to AI MS-22, for both "Ending a Lane" and "Resumption of Paving Operations."

3.6 COMPACTION

- A. General: Begin compaction as soon as placed hot-mix paving will bear roller weight without excessive displacement. Compact hot-mix paving with hot, hand tampers or with vibratory-plate compactors in areas inaccessible to rollers.
 1. Complete compaction before mix temperature cools to 185 deg F.
- B. Breakdown Rolling: Complete breakdown or initial rolling immediately after rolling joints and outside edge. Examine surface immediately after breakdown rolling for indicated crown, grade, and smoothness. Correct laydown and rolling operations to comply with requirements.
- C. Intermediate Rolling: Begin intermediate rolling immediately after breakdown rolling while hot-mix asphalt is still hot enough to achieve specified density. Continue rolling until hot-mix asphalt course has been uniformly compacted to the following density:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Average Density: 92 percent of reference maximum theoretical density according to ASTM D 2041, but not less than 90 percent or greater than 96 percent.
- D. Finish Rolling: Finish roll paved surfaces to remove roller marks while hot-mix asphalt is still warm.
- E. Edge Shaping: While surface is being compacted and finished, trim edges of pavement to proper alignment. Bevel edges while asphalt is still hot; compact thoroughly.
- F. Protection: After final rolling, do not permit vehicular traffic on pavement until it has cooled and hardened.
- G. Erect barricades to protect paving from traffic until mixture has cooled enough not to become marked.

3.7 ASPHALT CURBS

- A. Construct hot-mix asphalt curbs over compacted pavement surfaces. Apply a light tack coat unless pavement surface is still tacky and free from dust. Spread mix at a minimum temperature of 250 deg F.
 1. Asphalt Mix: Same as pavement surface-course mix.
- B. Place hot-mix asphalt to curb cross section indicated or, if not indicated, to local standard shapes, by machine or by hand in wood or metal forms. Tamp hand-placed materials and screed to smooth finish. Remove forms after hot-mix asphalt has cooled.

3.8 INSTALLATION TOLERANCES

- A. Pavement Thickness: Compact each course to produce the thickness indicated within the following tolerances:
 1. Base Course: Plus or minus 1/2 inch.
 2. Surface Course: Plus 1/4 inch no minus.
- B. Pavement Surface Smoothness: Compact each course to produce a surface smoothness within the following tolerances as determined by using a 10-foot straightedge applied transversely or longitudinally to paved areas:
 1. Base Course: 1/4 inch.
 2. Surface Course: 1/8 inch.
 3. Crowned Surfaces: Test with crowned template centered and at right angle to crown. Maximum allowable variance from template is 1/4 inch.

3.9 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Replace and compact hot-mix asphalt where core tests were taken.
- C. Remove and replace or install additional hot-mix asphalt where test results or measurements indicate that it does not comply with specified requirements.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.10 WASTE HANDLING

- A. General: Handle asphalt-paving waste according to approved waste management plan required in Section 017419 "Construction Waste Management and Disposal."

END OF SECTION 32 12 16

SECTION 32 13 13 - CONCRETE PAVING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Driveways.
2. Roadways.
3. Parking lots.
4. Curbs and gutters.
5. Walks.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For each exposed product and for each color and texture specified.
- C. Other Action Submittals:
1. Design Mixtures: For each concrete paving mixture. Include alternate design mixtures when characteristics of materials, Project conditions, weather, test results, or other circumstances warrant adjustments.

1.3 QUALITY ASSURANCE

- A. Ready-Mix-Concrete Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products and that complies with ASTM C 94/C 94M requirements for production facilities and equipment.
- B. ACI Publications: Comply with ACI 301 unless otherwise indicated.

PART 2 - PRODUCTS

2.1 CONCRETE MATERIALS

- A. Cementitious Material: Use the following cementitious materials, of same type, brand, and source throughout Project:
1. Portland Cement: ASTM C 150, gray portland cement Type I
 - a. Fly Ash: ASTM C 618, Class C.
 - b. Ground Granulated Blast-Furnace Slag: ASTM C 989, Grade 100 or 120.
 2. Blended Hydraulic Cement: ASTM C 595, Type IS, portland blast-furnace slag cement.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Normal-Weight Aggregates: ASTM C 33, Class 4S, uniformly graded. Provide aggregates from a single source.
- C. Water: Potable and complying with ASTM C 94/C 94M.
- D. Air-Entraining Admixture: ASTM C 260.
- E. Chemical Admixtures: Admixtures certified by manufacturer to be compatible with other admixtures and to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material.

2.2 FIBER REINFORCEMENT

- A. Synthetic Fiber: Monofilament polypropylene fibers engineered and designed for use in concrete paving, complying with ASTM C 1116/C 1116M, Type III.

2.3 CURING MATERIALS

- A. Absorptive Cover: AASHTO M 182, Class 3, burlap cloth made from jute or kenaf, weighing approximately 9 oz./sq. yd.
- B. Moisture-Retaining Cover: ASTM C 171, polyethylene film or white burlap-polyethylene sheet.
- C. Water: Potable.
- D. Evaporation Retarder: Waterborne, monomolecular, film forming, manufactured for application to fresh concrete.
- E. Clear, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 1, Class B, dissipating.
- F. White, Waterborne, Membrane-Forming Curing Compound: ASTM C 309, Type 2, Class B, dissipating.

2.4 RELATED MATERIALS

- A. Joint Fillers: ASTM D 1751, asphalt-saturated cellulosic fiber in preformed strips.
- B. Slip-Resistive Aggregate Finish: Factory-graded, packaged, rustproof, nonglazing, abrasive aggregate of fused aluminum-oxide granules or crushed emery aggregate containing not less than 50 percent aluminum oxide and not less than 20 percent ferric oxide; unaffected by freezing, moisture, and cleaning materials.

2.5 PAVEMENT MARKINGS

- A. Pavement-Marking Paint: Latex, waterborne emulsion, lead and chromate free, ready mixed, complying with FS TT-P-1952, Type II, with drying time of less than 45 minutes.
- B. Pavement-Marking Paint: MPI #97 Latex Traffic Marking Paint.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.6 WHEEL STOPS

- A. Wheel Stops: Precast, air-entrained concrete
 - 1. Color: Gray.
 - 2. Dowels: Steel, 3/4 inch in diameter, 10-inch minimum length.
 - 3. Adhesive: As recommended by wheel stop manufacturer for application to concrete pavement.

2.7 CONCRETE MIXTURES

- A. Prepare design mixtures, proportioned according to ACI 301, with the following properties:
 - 1. Compressive Strength (28 Days): 4000 psi
 - 2. Maximum Water-Cementitious Materials Ratio at Point of Placement: 0.45.
 - 3. Slump Limit: 4 inches.
 - 4. Air Content: 5-1/2 percent plus or minus 1.5 percent.
- B. Chemical Admixtures: Use admixtures according to manufacturer's written instructions.
- C. Synthetic Fiber: Uniformly disperse in concrete mixture at manufacturer's recommended rate, but not less than 1.0 lb/cu. yd.

2.8 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, and mix concrete materials and concrete according to ASTM C 94 and ASTM C1116. Furnish batch certificates for each batch discharged and used in the Work.

PART 3 - EXECUTION

3.1 EXAMINATION AND PREPARATION

- A. Proof-roll prepared subbase surface below curb line and sidewalk areas. to identify soft pockets and areas of excess yielding.
- B. Remove loose material from compacted subbase surface immediately before placing concrete.

3.2 EDGE FORMS AND SCREED CONSTRUCTION

- A. Set, brace, and secure edge forms, bulkheads, and intermediate screed guides to required lines, grades, and elevations. Install forms to allow continuous progress of work and so forms can remain in place at least 24 hours after concrete placement.
- B. Clean forms after each use and coat with form-release agent to ensure separation from concrete without damage.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.3 JOINTS

- A. General: Form construction, isolation, and contraction joints and tool edges true to line, with faces perpendicular to surface plane of concrete. Construct transverse joints at right angles to centerline unless otherwise indicated.
- B. Construction Joints: Set construction joints at side and end terminations of paving and at locations where paving operations are stopped for more than one-half hour unless paving terminates at isolation joints.
- C. Isolation Joints: Form isolation joints of preformed joint-filler strips abutting concrete curbs, catch basins, manholes, inlets, structures, other fixed objects, and where indicated.
- D. Contraction Joints: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of the concrete thickness, if required.
- E. Edging: After initial floating, tool edges of paving, gutters, curbs, and joints in concrete with an edging tool to a $\frac{1}{4}$ inch radius. Repeat tooling of edges after applying surface finishes. Eliminate edging-tool marks on concrete surfaces.

3.4 CONCRETE PLACEMENT

- A. Moisten subbase to provide a uniform dampened condition at time concrete is placed.
- B. Comply with ACI 301 requirements for measuring, mixing, transporting, placing, and consolidating concrete.
- C. Deposit and spread concrete in a continuous operation between transverse joints. Do not push or drag concrete into place or use vibrators to move concrete into place.
- D. Screed paving surface with a straightedge and strike off.
- E. Commence initial floating using bull floats or darbies to impart an open-textured and uniform surface plane before excess moisture or bleed water appears on the surface. Do not further disturb concrete surfaces before beginning finishing operations or spreading surface treatments.

3.5 FLOAT FINISHING

- A. General: Do not add water to concrete surfaces during finishing operations.
- B. Float Finish: Begin the second floating operation when bleed-water sheen has disappeared and concrete surface has stiffened sufficiently to permit operations. Float surface with power-driven floats or by hand floating if area is small or inaccessible to power units. Finish surfaces to true planes. Cut down high spots and fill low spots. Refloat surface immediately to uniform granular texture.
 - 1. Burlap Finish: Drag a seamless strip of damp burlap across float-finished concrete, perpendicular to line of traffic, to provide a uniform, gritty texture.
 - 2. Medium-to-Fine-Textured Broom Finish: Draw a soft-bristle broom across float-finished concrete surface perpendicular to line of traffic to provide a uniform, fine-line texture.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3. Medium-to-Coarse-Textured Broom Finish: Provide a coarse finish by striating float-finished concrete surface 1/16 to 1/8 inch deep with a stiff-bristled broom, perpendicular to line of traffic.
- C. Slip-Resistive Aggregate Finish: Before final floating, spread slip-resistive aggregate finish on paving surface according to manufacturer's written instructions.
 1. Cure concrete with curing compound recommended by slip-resistive aggregate manufacturer. Apply curing compound immediately after final finishing.
 2. After curing, lightly work surface with a steel wire brush or abrasive stone and water to expose nonslip aggregate.

3.6 CONCRETE PROTECTION AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
- B. Comply with ACI 306.1 for cold-weather protection.
- C. Evaporation Retarder: Apply evaporation retarder to concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete but before float finishing.
- D. Begin curing after finishing concrete but not before free water has disappeared from concrete surface.
- E. Curing Methods: Cure concrete by moisture-retaining-cover curing & curing compound or a combination of both.

3.7 PAVING TOLERANCES

- A. Comply with tolerances below:
 1. Elevation: 1/2 inch
 2. Thickness: 1/8 inch
 3. Surface: Gap below 10 foot long, unleveled straightedge not to exceed 1/2 inch.
 4. Joint Spacing: 3 inches
 5. Contraction Joint Depth: Plus 1/4 inch
 6. Joint Width: 1/8 inch

3.8 PAVEMENT MARKING

- A. Allow concrete paving to cure for a minimum of 28 days and be dry before starting pavement marking.
- B. Sweep and clean surface to eliminate loose material and dust.
- C. Apply paint with mechanical equipment to produce markings of dimensions indicated with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.9 WHEEL STOPS

- A. Install wheel stops in bed of adhesive applied as recommended by manufacturer.
- B. Securely attach wheel stops to paving with not less than two steel dowels located at one-quarter to one-third points. Install dowels in drilled holes in the paving and bond dowels to wheel stop. Recess head of dowel beneath top of wheel stop.

3.10 REPAIRS AND PROTECTION

- A. Remove and replace concrete paving that is broken, damaged, or defective or that does not comply with requirements in this Section. Remove work in complete sections from joint to joint unless otherwise approved by Architect.
- B. Protect concrete paving from damage. Exclude traffic from paving for at least 14 days after placement. When construction traffic is permitted, maintain paving as clean as possible by removing surface stains and spillage of materials as they occur.
- C. Maintain concrete paving free of stains, discoloration, dirt, and other foreign material. Sweep paving not more than two days before date scheduled for Substantial Completion inspections.

END OF SECTION 32 13 13

SECTION 32 17 23 - PAVEMENT MARKINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes painted markings applied to asphalt and concrete pavement.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Benjamin Moore & Co.
 - 2. M.A.B. Paints.
 - 3. Sherwin-Williams Company.

2.2 PAVEMENT-MARKING PAINT

- A. Pavement-Marking Paint: MPI #32, alkyd traffic-marking paint.
 - 1. Color: Blue at accessible parking spaces, white elsewhere unless otherwise noted on plans.
- B. VOC Content: Pavement markings used on building interior shall have a VOC content of 150 g/L or less.

PART 3 - EXECUTION

3.1 PAVEMENT MARKING

- A. Do not apply pavement-marking paint until layout, colors, and placement have been verified with Architect.
- B. Allow paving to age for a minimum of 30 days before starting pavement marking.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- C. Sweep and clean surface to eliminate loose material and dust.
- D. Apply paint with mechanical equipment to produce pavement markings, of dimensions indicated, with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils (0.4 mm).
 - 1. Apply graphic symbols and lettering with paint-resistant, die-cut stencils. Apply paint so that it cannot run beneath the stencil.

END OF SECTION 32 17 23

SECTION 32 92 00 - TURF AND GRASSES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Hydro Seeding.
 - 2. Sodding.

1.2 DEFINITIONS

- A. Finish Grade: Elevation of finished surface of planting soil.
- B. Surface Soil: Whatever soil is present at the top layer of the existing soil profile at the Project site. In undisturbed areas, the surface soil is typically topsoil, but in disturbed areas such as urban environments, the surface soil can be subsoil.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Certification of grass seed.
 - 1. Certification of seed mixture.

1.5 QUALITY ASSURANCE

- A. Installer's Field Supervision: Require Installer to maintain an experienced full-time supervisor on Project site when work is in progress.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Sod: Harvest, deliver, store, and handle sod according to requirements in "Specifications for Turfgrass Sod Materials" and "Specifications for Turfgrass Sod Transplanting and Installation" in Turfgrass Producers International's "Guideline Specifications to Turfgrass Sodding." Deliver sod in time for planting within 24 hours of harvesting. Protect sod from breakage and drying.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1.7 WARRANTY

- A. Special Warranty: Installer agrees to repair or replace sod and hydro seeding that fails in materials, workmanship, or growth within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Death and unsatisfactory growth, except for defects resulting from abuse, lack of adequate maintenance, or neglect by Owner, or incidents that are beyond Contractor's control.
 - 2. Warranty Periods from Date of Planting Completion.
 - a. Sod and Hydro seed areas: 12 months.

1.8 MAINTENANCE SERVICE

- A. Initial Turf Maintenance Service: Provide full maintenance by skilled employees of landscape Installer. Maintain as required in Part 3. Begin maintenance immediately after each area is planted and continue until acceptable turf is established but for not less than the following periods:
 - 1. Hydro -Seeded Turf: 3 months from date of planting completion.
 - 2. Sodded Turf: 3 months from date of planting completion.

PART 2 - PRODUCTS

2.1 HYDRO SEED

- A. Grass Seed Mix: An approved seed mix as specified by the State of South Carolina DOT (lower region) in it's Technical Specifications for Seeding. SCDOT Designation: SC-M-810-2 (04/11) The seed from table 1 must be Centipede.

2.2 TURFGRASS SOD

- A. Turfgrass Sod: sod must comply with "Specifications for Turfgrass Sod Materials" in Turfgrass Producers International "Guideline Specifications to Turfgrass Sodding." Furnish viable sod of uniform density, color, and texture, strongly rooted, and capable of vigorous growth and development when planted. No turf reinforcement netting allowed on sod.
- B. Turfgrass Species: Sod of grass species as follows:
 - 1. Full Sun: 100 % Centipede soda
 - 2. Sun and Partial Shade: 100 % Centipede sod

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.3 PLANTING SOILS

- A. Planting Soil Verify suitability of soil to produce viable planting soil. Clean soil of roots, plants, sod, stones, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to sod growth.

PART 3 - EXECUTION

3.1 TURF AREA PREPARATION

- A. Finish Grading: Grade planting areas to a smooth, uniform surface plane with loose, uniformly fine texture. Grade to within plus or minus 1/2 inch of finish elevation. Roll and rake, remove ridges, and fill depressions to meet finish grades. Limit finish grading to areas that can be planted in the immediate future.
- B. Moisten prepared area before planting if soil is dry. Water thoroughly and allow surface to dry before planting. Do not create muddy soil.
- C. Before planting, obtain Architect's acceptance of finish grading; restore planting areas if eroded or otherwise disturbed after finish grading.

3.2 HYDRO SEEDING

- A. Seed at a total rate specified in the SCDOT technical specifications for the selected product for 'permanent ' cover application. (SC-M-810-2 04-11)
- B. Promote seed germination as needed to ensure 90% coverage at end of maintenance period.
- C. Protect seeded areas from hot, dry weather or drying winds as needed to ensure 90 % coverage at end of maintenance period.

3.3 SODDING

- A. Lay sod within 24 hours of harvesting. Do not lay sod if ground is frozen or muddy.
- B. Lay sod to form a solid mass with tightly fitted joints. Butt ends and sides of sod; do not stretch or overlap. Stagger sod strips or pads to offset joints in adjacent courses. Avoid damage to subgrade or sod during installation. Tamp and roll lightly to ensure contact with subgrade, eliminate air pockets, and form a smooth surface. Work sifted soil or fine sand into minor cracks between pieces of sod; remove excess to avoid smothering sod and adjacent grass.
 - 1. Lay sod across angle of slopes exceeding 1:3.
 - 2. Anchor sod on slopes exceeding 1:6 with wood pegs spaced as recommended by sod manufacturer but not less than 2 anchors per sod strip to prevent slippage.
- C. Saturate sod with fine water spray within two hours of planting. During first week after planting, water daily or more frequently as necessary to maintain moist soil to a minimum depth of 1-1/2 inches below sod.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

3.4 TURF MAINTENANCE

- A. Maintain and establish turf by watering, fertilizing, weeding, mowing, trimming, replanting, and performing other operations as required to establish healthy, viable turf. Roll, regrade, and replant bare or eroded areas and remulch to produce a uniformly smooth turf. Provide materials and installation the same as those used in the original installation.
- B. Mow turf as soon as top growth is tall enough to cut. Repeat mowing to maintain height appropriate for species without cutting more than 1/3 of grass height. Remove no more than 1/3 of grass-leaf growth in initial or subsequent mowings.
- C. If necessary, apply pesticides and other chemical products and biological control agents in accordance with authorities having jurisdiction and manufacturer's written recommendations. Coordinate applications with Owner's operations and others in proximity to the Work. Notify Owner before each application is performed.

3.5 SATISFACTORY TURF

- A. Turf installations shall meet the following criteria as determined by Architect:
 - 1. Satisfactory Hydro Seeded Turf: At end of maintenance period, a healthy, uniform, close stand of grass has been established, free of weeds and surface irregularities, with coverage exceeding 90 percent over any 10 sq. ft. and bare spots not exceeding 5 by 5 inches.
 - 2. Satisfactory Sodded Turf: At end of maintenance period, a healthy, well-rooted, even-colored, viable turf has been established, free of weeds, open joints, bare areas, and surface irregularities.
- B. Use specified materials to reestablish turf that does not comply with requirements and continue maintenance until turf is satisfactory.

END OF SECTION 32 92 00

SECTION 33 41 00 - STORM UTILITY DRAINAGE PIPING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Pipe and fittings.
2. Manholes.
3. Cleanouts.
4. Nonpressure transition couplings.
5. Expansion joints.
6. Catch basins.
7. Stormwater inlets.
8. Pipe outlets.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings:

1. Manholes: Include plans, elevations, sections, details, frames, and covers.
2. Catch basins and curb inlets. Include plans, elevations, sections, details, frames, covers, and grates.

1.3 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show pipe sizes, locations, and elevations. Show other piping in same trench and clearances from storm drainage system piping. Indicate interface and spatial relationship between manholes, piping, and proximate structures.
- B. Product Certificates: For each type of pvc fitting for the condensate and downspout drainage lines from the manufacturer.
- C. Field quality-control reports.

1.4 PROJECT CONDITIONS

- A. Interruption of Existing Storm Drainage Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:
 1. Notify Architect /Engineer/Owner no fewer than two days in advance of proposed interruption of service.
 2. Do not proceed with interruption of service without Architects and Owners written permission and pertinent permits/approvals from the regulatory authority.

PART 2 - PRODUCTS

2.1 DUCTILE-IRON, CULVERT PIPE AND FITTINGS

- A. Pipe: ASTM A 716, for push-on joints.
- B. Standard Fittings: AWWA C110, ductile or gray iron, for push-on joints.
- C. Compact Fittings: AWWA C153, for push-on joints.
- D. Gaskets: AWWA C111, rubber.
- E. Reinforced-Concrete Sewer Pipe and Fittings: ASTM 76.
 - 1. Tongue and groove with sealant joints with ASTM C990 butyl-rubber sealant.
 - 2. Class III – wall B.

2.2 NONPRESSURE TRANSITION COUPLINGS

- A. Sleeve Materials:
 - 1. For Concrete Pipes: ASTM C443 rubber.
- B. Ring-Type, Flexible Couplings:
 - 1. Description: Elastomeric compression seal with dimensions to fit inside bell of larger pipe and for spigot of smaller pipe to fit inside ring.

2.3 EXPANSION JOINTS

- A. Ductile-Iron Flexible Expansion Joints:
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - b. EBAA Iron Sales, Inc.
 - c. Romac Industries, Inc.
 - 2. Description: Compound fitting with combination of flanged and mechanical-joint ends complying with AWWA C110 or AWWA C153. Include two gasket ball-joint sections and one or more gasket sleeve sections, rated for 250-psig minimum working pressure and for offset and expansion indicated.

2.4 CLEANOUTS

- A. Cast-Iron Cleanouts:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

1. Description: ASME A112.36.2M, round, gray-iron housing with clamping device and round, secured, scoriated, gray-iron cover. Include gray-iron ferrule with inside calk or spigot connection and countersunk, tapered-thread, brass closure plug.
2. Top-Loading Classification(s): Heavy Duty
3. Sewer Pipe Fitting and Riser to Cleanout: ASTM A 74, Service class, cast-iron soil pipe and fittings.

2.5 MANHOLES

A. Standard Precast Concrete Manholes:

1. Description: ASTM C 478, precast, reinforced concrete, of depth indicated, with provision for sealant joints.
2. Diameter: 48 inches minimum unless otherwise indicated.
3. Ballast: Increase thickness of precast concrete sections or add concrete to base section as required to prevent flotation.
4. Base Section: 6-inch minimum thickness for floor slab and 4-inch minimum thickness for walls and base riser section, and separate base slab or base section with integral floor.
5. Riser Sections: 4-inch minimum thickness, and lengths to provide depth indicated.
6. Top Section: Eccentric-cone type unless concentric-cone or flat-slab-top type is indicated, and top of cone of size that matches grade rings.
7. Joint Sealant: ASTM C 990 bitumen or butyl rubber.
8. Resilient Pipe Connectors: ASTM C 923, cast or fitted into manhole walls, for each pipe connection.
9. Steps: Steps are required in the sewer manholes.
10. Adjusting Rings: Interlocking HDPE rings with level or sloped edge in thickness and diameter matching manhole frame and cover, and of height required to adjust manhole frame and cover to indicated elevation and slope. Include sealant recommended by ring manufacturer.
11. Grade Rings: Reinforced-concrete rings, 6- to 9-inch total thickness, to match diameter of manhole frame and cover, and height as required to adjust manhole frame and cover to indicated elevation and slope.

B. Manhole Frames and Covers:

1. Description: Ferrous; 24-inch ID by 7- to 9-inch riser with 4-inch minimum width flange and 26-inch diameter cover. Include indented top design with lettering cast into cover, using wording equivalent to "STORM SEWER."
2. Material: ASTM A536 Grade 60-40-18 ductile iron unless otherwise indicated.

2.6 CONCRETE

A. General: Cast-in-place concrete according to ACI 318, ACI 350/350R and the following:

1. Cement: ASTM C 150, Type II.
2. Fine Aggregate: ASTM C 33, sand.
3. Coarse Aggregate: ASTM C 33, crushed gravel.
4. Water: Potable.

B. Portland Cement Design Mix: 4000 psi minimum, with 0.45 maximum water/cementitious materials ratio.

1. Reinforcing Fabric: ASTM A 185/A 185M, steel, welded wire fabric, plain.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (420 MPa) deformed steel.
- C. Ballast and Pipe Supports: Portland cement design mix, 4000 psi minimum, with 0.58 maximum water/cementitious materials ratio.
1. Reinforcing Fabric: ASTM A 185/A 185M, steel, welded wire fabric, plain.
 2. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (420 MPa) deformed steel.

2.7 CATCH BASINS

- A. Standard Precast Concrete Catch Basins:
1. Description: ASTM C 478, precast, reinforced concrete, of depth indicated, with provision for sealant joints.
 2. Base Section: 6-inch minimum thickness for floor slab and 4-inch minimum thickness for walls and base riser section, and separate base slab or base section with integral floor.
 3. Riser Sections: 4-inch minimum thickness, 48-inch diameter, and lengths to provide depth indicated.
 4. Top Section: Eccentric-cone type unless concentric-cone or flat-slab-top type is indicated. Top of cone of size that matches grade rings.
 5. Joint Sealant: ASTM C 990, bitumen or butyl rubber.
 6. Adjusting Rings: Interlocking rings with level or sloped edge in thickness and shape matching catch basin frame and grate. Include sealant recommended by ring manufacturer.
 7. Grade Rings: Include two or three reinforced-concrete rings, of 6 to 9 inch total thickness, that match 24 inch diameter frame and grate.
 8. Pipe Connectors: ASTM C923, resilient, of size required, for each pipe connecting to base section.
- B. Frames and Grates: ASTM A 536, Grade 60-40-18, ductile iron designed for A-16, structural loading. Include flat grate with small square or short-slotted drainage openings.
1. Size: 24 by 24 inches minimum unless otherwise indicated.
 2. Grate Free Area: Approximately 50 percent unless otherwise indicated.
- C. Frames and Grates: ASTM A 536, Grade 60-40-18, ductile iron designed for A-16, structural loading. Include 24 inch 7 to 9 inch riser with 4 inch minimum width flange, and 26 inch diameter flat grate with small square or short-slotted drainage openings.
1. Grate Free Area: Approximately 50 percent unless otherwise indicated.

2.8 STORMWATER INLETS

- A. Gutter Inlets: Made with horizontal gutter opening. Include heavy-duty frames and grates.
- B. Frames and Grates: Heavy duty.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

2.9 PIPE OUTLETS

PART 3 - EXECUTION

3.1 EARTHWORK

- A. Excavation, trenching, and backfilling are specified in Section 312000 "Earth Moving."

3.2 PIPING INSTALLATION

- A. General Locations and Arrangements: Drawing plans and details indicate general location and arrangement of underground storm drainage piping. Location and arrangement of piping layout take into account design considerations. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.
- B. Install piping beginning at low point, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements.
- C. Install manholes for changes in direction unless fittings are indicated. Use fittings for branch connections unless direct tap into existing sewer is indicated.
- D. Install proper size increasers, reducers, and couplings where different sizes or materials of pipes and fittings are connected. Reducing size of piping in direction of flow is prohibited.
- E. Install gravity-flow, nonpressure drainage piping according to the following:
 - 1. Install piping pitched down in direction of flow.
 - 2. Install reinforced concrete pipe with a minimum 12" cover.
 - 3. Install PVC sewer piping according to ASTM D 2321 and ASTM F 1668.
 - 4. Install reinforced-concrete sewer piping according to ASTM C 1479 and ACPA's "Concrete Pipe Installation Manual."

3.3 PIPE JOINT CONSTRUCTION

- A. Join gravity-flow, nonpressure drainage piping according to the following:
 - 1. Join reinforced-concrete sewer piping according to ACPA's "Concrete Pipe Installation Manual" for rubber-gasketed joints.

3.4 CLEANOUT INSTALLATION

- A. Install cleanouts and riser extensions from PVC storm drainage sewer pipes to cleanouts at grade. Use cast-iron soil pipe fittings in sewer pipes at branches for cleanouts and cast-iron soil pipe for riser extensions to cleanouts. Install piping so cleanouts open in direction of flow in sewer pipe.
 - 1. Use Extra-Heavy-Duty, top-loading classification cleanouts in at all locations where cleanouts are specified on the plans.

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- B. Set cleanout frames and covers in earth in at an elevation 1 inch above surrounding earth grade.
- C. Set cleanout frames and covers in sidewalks and roadways/parking areas flush with the concrete and pavement surface.

3.5 MANHOLE INSTALLATION

- A. General: Install manholes, complete with appurtenances and accessories indicated.
- B. Install precast concrete manhole sections with sealants according to ASTM C 891.
- C. Where specific manhole construction is not indicated, follow manhole manufacturer's written instructions.
- D. Set tops of frames and covers flush with finished surface of manholes that occur in pavements. Set tops 2 inches above finished surface elsewhere unless otherwise indicated.

3.6 CATCH BASIN INSTALLATION

- A. Set frames and grates to elevations indicated.

3.7 STORMWATER INLET AND OUTLET INSTALLATION

- A. Install outlets that spill onto grade, with flared end sections that match pipe, where indicated.
- B. Construct energy dissipaters at outlets, as indicated.

3.8 CONCRETE PLACEMENT

- A. Place cast-in-place concrete according to ACI 318.
- B. Fasten grates to catch basins and curb inlets.

3.9 IDENTIFICATION

- A. Materials and their installation are specified in Section 312000 "Earth Moving." Arrange for installation of #12 tracer wire over piping and at outside edge of underground structures.
 - 1. Use #12 tracer wire over all plastic and PVC piping.

3.10 FIELD QUALITY CONTROL

- A. Inspect interior of piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place, and again at completion of Project.
 - 1. Submit separate reports for each system inspection.
 - 2. Defects requiring correction include the following:

MYRTLE BEACH INTERMEDIATE SCHOOL RENOVATIONS
Myrtle Beach, South Carolina

- a. Alignment: Less than full diameter of inside of pipe is visible between structures.
 - b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
 - c. Damage: Crushed, broken, cracked, or otherwise damaged piping.
 - d. Infiltration: Water leakage into piping.
 - e. Exfiltration: Water leakage from or around piping.
3. Replace defective piping using new materials, and repeat inspections until defects are within allowances specified.
4. Reinspect and repeat procedure until results are satisfactory.
- B. Test new piping systems, and parts of existing systems that have been altered, extended, or repaired, for leaks and defects.
 1. Do not enclose, cover, or put into service before inspection and approval.
 2. Test completed piping systems according to requirements of authorities having jurisdiction.
 3. Schedule tests and inspections by authorities having jurisdiction with at least 24 hours' advance notice.
 4. Submit separate report for each test.
- C. Leaks and loss in test pressure constitute defects that must be repaired.
- D. Replace leaking piping using new materials, and repeat testing until leakage is within allowances specified.

END OF SECTION 33 41 00