



## Stormwater System Improvements-Historic District

Project #4015

EDA Grant # 04-79-07494

### **ADDENDUM I**

Date: 7-1-2021

1. The engineering scope of work is hereby modified for Phase 3- Queen Street System. SCDOT is presently installing the storm drain pipes along Queen Street from Front Street to Prince Street. The City will complete the Queen Street drainage system with all the necessary appurtenances and pavement restoration from Prince Street to Highmarket Streets. The City installed a new 48" RCP drainage pipe, a 48" check valve, and junction boxes from the Harborwalk Marina to the intersection of Front Street and Queen Streets. Currently, SCDOT is installing new 48", 42", 30", and 29"x45" RCP drainage pipes with catch basins on Queen Street from Front to Prince Streets.

Attachment:

1-1. SCDOT Queen Street Plan

2. The City has obtained the bulkhead permits from the United States Army Corps of Engineers (USACE) and the South Carolina Department of Health and Environmental Control Office of Coastal Resources Management (SCDHEC-OCRM), attached to this Addendum I.

Attachments:

2-1. USACE bulkhead permit

2-2. OCRM CCU Building bulkhead permit

2-3. OCRM Constitution Park bulkhead permit