

## RENOVATIONS TO LAGRANGE POLICE DEPARTMENT

### FOR CITY OF LAGRANGE

#### **ADDITIVE ALTERNATIVES**

BASE BID - ALL WORK IN PHASE ONE

#### **ADDITIVE ALTERNATIVE NO.1**

IN SPACES 128 AND 129 INSTALL NEW PORCELAIN TILE FLOORS AND NEW PORCELAIN TILE (FULL HEIGHTS) ON ALL WALLS, PROVIDE NEW PLUMBING FIXTURES, NEW CEILING, NEW LIGHTS AND NEW VANITY PER DETAIL 4/A7-1.

ADDITIVE ALTERNATIVE NO.2- ALL WORK IN PHASE II (2)

ADDITIVE ALTERNATIVE NO.3 - ALL WORK IN PHASE III (3)

ADDITIVE ALTERNATIVE NO.4- ALL WORK IN PHASE IV (4)

#### ADDITIVE ALTERNATIVE NO.5

TO REMOVE ALL EXISTING DATA CABLING ON THE 100 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 108. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 108 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

#### ADDITIVE ALTERNATIVE NO.6

TO REMOVE ALL EXISTING DATA CABLING ON THE 200 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 225. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 225 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

#### ADDITIVE ALTERNATIVE NO.7

TO REMOVE ALL EXISTING DATA CABLING ON THE 300 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 338. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 338 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

## 100 W HARALSON STREET LAGRANGE, GEORGIA

(ELECTRICAL)

PROJECT NUMBER 1911

FOR BID AND PERMIT

12 AUGUST 2019

#### **Phasing and Liquidated Damages**

#### Phase 1

To be Substantial Complete within 190 Consecutive Calendar Days, after commencement of work, on Phase 1. Liquidated Damages in the sum of \$100 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### Phase 2

To begin 14 Days after Substantial Completion of Phase 1, and To be Substantial Complete within 140 Consecutive Calendar Days, after commencement of work, on Phase 2. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### Phase 3

To begin 14 Days after Substantial Completion of Phase 2, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 3. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.


#### Phase 4

To begin 14 Days after Substantial Completion of Phase 3, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 4. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### ABBREVIATIONS:

@ ^ D	At Anchor Polt	JAN.	Janitor
A.B. A.C.	Anchor Bolt Air Conditioner	J.B. JST.	Joist Bearing Joist
ACOUST.	Acoustical	J.T.	Joist
ALUM.	Aluminum	•	00.01
ARCH.	Architectural		
A.T.	Acoustical Tile	LAV.	Lavatory
		LLV.	Long Leg Vertical
B.C.	Dattom of Curb		
BLK.	Bottom of Curb Block	MAS.; MSRY	Masonry
BOTT.	Bottom	MCS	Modular Cabinet System
20	20110111	MECH.	Mechanical
		MIN.	Minimum
CER.	Ceramic		
CHM.	Custom Hollow Metal	N.I.	Nicostic
C.I.	Curb Inlet Centerline	N NA	North Not Applicable
CLO.	Closet	N.I.C.	Not In Contract
CMU.	Concrete Masonry Unit	NTS	Not to Scale
C.O.	Clean Out		
COL.	Column		
CONC.	Concrete	O.C.	On Center
CONST.	Construction	OPP.	Opposite
CONT.	Continuous		
C.T. CHR.	Ceramic Tile Coat & Hat Rack	PL	Plate
C.J.	Coat & Hat Nack Control Joint	PT	Pressure Treated
0.0.	Control count	PEJ	Premolded Expansion
		PLAST	Plaster
D: DIAM.	Diameter	PSF	Pounds Per Square Foot
DF	Drink Fountain	PSI	Pounds Per Square Inch
DI	Drain Inlet		
DN	Down	Б	Dadius
DRIV. DS	Driver Downspout	R REF	Radius Refrigerator
DWGS.	Drawings	REQ'D	Required
DWLS.	Dowels	RL	Roof Level
DR	Drawer	RM	Room
		RT	Resilient Tile
		RW	Regular Weight
E.J.; EXP. JT.	Expansion Joint		Round
EL.; ELEV	Elevation		
EQ EQUIP.	Equal Equipment	SQ.	Square
E.F.I.S.	Exterior Finish	SIM	Similar
	Insulation System	SLV	Short Leg Vertical
	·	S.M.	Sheet Metal
		STL	Steel
F.E.	Fire Extinguisher	STO.; STOR	Storage
F.H. FES	Fire Hose Fire Extinguisher Sign	STRUCT. SH	Structural Shelves
FIN.	Finish	SH	Sileives
FLEX.	Flexible		
FLR.	Floor	TC	Teacher Cabinet
FT.	Foot	T.C.	Top of Curb
FTG.	Footing	TD	Turn Down
		TFF	Top of Finished Floor
GA	Caugo	TFS T & G	Top of Finished Slab Tongue and Groove
GA G.C.	Gauge General Contractor	T.M.	Transitional Material
GYP. BRD.	Gypsum Wallboard	TP	Top of Pavement
J.1. DIND.	2,523	T/S	Top of Steel
		TYP.	Typical
Н	Height		•
HC	Handicapped	U.N.O.	Unless Noted Otherwise
HCM	Hollow Concrete Masonry		
HORIZ. HW	Horizontal Hand Wash	V.C.J.	Veneer Control Joint
1100	i iailu vvasii	v.c.j. VERT.	Vertical
		VERT. VRS	Varies
I.D.	Inside Diameter	VWC	Vinyl Wall Covering
IND.	Industrial		5
INV.	Invert	144	14 <i>0</i> 10
		W	Width

#### **INDEX OF SYMBOLS:**




VIEW TITLE

#### CONSTRUCTION MATERIALS:

W.C. WD

PLAN / SECTION



resilient flooring carpet

steel/iron

**aluminum** small scale metal

rough lumber large scale finish lumber small scale finish lumber

large scale plywood small scale plywood batt/blanket insulation

laminated plastic

#### **Phasing and Liquidated Damages**

Width With Water Cooler

Welded Wire Fabric

Wood

To be Substantial Complete within 190 Consecutive Calendar Days, after commencement of work, on Phase 1. Liquidated Damages in the sum of \$100 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved

To begin 14 Days after Substantial Completion of Phase 1, and To be Substantial Complete within 140 Consecutive Calendar Days, after commencement of work, on Phase 2. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.


Phase 3

To begin 14 Days after Substantial Completion of Phase 2, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 3. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

To begin 14 Days after Substantial Completion of Phase 3, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 4. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

	INDEX OF SHEETS		INDEX OF SHEETS		INDEX OF SHEETS
	GENERAL		CONTINUED		MECHANICAL
G-1	COVER SHEET	A3-1	PARKING DECK ELEVATIONS PROPOSED	GM-1	COVER SHEET
G-2	INDEX OF SHEETS	A3-2	PARKING DECK ELEVATIONS PROPOSED	GM-2	INDEX OF SHEETS
G-3	ORIENTATION PLANS	A3-3	PARKING DECK ELEVATIONS PROPOSED	GM-3	ORIENTATION PLANS
G-4	ORIENTATION PLANS	A3-4	PARKING DECK ELEVATIONS PROPOSED	GM-4	ORIENTATION PLANS
G-5	LIFE SAFETY PLANS	A3-5	NEW COMMUNITY ENTRANCE ELEVATIONS	GM-5	LIFE SAFETY PLANS
G-6	LIFE SAFETY PLANS	A3-6	NEW COMMUNITY ENTRANCE ELEVATIONS	GM-6	LIFE SAFETY PLANS
G-7	GENERAL NOTES	A3-7	NEW COMMUNITY ENTRANCE ELEVATIONS	GM-7	GENERAL NOTES
G-8	CONSTRUCTION STAGING SITE PLAN	A3-8	NEW COMMUNITY ENTRANCE ELEVATIONS	GM-8	CONSTRUCTION STAGING SITE PLAN
G-9	PHASING PLANS	A3-9	EXTERIOR ELEVATIONS	GM-9	PHASING PLANS
G-10	PHASING PLANS	A3-10	EXTERIOR ELEVATIONS	GM-10	PHASING PLANS
SD-0	SITE DETAILS	A3-11	EXTERIOR ELEVATIONS	M0.1	HVAC SPECIFICATIONS
SD-1	SITE DETAILS	A3-12	EXTERIOR ELEVATIONS	M0.2	HVAC DETAILS AND SCHEDULES
SD-2	SITE DETAILS	A4-1	EXISTING BUILDING SECTION	M1.1	HVAC DEMOLITION - 100 LEVEL
SD-3	SITE DETAILS	A4-2	EXISTING BUILDING SECTION	M1.2	HVAC DEMOLITION - 200 LEVEL
SD-4	SITE DETAILS	A4-3	EXISTING BUILDING SECTION	M1.3	HVAC DEMOLITION - 300 LEVEL
D-1	LEVEL 100 - PARTIAL DEMOLITION PLAN	A4-4	EXISTING BUILDING SECTION	M2.1	HVAC NEW WORK - 100 LEVEL
D-2	LEVEL 100 - PARTIAL DEMOLITION PLAN	A4-5	BUILDING SECTION PROPOSED	M2.2	HVAC NEW WORK - 200 LEVEL
D-3	LEVEL 200 DEMOLITION PLAN	A4-6	BUILDING SECTION PROPOSED	M2.3	HVAC NEW WORK - 300 LEVEL
D-4 D-5	LEVEL 300 DEMOLITION PLAN  EXISTING / DEMOLITION ELEVATIONS	A5-1 A5-2	SECTION AT PARKING DECK RAILING SECTION AT NEW COMMUNITY ENTRANCE	P0.1 P1.1	PLUMBING SPECIFICATIONS, DETAILS, SCHEDULES PLUMBING DEMOLITION - 100 LEVEL
D-5 D-6	EXISTING / DEMOLITION ELEVATIONS  EXISTING / DEMOLITION ELEVATIONS	A5-2 A5-3	SECTION AT NEW COMMUNITY ENTRANCE SECTION AT NEW COMMUNITY ENTRANCE CANOPY	P1.1	PLUMBING DEMOLITION - 100 LEVEL  PLUMBING DEMOLITION - 200 LEVEL
D-6 D-7	EXISTING / DEMOLITION ELEVATIONS  EXISTING / DEMOLITION ELEVATIONS	A5-3	SECTION AT NEW COMMUNITY ENTRANCE CANOPY  SECTION AT 100 LEVEL RAMP	P1.2	PLUMBING DEMOLITION - 200 LEVEL  PLUMBING DEMOLITION - 300 LEVEL
D-7	EXISTING / DEMOLITION ELEVATIONS  EXISTING / DEMOLITION ELEVATIONS	A5-4	STEP / RAINING DETAILS	P1.3	SANITARY PIPING - 100 LEVEL
D-9	EXISTING / DEMOLITION ELEVATIONS	A5-6	STEP / RAMP DETAILS	P2.2	SANITARY PIPING - 200 LEVEL
D-10	EXISTING / DEMOLITION ELEVATIONS	A5-7	100 LEVEL RAMP PLAN	P2.3	SANITARY PIPING - 300 LEVEL
D-11	EXISTING / DEMOLITION ELEVATIONS	A5-8	WALL SECTION EXISTING	P2.4	WATER & GAS PIPING - 100 LEVEL
D-12	EXISTING RETAINING WALL / PARKING RAIL DETAIL	A5-9	PLANTER WALL DETAIL	P2.5	WATER PIPING - 200 LEVEL
D-13	100 LEVEL - PARTIAL DEMOLITION RCP	A5-10	WALL SECTION	P2.6	WATER PIPING - 300 LEVEL
D-14	100 LEVEL - PARTIAL DEMOLITION RCP	A5-11	DETAILS		ELECTRICAL
D-15	200 LEVEL - DEMOLITION RCP	A5-12	SECTION	GE-1	COVER SHEET
D-16	300 LEVEL - DEMOLITION RCP	A5-13	100 LEVEL - ENTRY FOUNDATION PLAN	GE-2	INDEX OF SHEETS
D-17	100 LEVEL - EXISTING ELECTRIC	A5-14	100 LEVEL - ENTRY FRAMING PLAN	GE-3	ORIENTATION PLANS
D-18	100 LEVEL - EXISTING ELECTRIC	A5-15	STRUCTURAL NOTES	GE-4	ORIENTATION PLANS
D-19	200 LEVEL - EXISTING ELECTRIC	A5-16	STRUCTURAL DETAILS	GE-5	LIFE SAFETY PLANS
D-20	300 LEVEL - EXISTING ELECTRIC	A5-17	STRUCTURAL DETAILS	GE-6	LIFE SAFETY PLANS
S-1	FOUNDATION PLAN - COMMUNITY ROOM	A5-18	100 LEVEL - ENTRY SECTION	GE-7	GENERAL NOTES
S-2	FRAMING PLAN - COMMUNITY ROOM ENTRANCE	A6-1	ROOF PLAN PROPOSED	GE-8	CONSTRUCTION STAGING SITE PLAN
S-3	CANOPY ENTRANCE SECTION	A6-2	ROOF PLAN PROPOSED	GE-9	PHASING PLANS
A1-1	100 LEVEL NORTH - PARTIAL PLAN PROPOSED	A6-3	ROOF PLAN PROPOSED	GE-10	PHASING PLANS
A1-2	100 LEVEL EAST - PARTIAL PLAN PROPOSED	A6-4	ROOF DETAILS	E0.1	ELECTRICAL CRITERIA
A1-3	200 LEVEL - PARKING DECK PROPOSED	A6-5	ROOF DETAILS	E0.2	ELECTRICAL RISER & SCHEDULE
A1-4	200 LEVEL - FLOOR PLAN PROPOSED	A7-1	TOILET DETAILS	E0.3	ELECTRICAL SCHEDULES
A1-5 A1-6	300 LEVEL - FLOOR PLAN PROPOSED	A7-2 A7-3	TOILET PLANS TOILET PLANS	E0.4 E0.5	ELECTRICAL SCHEDULES  ELECTRICAL SCHEDULES
A1-6	100 LEVEL - PARTIAL LARGE SCALE PLAN  100 LEVEL - PARTIAL LARGE SCALE PLAN	A7-3	TOILET PLANS TOILET ELEVATIONS	E0.5	ELECTRICAL SCHEDULES  ELECTRICAL & LIGHTING 200 LEVEL PARKING DECK
A1-7	100 LEVEL - PARTIAL LARGE SCALE PLAN  100 LEVEL - PARTIAL LARGE SCALE PLAN	A7-4	TOILET ELEVATIONS TOILET ELEVATIONS	E-1.1	ELECTRICAL & LIGHTING 200 LEVEL PARKING DECK
A1-9	100 LEVEL - PARTIAL LARGE SCALE PLAN	A7-5	INTERIOR ELEVATIONS / DETAILS	E-1.1	ELECTRICAL / MECHANICAL - 200 LEVEL
A1-10	200 LEVEL - PARTIAL LARGE SCALE PLAN	A8-2	INTERIOR ELEVATIONS / DETAILS	E-1.3	ELECTRICAL / MECHANICAL - 300 LEVEL
A1-11	200 LEVEL - PARTIAL LARGE SCALE PLAN	A8-3	INTERIOR ELEVATIONS / DETAILS	E-2.1	ELECTRIC PLAN - 100 LEVEL
A1-12	200 LEVEL - PARTIAL LARGE SCALE PLAN	A8-4	INTERIOR ELEVATIONS / DETAILS	E-2.2	ELECTRIC PLAN - 200 LEVEL
A1-13	300 LEVEL - PARTIAL LARGE SCALE PLAN	A8-5	INTERIOR ELEVATIONS / DETAILS	E-2.3	ELECTRIC PLAN - 300 LEVEL
A1-14	300 LEVEL - PARTIAL LARGE SCALE PLAN	A8-6	INTERIOR ELEVATIONS / DETAILS	E-3.0	LIGHTING SCHEDULES / SYMBOLS
A1-15	300 LEVEL - PARTIAL LARGE SCALE PLAN	A8-7	INTERIOR ELEVATIONS / DETAILS	E-3.1	LIGHTING PLAN - 100 LEVEL
A2-1	DOOR AND FRAME SCHEDULE	A8-8	INTERIOR ELEVATIONS / DETAILS	E-3.2	LIGHTING PLAN - 200 LEVEL
A2-1A	DOOR AND FRAME SCHEDULE	A8-9	INTERIOR ELEVATIONS / DETAILS	E-3.3	LIGHTING PLAN - 300 LEVEL
A2-2	INTERIOR FINISH SCHEDULE	RC-1	100 LEVEL NORTH - PARTIAL RCP PROPOSED		
A2-3	DOOR AND FRAME TYPES	RC-2	100 LEVEL EAST - PARTIAL RCP PROPOSED		
A2-3A	WINDOW TYPES	RC-3	200 LEVEL RCP PROPOSED		
A2-4	HEAD, JAMB, SILL DETAILS	RC-4	300 LEVEL RCP PROPOSED		
A2-5	WALL TYPES	RC-5	200 LEVEL PARTIAL LARGE SCALE RCP		
A2-6	HEAD, JAMB, SILL DETAILS	RC-6	200 LEVEL PARTIAL LARGE SCALE RCP		
A2-7	FRAME TYPES	RC-7	300 LEVEL PARTIAL LARGE SCALE RCP		
A2-8	MISCELLANEOUS DETAILS	RC-8	300 LEVEL PARTIAL LARGE SCALE RCP		
A2-9	MISCELLANEOUS DETAILS	RC-9	CEILING DETAILS		
A2-10	MISCELLANEOUS DETAILS				
A2-11	MISCELLANEOUS DETAILS				





SMITH DESIGN GROUP, INC.

206 WEST HARALSON STREET LAGRANGE, GEORGIA 30240

706-882-5511 www.SDGarch.net

		REVISIONS
$\triangle$	DATE	DESCRIPTION
DD		<u> </u>

PROJECT:

RENOVATIONS TO LAGRANGE POLICE DEPT

> 100 W HARALSON ST LAGRANGE, GEORGIA


TITLE:


INDEX OF SHEETS


**ABBREVIATIONS LEGENDS** 


MODIFIED DATE:	JOB NO:
	1911
ISSUED DATE:	
IOOOLD DATE.	SHEET:


FOR BID AND PERMIT 12 AUG 2019











200 LEVEL - LIFE SAFETY PLAN

Scale: 1/16" = 1'-0"

9,400 S.F. OF FIRE AREA

O.L. @ 100 SF/ PERSON = 94 PERSONS

**LEVEL 200 - 300 FIRE AREA SUMMARY** 

**LEVEL 300 =** 9030 S.F. OF FIRE AREA

90 PERSONS

**LEVEL 200 =** 9,400 S.F. OF FIRE AREA

**94 PERSONS** 

MAXIMUM OCCUPANCY = 184 PERSONS

TOTAL OCCUPANT LOAD FOR ENTIRE **FACILITY = 363 PERSONS** 

ARCHITECT'S STAMP	
STATE OF GEORGE	
* 7575 *	5
TERED ARCHITE	
SIGNATURE REQUIRED	

SMITH DESIGN GROUP, INC.

206 WEST HARALSON STREET LAGRANGE, GEORGIA 30240

706-882-5511 www.SDGarch.net

LEGEND OF WALLS

SEAL TIGHT TO DECK AND SEAL ALL PENETRATIONS. PROVIDE FIRE DAMPER IN ALL DUCTWORK PENETRATING 2 HOUR WALL.

		REVISIONS
Z	DATE	DESCRIPTION
RO	DJECT:	

RENOVATIONS TO LAGRANGE POLICE DEPT

100 W HARALSON ST LAGRANGE, GEORGIA

MODIFIED DATE:

ISSUED DATE:

FOR BID AND PERMIT

12 AUG 2019

LIFE SAFETY PLANS

JOB NO:

SHEET:

1911

1	1
$\overline{}$	$\overline{}$

GENERAL NOTES

- 1. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR REVIEWING ALL DRAWINGS AND FOR NOTING ANY DISCREPANCIES BETWEEN DRAWINGS, PLANS, DETAILS, TRADES, ETC. PRIOR TO THE CONSTRUCTION COMMENCEMENT.
- 2. THE 2007 VERSION OF THE "GENERAL CONDITIONS" OF THE AMERICAN INSTITUTE OF ARCHITECTS IS A PART OF THESE CONTRACT DOCUMENTS.
- 3. ALL EXTERIOR DIMENSIONS ARE TAKEN FROM BACK OF CURB UNLESS OTHERWISE NOTED.
- 4. PATCH AND REPAIR ALL EXISTING FINISHES AFFECTED BY DEMOLITION. NEW WORK PATCH AND REPAIR WORK SHALL MATCH EXISTING FINISHES FOR TEXTURE, COLOR AND MATERIAL.
- 5. REVISE AND / OR PROVIDE EXIT SIGNAGE AND LIGHTING AS REQUIRED BY ALL CODES.
- 6. CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND REQUIRED DIMENSIONS AS THEY RELATE TO THE INTENT OF THE NEW CONSTRUCTION. THIS VERIFICATION WORK MUST BE COMPLETED PRIOR TO THE START OF CONSTRUCTION, AND ANY DISCREPANCIES FOUND BETWEEN THE EXISTING WORK AND THE DRAWINGS SHALL BE REPORTED TO THE ARCHITECT PRIOR TO WORK COMMENCING.
- 7. CONTRACTOR SHALL COORDINATE ALL TRADE REQUIREMENTS AND REPORT CONFLICTS IMMEDIATELY IF FOUND. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONAL DATA AND LOCATIONS OF ALL OPENINGS, EQUIPMENT, AND OWNER FURNISHED EQUIPMENT.
- 8. DISCONNECT ANY ELECTRICAL, GAS, WATER OR OTHER LINES SERVICING THE EQUIPMENT PER RULES AND REGULATIONS OF AUTHORITIES HAVING JURISDICTION PRIOR TO BEGINNING WORK.
- 9. CONTRACTOR SHALL VERIFY WITH OWNER ALL EXISTING EQUIPMENT AND FURNISHINGS TO BE REMOVED, REPLACED, OR RELOCATED. CONTRACTOR SHALL PROVIDE AS REQUIRED, ALL PLUMBING, HVAC, AND ELECTRICAL NECESSARY FOR PROPER INSTALLATION OF NEW OR RELOCATED EQUIPMENT.
- 10. REPAIR ALL FLOOR FINISHES LEFT VOID OR DAMAGED BY DEMOLITION WORK AND MATCH EXISTING ADJACENT FINISH.
- 11. REPAIR EXISTING CONSTRUCTION (AS REQUIRED) TO MATCH ADJACENT CONSTRUCTION IN QUANTITY,
- 12. PROTECT EXISTING BUILDING DURING CONSTRUCTION. CONTRACTOR SHALL TAKE PROPER AND NECESSARY PRECAUTIONS TO PROTECT EXISTING BUILDING FROM TEMPERATURE AND HUMIDITY EXTREMES, DUST AND WATER PENETRATIONS. CONSTRUCT TEMPORARY WEATHER TIGHT ENCLOSURES.

SIZE, TEXTURE, AND FINISH, WHERE DAMAGED BY DEMOLITION WORK.

REPAIR ALL WATER DAMAGED ITEMS AT NO ADDITIONAL EXPENSE TO OWNER.

- 13. COORDINATE CONSTRUCTION OPERATIONS WITH OWNER WHERE THEY AFFECT EXISTING WORK AREAS AND NORMAL OPERATING PROCEDURES.
- 14. PHASE NEW DEMOLITION WORK WITH NEW CONSTRUCTION TO PROVIDE OWNER WITH ADEQUATE FACILITIES FOR TEMPORARY OPERATIONS AT ALL TIMES. COORDINATE WITH OWNER AND ALL TRADES.
- 15. DEMOLITION OF ANY EXISTING CONSTRUCTION REQUIRED BY ANY TRADE TO PROPERLY COMPLETE THEIR WORK SHALL BE ACCOMPLISHED AS PART OF THEIR WORK AND SHALL BE COVERED BY THE PRIME CONTRACT.
- 16. WHERE REMOVAL OF ANY ITEM IS CALLED FOR, IT SHALL BECOME THE PROPERTY OF THE BUILDING. THE CONTRACTOR IS TO CONTACT THE OWNER AND DETERMINE IF THE ITEM IS TO BE SALVAGED OR DELIVERED TO A LOCATION IN THE BUILDING AS DIRECTED BY OWNER, OR TO BE DISPOSED OF OFF SITE.
- 17. WHERE AN ITEM IS CALLED OUT TO BE RELOCATED, THE CONTRACTOR SHALL REMOVE IT UNDAMAGED AND REINSTALL IT IN ITS NEW LOCATION, INCLUDING ANY REQUIRED SUPPORTS, UTILITIES
- 18. WHERE ANY ITEM IS CALLED OUT TO BE SALVAGED, IT SHALL BE DELIVERED TO THE OWNER AT A DESIGNATED PLACE UNLESS IT IS ALSO CALLED OUT TO BE RELOCATED IN WHICH CASE, THE ITEM SHALL BE REMOVED, REFURBISHED AND REINSTALLED IN THE WORK.
- 19. WHERE EXISTING WALLS ARE TO BE REMOVED, THE ENTIRE ASSEMBLY SHALL BE REMOVED FROM CORNER TO CORNER COMPLETE, INCLUDING DOORS, WINDOWS, AND ALL ELECTRICAL AND MECHANICAL ITEMS INCLUDED IN THE ASSEMBLY.
- 20. WHERE CEILING ASSEMBLIES ARE CALLED OUT TO BE REMOVED, THE ENTIRE ASSEMBLY SHALL BE REMOVED, INCLUDING ALL HANGERS, FASTENERS, LIGHTS, AND MECHANICAL ITEMS.
- 21. WHERE WATER AND WASTE LINES ARE TO BE ABANDONED, THEY SHALL BE REMOVED AND CAPPED TO A POINT WHERE THEY WILL NOT BE VISIBLE WHEN NEW CONSTRUCTION IS FINISHED.
- 22. WHERE ELECTRICAL CIRCUITS ARE TO BE ABANDONED, THE CONDUIT SHALL BE REMOVED TO A POINT BEHIND THE SURFACE OF REMAINING OR NEW CONSTRUCTION AND CAPPED. THE WIRE SHALL BE REMOVED BACK TO THE PANEL AND THE BREAKER REPLACED WITH A SPARE BLANK.
- 23. ALL SURFACES RECEIVING WORK SHALL BE COMPLETED AND PROPERLY PREPARED TO RECEIVE THE FINISH MATERIAL SCHEDULED OR OTHERWISE CALLED FOR ON THE PLANS.
- 24. PATCH AND REPAIR CONCRETE FLOOR SURFACES WHERE EXISTING HOLES, SPALLING, AND CRACKS OCCUR IN AREAS OF THE BUILDING WHERE REMODEL WORK IS CALLED FOR AND WHERE DAMAGE FROM DEMOLITION OR NEW CONSTRUCTION OCCURS. ALL TO PROVIDE A FLUSH, SMOOTH AND CLEAN
- 25. PATCH AND REPAIR ALL SURFACES WHERE EXISTING HOLES, SPALLING, AND CRACKS OCCUR, WHERE DAMAGED OR DETRIORATED WALLS ARE REMOVED AND WHERE DAMAGE FROM DEMOLITION OR NEW CONSTRUCTION OCCURS, IN AREAS OF EXISTING BUILDING WHERE REMODELED WORK IS CALLED FOR. THE PATCHED AND REPAIRED SURFACE SHALL MATCH THE ADJACENT SURFACE IN MATERIAL, LINE AND TEXTURE.
- 26. PATCH AND REPAIR ALL SURFACES WHERE HOLES OR SLOTS FROM ANCHORING DEVICES OCCURED AFTER FINISH MATERIAL OR OTHER CONSTRUCTION HAS BEEN REMOVED. THE PATCH AND REPAIRED SURFACE SHALL MATCH THE ADJACENT SURFACE IN MATERIAL, LINE AND TEXTURE.
- 27. FILL OPENING AND PATCH AND REPAIR MATERIAL TO MATCH ADJACENT SURFACES WHERE MATERIALS ARE REMOVED BY ANY TRADE TO PREFORM THEIR WORK.
- 28. FILL ALL HOLES IN FLOORS, WALLS (INTERIOR AND EXTERIOR) AND CEILING TO MATCH ADJACENT SURFACES IN MATERIALS, LINE AND TEXTURE WHERE MECHANICAL, PLUMBING, OR ELECTRICAL ITEMS ARE REMOVED.
- 29. PATCH AND REALIR EXISTING WALLS TO MATCH ADJACENT SURFACES WHERE PORTIONS OF WALL WERE REMOVED FOR INSTALLATION OF NEW DOORS.
- 30. WHERE EXISTING PLUMBING OR ELECTRICAL LINES ARE TO REMAIN IN SERVICE BUT ARE LOCATED IN CONSTRUCTION TO BE REMOVED, SUCH LINES SHALL BE RELOCATED OR REDIRECTED AS NECESSARY TO REMAIN IN SERVICE.

#### **Current Mandatory Codes as Adopted by DCA:**

#### **International Building Code**

2012 Edition, with Georgia Amendments (2014) (2015) (2017)(2018)

#### **International Residential Code**

2012 Edition, with Georgia Amendments (2014) (2015)(2018)

#### **International Fire Code**

2012 Edition, with Georgia Amendments (2014)

#### International Plumbing Code

2012 Edition, with Georgia Amendments (2014) (2015)

#### **International Mechanical Code**

2012 Edition, with Georgia Amendments (2014) (2015)

#### International Fuel Gas Code

2012 Edition, with Georgia Amendments (2014) (2015)

#### **National Electrical Code**

2017 Edition (No Georgia Amendments)

#### **International Energy Conservation Code**

2009 Edition, with Georgia Supplements and Amendments (2011) (2012)

#### International Swimming Pool and Spa Code

2012 Edition, with Georgia Amendments (2014)

For information and questions regarding the Life Safety Code (NFPA 101) or the Georgia Accessibility Code please contact the State Fire Marshal's Office.

### LEGEND OF CONSTRUCTION MATERIALS

PLAN / SECTION	
face brick	<b>aluminum</b>
hollow concrete masonry	
gypsum wallboard	rough lumber scale m
ceramic/quarry tile	large scale finish lumber
acoustical tile	small scale finish lumber
resilient flooring	large scale plywood
carpet	small scale plywood
steel/iron	batt/blanket insulation
	laminated plastic

#### CODE SUMMARY AND PROJECT DATA

PROJECT NAME	ENHANCEMENTS TO LAGRANGE POLICE DEPARTMENT
PROJECT DESCRIPTION	RENOVATIONS AND ADDITIONS
OWNER	CITY OF LAGRANGE
CONTACT	
PROPOSED USE	BUSINESS
ARCHITECT OF RECORD	SMITH DESIGN GROUP, INC.
OCCUPANCY	BUSINESS
OCCUPANT LOAD	N/A
HAZARD	ORDINARY
MIXED OCCUPANCY	NO
CONSTRUCTION TYPE	TYPE TWO (II)B
SPRINKLERED	NO
STANDPIPE	NO
FIRE DISTRICT	NO
NUMBER OF STORYS	THREE (3)
HEIGHT ALLOWED	N/A
BUILDING HEIGHT	29'-0"
MEZZANINE	NO
HIGH RISE	NO
GROSS BUILDING AREA ALLOWED	
TOAL GROSS AREA HEATED	N/A
AREA SEPARATION PROVIDED	N/A
VERTICAL SHAFTS	N/A
EMERGENCY LIGHTING AND EXIT SIGNS	YES
FIRE ALARM AND SMOKE DETECTOR SYSTEM	NO
PANIC HARDWARE	NO
COMMON PATH OF TRAVEL ALLOWED	20' MAX
DEAD END LIMIT	20' MAX.
TRAVEL DISTANCE TO EXIT ALLOWED	200' WHEN SPRINKLED
NUMBER OF EXITS REQUIRED	NOT LESS THAN THREE (3)
PARKING SPACES REQUIRED	EXISTING





SMITH DESIGN GROUP, INC.

206 WEST HARALSON STREET LAGRANGE, GEORGIA 30240

706-882-5511 www.SDGarch.net

REVISIONS				
$\checkmark$	DATE	DESCRIPTION		

PROJECT:

RENOVATIONS TO LAGRANGE POLICE DEPT

100 W HARALSON ST LAGRANGE, GEORGIA

TITLE:

GENERAL NOTES

MODIFIED DATE:


JOB NO:

1911

ISSUED DATE:

FOR BID AND PERMIT

12 AUG 2019



#### **ADDITIVE ALTERNATIVES**

**BASE BID** - ALL WORK IN PHASE ONE

#### **ADDITIVE ALTERNATIVE NO.1**

IN SPACES 128 AND 129 INSTALL NEW PORCELAIN TILE FLOORS AND NEW PORCELAIN TILE (FULL HEIGHTS) ON ALL WALLS, PROVIDE NEW PLUMBING FIXTURES, NEW CEILING, NEW LIGHTS AND NEW VANITY PER DETAIL 4/A7-1.

ADDITIVE ALTERNATIVE NO.2- ALL WORK IN PHASE II (2)

ADDITIVE ALTERNATIVE NO.3- ALL WORK IN PHASE III (3)

ADDITIVE ALTERNATIVE NO.4- ALL WORK IN PHASE IV (4)

#### ADDITIVE ALTERNATIVE NO.5

TO REMOVE ALL EXISTING DATA CABLING ON THE 100 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 108. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 108 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.


#### ADDITIVE ALTERNATIVE NO.6

TO REMOVE ALL EXISTING DATA CABLING ON THE 200 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 225. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 225 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.


#### ADDITIVE ALTERNATIVE NO.7

TO REMOVE ALL EXISTING DATA CABLING ON THE 300 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 338. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 338 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

**100 LEVEL NORTH** 



#### **EAST HARALSON STREET**



100 LEVEL - PHASING Scale: 1/16" = 1'-0" GRAPHIC SCALE

# DESCRIPTION

#### RENOVATIONS TO LAGRANGE POLICE DEPT

100 W HARALSON ST LAGRANGE, GEORGIA

TITLE:

MODIFIED DATE: JOB NO: 1911 ISSUED DATE:

FOR BID AND PERMIT 12 AUG 2019

GE-9

#### SMITH DESIGN GROUP, INC. 206 WEST HARALSON STREET LAGRANGE, GEORGIA 30240 706-882-5511 www.SDGarch.net

REVISIONS 1 DATE PROJECT:

PHASING

## SHEET:

#### **Phasing and Liquidated Damages**

To be Substantial Complete within 190 Consecutive Calendar Days, after commencement of work , on Phase 1. Liquidated Damages in the sum of \$100 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.


#### Phase 2

To begin 14 Days after Substantial Completion of Phase 1, and To be Substantial Complete within 140 Consecutive Calendar Days, after commencement of work, on Phase 2. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.


To begin 14 Days after Substantial Completion of Phase 2, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 3. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### Phase 4

To begin 14 Days after Substantial Completion of Phase 3, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 4. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.



300 LEVEL - PHASING Scale: 1/16" = 1'-0"



Scale: 1/16" = 1'-0"

#### **ADDITIVE ALTERNATIVES**

**BASE BID** - ALL WORK IN PHASE ONE

#### **ADDITIVE ALTERNATIVE NO.1**

IN SPACES 128 AND 129 INSTALL NEW PORCELAIN TILE FLOORS AND NEW PORCELAIN TILE (FULL HEIGHTS) ON ALL WALLS, PROVIDE NEW PLUMBING FIXTURES, NEW CEILING, NEW LIGHTS AND NEW VANITY PER DETAIL 4/A7-1.

ADDITIVE ALTERNATIVE NO.2- ALL WORK IN PHASE II (2)

**ADDITIVE ALTERNATIVE NO.3**- ALL WORK IN PHASE III (3)

ADDITIVE ALTERNATIVE NO.4- ALL WORK IN PHASE IV (4)

#### ADDITIVE ALTERNATIVE NO.5

TO REMOVE ALL EXISTING DATA CABLING ON THE 100 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 108. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 108 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

#### ADDITIVE ALTERNATIVE NO.6

TO REMOVE ALL EXISTING DATA CABLING ON THE 200 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 225. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 225 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

#### ADDITIVE ALTERNATIVE NO.7

TO REMOVE ALL EXISTING DATA CABLING ON THE 300 LEVEL, IN ITS ENTIRETY FROM THE SITE. INSTALL NEW CAT 7 CABLING FROM ALL NEW AND EXISTING DATA DROPS, HOMERUN EACH DROP TO SPACE 338. MAKE TERMINATIONS AT WALL LOCATIONS, LEAVE SIX (6) FEET OF SLACK IN SPACE 338 FOR OWNER TO TERMINATE. COORDINATE TO TEST AND LABEL ALL DROPS.

#### **Phasing and Liquidated Damages**

#### Phase 1

To be Substantial Complete within 190 Consecutive Calendar Days, after commencement of work , on Phase 1. Liquidated Damages in the sum of \$100 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### Phase 2

To begin 14 Days after Substantial Completion of Phase 1, and To be Substantial Complete within 140 Consecutive Calendar Days, after commencement of work, on Phase 2. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

#### Phase 3


MORGAN

S

TRE

To begin 14 Days after Substantial Completion of Phase 2, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 3. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.

To begin 14 Days after Substantial Completion of Phase 3, and To be Substantial Complete within 120 Consecutive Calendar Days, after commencement of work, on Phase 4. Liquidated Damages in the sum of \$200 a day (Consecutive Calendar Days) will be due the Owner, If Substantial Completion deadline is not met by the General Contractor. No time extensions will be granted for Rain and Mud days since this project is Mainly Interior Renovations, and the Contractor's Staging Areas are already a paved surface.







SMITH DESIGN GROUP, INC.

206 WEST HARALSON STREET LAGRANGE, GEORGIA 30240

706-882-5511 www.SDGarch.net

	REVISIONS				
1	DATE	DESCRIPTION			

PROJECT:

**RENOVATIONS TO** LAGRANGE POLICE DEPT

> 100 W HARALSON ST LAGRANGE, GEORGIA

TITLE:

PHASING

MODIFIED DATE: JOB NO: 1911 ISSUED DATE: SHEET:

FOR BID AND PERMIT 12 AUG 2019

#	Rv #	ELECTRICAL CRITERIA - GENERAL CONDITIONS	Check Off
EC- 01	-	PERMITS & FEES: Secure & pay for all fees, licenses, permits, inspections. <u>Submit Copy</u> Of Each Permit	
EC- 02	-	LICENSE(S)-BUSINESS: This Contactor Shall Be Properly Licensed Business Wise, In This Project State, In Accordance With All Applicable State Laws. Submit Copies Of Business License(s).	
EC- 03	-	BONDING & INSURANCE(s): This Contactor Shall Be Properly Bonded And Insured In Accordance With The General & Supplements Requirement Of The Project Document.  Submit Copies Of All Such Documents.	
EC- 04	-	COORDINATION OF OTHER TRADES- This contractor is responsible for coordinating with all other trades for the proper installation of this work, maintaining required clearances, and confirming the electrical characteristics and requirement of electrical power equipment of other trades (prior to ordering equipment). Submit Copies Of All Such Documents.	
EC- 05	-	MANUFACTURERS, ALTERNATES & SUBSTITUTIONS- Components & products are to be provided matching the prescribed characteristics, features, performance, types, etc. based on the Manufacturer & Series as given. No After-"Bid" Alternates, Changes Or Substitutions Accepted Or Allowed. Prior-To-Bid Request For Acceptance Must Be Submitted To Architect & Engineer NO-LESS Than Two-Business-Weeks Prior To Bid Date. Request-For-Acceptance Must Include Complete & Marked Product Data Indicating Full Matching Compliance. Any Variations Must Be Marked & Noted. Acceptance Will Be At The Description Of The A/E Judgment.	
EC- 06	-	SUBMITTALS- Provide compete submittals on all items. Mark & indicate specific items to be used. Submit prior to finalizing orders. Submit three sets min., or per General Conditions.	
EC- 07	-	WARRANTY- This contractor shall warrant all materials, labor & installation for one full year from date of Substantial Completion. Any extended product warranties shall be passed onto the owner.	

#	Rv #	ELECTRICAL CRITERIA - BASICS CRITERIA	Check Off
EB- 01	-	GENERAL- Provide a complete electrical system, left in proper working order. Provide herein means installed completely, including labor & materials.	
EB- 02		LICENSE(S)-ELECTRICAL: This Contactor Shall Be Fully Licensed To Perform Electrical Work, In This Project State, For The Type Of Work To Be Performed In Accordance With All Applicable State Laws. Submit Copies Of Electrical License(s).	
EB- 03	-	CODES - Meet & comply with all prevailing Federal, State, County & City Codes Including NEC (NFPA-70); ICC-IBC & any Ga Amendments; ICC-IEC & any Ga Amendments.	
EB- 04	-	PERMITS & FEES: Secure & pay for all fees, licenses, permits, inspections. <u>Submit Copy</u> Of Each Permit	
EB- 05	_	COORDINATION OF POWER UTILITY- Coordinate & verify, in writing, with the utility power company, confirming the electrical power arrangements, characteristics (Voltage, Phase, Transformer Type & KVA, Fault-Current, Etc.), metering arrangement and equipment locations. Copy Own/ Archt/ Engr.	
EB- 06	_	COORDINATION OF LV COMMUNICATIONS UTILITY- Coordinate & verify, in writing, with the LV Communications Utility Company, confirming the LV Com Service routing, conduit quantity & sizes, termination locations, and other related requirements.	
EB- 07	_	PROVISIONS TO BE INCLUDED- Labor, supplies and materials, tools, equipment, etc.; installation of all electrical equipment & connections; coordination with other trades; material shipping, delivery, receiving, storage, & protection; excavation, backfilling, cutting, patching and cleaning; guarantee for one year, plus any extended manufacturer's warranties; as-built reproducible Mylar record documents.	
EB- 08	-	MATERIALS- All materials shall be new, currently manufactured, U.L. labeled, and meet all industry standards. Label all equipment. Provide 3000 PSI class concrete for bases and backfill. Provide 3/4" thick A/D fire retardant grade backboards. Provide all support hardware and systems for electrical work. Fire/smoke seal each penetration of any rated barrier (floor, wall, etc.).	
EB- 09	_	MOTORS & CONTROLS- Motors are furnished and installed under other specification sections. Control and interlock wiring is furnished and installed under other specification sections. Individually mounted starters are furnished under other sections, mounted and power wiring connections provided under this section.	
EB- 10	_	ELECTRICAL CONNECTIONS- Provide power wiring complete to all items. Coordinate actual equipment characteristics with drawing. Provide backboards for equipment mounting. Label all equipment and over-current protective devices with equipment name, voltage, ratings, and O.C.P. ratings.	1
FR.		INSTALLATION STANDARDS: All electrical work shall be installed in accordance with the	

NEC, NEIS (Nat. Electrical Installation Stds..), related codes and the manufacturer's

End Of Electrical Criteria - Basic Materials & Methods

published requirements.

#	Rv #	ELECTRICAL CRITERIA - BONDING & GROUNDING	Check Off
EG- 01	-	BONDING & GROUNDING GENERAL: Provide components, conductors, fittings and hardware to provide for an electrical system that is completely bonded and grounded with the NEC and these requirements	
EG- 02	-	GENERAL REQUIRMENTS: Provide for the complete Bonding & Grounding of the entire electrical system, including bonding for communication systems.	
EG- 03	-	BUILDING BONDING: Provide for the Bonding together of all metallic systems in the facility, including but not limited to, structural steel, slab rebar, water piping, fire-protection piping, gas piping, HVAC system piping.	
EG- 04	-	SUBMITTALS- Provide compete submittals on all items. Mark & indicate specific items to be used. Submit prior to finalizing orders. Submit three sets min., or per General Conditions.	
EG- 05	-	GROUNDING IN-GRADE CONDUCTORS: Bare, Tin-Plated Copper Of Size & Rating As Scheduled or Required.	
EG- 06	-	BONDING & GROUNDING CONDUCTORS:- #10 and smaller - solid copper THHN/THWN Green Jacket Color; #6 & 8 - stranded copper THHN/THWN black jacket; #4 & larger - stranded copper THHN/THWN identified with Green Tape.	
EG- 07	-	CONNECTIORS, IN-GRADE TYPE: UL Labeled for the application, location & use. Heavy- Duty Pure Wrought Copper fitting & devices. Compression type connections. BURNDY HYGROUND Series or Equivalent.	
EG- -08	-	CONNECTIONS, COPPER- Twist on type for #8 and smaller copper conductors. Set screw/bolted type for #4 and larger copper conductors. Completely insulate each connection, splice, termination.	
EG- 09	-	GROUND RODS (ERITECH 683400 Rod): Provide 10 Foot Long, 0. 75 In Diameter, Tin-On-Copper 10 Mil. Plated Steel Pointed Ground Rod, driven into earth with top 18 Inches below finished grade with inspection/ test well cover, top flush with grade. ANSI/UL-467 & ANSI/NEMA-GR1. Mechancial Direct-Burial Ground Connector or Exothermic-Weld all ground cables to rods.	
EG- 10	-	GROUND ROD INSPECTION WELLS/ ERITECH Wells - Where indicated or required, provide Ground Rod Inspection/ Test Well & Cover, top flush with grade.	
EG- 11	-	MASTER GROUND BAR (MGB) (BURNDY BBB or ERICO TGB/TMGB)- Provide bare solid Alloy 110 Cu bus bar, electro-tin-plated, with pre-punched holes for two-bolt ground lugs, mounted on stainless steel brackets with insulated flame-resistant stand-offs. 0.25 Inch Thick, 4 Inch High, 20 Inch Long. UL 467 & C22.2 Listed. Anchor to structural wall at height as indicated or noted. Connection to this bar shall be by two-hole bolt lugs, exothermic welded or irreversible crimp connected to the respective cable. Locate at or near the electrical service main disconnect. Label MASTER GROUND BAR	
EG- 12	-	ISBT (Inter-System-Bonding-Termination) GROUND BAR (ISBT) (ILSCO PET or Equal): Provide dual-rated, 8-hole lug with 2-predrilled mounting holes. Attach to each TELCO backboard for bonding of LV systems by others. Label ISBT GRND.	
EG- 13	-	INSTALLATION STANDARDS: All bonding & grounding shall be installed in accordance with the NEC, NEIS (Nat. Electrical Installation Stds.), related codes and the manufacturer's published requirements.	
- ]	-	End Of Electrical Criteria - Bonding & Grounding	

#	Rv #	ELECTRICAL CRITERIA - CONDUITS, BOXES & FITTINGS	Chl Off
ER- 01	-	GENERAL- All wiring for power and systems shall done in accordance with the applicable codes. All materials shall be U.L. labeled, matched for proper applications and installed in accordance with U.L. & manufacturer's requirements.	
ER- 02	-	SUBMITTALS- Provide compete submittals on all items. Mark & indicate specific items to be used. Submit prior to finalizing orders. Submit three sets min., or per General Conditions.	
ER- 03	-	GENERAL UNDERGROUND- All underground, in-slab, exterior and exposed or surface mounted wiring shall be in conduits, unless otherwise directed.	
ER- 04	-	GENERAL CONCEALED- All wiring shall be concealed where possible (i. eabove ceilings, in walls, in slabs, or underground).	
ER- 05	-	GENERAL EXPOSED- Exposed conduits shall be routed as high as possible and parallel or perpendicular to structural elements.	
ER- 06	-	GENERAL BOXES- Provide boxes for all connections, devices, system, etc. Coordinate box sizes with structure to which it will be secured. Coordinate the exact final box location with the architectural/interior drawings prior to rough-in of box.	
ER- 07	-	CONDUITS, IMC- conduit & fittings shall be utilized for exterior exposed locations and interior exposed locations subject to damage.	
ER- 08	-	CONDUITS, EMT- EMT conduit & fittings shall be utilized for in slabs not on grade, concealed dry interior locations, interior exposed locations above 10'0" A. F. F.with set screw fittings indoor concealed dry locations and compression raintight fittings in slabs, and damp locations.	
ER- 09	-	CONDUITS, PVC- conduit & fittings shall be utilized in slabs on grade, conduits in earth. PVC fittings, boxes, etc. shall be of same manufacture with solvent bond. Depth per code.	
ER- 10	-	CONDUITS, FLEXIBLE- Flexible metallic conduit & fittings shall be utilized where motion or vibrations are encountered. Liquid-tight type flex shall be used in damp or wet locations, (i. e outdoors, kitchens, areas subject to wash down, shops & industrial areas, etc.). Provide ground wire in all flex.	
ER- 11	-	CONDUIT MISC. FITTINGS- Conduit expansion/deflection fittings shall be utilized where crossing expansion joints, floating slabs or isolated slabs. Conduit thru wall seals shall be utilized where crossing between interior/exterior or damp locations. Conduit fire seals shall be utilized where passing thru fire rated construction, U. L. fire and smoke seal to maintain the fire rating of the barrier.	
ER- 12	-	CONDUIT BOXES- Utilize interior stamped steel for indoors dry flush mounted devices.  Masonry/tile for indoors dry flush mounted devices. Concrete boxes for flush mounting in poured concrete. Cast metal boxes for surface mounted devices, or damp/wet locations.  Junction & pull boxes as required or needed. Galvanized steel wire-ways with hinged front cover, only permitted where noted.	
ER- 13	-	FLOOR BOXES - Utilize flush-in-floor type, adjustable post-pour, PVC base with brass flip-lid covers. Gang qty to match application & conduit entries., Covers to match device types. Hubbell, Steel City or Wiremold	
ER- 14	-	SIESMIC BRACING & SUPPORT- All work shall be anchored, braced & supported in accordance with he Local Seismic Zone rating requirements.	
ER- 15	-	INSTALLATION STANDARDS: Each item shall be installed in accordance with the NEIS (Nat. Electrical Installation Stds.), NEC & related codes and the manufacturer's published requirements.	
-	-	End Of Electrical Criteria - Conduits, Boxes & Fittings	

	_	requirements.		ED-	pressure contac
	1	End Of Electrical Criteria - Conduits, Boxes & Fittings		26	fuses (as requir
					manual/electric GFCl on switch
					FUSES- Fuses
	Rv	ELECTRICAL CRITERIA - LOW VOLTAGE CONDUCTORS	Chk	ED-	three wire O.C.
$\perp$	#	ELECTRICAL CRITERIA - LOW VOLTAGE CONDUCTORS	Off	27	L) for protection
;-  	-	CONDUCTORS GENERAL: Provide conductors for all circuiting, wiring and systems.			(600V) (U.L. 198
		OLIDANITTAL C. Duravida a compansa a colonidada anno all'itanno Mante 9 indicata anno sife itanno ta la			PANELBOARD
	_	SUBMITTALS- Provide compete submittals on all items. Mark & indicate specific items to be			door, NEMA 1
-		used. Submit prior to finalizing orders. Submit three sets min., or per General Conditions.		ED-	phase, ampacit
		CONDUCTORS COLOR CODED: Each conductor shall be properly color coded to represent		30	rated and label
)-		it's respective phase, neutral, ground, etc. Wire sizes #12 thru #8 shall have continuous			All lugs & termi
3	-	color-coded jacket. Larger wire sizes shall have colored tape at each termination, pull-box,			PANELBOARD
		etc.		ED-	and PB1; NFPA
;-		CONDUCTOR LARGE INC. Each sirewit labeled on the conductor and at each have		31	& Fusible Switch
ŀ	-	CONDUCTOR LABELING: Each circuit labeled on the conductor and at each box.			SHORT CIRCUI
		CONDUCTORS, COPPER- #12 & #10 - solid copper THHN/THWN color coded; #6 & 8 -		ED-	Circuit Current a
	-	stranded copper THHN/THWN black jacket; #4 & larger - stranded copper THHN/THWN. No		32	Level & protect
1		conductors less than #12 Cu allowed, unless specifically noted or control wiring.			PANELBOARD
}-		CONDUCTORS, ALUMINUM- Aluminum (AL) not permitted unless noted. Where noted,		ED-	numbering, sec
3	-	conductors shall be compact strand type, THHN/ THWN.		33	& neutral bus, 5
		CONNECTIONS, COPPER- U.L. Listed, 600V, 90C rated; Twist on type for #8 and smaller			OCP DEVICES
,-	-	copper conductors. Set-Screw, Bolted or Compression type for #4 and larger copper		ED-	components an
		conductors. Completely insulate each connection, splice, termination.		34	Refer to Over-C
		CONNECTIONS, ALUMINUM- U.L. Listed, 600V, 90C rated, compression, split-bolt, or set-		ED-	PANEL DIRECT
,-	-	screw type(s),for Aluminum or Dual-Rated. Completely insulate each connection, splice,		35	NEC-110.22 & 4
'		termination.			1,12,2,12,2
)-		CONNECTIONS, DAMP & WET LOCATION- UL Listed 486D type connector for damp & wet			SWITCHBOARD
)		locations, sealant filled type. IDEAL Model 66 or Equal		ED-	scheduled. Vol
)-		CONNECTIONS, IN-GRADE, UNDER-GROUND, SUBMERSIBLE, WATER-TIGHT- UL Listed		40	applicable. Fre
)	-	486D, 600V, 90C rated for In-Grade, Direct-Burial, Submersible.			terminals 60/75
		GROUNDING CONNECTIONS, IN-GRADE, UNDER-GROUND, SUBMERSIBLE- UL 467 Listed,		ED-	SWITCHBOARD
	-	90C rated, Compress Or Bolt Type With Inhibiting compound; For Use In Earth or Concrete.		41	Listed & Labele
		300 fated, compless of boil type with initiality compound, for ose in Earth of Contrete.		41	Specs. W-P-11
	- 1	METAL-CLAD (MC) CABLE (CONCEALED WIRING)- Contractor may utilize Metal-Clad (Type		ED-	SHORT CIRCUI
		MC) for interior concealed branch circuit wiring in accordance with the code. All materials,			Circuit Current a
	-	fittings, hardware, etc. shall be U.L. labeled for use with MC cable and properly installed and		42	Level & protect
-		supported. Type MC cable shall have an integral full length ground conductor, bonded to a		ED-	SWITCHBOARD
		ground lug or terminal at each end.		43	aluminum busin
$\prod$		INSTALLATION STANDARDS: All wiring & connects shall be installed in accordance with the		43	bus.
-	-	NEIS (Nat. Electrical Installation Stds.), NEC & related codes and the manufacturer's		ED-	OCP DEVICES
_		published requirements.		44	components an
1	-	End Of Electrical Criteria - Low Voltage Conductors		44	Refer to Over-C
		citu Oi Electrical Criteria - Low Voltage Conductors		ED-	CIRCUIT DIREC
				45	NEC-110.22 & 4

03 ED-	and interference with work of other trades.  SUBMITTALS- Provide compete submittals on all items. Mark & indicate specific items to be
04	used. Submit prior to finalizing orders. Submit three sets min., or per General Conditions.  LABELING & INSTALLATION
ED- 10	EQUIPMENT LABELS: Provide Engraved Melamine Equipment Labels, Adhesive Attached - To The Items Face Or Interior Cover. Label To Include Equipment Name, Voltage(s) And OCP Device Ratings If Applicable.
ED-	SAFETY & WARNING LABELS: Provide Clear & Legible Safety & Warning Labels On Each Item Of Electrical Distribution Gear As Required By The NEC, OSHA & Other Regulations.
ED- 12	ARC-FLASH LABELS: Provide Clear & Legible Arc-Flash Labels On Each Item Of Electrical  - Distribution Gear, Giving The Minimum Ratings, Arc-Flash Energy Level & Required PPE For Each Specific Location.
ED- 13	SIESMIC BRACING & SUPPORT- Equipment shall be anchored, braced & supported in accordance with he Local Seismic Zone rating requirements.
ED- 14	INSTALLATION STANDARDS: Each item shall be installed in accordance with the NEIS (Nat Electrical Installation Stds.), NEC & related codes and the manufacturer's published requirements.
ED- 21	OCP GENERAL- Provide over-current-protective (O.C.P.) devices as required by code
ED- 22	and/or otherwise prescribed. All lugs and terminals 60/75 deg. C rated.  MOLDED CASE (MC) CIRCUIT BREAKERS- Thermal-magnetic, bolt-in, quick-make/quick-break type. Trip free operation with ON, OFF & TRIPPED position. Monolithic tie-handle common trip and common reset multi-pole breakers. Trip rating molded on handle or face. Lugs to match cable type terminations. Single pole 15 and 20 ampere breakers to be "SWITCHING" rated.
ED- 23	DISCONNECT REQUIRMENTS - NEMA 1 enclosure indoors, NEMA 3R for damp/wet locations. Voltage, poles, amperage, fusible as required. Equipped with both isolated neutral and ground lugs. Class H, J, R or T fuse with rejection features. Provide switch label.
ED- 24	DISCONNECTS 30AMP. – 200AMP (240V Max) - Labeled per UL #98. NEMA KS1 general duty type, load make/break rated. Interrupting rating of 100,000 RMS amps (with R/ T fuse).
ED- 25	DISCONNECTS 400 & 600 AMPERES - Labeled per UL #98. NEMA KS-1 heavy duty type, load make/break rated. Interrupting rating of 200,000 RMS amps (with fuse).  DISCONNECT OVER 600 AMPERES- Labeled per Ulf #977, bolted pressure or high
ED- 26	pressure contact type. NEMA heavy duty type, load make/break rated. Accept Class L fuses (as required). Interrupting rating of 200,000 RMS (with fusing). Manual close - manual/electric trip open. Load side phase under voltage detection/trip. Zero sequence GFCl on switches 1000A @ 277 and greater.  FUSES- Fuses shall be of same make, manufacturer, type & rating where providing two or
ED- 27	three wire O.C.P. at a device. Provide Busman LOW-PEAK KRP-C. fuses (U.L. 198 C Class L) for protection over 600 amperes. Provide Busman LOW-PEAK LPN-RK (250V) or LPS-RK (600V) (U.L. 198E Class RK1) for protection up to 600 amperes.
	PANELBOARDS  PANELBOARDS GENERAL- Provide dead front design with hinged & locking front cover
30	door, NEMA 1 cabinet unless otherwise noted and with devices as scheduled. Voltage, phase, ampacity and devices as scheduled. Service entrance rated as applicable. Series rated and labeled, unless indicated otherwise. Flush or surface mounted NEMA 1 enclosure. All lugs & terminals 60/75 deg. C rated.
ED- 31	PANELBOARD STANDARDS- Labeled UL 67 and 50 (Cabinets, Boxes & Trim); NEMA 250 and PB1; NFPA 70-384 and 373; Federal Specs. W-P-115c; Circuit Breakers- Type I Class 1 & Fusible Switches- Type II, Class 1.
ED- 32	SHORT CIRCUIT RATING & ARC-FLASH LABELS: Match or exceed the Available Short Circuit Current available at the actual panel location; Properly label with Arc-Flash Energy Level & protective requirements (PPE).
ED- 33	PANELBOARD INTERIOR- Factory assembled, double row construction. Staggered numbering, sequence phased. Tin-plated copper or aluminum busing. Full ampacity phase
ED- 34	& neutral bus, 50% ground bus.  OCP DEVICES, COMPONENTS, ETC: Provide all over-current-devices and other components and related as scheduled and / or required. Refer to panel schedule for details.
ED- 35	Refer to Over-Current Protective (OCP) devices criteria.  PANEL DIRECTORIES - All Panel Directories Shall Be Current, Fully Detailed & Legible Per NEC-110.22 & 408.4(A)
ED- 40	SWITCHBOARDS  SWITCHBOARDS  SWITCHBOARDS GENERAL- Provide equipment with dead front design and with devices as scheduled. Voltage, phase, ampacity and devices as scheduled. Service entrance rated as applicable. Free-Standing, NEMA 1 enclosure unless otherwise required. All lugs &
ED- 41	terminals 60/75 deg. C rated.  SWITCHBOARD STANDARDS- The equipment and all installed components shall be UL Listed & Labeled UL 891; NEMA 250 and PB2; NFPA 70-384 and 373; Federal Specs. W-P-115c; Circuit Breakers- Type I Class 1 & Fusible Switches- Type II, Class 1.
ED- 42	SHORT CIRCUIT RATING & ARC-FLASH LABELS: Match or exceed the Available Short Circuit Current available at the actual panel location; Properly label with Arc-Flash Energy
ED- 43	Level & protective requirements (PPE).  SWITCHBOARD INTERIOR- Factory preassembled, sequence phased. Tin-plated copper or aluminum busing unless otherwise noted. Full ampacity phase & neutral bus, 50% ground
ĒD-	bus.  OCP DEVICES, COMPONENTS, ETC: Provide all over-current-devices and other components and related as scheduled and / or required. Refer to panel schedule for details.
44 ED-	Refer to Over-Current Protective (OCP) devices criteria.  CIRCUIT DIRECTORIES - All Circuit Directories Shall Be Current, Fully Detailed & Legible Per
45	NEC-110.22 & 408.4(A)  TRANSFORMERS  TRANSFORMERS GENERAL- Provide dead-front dry-type transformer. Labeled per UL
ED- 50	#506, conform with NEMA #250, #ST20 and TR27. General purpose air-cooled dry-type construction. Size, capacity, primary and secondary voltage, as indicated. NEMA 1 enclosure for indoor dry locations, NEMA 3R enclosure for damp/wet locations. Dead-front construction with removable covers. Maximum temperature rise by resistance of 115 degrees C. in a 40 degrees C. ambient. 75 degrees C. maximum terminal compartment with 60/75 degree C. lugs to match the conductor types. Two 2-1/2% above normal and four 2-1/2% below normal full capacity winding taps.
-	End Of Electrical Criteria - Low Voltage Electrical Distribution Gear

ELECTRICAL CRITERIA - LOW VOLT. ELECT. DISTRIB. GEAR

GENERAL- Provide Low-Voltage Electrical Distribution Gear as required to provide for a

complete system to distribute electrical power.

	Rv		Chk	40	00	42	LaCrana Palias David 2040 Ma
#	#	ELECTRICAL CRITERIA - PROJECT CLOSE-001	Off			.12	LaGrange Police Dept 2019 Mo
EZ-		REVIEW REQUEST NOTICE(s)- This Contractor Shall Notify, In Writing, At Least 10 Days In		DN	I-	Rv	ELECTRICAL DISCLAIMERS & PROJECT N
01	-	Advance, To Own/ Archt/ Engr, Of The Desired Date To Request Having An On-Site Review Performed.		0			CONSTRUCTION MODS- This Project Is Consist Of Impro
EZ-		AHJ INSPECTION REPORTS- This Contractor Shall Submitt Copy(s) Of Each Inspection		0		-	Modifications, & Renovations Within An Existing Building. Co Phased, See Architectural Criteria.
02 EZ-	Ŀ	Report As Given By The Authority Having Jurisdiction (AHJ) To The Own/ Archt/ Engr.			+		rnaseu, see Ardinectural Ontena.
	_	ROUGH IN REVIEWS - Request Rough-In Reivew(s) Before Any Mateiral Or Work Is					<b>EXISTING CONDITIONS</b> > This Project Involves Existing 0
03 EZ-	-	Covered And Unobservable.		02		_	Contractor Is Responsible For Making An On-Site Review &
E∠- 04	-	CERTIFICATIONS & TEST REPORTS- Provide Copies Of All Required Certifications And Test Results Prior To Requesting Final Review.		02	-		All Existing Conditions & Providing For Accommodating The
EZ-		CONTRACTOR REVIEW- This Contractor Shall Throughly Review & Document That The					Conditions In The Pricing For This Work, Prior To Work Sta
05	-	Complete Work Is Properly Functioning & Opeating Prior To Requesting A Final Review.			$\dagger$		EXISTING ELECT. DISTB.> This Project's Electrical Powe
EZ-	_	REVIEW ELECTRICAL BONDING & GROUNDS- Veirfy Each Service Ground & Bond Is					Metering & Distribution Is Existing. This Contractor Is Respo
06		Properly Installed, Connected & Labled.\		03	3	_	Making An On-Site Review & Familiarizing Of All Existing Co
EZ- 07	1 -	REVIEW ELECTRICAL SERVICE & VOLTAGE- Test & Record The Actual Voltages (L-L, L-N,L-G, N-G) And Amperages Of Each Line, Netural & Ground At The Service Entrance					Providing For Accommodating The Existing Conditions In TI
		REVIEW ELECTRICAL DISTRIBUTION- Review & Document Each Part Of The Electrical					This Work.
EZ-	1	Distribution System. Verify Proper Size & Ratings Of Each Item, Proper Connections &			$\dagger$		SEQUENCING OF WORK> Prior To Start, All Work Shall I
80		Torque Values. Verify Proper Bonding & Grounding.		04		_	With The Owner-Occupant, And Documented In Writing The
EZ-		REVIEW ELECTRICAL PANEL DIRECTORIES - Review & Verify Detial Panel Directories Are					The Owner-Operator-Occupant(s). Update As Required.
09	-	Complete, Correct & Installed. Provide Complete "As-Built" Panel Schesule, In PDF Format			$\top$		POWER OUTAGE> Any Power Outages Shall Be Fully Pre
	-	To Owner For Their Records.			.		The Owner-Operator Well In Advance Of The Actual Outage
EZ-		REVIEW ELECTRICAL EQUIPMENT WIRING- Review Each Equipment Connection, Verify		05		-	As Contracted With Owner-Operator Provide For Any Nece
10	-	Circuit Protection Complies With The Equipment UL Listings & Ratings. Verify Disconnects					Temporary-Backup Power Needs.
		Are Properly Labeled. Check For Proper Voltage & Phase Rotation For Equipment.			$\top$		LIGHTING COORDINATION: Refer To & Coordinate With
		REVIEW ELECTRICAL WIRING & DEVICES- Review & Document That All Branch Circuit		06	3		Interiors (A/I) (i.eCeiling Types & Layouts, Fire-Ratings, N
EZ-	-	Wiring Is Properly Installed, Bonded & Operational. Test Each Outlet With For Proper					Etc.).
11		Contunity, Polarity & Grounding. Test Using An IDEAL INDUSTRIES SURE-TEST Model 61-			$\uparrow$		EMERGENCY EGRESS & EXIT LIGHTING Is Provided V
	-	165 Or Equal.  REVIEW ELECTRICAL LIGHTING & CONTROLS- Review & Document That All LIGHTING		06	5	-	Backup Units. Refer To The Lighting Fixture Schedule.
EZ-	-	Fixtures Are Properly Operating And Clean. Verify Proper Operation Of All Lighting Controls.			$\top$		GENERATOR POWER SYSTEM (OPTIONAL STAND-BY
12		Program & Set An Control Operations And/ Or Schedules Per Owner.		07	,		Has A Generator Power Source & Automatic Transfer Switch
		REVIEW ELECTRICAL EMERGENCY EGRESS LIGHTNG & EXIT SIGNS:- Review &					Normal Utility Power.
EZ-	_	Document That Each Emergency Lighting Fixture And / Or System And Each Exit Sign Is			$\top$		SLAB PENETRATIONS: Verify Each With Building Owner
13		Properly Functioning. Turn Off Building / Suite Power For 90 Minutes And Verify Emergency		30	3	_	Provide Scanning / X-Ray If Required Prior To Penetration
EZ-		Lighting & Exit Are Operational Per Code.  REVIEW ELECTRICAL SUB-SYSTEMS- Refer To The Specific Requirments Of Each "Sub-					Location Acceptability.
 14	-	Systems" (i.eFire Alalrm, Data-Voice, Etc.).		09		_	FIRE ALARM - Not In This Work-Scope.
EZ-		KEYS & SPARE PARTS- Label & Turn Over All Keys To Owner's Personell. Review & Show		10			TELCO-VOICE-DATA SYSTEM(s)- Not In This Work-Scor
16	-	All Spare Components & Parts To Owner's Personell & Document With Transmittal.		1		_	TV-BROADBAND SYSTEM(s)- Not In This Work-Scope.
EZ-		"AS_BUILTS" - Provide Copies, In Hard-Copy & PDF Format, Of The Field Recored		12			ACCESS CONTROL & SECURITY- Not In This Work-Sco
17	-	Documents With All "As-Built" Field Documentation Reflecting The Final Installed Conditions.			+		
	-	Copy To Own/ Archt/ Engr.  WARRANTY- This contractor shall warrant all materials, labor & installation for one full year					OWNER-TENANT-USER PRODUCTS: It Is Our Understa
EZ-	1	from date of Certificate of Occupancy. Any extended product warranties shall be passed		13	3	_	Hazardous Environments Or Product Requiring Special Hai
18		onto the owner.					Etc. Are Involved. Any Hazardous Products, Use, Etc. Are
		INSTRUCTIONS & TRAINING:- Schedule & Provide A Instructional & Traning Session With					& Properly Used So As To Not Require Special Environme
EZ-	_	The Owner's Designated Personell. Review The Project Manual, Perform A "Walk-Thru"			$\dagger$		OWNER-TENANT FFE- Some Items Are Owner or Tenant
20		Review Of The All Electrical System(s) And Their Proper Operation, Including Resetting Of			.		Installed. Prior To Start Of Work Verify Each Items Final Loc
		Breaker & Replacment Of Fuses.  PROJECT MANUAL(S)- Provide Both A Bound "Hard-Copy" & PDF Version To The Owner &		14	1	-	Supply & Drain Connection Requirements Match Provisions
		PDF Copy To The Archt/ Engr. The Project Manual Shall Include The Contractors Contact					The Documents. Advise of Any Discrepancy.
EZ-		Information, Permits, Copies Of All "As-Builts", Product Submittal Data, Copies Of All			$\top$		
21		Inspection Reports, Certifications & Test Results. Include All Mainteance Data, Instructions, &		15	5	_	OWNER-TENANT-USER RESPONSIBILITIES - To Revi
		Warranty Information.					Proper Operations & Maintenance Of The Electrical Compo
EZ-		FINAL REVIEWS - Request A Final Reivew Once All Work & Systems Are Completed,			$\top$		OWNER TENANT HOER CONTRACTOR REVIEW & TE
22	-	Checked And In Proper Operation					OWNER-TENANT-USER -CONTRACTOR REVIEW & TR
		End Of Electrical Criteia - Project Close-Out		16	3	-	Is To Provide Complete Copies Of Legible Field Record Dr.
							Built) & Review Them With The Owner & Owners Represer
							Proper Operations & Maintenance Of The Electrical Compo
#	Rv		Chk	17	,	_	OWNER-TENANT-USER RESPONSIBILITIES- Regular
"	#		Off	''		_	Months) GFCI & AFCI Devices To Ensure Proper Operatio
ET-	- 1	TELCO RACEWAY SCOPE-OF-WORK: Providing raceways, backboards and wall boxes with conduit stub-ups & pull-strings only for devices, cabling & equipment installation by others					OWNER-TENANT-USER EMERGENCY SYSTEM TESTI
01		(Telco, Voice, Data, Broadband, Etc.)					RESPONSIBILITIES- To Regularly (Verify Monthly) Chec
ET-		TELCO DEVICES, CABLING & EQUIPMENT: All cabling, jacks, devices, hardware,		18	3	-	Document The Proper Operation Of The Emergency Lightin
02	-	equipment & software & related installation is the responsibility of the owner or tenant.					To NFPA-101 & OSHA Regulations. Documentation & Forn
ΞT-		TELCO UTILITY COORDINATION: Prior to any rough in, coordinate, in writing, with the Telco					Automatic Self-Testing Units May Qualify, Check Regs.
03	_	Service Provider all related requirements- route, conduit qty & sizes, grounding, etc.			-	-	
		TELCO SYSTEM PROVIDER COORDINATION: Prior to any rough in, coordinate, in writing,		19	)-12	21	End Of Disclaimer & Project Notes
ET-	- 1	with the Telco Service Provider all related requirements- route, conduit qty & sizes,					
04	- 1	grounding, etc.					
ET-		TELCO SERVICE CONDUITS: Quanity & size as required or shown, use long radius bends					
05	_	(10X) on all raceway bends & turns. Install Pull-Strings, tagged & tied-off at each end.					
ET-	- 1	TELCO- V/D BACKBOARDS: 3/ 4" Thick A/D Grade fire-retardant plywood, painted with two coats of fire-retardant grey paint, bottom 18 in AFF, secured to wall structure. Provide 4-Hole					
06	- 1	ground lug with #6 ground extended to main service ground & bonded.					
		V/D WALL BACKBOXES & STUB-UPS: Provide double gang wall boxes with plaster ring					
ET- 07	- 1	with 1" C. stub-up & turn-out into an accessible plenum. Jacks, devices & covers by owner					
UI		or tenant's vendor-installer. Install Pull-Strings, tagged & tied-off at each end.					

or tenant's vendor-installer. Install Pull-Strings, tagged & tied-off at each end.

or tenant's vendor-installer. Install Pull-Strings, tagged & tied-off at each end.

V/D WALL FLOOR BOXES & STUB-UPS: Provide flush-in-floor box(s) with 1" C. under floor, to a wall & stub-up & turn-out into an accessible plenum. Jacks, devices & covers by owner

End Of Electrical Criteria - TELCO V/D/B Raceways





Revisions Description

RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

ELECTRICAL CRITERIA

Modified Date: SDG Job No: 1911 Bid & Permit E-0.1


19121\_E01.dgn 8/15/2019 6:07:34 PM TMG

2019.08.12 Issued Date:

2019.08.12

Proj Place		ige Police Dept 2019 Mod: ie, GA. 30240	9			MA	MDP IN SERVICE DISTRI	RII	TION R	OAPD		19.08.12 Const	
	ed From:				Bu	s Amps			(CU/AL)	CUc	orAl	Volts-LL	240
			ina			'	1-00		eut Bus %		0%		
	nds Type:		ing			n Type	MCB					Volt-LN	120
	Cover:				Main A	Amps C- kAIR	1200 100 kA		nd Bus % 100% anch OCP MCCB			Phase Wires	3
G01		G DISTB BOARD, Sq-D I-Line		G04			O MATCH EXIST TYPES		nch OCP Delta Hi-				4
G03		AIN & BE REUSED		G04 G05			40D-120V Delta Hi-Leg		Utility Pe	•	_	-	
Ckt	Exist.	Load Description	Nt.	Frame		#	Wiring			ted VA Pe		TOTAL	Rev
#		Verify Exist, Update Directory			LT	PH A	PH B	PH C	kVA	#			
				<del>- '-</del>	<u>'</u>	1 0103	( )		7117				#
01	Ex	Verify	01	60	20	I	Verify		0	0	0	0.0	
02	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
03	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
04	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
05	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
06	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
07	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
08	Ex	Verify	01	60	20	1	Verify		0	0	0	0.0	
09	Ex	MA Pnl, 1-Phs (Existing)	01	100	100	2	(1Cu) 3# 1+ 8G- 1.50"C	Р	2,600	0	2,720	5.3	
10	Ex	MB Pnl, 1-Phs	01	100	100	2	(1Cu) 3# 1+ 8G- 1.50"C	Р	3,546	0	3,750	7.3	
11	Ex	LAA Pnl, 1-Phs	01	400	225	2	(1Cu) 3# 4/0+ 4G- 2.50"C	Р	7,125	0	6,305	13.4	
12	Ex	LCA Pnl, 1-Phs	01	400	225	2	(1Cu) 3# 4/0+ 4G- 2.50"C	Р	14,575	0	15,325	29.9	
13	Ex	LBA & LBB Pnl, 1-Phs	01	400	225	2	(1Cu) 3# 4/0+ 4G- 2.50"C	Р	7,200	0	4,600	11.8	
14	Ex	P-03 Pump (Verify> 5.0 HP)	01	60	20	3	(1Cu) 3# 12+ 12G- 0.50"C	М	2,000	2,000	2,000	6.0	
15	Ex	P-01 Pump (Verify> 5.0 HP)	01	60	20	3	(1Cu) 3# 12+ 12G- 0.50"C	М	2,000	2,000	2,000	6.0	
16	Ex	P-03 Pump (Verify> 5.0 HP)	01	60	20	3	(1Cu) 3# 12+ 12G- 0.50"C	М	2,000	2,000	2,000	6.0	
17	Ex	Verify	01	60	20	3	(1Cu) 3# 12+ 12G- 0.50"C		0	0	0	0.0	
18	Ex	Elevator Drive (Verify> 20 HP)	01	100	90	3	(1Cu) 3# 4+ 8G- 1.00"C	М	7,170	7,170	7,170	21.5	
19	Ex	P-04 Pump (Verify> 5.0 HP)	01	60	20	3	(1Cu) 3# 12+ 12G- 0.50"C	М	2,000	2,000	2,000	6.0	
20	Ex	Verify	01			3	Verify		0	0	0	0.0	
21	Ex	Verify	01			3	Verify		0	0	0	0.0	
22	Ex	L1A & L1B Pnl, 3-Phs, 4-Wire	01	400	225	3	(1Cu) 4# 4/0+ 4G- 2.50"C	Р	21,470	14,200	25,440	61.1	
23	NEW	L1M Pnl, 3PH, 3W		400	400	3	(1Cu) 4# 500+ 3G- 4.00"C	Р	47,076	39,168	42,348	128.6	
24	Ex	Chiller (Verify> 292-MCA)	01	400	350	3	(1Cu) 4# 500+ 3G- 4.00"C	С	36,252	36,252	36,252	108.8	
25	NEW	M2D Pnl, 3PH, 3W		400	225	3	(1Cu) 4# 4/0+ 4G- 2.50"C	Р	26,196	25,068	19,392	70.7	
26	Ex	ATS-GEB, GEA, GEC, 3P/4W	1,2	100	100	3	(1Cu) 4# 1+ 8G- 1.50"C	Р	17,870	0	18,200	36.1	
27	New	LSA Pnl, 1Ph, 3W		400	225	2	(1Cu) 3# 4/0+ 4G- 2.50"C	Р	7,715	0	5,855	13.6	
28	New	L1N Pnl, 1Ph, 3W		100	100	2	(1Cu) 3# 1+ 8G- 1.50"C	Р	9,000	0	7,600	16.6	
29	Ex	Verify	01			3	Verify		0	0	0	0.0	
30	Ex	Verify	01			3	Verify		0	0	0	0.0	
		Item Notes (Nt #):							otals & Ca		,		
1-		erify & Document Existing OCP, F					Connected Watts / VA		<del></del>	-	202,957		kVA
2-	Fully Che	eck, Verify & Document The Gene	rator,	ATS &	Distribution	on	Conn. 1-Phs Amps /		1,557	937	<u> </u>	·	
)3-							Factored Load I	kVA:		278	kVA	669	Amp
)4-							Additional Spare Capa	15%	42	kVA		Amp	
)5-							TOTAL FINAL LO	AD:		320	kVA	769	Amp
Зу:	MADDO	K GROUP INC.					End Of Switchboard Schedule	)					19

	<b>ange Po</b> l ange, GA	lice Dept 2019 Mods		ELECTRICAL SYSTEM  E & DISTRIBUTION SCHEDULE			8.12 nst
	Tag ID#	Description / Label	Volts/ Phase/ Wires	Wiring (#Sets,Cu/AI), Ratings, Size, Etc.		Arc- Flash	Item
			Service Bonding	& Grounding (Each Service)			
-	G00	Master Grnd Bus (MGB)	Ground-Bus, Mtd. High On Wall Wth Label	Term. Cables With 2-Hole Cable Lugs & Label Each Cable; Burndy BBB or Erico TGB/ TMGB			-
-	G01	Bond/Grnd- To CW Main	(1) #3/0G- 1"PVC	Clamp With-In 5 Ft Of Pipe Entrance			-
-	G02	Grnd- To Slab Rebar	(1) #4G- 1"PVC	20 Ft 1/2" OD Rebar Or #4 Bare Cu			-
-	G03	Grnd- To Grnd Rod Field	(1) #4G- 1"PVC	(3) 10 Ft SS Grnd Rods Space 10 Ft Apart			-
-	G04	Bond/Grnd- To Bldg Steel	(1) #3/0G- 1"PVC	U.L Bond To Major Steel Member			-
-	G05	Bond/Grnd- To FP Main	(1) #3/0G- 1"PVC	Clamp With-In 5 Ft Of Pipe Entrance (IF PRESENT)			-
-	G06	Bond- To Gas Main Pipe	(1) #4G- 1"PVC	Clamp With-In 5 Ft Of Pipe Entrance (IF PRESENT)			-
-	G07	Bond/Grnd- To Lightning Prot	(1) #3/0G- 1"PVC	Bond To Ltgn Prot (IF PRESENT)			-
-	G10	Grnd Electrode To Each Serv	(1) #3/0G- 1"PVC	Bond To Main Grnd @ Service			-
-	G11	Main Bonding Jumper (G-N)	(1) #3/0G- 1"PVC	Unspliced Inside Each Serv Disc			-
-	G20	Bond- To Telco ISBT	(1) #2G- 1"PVC	Grnd To Each LV Comm Service(s)			-
-	G21	ISBT(Inter-System Bonding Terminal) Ground Bar	ILSOC PET Or Equal	Dual-Rated, 8-Hole Lug With 2-Mtg Holes			-
_	-				-	-	-





Revisions

RENOVATIONS TO

LAGRANGE POLICE DEPT

100 West Haralson St.

LaGrange, GA. 30240

**ELECTRICAL** 

RISER & SCHEDULES

SDG Job No:

1911

E-02

Project Title:

Sheet Title:

Modified Date:

Issued Date:

2019.08.12

Bid & Permit

2019.08.12

SMITH DESIGN GROUP, INC. 206 WEST HARALSON ST

Architect's Stamp

Signature Required

RISER LEGEND

New Work (Equip, Wiring, Etc)- Solid Heavy Line Work
Existing Equipment, Etc. To Remain- Solid Thin Line Work
Exist. Cabling, Conduit, Etc. To Remain - Dashed Thin Line Work

X-X-XDemo Work (See Demo Notes)- Dash-Dot Thin Line Work

RISER GENERAL NOTES

1- This Riser Represent Existing Work To Remain Unless Noted As Modifications Or New Work

2- This Existing Riser Drawing Is Based On Available Inform & Thus May Not Match Field Conditions.

3- This Contractor Is To Thoroughly Field Review & Document The Actual Distribution Arrangement.

4- Document Each Service & Feeder Routing, # Sets, Conductors & Raceway Size.


5- Document Each Distribution Board, Panel, Etc. Make A Complete Schedule For Each.

6- Thoroughly Verify Each Bond & Ground For Proper Size, Good Condition, Label & Document.

7- Ensure Each Electrical Distribution Item Is Properly Labeled With Equipment Name, Etc.

8- Ensure Each Electrical Distribution Item Has Proper Safety & Arc-Flash Labeling.

9- Immediately Notify, In Writing, The Owner, Architect & Engineer Of An Deficiencies Found.



01	#		Of
	-	The contractor shall visit this project facility, prior to quote, and become familiar with the existing layouts, structure and	
		types of construction, the present electrical system and other trades.  Alterations to existing work are of such nature that every facet of the work is impractical to detail and specify, it is	
)2	-	therefore the responsibility of the contractor to carefully examine the present facility and the scope of the proposed new work. No additional compensations will be made due to problems with existing conditions.	
	-		
12		The documents indicate the completed design after demolition, modifications, and additions. The contractor shall	
)3	-	provide all work necessary to achieve this design. Any items noted as existing to remain, be modified, or deleted shall be field verified, and any variances to accommodate field conditions shall be provided by the contractor in his quote.B5	
	-	The contractor shall provide any and all required demolition to accommodate the work. Note that the demolition work is	
)4	-	not necessarily indicated or detailed. The contractor is responsible for the planning, investigation, and demolition work.	
		This shall include all work needed to modify or accommodate any electrical or related system(s) that must be maintained during and/or after construction.	
		This contractor shall provide for any cutting, patching and refinishing of floors, walls ceilings, etc. necessary for the	
		installation of this work. Patching and refinishing shall match the condition and material of the work being cut. Prior to	
05	-	cutting or digging verify and provide for any existing system or utility lines. No cutting, coring or other modifications or	
		alterations shall be made that impact the building structural integrity. No coring, boring or cutting allowed on post-	
		tension structures with out written approval of the structural engineer.  This contractor shall provide for and maintain any owner's waterproofed barrier/roof warranty to roofs, etc. by utilizing	
06	-	the services of the warranty provider for cutting, patching, or other work to waterproofed barriers.	
 07	_	Any dimensions given shall be field verified and coordinated with the existing conditions. Field verify the final exact	
		locations for stub-up, floor boxes, etc. with architect/tenant prior to rough-in.	
		Contractor shall schedule all work with owner/tenant. Any shut-downs or power outages shall be planned a minimum of 72 hours in advance. Shut-downs and outages shall occur after normal business hours. The contractor shall	
80	-	provide for temporary power for any system(s) or equipment that cannot remain off-line for the duration of the shut-	
		down.	
		Where access to the adjacent spaces, floor(s) below or above is required, the contractor shall coordinate with both the	
09	-	landlord and occupant(s) of these spaces for access. The contractor shall protect the existing occupant(s) space & equipment during construction. These spaces shall be left in pre-construction condition. Contractor shall work in these	
		spaces during off-hours to avoid disrupting the normal occupancy use.	
		The contractor shall, prior to ordering, field verify and document the manufacturer, model, make, type, finish,	
10	_	characteristics, etc. of any existing equipment, items, materials, fixtures, etc. that will be added to, modified, replaced,	
10		etc. Any new, additions to, modifications to or replacements involving existing work shall be verified with the	
		manufacturer(s) for compatibility, proper operation and shall not void any warranty.  Where any new work involves demolition, additions to, or modifications to any existing systems, such as fire alarm	
		system, controls systems, etc., the contractor shall involve the services of the system manufacturer's authorized	
11	-	representative to insure the proper operation of the system and the integrity of any system service or maintenance	
		agreement(s).	
		Prior to the start of any work, the contactor shall field document the present loads and capacities of every panel, feeder,	
12	-	distribution equipment and service which will be affected by load addition(s), modification(s) or change(s), by taking actual Amperage reading with a "TrueRMS Ampmeter. Use schedules to record the data, including date, time,	
		personnel name(s) & weather & temperature. Distribute to Owner, Architect & Engineer as record data.	
		Prior to the modifications or demolition of any existing cricuts, the contractor shall trace the circuits from the point of	
40		origin (i.epanel, etc.) and determine which devices, items, etc. are powered by that circuit & shall label them with a	
13	-	circuit ID (i.ePanel Name & Ckt #). Circuits that are to remain "As-Is" shall be clearly indicated in the panel box & circuit directory & on the plans. Any circuits to "Critical Items" (i.e security, Fire Alarm, etc.) shall be espically noted &	
		protected & noted on the plans.	
14	_	This contractor, once the existing wiring is exposed but prior to any removal, shall create an "Pre-Demo Field	
		Drawing(s)" showing the existing layouts, wireing, sizes, etc Provide copies to the Owner, Archt & Engineer.	
15	-	This contractor shall, once the existing wiring is exposed but prior to any removal, label-mark the existing wiring & related. Where wiring of will be removed, mark same close to each cut location on the remaining work.	
		Where work is to be removed, the electrical conductors and devices shall be completely removed from device-to-	
16	-	device. The conduits & boxes may remain abandoned where they do not interfere with other existing or new work.	
		Modify panel directories and drawings to reflect any modified conditions.	
17	-	Any removed materials shall become the property of the contractor and shall be removed from the site. Proper	
	-	disposal is the responsibility of the contractor.  Where circuits are broken, or modified, the continuity of down-stream wiring shall be maintained. Provide any new	
18	-	work necessary to maintain continuity.	
19	_	Existing conduits and raceways may be reused if they are in good condition and adequate size. Clean and swab-out	
	_	raceway prior to installing new wiring.	
20	-	Any existing circuits, devices, and fixtures being reused shall be checked by the contractor for good condition and	
	-	proper working order.  Any over-current-protective devices (fuses/breakers) that are replaced or added to existing equipment shall meet or	
21	-	exceed the ratings and interrupting ratings for the existing equipment and be listed as compatible for that equipment by	
		the equipment manufacturer.	
		Generally, the circuiting shown shall go to the panel and circuit as indicated. However, where existing circuits are	
22	-	being reused and conflicts with new circuits numbers occur, the new circuits may be shifted to other circuit numbers in that panel. Circuit balancing, shared neutrals, and phasing shall be adjusted as necessary to maintain circuit integrity.	
22		Label all work with circuit numbers at junction boxes, pull boxes, etc. Update each panel directory, label panels,	
23	-	disconnects and all equipment, both new & existing. Maintain an accurate set of As-Built drawings and equipment schedules.	
21		Any existing lighting fixtures being reused shall be thoroughly cleaned and relamped with new lamps to provide	
24	-	uniform lamp types between new and existing fixtures. Lamps shall be of the energy saving type.	
		After the completion of the circuit work, the contactor shall field document the final loads of every panel, feeder,	
25	-	distribution equipment and service which will be affected by load addition(s), modification(s) or change(s), by taking actual Amperage reading with a "TrueRMS Ammeter. Use schedules to record the data, including date, time,	
		personnel name(s) & weather & temperature. Distribute to Owner, Architect & Engineer as record data	
		Alternate Power Sources (APS) (i.e Generators, UPS, etc.): Where APS are present, their output readings	
	1	(Voltages, Phase, Amperage, kW, kVA, etc) shall be recorded (with owners assistance), documented & distributed to	
26	-		
26	-	Owner, Architect & Engineer as record data. This shall be done under operational load, prior to the start of the project work and once work is fully completed.	

End Of Electrical Criteria - Existing Condittions & Demolition

Project:	LaGrange Poli	ce Dept 2019	M	ods			GI	EB		Schd				LaGrai	nge, GA. 30240	City,	St
Gen Nt 1	Existing, Remaining &	Reused - Verify Exis	t Lo	ads Remain	ing		Volt-	- LL	240		End	closure-Mtg:	NEN		Wall Surf Mtd.	•	
Gen Nt 2	Provide New Matching	Type Devices As Ma	у Ве	Required.			Volt-	LN	120		Со	ver & Door:	Exis	st			
Gen Nt 3	Warning: 240D-120V, 3	P-4W, Delta Hi-Leg	(B-Pl	hs-Orange)			Phs. 3		W.	4	(	OCP Types:	Maii	n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	,
Gen Nt 4	Warning: Gen Set Sou	rce> 208Y120V, 3Ph	s, 4W	/ire				•	os <b>225</b> , <b>100A-F</b>		All Busing: C∪				100% N & G Busing		
	: Verify Existing Ckts, Upda	te Directory, Clean &	Relal				Main C							eled Per NEC & OSH			
19-121				Spare % =			-AIC S	SCA				19.08.12	_	1	Const		
Rv Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	Rv
	Ltg- 300 LvI	#10+ 10G	L	425	20	1	1	Α	2	20	1	500	E	#12+ 12G	ERcpt- 200 Lv FACP		
	Hi-Leg	No 120-V Use		0	Sp	1	3	<u>B</u>	4	Sp	1	0		No 120-V Use	Hi-Leg		
	Ltg- 200 LvI	#12+ 12G	L	450	20	1	5	С	6	100	-	4,200	Р	See Riser	PnI GEA		
	Ltg- 200 LvI	#12+ 12G	L	420	20	1	7	Α	8	-	2	4,200	Р		SubFeed		
	Hi-Leg	No 120-V Use		0	Sp	1	9	<u>B</u>	10	Sp	1	0		No 120-V Use	Hi-Leg		
	Ltg- 200 LvI	#12+ 12G	L	330	20	1	11	С	12	100	-	6,700	Р	See Riser	Pnl GEC		
	Ltg- 100 LvI	#10+ 10G	L	345	20	1	13	Α	14	-	2	6,300	Р		SubFeed		
	Hi-Leg	No 120-V Use		0	Sp	1	15	В	16	Sp	1	0		No 120-V Use	Hi-Leg		
	Ltg- 100 LvI	#10+ 10G	L	420	20	1	17	С	18	20	1	500	Ε	#12+ 12G	ERcpt- 200 Lv Access Pnl		
	Ltg- 100 LvI	#10+ 10G	L	480	20	1	19	Α	20	20	1	500	Ε	#12+ 12G	ERcpt- 200 Lv Security		
	Hi-Leg	No 120-V Use		0	Sp	1	21	<u>B</u>	22	Sp	1	0		No 120-V Use	Hi-Leg		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	600	20	1	23	С	24	20	1	200	R	#12+ 12G	Rcpt- 200 Lv Off		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	600	20	1	25	Α	26	20	1	0			> Spare <		
	Hi-Leg	No 120-V Use		0	Sp	1	27	<u>B</u>	28	Sp	1	0		No 120-V Use	Hi-Leg		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	600	20	1	29	С	30	20	1	1,300	Ε	#10+ 10G	Rcpt- 200 Lv Cubes		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	600	20	1	31	Α	32	20	1	1,300	Ε	#10+ 10G	Rcpt- 200 Lv Cubes		
	Hi-Leg	No 120-V Use		0	Sp	1	33	<u>B</u>	34	Sp	1	0		No 120-V Use	Hi-Leg		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	1,300	20	1	35	С	36	20	1	1,200	E	#10+ 10G	Rcpt- 300 Lv		
	Rcpt- 200 Lv Cubes	#10+ 10G	Е	1,300	20	1	37	Α	38	20	1	900	Ε	#10+ 10G	Rcpt- 300 Lv		
	Hi-Leg	No 120-V Use		0	Sp	1	39	<u>B</u>	40	Sp	1	0		No 120-V Use	Hi-Leg		
	Rcpt- 300 Lv	#10+ 10G	Е	200	20	1	41	С	42	20	1	200	Е	#10+ 10G	Rcpt- 300 Lv		
Nt# 01-	HACR Listed & Labeled N	MCCB			Phs-	Α	49.5	5 %	129	Α		17,870	VA	18.3	KVA Facotred End Use	44	A
Nt# 02-	Not Used				Phs-	<u>B</u>	0.0	) %	0	Α		0	VA	19.1	KVA Pass Thru Load	46	6 A
Nt# 03-	Not Used				Phs-	С	50.5	5 %	131	Α		18,200	VA	0.0	KVA Spare	0	) A
Nt# 04-	Not Used				S	umn	nary =		87	Α		36,070	VA		KVA Total	90	Α


Projec	t:	LaGrange Police De	pt 2019 Mods					Gl	EA		Schd			l	_aGrange, GA. 30240 City,St		
Gen N	t 1:							Volt-	- LL	240		Er	nclosure-Mtg: NEN	1A-1	Wall Surf Mtd.		
Gen N	t 2:							Volt-	LN	120		С	over & Door: Doo	r-In-Door, With Locks	3		
Gen N	t 3:	Warning: 240D-120V, 3F	-4W, Delta Hi-Leg	(B-P	hs-Orange)			Phs.	1	W.	3		OCP Types: Mair	n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen N	t 4:						Ε	Buss Ai	nps	100			All Busing: CU		100% N & G Busing		
Gen N	t 5:	New Panel, Generator Po	ower System, 100 l	_vl				Main C	CP	MLO			Arc-Flash: Lab	eled Per NEC & OSH	1A		
19-12	21	MADDOX GROUP INC.			Spare % =	15%	KA	-AIC S	SCA	45			<b>19.08.12</b> Date	e:	Const	Const	
Rv I	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA ID	Wiring	Description	Nt Rv	
		Rcpt- 100 Lv Cubes	#10+ 10G	R	800	20	1	1	Α	2	20	1	200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		Rcpt- 100 Lv Cubes	#10+ 10G	E	800	20	1	3	С	4	20	1	200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		Rcpt- 100 Lv Cubes	#10+ 10G	R	800	20	1	5	Α	6	20	1	1,200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		Rcpt- 100 Lv Cubes	#10+ 10G	E	800	20	1	7	С	8	20	1	1,200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		> Spare <			0	20	1	9	Α	10	20	1	1,200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		> Spare <			0	20	1	11	С	12	20	1	1,200 R	#12+ 12G	Rcpt- 100 Lv Offs		
		> Spare <			0	20	1	13	Α	14	20	1	0		> Spare <		
		> Spare <			0	20	1	15	С	16	20	1	0		> Spare <		
		> Spare <			0	20	1	17	Α	18	20	1	0		> Spare <		
		> Spare <			0	20	1	19	С	20	20	1	0		> Spare <		
		> Spare <			0	20	1	21	Α	22	20	1	0		> Spare <		
		> Spare <			0	20	1	23	С	24	20	1	0		> Spare <		
		< Space Only >			0	Sp	1	25	Α	26	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	27	С	28	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	29	Α	30	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	31	С	32	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	33	Α	34	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	35	С	36	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	37	Α	38	Sp	1	0		< Space Only >		
		< Space Only >			0	Sp	1	39	С	40	Sp	1	0		< Space Only >		
Nt# 0	1-	HACR Listed & Labeled M	CCB			Phs	Α	50.0	) %	35	Α		4,200 VA	8.8	KVA Facotred End Use	37 A	
Nt# 02	2-	Not Used				Phs	С	50.0	) %	35	Α		4,200 VA	0.0	KVA Pass Thru Load	0 A	
Nt# 03	3-	Not Used				S	umn	nary =		35	Α		8,400 VA	1.3	3 KVA Spare	6 A	
Nt# 04	4-	Not Used												10.1	KVA Total	42 A	

Project:	LaGrange Police De	pt 2019 Mods					GI	GEC				LaGrange, GA. 30240								
Gen Nt 1.							Volt-	· LL	240		Enc	closure-Mtg:	NEM	A-1	Wall Surf Mtd.					
Gen Nt 2.							Volt-	LN	120		Co	ver & Door:	Door	-In-Door, With Locks	3					
Gen Nt 3.	Warning: 240D-120V, 3F	P-4W, Delta Hi-Leg	(B-Pl	ns-Orange)		Phs. 1 W. 3						OCP Types:	Main	- MCCB-60C/75C	Branch- MCCB, 60C/75C Lugs					
Gen Nt 4.						Ε	Buss Ar	nps	100			All Busing:	CU o	r AL	100% N & G Busing					
Gen Nt 5.	New Panel, Generator Po	ower System, 300	Lvl				Main C	CP	MLO			Arc-Flash:	Labe	led Per NEC & OSH						
19-121	MADDOX GROUP INC.		Spare % =	15%	KA	-AIC S	CA	45			19.08.12	Date:		Const	Cons	st				
Rv Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	Rv			
	Rcpt- 300 Lv Cubes	#10+ 10G	R	800	20	1	1	Α	2	20	1	800	Е	#10+ 10G	Rcpt- 300 Lv Cubes					
	Rcpt- 300 Lv Cubes	#10+ 10G	E	800	20	1	3	С	4	20	1	800	R	#10+ 10G	Rcpt- 300 Lv Cubes					
	Rcpt- 300 Lv Cubes	#10+ 10G	R	800	20	1	5	Α	6	20	1	800	Е	#10+ 10G	Rcpt- 300 Lv Cubes					
	Rcpt- 300 Lv Cubes	#10+ 10G	E	800	20	1	7	С	8	20	1	800	R	#10+ 10G	Rcpt- 300 Lv Cubes					
	Rcpt- 300 Lv Ph Rm	#12+ 12G	R	500	20	1	9	Α	10	20	1	600	E	#10+ 10G	Rcpt- 300 Lv War Rm					
	Rcpt- 300 Lv Ph RM	#12+ 12G	R	500	20	1	11	С	12	20	1	800	R	#12+ 12G	Rcpt- 300 Lv Admin					
	Rcpt- 300 Lv Video Rm	#12+ 12G	E	1,800	20	1	13	Α	14	20	1	600	R	#12+ 12G	Rcpt- 300 Lv Admin					
	Rcpt- 300 Lv Video Rm	#12+ 12G	E	1,800	20	1	15	С	16	20	1	0			> Spare <					
	> Spare <			0	20	1	17	Α	18	20	1	0			> Spare <					
	> Spare <			0	20	1	19	С	20	20	1	0			> Spare <					
	> Spare <			0	20	1	21	Α	22	20	1	0			> Spare <					
	> Spare <			0	20	1	23	С	24	20	1	0			> Spare <					
	< Space Only >			0	Sp	1	25	Α	26	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	27	С	28	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	29	Α	30	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	31	С	32	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	33	Α	34	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	35	С	36	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	37	Α	38	Sp	1	0			< Space Only >					
	< Space Only >			0	Sp	1	39	С	40	Sp	1	0			< Space Only >					
Vt# 01-	HACR Listed & Labeled M	CCB			Phs	Α	51.5	%	56	A		6,700	VA	14.9	KVA Facotred End Use	62	Α			
Vt# 02-	Not Used				Phs	С	48.5	%	53	Α		6,300	VA	0.0	KVA Pass Thru Load	0	Α			
Vt# 03-	Not Used				S	umm	nary =		54	Α		13,000	VA	2.2	KVA Spare	9	Α			
V# 04-	Not Used													17.1	KVA Total	71	Α			


Project:	LaGrange Police	ce Dept 2019	M	ods			M2	2 <b>D</b>		Schd					nge, GA. 30240	City,	3t
Gen Nt 1:							Volt-	· LL	240		En	closure-Mtg:	NEM	1A 1	Wall Surf Mtd.		
Gen Nt 2:							Volt-	LN	120		Co	over & Door:	Exis	t			
Gen Nt 3:	Warning: 240D-120V, 3I	P-4W, Delta Hi-Leg (	B-P	hs-Orange)			Phs.	3	W.	3		OCP Types:	Mair	- MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen Nt 4:							uss Ar	•				All Busing:			100% N & G Busing		
	New Panel, 3-Phs, 3-Wi	re					Лаin О							eled Per NEC & OSH			
	MADDOX GROUP INC.			Spare % =		<del></del>	-AIC S	CA	65			19.08.12	Date		Const		
Rv Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	R
	HP-08, 3.0T	2# 10+ 10G	С	2,148	35	-	1	Α	2	50	-	5,820	G	2# 8+ 10G	FCU-08, 8.0 KwHt		
	240V, 1Phs, 22.1 MCA	DS-30A,2P,G,N3R	С	2,148	-	2	3	<u>B</u>	4	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
	HP-09, 3.5T	2# 10+ 10G	С	2,688	40	-	5	С	6	50	-	5,820	G	2# 8+ 10G	FCU-09, 8.0 KwHt		
	240V, 1Phs, 27.6 MCA	DS-60A,2P,G,N3R	С	2,688	-	2	7	Α	8	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
	HP-10, 5.0T	2# 8+ 10G	С	3,312	50	-	9	<u>B</u>	10	60	-	5,820	G	2# 6+ 10G	FCU-10, 10 kW Ht		
	240V, 1Phs, 34.2 MCA	DS-60A,2P,G,N3R	С	3,312	-	2	11	С	12	-	2	5,820	G	DS: 60A,2P,N1	240V, 1Phs, 58.5 MCA		
	HP-11, 3.0T	2# 10+ 10G	С	2,148	35	-	13	Α	14	50	-	5,820	G	2# 8+ 10G	FCU-11, 8.0 KwHt		
	240V, 1Phs, 22.1 MCA	DS-30A,2P,G,N3R	С	2,148	-	2	15	В	16	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
	HP-12, 1.0T DL	2# 10+ 10G	С	1,752	15	-	17	С	18	Sp	1	0			< Space Only >		
	240V, 1Phs, 12.0 MCA	DS-30A,2P,G,N3R	С	1,752	-	2	19	Α	20	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	21	<u>B</u>	22	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	23	С	24	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	25	Α	26	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	27	<u>B</u>	28	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	29	С	30	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	31	Α	32	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	33	<u>B</u>	34	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	35	С	36	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	37	Α	38	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	39	<u>B</u>	40	Sp	1	0			< Space Only >		
	< Space Only >			0	Sp	1	41	С	42	Sp	1	0			< Space Only >		
Nt# 01-	HACR Listed & Labeled N	ICCB			Phs-	Α	37.1	%	189	A		26,196	VA	73.2	KVA Facotred End Use	176	Α
Nt# 02-	Not Used				Phs-	<u>B</u>	35.5	%	181	Α		25,068	VA	0.0	KVA Pass Thru Load	0	Α
Nt# 03-	Not Used				Phs-	С	27.4	%	140	Α		19,392	VA	0.0	KVA Spare	0	Α
Nt# 04-	Not Used				S	umm	ary =		170	Α		70,656	VΔ		KVA Total	176	Α

Proje	ect:	LaGrange Police	ce Dept 2019	M	ods			Ľ	M		Schd				LaGrai	nge, GA. 30240	City,	3t
Gen	Nt 1:							Volt	- LL	240		En	closure-Mtg:	NEM	IA 1	Wall Surf Mtd.		
Gen	Nt 2:							Volt-	LN	120		Co	over & Door:	Exist				
Gen	Nt 3:	Warning: 240D-120V, 3F	P-4W, Delta Hi-Leg (	B-P	hs-Orange)			Phs.		W.	3		OCP Types:	Main	- MCCB-60C/75C		Lugs	
								Buss Ai	,				All Busing:			100% N & G Busing		
		New Panel, 3-Phs, 3-Wi	re					Main C		MLO					eled Per NEC & OSH			
		MADDOX GROUP INC.			Spare % =		<u> </u>	-AIC S					19.08.12			Const		
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р		ID	Wiring	Description	Nt	R
		HP-01, 2.5T	2# 12+ 12G	С	1,752	30	-	1	Α	2	50	_	5,820	G	2# 8+ 10G	FCU-01, 8.0 KwHt		
		240V, 1Phs, 18.1 MCA	DS-30A,2P,G,N3R	С	1,752	-	2	3	<u>B</u>	4	-	2	5,820		DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
		HP-02, 3.0T	2# 10+ 10G	С	2,148	35	-	5	С	6	50	-	5,820	G	2# 8+ 10G	FCU-02, 8.0 KwHt		
		240V, 1Phs, 22.1 MCA	DS-30A,2P,G,N3R	С	2,148	-	2	7	Α	8	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
		HP-03, 1.5T	2# 12+ 12G	С	1,140	20	-	9	<u>B</u>	10	30	-	5,820	G	2# 10+ 10G	FCU-03, 5.0 KwHt		
		240V, 1Phs, 11.8 MCA	DS-30A,2P,G,N3R	С	1,140	-	2	11	С	12	-	2	5,820	G	DS-30A,2P,G,N1	240V, 1Phs, 28.4 MCA		
		HP-04, 2.0T	2# 12+ 12G	С	1,596	25	-	13	Α	14	30	-	5,820	G	2# 10+ 10G	FCU-04, 5.0 KwHt		
		240V, 1Phs, 16.5 MCA	DS-30A,2P,G,N3R	С	1,596	-	2	15	В	16	-	2	5,820	G	DS-30A,2P,G,N1	240V, 1Phs, 28.4 MCA		Г
		HP-05, 4.0T	2# 10+ 10G	С	2,760	40	-	17	С	18	50	-	5,820	G	2# 8+ 10G	FCU-05, 8.0 KwHt		
		240V, 1Phs, 28.5 MCA	DS-60A,2P,G,N3R	С	2,760	-	2	19	Α	20	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
		HP-06, 3.5T	2# 10+ 10G	С	2,688	40	-	21	<u>B</u>	22	50	-	5,820	G	2# 8+ 10G	FCU-06, 8.0 KwHt		
		240V, 1Phs, 27.6 MCA	DS-60A,2P,G,N3R	С	2,688	-	2	23	С	24	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
		HP-07, 1.5T	2# 12+ 12G	С	1,140	20	-	25	Α	26	30	-	5,820	G	2# 10+ 10G	FCU-07, 5.0 KwHt		
		240V, 1Phs, 11.8 MCA	DS-30A,2P,G,N3R	С	1,140	-	2	27	<u>B</u>	28	-	2	5,820	G	DS-30A,2P,G,N1	240V, 1Phs, 28.4 MCA		
		HP-E01, 4.0T	2# 10+ 10G	С	2,760	40	-	29	С	30	50	-	5,820	G	2# 8+ 10G	FCU-E01, 8.0 KwHt		
		240V, 1Phs, 28.5 MCA	DS-60A,2P,G,N3R	С	2,760	-	2	31	Α	32	-	2	5,820	G	DS-60A,2P,G,N1	240V, 1Phs, 48.5 MCA		
		HP-13, 1.0T DL	2# 10+ 10G	С	1,752	15	-	33	<u>B</u>	34	Sp	1	0			< Space Only >		
		240V, 1Phs, 12.0 MCA	DS-30A,2P,G,N3R	С	1,752	-	2	35	С	36	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	37	Α	38	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	39	<u>B</u>	40	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	41	С	42	Sp	1	0			< Space Only >		
Vt#	01-	HACR Listed & Labeled M	ICCB			Phs-	Α	36.6	6 %	340	A		47,076	VA	131.1	KVA Facotred End Use	315	Α
Vt# (	02-	Not Used				Phs-	<u>B</u>	30.5	5 %	283	Α		39,168	VA	0.0	KVA Pass Thru Load	0	Α
Vt#	03-	Not Used				Phs-	С	32.9	%	306	Α		42,348	VA	0.0	KVA Spare	0	Α
Nt#(	04-	Not Used				S	umm	ary =		309	Α		128,592	VΔ	131 1	KVA Total	315	Α


Proje	ect:	LaGrange Police Dep	ot 2019 Mods					Ľ	1 N		Schd					_aGrange, GA. 30240	City,	St
Gen	Nt 1:							Volt	- LL	240		En	closure-Mtg:	NEM	1A-1	Wall Surf Mtd.		
Gen	Nt 2:							Volt-	- LN	120		Co	over & Door:	Doo	r-In-Door, With Locks	3		
Gen	Nt 3:	Warning: 240D-120V, 3P	-4W, Delta Hi-Leg	(B-P	hs-Orange)			Phs.	. 1	W.	3		OCP Types:	Mair	- MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	3
Gen	Nt 4:				<u> </u>		E	Buss Ai	mps	100			All Busing:			100% N & G Busing		
Gen	Nt 5:	New Panel, 100 Lvl						Main C	ĊР	MLO			Arc-Flash:	Labe	eled Per NEC & OSH	IA		
19-	121	MADDOX GROUP INC.			Spare % =	15%	K/	A-AIC S	SCA	45			19.08.12	Date	);	Const	Con	st
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	R
		Mtr- Bay Door	#10+10G	R	1,000	20	1	1	Α	2	20	1	1,600	R	#12+ 12G	Rcpt- Evidence Bays		$\top$
		Mtr- Bay Door	#10+10G	R	1,000	20	1	3	С	4	20	1	0			> Spare <		
		Mtr- Bay Door	#10+10G	R	1,000	20	1	5	Α	6	20	1	900	R	#10+10G	Rcpt- Work Out Eq		
		Rcpt- Work Out	#10+10G	R	1,400	20	1	7	С	8	20	1	900	R	#10+10G	Rcpt- Work Out Eq		
		Rcpt- Work Out RR	#10+10G	R	200	20	1	9	Α	10	20	1	900	R	#10+10G	Rcpt- Work Out Eq		
		Rcpt- Off & Shop	#10+10G	R	1,400	20	1	11	С	12	20	1	900	R	#10+10G	Rcpt- Work Out Eq		
		Rcpt- Off & Shop	#10+10G	R	1,400	20	1	13	Α	14	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		Rcpt- Off & Evidence	#10+10G	R	1,400	20	1	15	С	16	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		Rcpt- Off & Evidence	#10+10G	R	1,400	20	1	17	Α	18	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		> Spare <			0	20	1	19	С	20	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		> Spare <			0	20	1	21	Α	22	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		> Spare <			0	20	1	23	С	24	20	1	200	R	#10+10G	Rcpt- Ded Shop Tool		
		< Space Only >			0	Sp	1	25	Α	26	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	27	С	28	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	29	Α	30	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	31	С	32	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	33	Α	34	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	35	С	36	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	37	Α	38	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	39	С	40	Sp	1	0			< Space Only >		
Vt#	01-	HACR Listed & Labeled MO	CCB			Phs	Α	54.2	2 %	75	A		9,000	VA	13.3	KVA Facotred End Use	55	5 A
Nt#	02-	NotUsed				Phs	С	45.8	3 %	63	Α		7,600	VA	0.0	KVA Pass Thru Load		) A
Nt#	03-	NotUsed				S	umn	nary =		69	Α		16,600	VA	2.0	KVA Spare	3	3 A
Nt#	04-	Not Used						-							15.3	KVA Total	64	4 A



SMITH DESIGN GROUP, INC.
206 WEST HARALSON ST
LAGRANGE, GEORGIA 30240



THE MADDOX GROUP, INC. DESIGN & ENGINEERING CONSULTANTS



RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

Sheet Title

ELECTRICAL SCHEDULES

lodified Date:	SDG Job No:
2019.08.12	1911
sued Date:	
Bid & Permit	F-03
2019.08.12	L-00

19.08	2 12	LOW-VOLTAGE RELAY PANEL SCHED.  LaGrange Police Dept 2019 Mods	Con
ID#	Rv	LOW-VOLTAGE RELAY SWITCHING (LVRS) CX-HARDWIRED SYSTEM	Che
, ,	#	. ,	Off
7.01	-	GENERAL - Providing complete Low-Voltage Switching System, consisting of LV Switching Panels with LV switching relays, completely pre-assembled & pre-wired with relays, power supply, controls and all components for a complete and properly operating system. Provide matching Hard-Wired LV switching devices, and controls.	
7.02	-	MANUFACTURER - The design is based on the products of Hubbell CX Lighting & Building Automation and shall be the manufacturer for the LV Relay Switching System.	
7.03	-	ALTERNATE MANUFACTURERS - Products of other manufacturers, providing the equivalent level of product quality, operation, functionality and features, shall be submitted as add / deduct to this manufacture for owner's considerations, complete with full product documentation and literature indicating complete compliance and performance.	
7.04	-	CODES & CERTIFICATIONS - All products shall be UL Listed, CSA approved, and comply with EEMAC / NEMA standards & NEC.	
7.05		WARRANTY - The system manufacturer shall warrant the complete system with a Full-Service-Warranty on all parts and labor for a minimum of 10 Years.	
7.06		SUBMITTALS - Prepare & submit project specific product documentation, including but not limited to, manufacturer's qualifications & personnel contact information, component product data, complete relay & component schedules and matching wiring diagrams for field use in the proper installation of the system.	
7.07		RELAY PANELS - Provide pre-assembled 16 or 24 Pole relay panels, pre-finished steel with hinged & locking cover / door for surface of flush mounting. The interior shall divider for LV siring per code, control power transformer sized for 125% of the load, LV devices and controls as required.	
		RELAYS - Provide relays as scheduled and required for proper operation. Relays shall be Heavy-Duty, Full Load Rated, UL-508 Labeled, HID, breaker snap-in style, mechanically latching type with a manual ON/OFF switch that	
7.08		display the switches' ON/OFF state. 1-Pole, 20 Amp relays rated at 120 & 277 VAC. 1-Pole, 30 Amp relays rated at 120, 277 & 347 VAC. 2-Pole 20-Amp relays shall be rate for up to 480 VAC. UL 508 short-circuit rating of 14,000 Amps. Rated for switching of incandescent, fluorescent, electronic ballast & HID loads. 3,000 Amps inrush capability. Relays shall have a 5 year warranty.	
7.09		CONTROLLER- Solid-state, programmable relay controller to receive all control inputs and control all ouptus to relays. Controller shall include Astronomical Schedule 365-Day Time Clock-Scheduler, Automatic Daylight Saving Time & Leap-Year Compenstion. Controller to have built-in keypad for programming & non-volatile memory.	
7.10		LCD USER INTERFACE- Provide front-mounted LCD display with touch-button interface device with instructions.	
7.11		CONTROL WIRING- Hard-Wired LV Two-Wire Per Switch Or Input Control Device	
7.12		SWITCHING STATIONS- Provide switching devices where shown and / or required. Devices shall be matching two-wire type. Each Switch Station shall provide for up to 6 Pilot-Light buttons. Devices located in wet locations shall be Wet-Location listed & labeled. Devices shall be of same manufacturer as the LV system manufacturer U.N.O.	
7.13		WALL SWTCH / LOCAL USE VANDAL RESISTIANT - Provide where shown or required heavy-duty, vandal resistant wet-location labeled switch & cover plate with tamper resistant screws. Engrave cover plate with switch function (i.e. lights). Douglas WR-8321 Series	
7.14		WALL SWTCH / KEY OPERATED - Provide where shown or required heavy-duty, key-operated switch & cover plate. Engrave cover plate with switch function (i.e. lights).	
7.15		WALL MASTER / GROUP SWTCHES - Provide where shown or required heavy-duty, multi-gang group mounted rocker type switches, complete with all switches, mounting hardware & cover plates. Label switches with their function (i.e. lights).	
7.16		INSTALLATION PER MANUFACTURER, NEC, NEIS - The LVRS shall be installed in accordance with the manufacturer's written documentation, NEC & NEIS. The manufacturer's factory authorized & trained agent shall provide installation guidance and assistance and system start-up.	
7.17		INSTALLATION CABLING - All wiring shall be CU in conduit or Type MC cable unless otherwise noted. The wire size shall be per the manufacturer. Wire size shall be increased to the next larger standard size for runs over 100 Feet.	_
7.18		INSTALLED MANUFACTURERS CHEK-OUT & CERTIFICATION: Prior to energizing the system, the Manufacturers Authorized Agent, shall perform and On-Site Check-Out of the completed system and provide written certification that the components and installation are acceptable, that the system is fully programmed / scheduled and fully functional & properly operating.	
7.19		INSTALLED DOCUMENTATION - Provide three sets of As-Installed Field Record document of the completed system, showing all equipment, components & wiring. Include complete manufacturer & product documentation and warranty forms.	
7.20		INSTALLATION DEMONSTARTION & TRANING - The complete system(s) shall be fully demonstrated to the Owners Representative(s) to show full compliance and proper operation. Train the Owner's Personnel in the proper operation, programming and maintenance of the system.	
			+

End Of Low Voltage Relay Switching Systems

						L	<u>.ow</u>	-VOL	TAGE	RELA	Y PAI	NEL (	LVRP) SCHEDULE										
Proj	LaGrange Police Dept 2019 I	lods																			_		-PnI
Place	- ·																				19	9.08.12	
For	Smith Design Group, Inc																					Const	
Basis	Hubbell Relay Systems - LX Se	ires							R							6					NEM	A-1R	-Enc
Rv#	Circuit Load Description	Rly#	Rly Type	Rly Amps	Rly Pole	PNL	CKT #	Master Ctrl- <b>LM</b> x	Group Ctrl- <b>LG</b> x	Local Ctrl- LLx	Specific Item Nt #	Rv#	Circuit Load Description	Rly#	Rly Type	Rly Amps	Rly Pole	PNL	CKT #	Maste r Ctrl- <b>LM</b> x	Group Ctrl- <b>LG</b> x	Local Ctrl- LLx	Specific Item
	Ltg- 300 Lvl Halls	01	-	20	1	LSA	01	-	-	LL	-		Ltg- 300 Extr	13	-	20	1	LSA	02	-	LA	-	-
	Ltg- 300 Lvl Halls	02	-	20	1	LSA	03	-	-	LL	-		Ltg- 200 Extr	14	-	20	1	LSA	04	-	LA	-	-
	Ltg- 200 Lvl Open Off	03	-	20	1	LSA	05	-	-	LL	-		Ltg- 100 Extr	15	-	20	1	LSA	06	-	LA	-	-
	Ltg- 200 Lvl Halls	04	-	20	1	LSA	07	-	-	LL	-		Ltg- 100 Extr	16	-	20	1	LSA	08	-	LA	-	-
	Ltg- 200 Lvl Lobby	05	-	20	1	LSA	09	-	-	LL	-		Ltg- Pk Deck	17	-	20	1	LSA	10	-	LA	-	T -
	Ltg- 100 Lvl Halls	06	-	20	1	LSA	11	-	-	LL	-		Ltg- Pk Deck	18	-	20	1	LSA	12	-	LA	-	-
	Ltg- 100 Lvl Halls	07	-	20	1	LSA	13	-	-	LL	-		> Spare <	19	-	20	1	LSA	14	-	-	-	-
	Ltg- 100 Lvl Halls	08	-	20	1	LSA	15	-	-	LL	-		> Spare <	20	-	20	1	LSA	16	-	-	-	-
	Ltg- 100 LvI	09	-	20	1	LSA	17	-	-	LL	- 1		Ltg- 100 LvI	21	-	20	1	LSA	18	-	-	LL	-
	> Spare <	10	-	20	1	LSA	19	-	-	-	- 1		Ltg- 100LvI	22	-	20	1	LSA	20	-	-	LL	-
	> Spare <	11	-	20	1	LSA	21	-	-	-	- 1		> Spare <	23	-	20	1	LSA	22	-	-	-	-
	< Space >	12	-	20	1	LSA	23	-	-	-	- 1		< Space >	24	-	Sp	1	LSA	24	-	-	-	-
	< Space >	25	-	20	1	LSA	25	-	-	-	-		< Space >	26	-	Sp	1	LSA	26	-	-	-	-
	< Space >	27	-	20	1	LSA	27	-	-	-	-		< Space >	28	-	Sp	1	LSA	28	-	-	-	-
	< Space >	29	-	20	1	LSA	29	-	-	-	-		< Space >	30	-	Sp	1	LSA	30	-	-	-	-
		Contro	l Fund	ction	& D	evice T	ype						Co	ntrol F	unctio	1 & D	)evic	e Type					
Rv#	Control Function Description	ID	Mtg			Туре		Control [	Device No	tes		Rv#	Control Function Description	ID	Mtg			Туре	Со	ntrol De	evice No	otes	
	Master All On-Off	LMx	Wall	LV	Push	-Button							Local On/ Off	LLx	Wall	LV	Push-	-Button					
	Group On-Off	LGx	Wall	LV	Push	-Button							Occupancy On-Off	LOx	Wall	O	cc. Se	ensor					
	Astro- Time Based Switching	LAx	Pnl	A	∖stro-	Schd							Sun Day-Light Control	LSx	Clg	Da	y LtS	Sensor					
	0-60 Min. Manual Over-Ride	LTx	Wall	LV	Push	-Button							Dimming Control	LDx	Wall	Dim	mer- I	Manual					
		Devic	e Type	And		revatio								neral N				To All					
	Astronomic Schedule Timer					Dimme		<u>.</u>				G01	Provide A Complete & Properly										
	t Day Light Sensor							eld Relay				G02	The Complete System(s) With Al						Of Sir	ngle Ma	nufactu	rer Res	3ponsi
	Low-Voltage Button Station				L	Latchir	ig Rela	ау				G03	Provide Complete Product & Wir	•									
LVD	Low-Voltage Dimmer Station				-							G04	Provide All Enviromental Return				•	Manufa	cturer				
												G05	Program System & Insturct User	On Pro	per Op	eratio	n.						
												G06											
Ву:	MADDOX GROUP INC.									End Of S	Schedule	- See Co	ontrol Device Schedule Also										19-12

Proje	ect:	LaGrange Police Dep	ot 2019 Mods					LS	SA		Schd				L	aGrange, GA. 30240	City,	St.
Gen								Volt-	LL	240		En	closure-Mtg:	NEN	1A-1	Wall Surf Mtd.		
Gen	Nt 2:							Volt-	LN	120					r-In-Door, With Locks	3		
Gen	Nt 3:	Warning: 240D-120V, 3P	-4W, Delta Hi-Leg	(B-P	hs-Orange)			Phs.	1	W.	3		OCP Types:	Mair	- MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	3
Gen	Nt 4:						Ε	Buss Ar	nps	225			All Busing:	CU (	or AL	100% N & G Busing		
Gen	Nt 5:	New Panel Adjacent Rela	y Panel					Main O	CP	MLO			Arc-Flash:	Labe	eled Per NEC & OSH	IA		
19-	121	MADDOX GROUP INC.			Spare % =	15%	K/	-AIC S	CA	65			19.08.12	Date	);	Const	Con	st
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	ОСР	Р	W/VA	ID	Wiring	Description	Nt	R
	2	Ltg- 300 Lvl Halls	#12+ 12G	L	250	20	1	01	Α	02	20	1	500	L	#10+ 10G	Ltg- 300 Extr	2	
	2	Ltg- 300 Lvl Halls	#12+ 12G	L	250	20	1	03	С	04	20	1	900	L	#10+ 10G	Ltg- 200 Extr	2	
	2	Ltg- 200 Lvl Open Off	#12+ 12G	L	700	20	1	05	Α	06	20	1	900	L	#10+ 10G	Ltg- 100 Extr	2	
	2	Ltg- 200 Lvl Halls	#12+ 12G	L	550	20	1	07	С	08	20	1	900	L	#10+ 10G	Ltg- 100 Extr	2	
	2	Ltg- 200 Lvl Lobby	#12+ 12G	L	1,100	20	1	09	Α	10	20	1	1,200	L	#10+ 10G	Ltg- Pk Deck	2	
	2	Ltg- 100 Lvl Halls	#10+ 10G	L	405	20	1	11	С	12	20	1	1,200	L	#10+ 10G	Ltg- Pk Deck	2	
	2	Ltg- 100 Lvl Halls	#10+ 10G	L	315	20	1	13	Α	14	20	1	0			> Spare <	2	
	2	Ltg- 100 Lvl Halls	#10+ 10G	L	650	20	1	15	С	16	20	1	0			> Spare <	2	
	2	Ltg- 100 LvI	#10+ 10G	L	1,660	20	1	17	Α	18	20	1	1,090	L	#10+ 10G	Ltg- 100 LvI	2	
		> Spare <			0	20	1	19	С	20	20	1	1,000	L	#10+ 10G	Ltg- 100LvI	2	
		> Spare <			0	20	1	21	Α	22	20	1	0			> Spare <		
		> Spare <			0	20	1	23	С	24	20	1	0			> Spare <		
		< Space Only >			0	Sp	1	25	Α	26	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	27	С	28	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	29	Α	30	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	31	С	32	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	33	Α	34	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	35	С	36	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	37	Α	38	Sp	1	0			< Space Only >		
		< Space Only >			0	Sp	1	39	С	40	Sp	1	0			< Space Only >		
Vt#	01-	HACR Listed & Labeled Mo	CCB			Phs	-A =	56.9	%	64	Α		7,715	VA	17.0	KVA Facotred End Use	71	1 A
Nt#	02-	Thru Relay Pnl				Phs	-C =	43.1	%	49	Α		5,855	VA	0.0	KVA Pass Thru Load	(	0 A
Nt#	03-	Not Used				S	umn	nary =		57	Α		13,570	VA	2.5	KVA Spare	11	1 A
Nt#	04-	Not Used													19.5	KVA Total	81	1 A

LCA Schd

Volt- LN 120

Buss Amps 225

Spare % = 15% KA-AIC SCA Exist

Main OCP MLO

 Wiring
 ID
 W/VA
 OCP
 P
 #
 P
 #
 OCP
 P
 W/VA
 ID
 Wiring

 # 12 +12G
 L
 900
 20
 1
 01
 A
 02
 20
 1
 0
 -- 

 # 12 +12G
 L
 935
 20
 1
 03
 C
 04
 20
 1
 0
 -- 

 # 12 +12G
 L
 675
 20
 1
 05
 A
 06
 20
 1
 600
 R
 # 12 +12G

 # 12 +12G
 L
 590
 20
 1
 07
 C
 08
 20
 1
 1,000
 R
 # 12 +12G

1 11 C 12 20 1

1 15 C 16 20 1

1 19 C 20 20 1

800 20 1 35 C 36 20 1

0 20 1 37 A 38 20 1 0 20 1 39 C 40 20 1

*Phs-A* = 48.7 % **121** A

*Phs-C* = 51.3 % **128** A

Summary = 125 A

Phs. 1 W. 3

Enclosure-Mtg: NEMA-1

All Busing: CU or AL

**19.08.12** Date:

1,000 R

1,000 R

1,200 R

1,200 R

1,000 R

1,500 E

1,400 R

200 R

800 R

1,500 R

15,325 VA

29,900 VA


Arc-Flash: Labeled Per NEC & OSHA


# 12 +12G

200 R # 12 +12G


200 R # 12 +12G

1,500 R # 12 +12G 1,500 R # 12 +12G





SMITH DESIGN GROUP, INC. 206 WEST HARALSON ST LAGRANGE, GEORGIA 30240



THE MADDOX GROUP, INC. DESIGN & ENGINEERING CONSULTANTS

,,,	<b>D</b> 1	Revisions	
#	Date	Description	
D			
Proje	ct Title:		

## RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

LaGrange, GA. 30240 City,St.
Wall Surf Mtd.

Const Const

Description Nt Rv

100% N & G Busing

> Spare <

> Spare <

Rcpt- Offices

Rcpt- Offices

Rcpt- Offices

Rcpt- Offices

Rcpt- Conf

Rcpt- Offices

Rcpt- Offices

Rcpt- Offices

Rcpt- Offices Rcpt- Offices

Rcpt- Jant GFCI

Rcpt- Offices

Rcpt- RR GFCI

Rcpt- RR GFCI

Rcpt- GFCI BrkRm

Rcpt- GFCI BrkRm

Rcpt- GFCI BrkRm

23.4 KVA Facotred End Use 98 A

112 A

Rcpt- GFCI BrkRm

0.0 KVA Pass Thru Load

3.5 KVA Spare

26.9 KVA Total

Cover & Door-In-Door, With Locks
OCP Types: Main - MCCB-60C/75C Branch- MCCB, 60C/75C Lugs

ELECTRICAL SCHEDULES

ed Date:	SDG Job No:
2019.08.12	191
Date:	
Bid & Permit	Sheet: F_0

201

)19.08.12	19
te: d & Permit 19.08.12	Sheet:

Projed	ct:	LaGrange Police Dep	ot 2019 Mods					N	1B		Schd				L	.aGrange, GA. 30240	City,S	st.
Gen N	Vt 1:	Existing, Remaining & R	eused - Verify Ex	ist Lo	ads Remain	ing		Volt	- LL	240		End	closure-Mtg:	NEI	/A-1	Wall Surf Mtd.		
Gen N	Vt 2:	Provide New Matching Ty	ype Devices As M	lay Be	Required.			Volt-	· LN	120		Co	ver & Door:	Doo	r-In-Door, With Locks			
Gen N	Vt 3:	Warning: 240D-120V, 3P-	-4W, Delta Hi-Leg	(B-Pl	hs-Orange)			Phs.	1	W.	3	(	OCP Types:	Mair	n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen N	Vt 4:	Verify Existing Ckts, Update	Directory, Clean 8	& Relal	bel Panel		E	Buss Ai	mps	100			All Busing:	CU	or AL	100% N & G Busing		
Gen N	Vt 5:							Main C	CP	MLO			Arc-Flash:	Labe	eled Per NEC & OSH	Ā		
19-1	21	MADDOX GROUP INC.			Spare % =	0%	K/	A-AIC S	SCA	Exist			19.08.12	Date	9:	Const	Cons	t
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	ОСР	Р	W/VA	ID	Wiring	Description	Nt	Rv
		> Spare <			0	20	1	01	Α	02	20	1	516	Н	Verify Exist	FCU-15, 4.3A		
		> Spare <			0	20	1	03	С	04	20	1	528	Н	Verify Exist	FCU-16, 4.4A		
		> Spare <			0	20	1	05	Α	06	20	1	516	Н	Verify Exist	FCU-17, 4.3A		
		> Spare <			0	20	1	07	С	08	20	1	624	Н	Verify Exist	FCU-18, 5.25A		
		> Spare <			0	20	1	09	Α	10	20	1	528	Н	Verify Exist	FCU-19, 4.4A		
		> Spare <			0	20	1	11	С	12	20	1	516	Н	Verify Exist	FCU-20, 4.3A		
		> Spare <			0	20	1	13	Α	14	20	1	528	Н	Verify Exist	FCU-21, 4.4A		
		> Spare <			0	20	1	15	С	16	20	1	528	Н	Verify Exist	FCU-22, 4.4A		
		> Spare <			0	20	1	17	Α	18	20	1	528	Н	Verify Exist	FCU-23, 4.4A		
		> Spare <			0	20	1	19	С	20	20	1	624	Н	Verify Exist	FCU-24, 5.25A		
		> Spare <			0	20	1	21	Α	22	20	1	930	Н	Verify Exist	FCU-25, 7.75A		
		> Spare <			0	20	1	23	С	24	20	1	930	Н	Verify Exist	FCU-26, 7.75A		
		> Spare <			0	20	1	25	Α	26	20	1	0			Ckt Demo > Spare		
		> Spare <			0	20	1	27	С	28	20	1	0			Ckt Demo > Spare		
		> Spare <			0	20	1	29	Α	30	20	1	0			> Spare <		
		> Spare <			0	20	1	31	С	32	20	1	0			> Spare <		
		> Spare <			0	20	1	33	Α	34	20	1	0			> Spare <		
		> Spare <			0	20	1	35	С	36	20	1	0			> Spare <		
		> Spare <			0	20	1	37	Α	38	20	1	0			> Spare <		
		> Spare <			0	20	1	39	С	40	20	1	0			> Spare <		
Nt# 0	)1-	HACR Listed & Labeled MC	CCB			Phs	-A =	48.6	6 %	30	Α		3,546	VA	9.1	KVA Facotred End Use	38	Α
Nt# 0	2-	Not Used				Phs	-C =	51.4	1 %	31	Α		3,750	VA	0.0	KVA Pass Thru Load	0	Α
Nt# 0	)3-	Not Used				S	umn	nary =		30	Α		7,296	VA	0.0	KVA Spare	0	Α
Nt# 0	)4-	Not Used													9.1	KVA Total	38	Α

Project: LaGrange Police Dept 2019 Mods

Gen Nt 1: Existing, Remaining & Reused - Verify Exist Loads Remaining

#10+ 10G

#10+ 10G

# 12 +12G

#10+ 10G

# 12 +12G

Gen Nt 2: Provide New Matching Type Devices As May Be Required.
Gen Nt 3: Warning: 240D-120V, 3P-4W, Delta Hi-Leg (B-Phs-Orange)

Gen Nt 4: Verify Existing Ckts, Update Directory, Clean & Relabel Panel

Gen Nt 5: - - - 19-121 MADDOX GROUP INC.

Lt- 300 Offices

Lt- 300 Offices

Lt- 300 Offices

> Spare <

> Spare <

> Spare <

> Spare <

Rcpt- Offices

Rcpt- Offices

Rcpt- Offices Rcpt- Offices

Rcpt- Offices

Rcpt- Offices

> Spare <

Rv Nt Description

Proje	ct:	LaGrange Police De	pt 2019 Mods					N	IA		Schd				L	.aGrange, GA. 30240	City,S	it
Gen	Nt 1:	Existing, Remaining & F	Reused - Verify Exis	t Lo	ads Remain	ing		Volt	- LL	240		End	closure-Mtg:	NEN	/A-1	Wall Surf Mtd.		
Gen	Nt 2:	Provide New Matching	Type Devices As Ma	у Ве	Required.			Volt-	LN	120		Cc	over & Door:	Doo	r-In-Door, With Locks			
Gen	Nt 3:	Warning: 240D-120V, 3F	P-4W, Delta Hi-Leg	(B-P	hs-Orange)			Phs.	1	W.	3	(	OCP Types:	Mair	n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen	Nt 4:	Verify Existing Ckts, Update	te Directory, Clean &	Relal	bel Panel		E	Buss A	mps	100			All Busing:	CU (	or AL	100% N & G Busing		
Gen	Nt 5:							Main C	)CP	MLO			Arc-Flash:	Labe	eled Per NEC & OSH	Ā		
19-	121	MADDOX GROUP INC.			Spare % =	15%	K/	N-AIC S	SCA	Exist			19.08.12	Date	e:	Const	Cons	t
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	Rv
		> Spare <			0	20	1	01	Α	02	20	1	0			Ckt Demo		
		> Spare <			0	20	1	03	С	04	20	1	528	Н	Verify Exist	FCU-02, 4.4A		
		Mech Ctrl Pnl	Verify Exist	Н	500	20	1	05	Α	06	20	1	516	Н	Verify Exist	FCU-03, 4.3A		
		> Spare <			0	20	1	07	С	08	20	1	324	Н	Verify Exist	FCU-04, 2.75A		
		Ckt Demo			0	20	1	09	Α	10	20	1	528	Н	Verify Exist	FCU-05, 4.45A		
		Boiler "B-01"	Verify Exist	Н	500	20	1	11	С	12	20	1	528	Н	Verify Exist	FCU-06, 4.45A		
		Ckt Demo			0	20	1	13	Α	14	20	1	528	Н	Verify Exist	FCU-07, 4.45A		
		> Spare <			0	20	1	15	С	16	20	1	324	Н	Verify Exist	FCU-08, 2.75A		
		> Spare <			0	20	1	17	Α	18	20	1	528	Н	Verify Exist	FCU-09, 4.45A		
		> Spare <			0	20	1	19	С	20	20	1	324	Н	Verify Exist	FCU-10, 2.75A		
		> Spare <			0	20	1	21	Α	22	20	1	0			Ckt Demo		
		> Spare <			0	20	1	23	С	24	20	1	192	Н	Verify Exist	FCU-12, 1.6A		
		Ckt Demo			0	20	1	25	Α	26	20	1	0			Ckt Demo		
		Ckt Demo			0	20	1	27	С	28	20	1	0			Ckt Demo		
		> Spare <			0	20	1	29	Α	30	20	1	0			Ckt Demo		
		> Spare <			0	20	1	31	С	32	20	1	0			Ckt Demo		
		> Spare <			0	20	1	33	Α	34	20	1	0			> Spare <		
		> Spare <			0	20	1	35	С	36	20	1	0			> Spare <		
		> Spare <			0	20	1	37	Α	38	20	1	0			> Spare <		
		> Spare <			0	20	1	39	С	40	20	1	0			> Spare <		
Vt#	01-	HACR Listed & Labeled M	ICCB			Phs	-A =	48.9	9 %	22	. A		2,600	VA	6.7	KVA Facotred End Use	28	Α
Vt#	02-	Not Used		Phs	-C =	51.	1 %	23	8 A		2,720	VA	0.0	KVA Pass Thru Load	0	Α		
Vt# (	03-	Not Used		S	umn	nary =		22	2 A		5,320	VA	1.0	KVA Spare	4	Α		
Vt# (	04-	Not Used													7.6	KVA Total	32	Α

Proje	ect:	LaGrange Police De	pt 2019 Mods					L/	AA		Schd				L	.aGrange, GA. 30240	City,S	št
Gen	Nt 1:	Existing, Remaining & R	eused - Verify Ex	st Lo	ads Remain	ing		Volt-	· LL	240		End	closure-Mtg:	NEN	ЛА-1	Wall Surf Mtd.		_
Gen	Nt 2:	Provide New Matching T	ype Devices As M	ay Be	Required.			Volt-	LN	120		Со	ver & Door:	Doo	r-In-Door, With Locks			
Gen	Nt 3:	Warning: 240D-120V, 3P	-4W, Delta Hi-Leg	(B-Pl	hs-Orange)			Phs.	1	W.	3	(	OCP Types:	Mair	n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen	Nt 4:	Verify Existing Ckts, Update	e Directory, Clean 8	Relal	bel Panel		E	Buss Ar	nps	225			All Busing:	CU	or AL	100% N & G Busing		
Gen	Nt 5:						1	Main O	СP	MLO			Arc-Flash:	Lab	eled Per NEC & OSH	A		
19-	121	MADDOX GROUP INC.			Spare % =	15%	KA	-AIC S	CA	Exist			19.08.12	Date	e:	Const	Cons	t
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	I
		Ltg- 200 Comm Rm	As Shown	L	900	20	1	1	Α	2	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Lobby		Γ
		Ltg- 200 Comm Rm	As Shown	L	500	20	1	3	С	4	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Lobby		
		Ltg- 200 TeleComm	As Shown	L	700	20	1	5	Α	6	20	1	600	R	#12+ 12G	Rcpt- 200Lv Files		
		Ltg- 200 Offices	As Shown	L	505	20	1	7	С	8	20	1	1,400	R	#12+ 12G	Rcpt- 200Lv Offices		
		Ltg- 200 Offices	As Shown	L	425	20	1	9	Α	10	20	1	900	R	#12+ 12G	Rcpt- 200Lv RR+ WC		
		> Spare <			0	20	1	11	С	12	20	1	900	R	#12+ 12G	Rcpt- 200Lv RR+ WC		
		> Spare <			0	20	1	13	Α	14	20	1	800	R	#12+ 12G	Rcpt- 200Lv Offices		
		> Spare <			0	20	1	15	С	16	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offices		
		> Spare <			0	20	1	17	Α	18	20	1	800	R	#12+ 12G	Rcpt- 200Lv Booking		Г
		> Spare <			0	20	1	19	С	20	20	1	400	R	#12+ 12G	Rcpt- 200Lv TeleComm		
		> Spare <			0	20	1	21	Α	22	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv TeleComm		
		> Spare <			0	20	1	23	С	24	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv TV Lobby		
		> Spare <			0	20	1	25	Α	26	20	1	0			> Spare <		
		> Spare <			0	20	1	27	С	28	20	1	0			> Spare <		Γ
		> Spare <			0	20	1	29	Α	30	20	1	0			> Spare <		
		> Spare <			0	20	1	31	С	32	20	1	0			> Spare <		
		> Spare <			0	20	1	33	Α	34	20	1	0			> Spare <		
		> Spare <			0	20	1	35	С	36	20	1	0			> Spare <		
		> Spare <			0	20	1	37	Α	38	20	1	0			> Spare <		
		> Spare <			0	20	1	39	С	40	20	1	0			> Spare <		
Nt#	01-	HACR Listed & Labeled Me	CCB			Phs	Α	53.1	%	59	Α		7,125	VA	14.0	KVA Facotred End Use	58	1
Nt#	02-	NotUsed				Phs	С	46.9	%	53	Α		6,305	VA	0.0	KVA Pass Thru Load	0	1
Nt#	03-	NotUsed				S	umm	nary =		56	Α		13,430	VA	2.1	KVA Spare	9	1
Nt#	04-	Not Used													16.1	KVA Total	67	1

ods					L	44		Schd				L	.aGrange, GA. 30240	City,S	t		
rify Ex	ist Lo	ads Remain	ing		Volt-	- LL	240		Enc	losure-Mtg:	NEN	ИА-1	Wall Surf Mtd.				
s As IV	ay Be	Required.			Volt-	LN	120		Co	ver & Door:	Doo	r-In-Door, With Locks					
Hi-Leg	(B-P	hs-Orange)			Phs.	1	W.	3				n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs			
Clean	& Relal	bel Panel		E	Buss Ar	mps	225			All Busing:	CU or AL 100% N & G Busing						
					Main C	СP	MLO			Arc-Flash:	Lab	_abeled Per NEC & OSHA					
		Spare % =	15%	K/	A-AIC S	SCA	Exist			19.08.12	Date	e:	Const	Const			
ıg	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	Rv		
wn	L	900	20	1	1	Α	2	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Lobby				
wn	L	500	20	1	3	С	4	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Lobby				
wn	L	700	20	1	5	Α	6	20	1	600	R	#12+ 12G	Rcpt- 200Lv Files				
wn	L	505	20	1	7	С	8	20	1	1,400	R	#12+ 12G	Rcpt- 200Lv Offices				
wn	L	425	20	1	9	Α	10	20	1	900	R	#12+ 12G	Rcpt- 200Lv RR+ WC				
		0	20	1	11	С	12	20	1	900	R	#12+ 12G	Rcpt- 200Lv RR+ WC				
		0	20	1	13	Α	14	20	1	800	R	#12+ 12G	Rcpt- 200Lv Offices				
		0	20	1	15	С	16	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offices				
		0	20	1	17	Α	18	20	1	800	R	#12+ 12G	Rcpt- 200Lv Booking				
		0	20	1	19	С	20	20	1	400	R	#12+ 12G	Rcpt- 200Lv TeleComm				
		0	20	1	21	Α	22	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv TeleComm				
		0	20	1	23	С	24	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv TV Lobby				
		0	20	1	25	Α	26	20	1	0			> Spare <				
		0	20	1	27	С	28	20	1	0			> Spare <				
		0	20	1	29	Α	30	20	1	0			> Spare <				
		0	20	1	31	С	32	20	1	0			> Spare <				
		0	20	1	33	Α	34	20	1	0			> Spare <				
		0	20	1	35	С	36	20	1	0			> Spare <				
		0	20	1	37	Α	38	20	1	0			> Spare <				
		0	20	1	39	С	40	20	1	0			> Spare <				
			Phs	Α	53.1	1 %	59	Α		7,125	VA	14.0	KVA Facotred End Use	58	Α		
			Phs	С	46.9	9 %	53	Α		6,305	VA	0.0	KVA Pass Thru Load	0	Α		
			S	umn	nary =		56	Α		13,430	VA	2.1	KVA Spare	9	Α		
										·			KVA Total	67			

Proje	ct:	LaGrange Police Dep	pt 2019 Mods					LE	BA		Schd				L	aGrange, GA. 30240	City,S	it.
Gen I	Vt 1:	Existing, Remaining & R	leused - Verify Exi	st Lo	ads Remain	ing		Volt-	LL	240		En	closure-Mtg:	NE	ЛА-1	Wall Surf Mtd.		
Gen I	Vt 2:	<b>Provide New Matching T</b>	ype Devices As Ma	ay Be	Required.			Volt-	LN	120		Co	over & Door:	Doc	r-In-Door, With Locks			
Gen I	Vt 3:	Warning: 240D-120V, 3P	-4W, Delta Hi-Leg	(B-P	hs-Orange)			Phs.	1	W.	3	OCP Types: M			n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	
Gen I	Vt 4:	Verify Existing Ckts, Update	e Directory, Clean &	Relal	bel Panel		E	Buss An	nps	225			All Busing:			100% N & G Busing		
Gen I	Vt 5:							Main O	ĊР	MLO			Arc-Flash:	Lab	eled Per NEC & OSH	A		
19-1	121	MADDOX GROUP INC.			Spare % =	15%	KA	-AIC S	CA	Exist			19.08.12	Dat	e <i>:</i>	Const	Const	t
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	Rv
		Rcpt- 200Lv Offs Cubes	#12+ 12G	R	400	20	1	1	Α	2	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Offs Cubes	#12+ 12G	R	400	20	1	3	С	4	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Offs Cubes	#12+ 12G	R	400	20	1	5	Α	6	20	1	1,000	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Offs Cubes	#12+ 12G	R	400	20	1	7	С	8	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Comm Ded	#12+ 12G	R	900	20	1	9	Α	10	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Comm Ded	#12+ 12G	R	900	20	1	11	С	12	20	1	600	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Comm Ded	#12+ 12G	R	900	20	1	13	Α	14	20	1	800	R	#12+ 12G	Rcpt- 200Lv Offs		
		Rcpt- 200Lv Comm Ded	#12+ 12G	R	300	20	1	15	С	16	20	1	800	R	#12+ 12G	Rcpt- 200Lv Gen		
		Rcpt- 200Lv Comm	#12+ 12G	R	1,200	20	1	17	Α	18	20	1	0			> Spare <		
		> Spare <			0	20	1	19	С	20	20	1	0			> Spare <		
		> Spare <			0	20	1	21	Α	22	20	1	0			> Spare <		
		> Spare <			0	20	1	23	С	24	20	1	0			> Spare <		
		> Spare <			0	20	1	25	Α	26	20	1	0			> Spare <		
		> Spare <			0	20	1	27	С	28	20	1	0			> Spare <		
		> Spare <			0	20	1	29	Α	30	20	1	0			> Spare <		
		> Spare <			0	20	1	31	С	32	20	1	0			> Spare <		
		> Spare <			0	20	1	33	Α	34	20	1	0			> Spare <		
		> Spare <			0	20	1	35	С	36	20	1	0			> Spare <		
		> Spare <			0	20	1	37	Α	38	20	1	0			> Spare <		
					0	na	-	Sub	Α	Sub	na	-	0			LBB		
					0	-	2	Load	B	Load	-	2	0			Sub Feed		
Nt# C	01-	HACR Listed & Labeled M	CCB			Phs	Α	61.0	%	60	Α		7,200	VA	10.9	KVA Facotred End Use	45	Α
Nt# C	02-	Not Used				Phs	С	39.0	%	38	Α		4,600		0.0	KVA Pass Thru Load	0	Α
Nt# C	03-	Not Used				S	umn	nary =		49	Α		11,800		1.6	KVA Spare	7	Α
Nt# C	04-	Not Used						_					,			KVA Total	52	Α

Proje		LaGrange Police De	•						3B		Schd					LaGrange, GA. 30240	City,	St.
		Existing, Remaining & F	•			ing		Volt-					closure-Mtg:			Wall Surf Mtd.		
		Provide New Matching			· ·			Volt-							r-In-Door, With Locks			
		Warning: 240D-120V, 3F	•		- ,			Phs.		W.	3	(			n - MCCB-60C/75C	Branch- MCCB, 60C/75C	Lugs	3
		Verify Existing Ckts, Update	te Directory, Clean	& Rela	bel Panel			Buss Ar	•				All Busing:			100% N & G Busing		
	Nt 5:							Main O							eled Per NEC & OSH			
		MADDOX GROUP INC.	•		Spare % =			I-AIC S					19.08.12		*	Const	_	_
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	R
		> Spare <			0	20	1	1	Α	2	20	1	0			> Spare <		
		> Spare <			0	20	1	3	С	4	20	1	0			> Spare <		
		> Spare <			0	20	1	5	Α	6	20	1	0			> Spare <		
		> Spare <			0	20	1	7	С	8	20	1	0			> Spare <		
		> Spare <			0	20	1	9	Α	10	20	1	0			> Spare <		
		> Spare <			0	20	1	11	С	12	20	1	0			> Spare <		
		> Spare <			0	20	1	13	Α	14	20	1	0			> Spare <		
		> Spare <			0	20	1	15	С	16	20	1	0			> Spare <		
		> Spare <			0	20	1	17	Α	18	20	1	0			> Spare <		
		> Spare <			0	20	1	19	С	20	20	1	0			> Spare <		
		> Spare <			0	20	1	21	Α	22	20	1	0			> Spare <		
		> Spare <			0	20	1	23	С	24	20	1	0			> Spare <		
		> Spare <			0	20	1	25	Α	26	20	1	0			> Spare <		
		> Spare <			0	20	1	27	С	28	20	1	0			> Spare <		
		> Spare <			0	20	1	29	Α	30	20	1	0			> Spare <		
		> Spare <			0	20	1	31	С	32	20	1	0			> Spare <		
		> Spare <			0	20	1	33	Α	34	20	1	0			> Spare <		Т
		> Spare <			0	20	1	35	С	36	20	1	0			> Spare <		
		> Spare <			0	20	1	37	Α	38	20	1	0			> Spare <		
		> Spare <			0	20	1	39	С	40	20	1	0			> Spare <		
Nt#	01-	HACR Listed & Labeled M	ICCB			Phs	Α	####	%	0	Α		0	VA	0.0	) KVA Facotred End Use	С	) A
Nt#	02-	Not Used				Phs	С	####	%	0	Α		0	VA	0.0	) KVA Pass Thru Load	C	ΟА
Nt#		Not Used				S		nary =		0	Α			VA	0.0	) KVA Spare	C	) A
Nt#	04-	Not Used														) KVA Total		0 A

Proje		LaGrange Police					L1A Schd					37						
Gen	Nt 1:	Existing, Remaining & F	Reused - Verify Exis	t Lo	ads Remain	ing		Volt-	LL	240		End	closure-Mtg:	NEN	1A 1	Wall Surf Mtd.		
		Provide New Matching		-	-		Volt- LN   <b>120</b>						ver & Door:		-			
		Warning: 240D-120V, 3F		•			Phs. 3 W. 4									Branch- MCCB, 60C/75C	Lugs	
Gen	Nt 4:	Verify Existing Ckts, Updat	te Directory, Clean &	Relal	oel Panel			Buss An					All Busing:			100% N & G Busing		
	Nt 5:							Main O					Arc-Flash:	Labe	eled Per NEC & OSH			
19-		MADDOX GROUP INC.			Spare % =	15%	K/	A-AIC S	CA	Exist			19.08.12	Date	);	Const	Status	;
Rv	Nt	Description	Wiring	ID	W/VA	OCP	Р	#	Р	#	OCP	Р	W/VA	ID	Wiring	Description	Nt	R۱
		Ltg- 100 LvI Offs	As Shown	L	585	20	1	1	Α	2	20	1	0		As Shown	??		
		Hi-Leg	No 120-V Use		0	Sp	1	3	<u>B</u>	4	Sp	1	0		No 120-V Use	Hi-Leg		
		Ltg- 100 Lvl Offs	As Shown	L	940	20	1	5	С	6	20	1	0		?	??		
		Ltg- 100 Lvl Offs	As Shown	L	585	20	1	7	Α	8	20	1	0		?	??		
		Hi-Leg	No 120-V Use		0	Sp	1	9	<u>B</u>	10	Sp	1	0		No 120-V Use	Hi-Leg		
		??	??		0	20	1	11	С	12	20	1	900	R	#12+ 12G	Rcpt- 100Lv Ded BrkRm		
		??	??		0	20	1	13	Α	14	20	1	900	R	#12+ 12G	Rcpt- 100Lv Ded BrkRm		
		Hi-Leg	No 120-V Use		0	Sp	1	15	<u>B</u>	16	Sp	1	0		No 120-V Use	Hi-Leg		
		??	??		0	20	1	17	С	18	20	1	1,200	R	#12+ 12G	Rcpt- 100Lv Offs		
		??	??		0	20	1	19	Α	20	20	1	1,200	R	#12+ 12G	Rcpt- 100Lv Offs		
		Hi-Leg	No 120-V Use		0	Sp	1	21	<u>B</u>	22	Sp	1	0		No 120-V Use	Hi-Leg		
		??	??		0	20	1	23	С	24	20	1	900	R	#12+ 12G	Rcpt- 100Lv Ded BrkRm		
		Rcpt- 100Lv Ded BrkRm	#12+ 12G	R	900	20	1	25	Α	26	20	1	900	R	#12+ 12G	Rcpt- 100Lv Ded BrkRm		
		Hi-Leg	No 120-V Use		0	Sp	1	27	<u>B</u>	28	Sp	1	0		No 120-V Use	Hi-Leg		
		> Spare <			0	20	1	29	С	30	20	1	900	R	#12+ 12G	Rcpt- 100Lv Ded BrkRm		
		Rcpt- 100Lv Offs	#12+ 12G	R	800	20	1	31	Α	32	20	1	1,200	R	#12+ 12G	Rcpt- 100Lv Offs		
		Hi-Leg	No 120-V Use		0	Sp	1	33	<u>B</u>	34	Sp	1	0		No 120-V Use	Hi-Leg		
		Ropt- 100Lv Offs	#12+ 12G	R	1,000		1	35	C	36	20	1	800	R	#12+ 12G	Rcpt- 100Lv Offs		
		< Space Only >			0	-	1	37	Α	38	20	1	1,200		#12+ 12G	Rcpt- 100Lv Offs		
		Hi-Leg	No 120-V Use		0		1	39	В	40	Sp	1	0		No 120-V Use	Hi-Leg		
		Rcpt- 100Lv Offs	#12+ 12G	R	1,400	· ·	1	41	C	42	20	1	0			< Space Only >		
					0	+	-	Sub	Α	Sub	na	-	13,200	Р		L1B		_
		Not Used			0	-	-	Feed	В	Feed	-	-	14,200			Sub-Feed		
					0	-	3			Load	-	3	17,400			Lugs		
Nt#	01-	HACR Listed & Labeled M	ICCB			Phs-		35.1	_	155	Α		21,470		14.7	KVA Facotred End Use	35	A
		NotUsed				Phs-		23.2		102	Α		14,200			KVA Pass Thru Load	114	
		NotUsed				Phs-	_	41.6		184	Α		25,440			KVA Spare	5	
		NotUsed						nary =		147			61,110			KVA Total	155	

ide New Matching Type Devices As May Be Required.         Volt- LN         120         C           ning: 240D-120V, 3P-4W, Delta Hi-Leg (B-Phs-Orange)         Phs.         3         W.         4           Existing Ckts, Update Directory, Clean & Relabel Panel         Buss Amps         225         Main OCP         MLO           DOX GROUP INC.         Spare % = 15%         KA-AIC SCA         Exist         Exist           Description         Wiring         ID         W/VA         OCP         P         #         P         #         OCP         P           ??         As Shown         0         20         1         1         A         2         20         1           RTU-01, Gas Ht         Verify existing         C         3,700         60         -         3         B         4         60         -           240V, 3Phs          C         3,700         -         -         5         C         6         -         -           6.0 Ton          C         3,700         -         3         7         A         8         -         3           RTU-02, Gas Ht         Verify existing         C         1,900         30         -         9 </th <th>All Busing: CU</th> <th>st n - MCCB-60C/75C or AL eled Per NEC &amp; OSH, e:</th> <th></th> <th>Status  Nt F</th>	All Busing: CU	st n - MCCB-60C/75C or AL eled Per NEC & OSH, e:		Status  Nt F
Phs.   3   W.   4   Buss Amps   225   Main OCP   MLO	OCP Types: Mair All Busing: CU of Arc-Flash: Labe 19.08.12 Date P W/VA ID 1 0 - 3,700 C - 3,700 C 3 3,700 C - 1,900 C	n - MCCB-60C/75C or AL eled Per NEC & OSH, e: Wiring As Shown Verify existing	A Const  Description ?? RTU-04, Gas Ht 240V, 3Phs	Status
Existing Ckts, Update Directory, Clean & Relabel Panel   Buss Amps   Main OCP   MLO	All Busing: CU of Arc-Flash: Laber 19.08.12 Date 19.08.12	or AL eled Per NEC & OSH, e: Wiring As Shown Verify existing	A Const  Description ?? RTU-04, Gas Ht 240V, 3Phs	Status
Main OCP   MLO	Arc-Flash:         Labe           19.08.12         Date           P         W/VA         ID           1         0         -           -         3,700         C           -         3,700         C           3         3,700         C           -         1,900         C	eled Per NEC & OSH, e: Wiring As Shown Verify existing	Const Description ?? RTU-04, Gas Ht 240V, 3Phs	
DOX GROUP INC.         Spare % = 15%         KA-AIC SCA         Exist           Description         Wiring         ID         W/VA         OCP         P         #         P         #         OCP         P           ??         As Shown         0         20         1         1         A         2         20         1           RTU-01, Gas Ht         Verify existing         C         3,700         60         -         3         B         4         60         -           240V, 3Phs          C         3,700         -         -         5         C         6         -         -           6.0 Ton          C         3,700         -         3         7         A         8         -         3           RTU-02, Gas Ht         Verify existing         C         1,900         30         -         9         B         10         30         -           0V, 1Phs, 2.5 Ton         -         C         1,900         -         2         11         C         12         -         2	19.08.12 Date       P     W/VA     ID       1     0     -       -     3,700 C     C       3     3,700 C     C       -     1,900 C     C	e: Wiring As Shown Verify existing	Const  Description ?? RTU-04, Gas Ht 240V, 3Phs	
Description         Wiring         ID         W/VA         OCP P         # P # OCP P           ??         As Shown         0 20 1 1 A 2 20 1           RTU-01, Gas Ht         Verify existing         C 3,700 60 - 3 B 4 60 - 20 1           240V, 3Phs          C 3,700 - 5 C 6 - 30 C 6 - 30 C 6 C 6 C 6 C 6 C 6 C 7 C 60 C 7 C 60 C 7 C 7 C 7 C 7 C 7 C 7 C 7 C 7 C 7 C	P         W/VA         ID           1         0         -           -         3,700         C           -         3,700         C           3         3,700         C           -         1,900         C	Wiring As Shown Verify existing	Pescription ?? RTU-04, Gas Ht 240V, 3Phs	
??         As Shown         0         20         1         1         A         2         20         1           RTU-01, Gas Ht         Verify existing         C         3,700         60         -         3         B         4         60         -           240V, 3Phs          C         3,700         -         -         5         C         6         -         -           6.0 Ton          C         3,700         -         3         7         A         8         -         3           RTU-02, Gas Ht         Verify existing         C         1,900         30         -         9         B         10         30         -           0V, 1Phs, 2.5 Ton         -         C         1,900         -         2         11         C         12         -         2	1 0 C S S S S S S S S S S S S S S S S S S	As Shown Verify existing	?? RTU-04, Gas Ht 240V, 3Phs	Nt R
RTU-01, Gas Ht       Verify existing       C       3,700       60       -       3       B       4       60       -         240V, 3Phs        C       3,700       -       -       5       C       6       -       -         6.0 Ton        C       3,700       -       3       7       A       8       -       3         RTU-02, Gas Ht       Verify existing       C       1,900       30       -       9       B       10       30       -         0V, 1Phs, 2.5 Ton        C       1,900       -       2       11       C       12       -       2	- 3,700 C - 3,700 C 3 3,700 C - 1,900 C	Verify existing	RTU-04, Gas Ht 240V, 3Phs	
240V, 3Phs        C       3,700       -       -       5       C       6       -       -         6.0 Ton        C       3,700       -       3       7       A       8       -       3         RTU-02, Gas Ht       Verify existing       C       1,900       30       -       9       B       10       30       -         0V, 1Phs, 2.5 Ton       -       C       1,900       -       2       11       C       12       -       2	- 3,700 C 3 3,700 C - 1,900 C		240V, 3Phs	
6.0 Ton        C       3,700       -       3       7       A       8       -       3         RTU-02, Gas Ht       Verify existing       C       1,900       30       -       9       B       10       30       -         0V, 1Phs, 2.5 Ton        C       1,900       -       2       11       C       12       -       2	3 3,700 C - 1,900 C		· ·	
RTU-02, Gas Ht	- 1,900 C		7.5 Ton	1
0V, 1Phs, 2.5 Ton C 1,900 - 2 11 C 12 - 2	-	Verify existing	1	
	2 1,900 C		RTU-03, Gas Ht	
?? ?? 0 20 1 13 A 14 20 1			240V, 1Phs, 2.5 Ton	
	1 0	?	??	
Hi-Leg No 120-V Use 0 Sp 1 15 <u>B</u> 16 Sp 1	1 0	No 120-V Use	Hi-Leg	
?? ?? 0 20 1 17 C 18 20 1	1 400 R	#12+ 12G	Rcpt- 100Lv	
Wtr Htr Verify existing R 3,000 30 - 19 A 20 20 1	1 1,000 R	#12+ 12G	Rcpt- 100Lv Offs	
240V, 3Phs R 3,000 21 <u>B</u> 22 Sp 1	1 0	No 120-V Use	Hi-Leg	
R 3,000 - 3 23 C 24 20 1	1 400 R	#12+ 12G	Rcpt- 100Lv Ded Eq	
> Spare < 0 20 1 25 A 26 20 1	1 400 R	#12+ 12G	Rcpt- 100Lv Ded Eq	
Hi-Leg No 120-V Use 0 Sp 1 27 <u>B</u> 28 Sp 1	1 0	No 120-V Use	Hi-Leg	
	1 400 R	#12+ 12G	Rcpt- 100Lv Ded Eq	
> Spare < 0 20 1 31 A 32 20 1	1 400 R	#12+ 12G	Rcpt- 100Lv Ded Eq	
Hi-Leg No 120-V Use 0 Sp 1 33 <u>B</u> 34 Sp 1	1 0	No 120-V Use	Hi-Leg	
> Spare < 0 20 1 35 C 36 20 1	1 1,000 R	#12+ 12G	Rcpt- 100Lv Assemb	
< Space Only > 0 20 1 37 A 38 20 1	1 1,000 R	#12+ 12G	Rcpt- 100Lv Assemb	
Hi-Leg No 120-V Use 0 Sp 1 39 <u>B</u> 40 Sp 1	1 0	No 120-V Use		
< Space Only > 0 20 1 41 C 42 20 1	1 0		< Space Only >	
R Listed & Labeled MCCB Phs- A 29.5 % 95 A	13,200 VA	44.8	KVA Facotred End Use	108 A
Jsed Phs- <i>B</i> 31.7 % 102 A	14,200 VA		KVA Pass Thru Load	0 A
Jsed Phs- C 38.8 % 126 A	17,400 VA		KVA Spare	16 A
Summary = 108 A	44,800 VA		KVA Total	124 A



THE MADDOX GROUP, INC.

DESIGN & ENGINEERING CONSULTANTS

TMG Job #: 19-121 Copywright -TMG- 2019

#	Date	Revisions  Description
#	T Date	Description
Proje	ect Title:	


## RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240


ELECTRICAL SCHEDULES

2019.08.12 Bid & Permit 2019.08.12

1911 E-05








RENOVATIONS TO LAGRANGE POLICE DEPT


100 West Haralson St. LaGrange, GA. 30240


Sheet Titl

ELECTRICAL & LIGHTING 200 LEVEL PARKING DECK


lified Date:	SDG Job No:
2019.08.12	1911
ed Date:	
Bid & Permit	Sheet:
2019.08.12	E-0.6









SMITH DESIGN GROUP, INC.




	$\rangle$	LEGEND NOTES <	$\bigcirc$
19.08	3.12	LaGrange Police Dept 2019 Mods	
#	Rv	LEGEND NOTES: E-1_	CO
		EXISTING EQUIP: Field Check & Verify, Update Pnl Schedules & Director. Clean Devices, Disconnect, Etc.,	
01	-	Check Condition Of Wiring & OCP, Label Disconnect, Etc. Prepare & Document & Submit A Listing Of The	
		Equipment Wiring Condition	
02	-	HVAC EQUIP( New): Coordinate & Provide For New Equipment As Shown & Scheduled.	
	-		
19-1	21	End Of Legend Notes	





206 WEST HARALSON ST LAGRANGE, GEORGIA 30240



I9.08.12 LaGrange Police Dept 2019 Mods

# Rv LEGEND NOTES: E-1\_ CO

EXISTING EQUIP: Field Check & Verify, Update Pnl Schedules & Director. Clean Devices, Disconnect, Etc.,

O1 - Check Condition Of Wiring & OCP, Label Disconnect, Etc. Prepare & Document & Submit A Listing Of The Equipment Wiring Condition

O2 - HVAC EQUIP( New): Coordinate & Provide For New Equipment As Shown & Scheduled.

Architect's Stamp

Signature Required

SMITH DESIGN GROUP, INC.
206 WEST HARALSON ST

LAGRANGE, GEORGIA 30240
706-882-5511 www.SDGarch.net



THE MADDOX GROUP, INC.

DESIGN & ENGINEERING CONSULTANTS

#	Date	Revisions  Description
Proje	ect Title:	


RENOVATIONS TO LAGRANGE POLICE DEPT


100 West Haralson St. LaGrange, GA. 30240


Sheet Title

ELECTRICAL MECHANICAL 300 LEVEL PLAN

Modified Date:	SDG Job No:
2019.08.12	1911
ssued Date:	
Bid & Permit	Sheet:
2019.08.12	<b>Ŀ-1.3</b>







**LEGEND NOTES** 19.08.12 LaGrange Police Dept 2019 Mods # Rv **LEGEND NOTES: E-23** CLG MTD 2-GANG AV-TVSS PWR: Flush Ceiling Box, 2-Gang With (1) TVSS-Duplex Receptacle, (1) Voice-Data Jack Provision, (1) Cable TV Jack Provision. Verify Exact Location With A/I. Support From Structure, Not Ceiling. Extend 1.25" EC To Wall Box For Future LV Screen Control & Wiring By Others. Legrand-P&S Recessed TV Box TV3W-TVSS-Series Or Equal. WALL MTD 3-GANG AV-PWR BOX: Flush Wall Box With (2) TVSS-Duplex Receptacle, (1) 4-Jack Plate (Voice-Data, Cable TV, Etc.) Provision. 12" Below Ceiling (Verify Final Height With A/I/Owner). Legrand-P&S Recessed TV Box TV3W-TVSS-Series Or Equal. TR-GFCI RCPT: Self-Testing & Audible Alarm GFCI Duplex Tamper-Resistant Receptacle & Cover-Plate, Decora Style. RoHS Compliant, Wall Mtd. 48" AFF (ADA), Color Per Archt-Owner. P&S Legrand Spec-Grade FURNITURE SYSTEM V-D WALL FEED: Field Verify Exact Location & Rough-In, Set 4x4 JBox 18" AFF & Extend 1 1/4"C To Accessible Plenum With Pull String For Use By Data/Telco Installer. FURNITURE SYSTEM POWER WALL FEED: Field Verify Electrical Requirements & Exact Location Prior To Rough-In, Set J-Box 18" AFF For Flex & Connection Work Station Power Connector. FURNITURE SYSTEM 4C-8W-G WIRING (4#10+2#10N+10IG+10G)(Field Verify): Extend Ckts. To 208Y-120V Panel(S), 20A Multi-Pole Breaker(S) (I.E.- 3 Ckt/ 4 Wire- 20A-3P Bkr) (Phase A-B-C) Or Provide Separate Neutrals. Updated Record Field Drawings & Panel Schedules & Directories With Load Information. Field Verify Exist. Panel Space & Capacity Prior To Pricing. Note: Circuits On Arc-Flash Protected OCPs Must Have Dedicated Neutrals (Grounded Conductor). Arc-Flash Circuits Cannot Share A Neutral. APPLIANCE GFCI DEDICATED RCPT: Provide 20A-120V-2W-G Duplex Receptacle, Extend 2#12+12G To Dedicated 120V-20A-1P Breaker, Update Pnl Directory. Label Outlet With Pnl & Ckt #.r. OFFICE EQUIP. 120V-20A DED. RCPT: Provide 20A-120V-2W-G Duplex Receptacle, Extend 2#12+12G To Dedicated 120V-20A-1P Breaker, Update Pnl Directory, Label Outlet With Pnl & Ckt #... VERIFY APPLIANCE GFCI DEDICATED RCPT: 20A-120V-2W-G Duplex Receptacle On Dedicated 120V-20A-1P Breaker. Test & Verify Proper Operation. Update "As-Builts" & Panel Directories. Label Outlet With Pnl & Ckt#.

End Of Legend Notes

19-121

Signature Required

SMITH DESIGN GROUP, INC.

206 WEST HARALSON ST


LAGRANGE, GEORGIA 30240

706-882-5511

www.SDGarch.net



THE MADDOX GROUP, INC. DESIGN & ENGINEERING CONSULTANTS



RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

Sheet Title:

Modified Date:

ELECTRICAL OUTLET 300 LEVEL PLAN

SDG Job No:

2019.08.12	1911
Issued Date:	
Bid & Permit	Sheet:
2019.08.12	E-2.3

#### LIGHTING GENERAL NOTES


NOTES & COMMNETS

FIXTURE TYPES ARE INDICATED BY UPPER CASE CHARACTERS SWITCHING GROUPS SHOWN BY LOWER CASE LTRS. WHERE APPLICABLE. CIRCUIT GROUPING SHOWN BY NUMBERS, WHERE APPLICABLE. REFER TO REFLECTED CEILING PLANS FOR EXACT FIXTURE LOCATIONS. WP INDICATES WEATHER PROOF SWITCH COVER.

LIGHTING FIXTURE SYMBOLS								
SYMBOLS	MTG/UNO	DESCRIPTIONS						
	SEE SCHD.	LIGHTING FIXTURES, GENERALLY CEILING MOUNTED SHAPE GENERALLY INDICATES SHAPE OF FIXTURE						
<del></del>	SEE SCHD.	FLUORESCENT STRIP TYPE FIXTURE						
	SEE SCHD.	WALL OR BRACKET MOUNTED TYPE FIXTURE						
ΔΔΔ	SEE SCHD.	LIGHTING TRACK & FIXTURES						
$  \otimes -\!\! \otimes  $	SEE SCHD.	EXIT SIGNAGE FIXTURE						
	SEE SCHD.	EXIT SIGNAGE WITH DIRECTIONAL ARROWS						
	SEE SCHD.	EXIT SIGNAGE WITH EMERGENCY FLOOD LIGHTS						
	SEE SCHD.	BATTERY TYPE EGRESS FIXTURES						
XXX	SEE SCHD.	LIGHTING FIXTURE TYPE ID / TAG- SEE LTG FIXTURE SCHEDULE						

LIGHTING CONTROLS - MANUAL, LINE-VOLTAGE, HARD-WIRED									
SYMBOLS	MTG UNO	GENERIC DESCRIPTIONS	RATINGS	MANUF. & SERIES LEGRAND/P&S- UNO					
	MANL	JAL DEVICES - LINE	<b>VOLTAG</b>	E TYPE					
Tx	48" AFF	(T)oggle Switch, 1= SPST; 2= 2PST; 3= 3-Way; 4= 4-Way	20A; Grnd 120V & 277V	PT-262-XX					
[Kx]	48" AFF	(K)ey Operated Switch, 1= SPST; 2= 2PST; 3= 3-Way; 4= 4-Way	20A; Grnd 120V & 277V	PT-20AC-XX					
Ix	48" AFF	(I)Iluminated When On Switch (UNO), 1= SPST; 2= 2PST; 3= 3-Way; 4= 4-Way	20A; Grnd 120V & 277V	PT-262-XX					
Ma	48" AFF	(M)omentary Contact Switch, 1-Pole 3-Position (a) Subscript Indicates Switching Group, Etc.	20A; Grnd 120V & 277V	TM811-DTMO-XX					
DL	48" AFF	(D)immer Line Volt, (1/3) Way,Full-Off, Incand., CFL & LED; NEMA-SSL7, Forward Phs Dim.	120V, G 150W-CFL, 600W-I	Lutron Maestro C-L Dimmers					
DO	48" AFF	(D)immer, 0-10V Analog Control; 1%-100%; On-Off Switch, Level Slider, Pwr-Fail Memory	0-10V Analog Control Wires	Lutron Diva Series					
WS)	48" AFF	(W)eather-(P) Toggle Switch, 1-Pole & WP Cover	20A,120V,277V,G	PT-262-XX & CA1GL					
SM	48" AFF	Switch Motor Rated, NEMA 3R Enclosure	3 Pole, 30A, 600V	7803 Switch & 7833 Encls					
		COMMENTS & NOTES							
1- Devices To Be UL20, Listed & Labeled Where Applicable. 2- Devices To Be NEMA WD-1 & WD-6 Compliant Where Applicable. 3- Devices To Be NFTA (Buy American) Where Avialable. 4- Devices To Be Legrand / P&S, PlugTail, Spec. Grade Devices, UNO. 5- Device Face To Decor Style Unless Not Available In Decor Style. 6- Provide Smooth Finish Matching P&S Trade-Master Grade Cover Plates. 7- Color As Selected By Owner / Tenant Or Architect. 8- Products Of Other Manufactures, Equivalent In Apperance, Features, Performance, Rating & Size, Are Acceptable.									

LIGHTING CONTROLS - SENSOR, LINE-VOLTAGE, HARD-WIRED										
SYMBOLS	MTG UNO	GENERIC DESCRIPTIONS	RATINGS	MANUF. & SERIES HUBBELL - UNO						
V1 V2	Wall Mt. 48" AFF	(V)acancy Sensor, (1/2) Ckt, PIR, Wall Mtd. Auto or Man On, Adjustable Time OFF	800W-F/I @ 120V 1200W-F @ 277V	(V1-1P) LHIRS1-xx-M (V2-2P) LHIRS2G-xx-M						
	Wall Mt. 48" AFF	(V)acancy Sensor - (D)immer, 1-Ckt, 0-10V Dimm, PIR, Auto or Man On, Self-Adjusting Time OFF	800W-CFL- @ 120V 1200W-CFL- @ 277V	LightHawk2- LHD-IRS-3-N						
U1) U2)	Wall Mt. 48" AFF	(U)ltra-Sonic/PIR Dual Sensor, (1/2) Ckt, Self-Adaptive, Off Warning, Man/ Auto Select 20x15 Minor & 35x30 Major Motion Range	800W-I @ 120V 800W-F @ 120V 1200W-F @ 277V	(U1-1P) LHMTS1G-xx (U2-2P) LHMTDS2G-xx						
P1 P2	Clg Mtd Per Manuf	(P)IR Occupancy Sensor, (1/2/x) Range, Power Pack, RFI & EMI Resistant, Adjust. Delay & Sensitivity P1- 500 Sq Ft, P2- 1200 Sq FT Coverage Range	24 VDC Sensor 20A, 120/ 277V Power Pack	(P1>500Sf) OMNI-IR (P2>1200Sf) OMNI-IRL						
U2 U1 U3	Clg Mtd Per Manuf	(U)Itra-Sonic Sensor, (1/2/x) Range, Power Pack, RFI & EMI Resistant, Adjust. Delay & Sensitivity U1- 500 SF, U2-1100 SF, U3- 2200 SF Range	24 VDC Sensor 20A, 120/ 277V Power Pack	(U1>500Sf) OMNI-US500 (U2>1100Sf) OMNI-US1000 (U3>2200Sf) OMNI-US2000						
(DL)	Clg Mtd Per Manuf	(D)ay(L)ight Switching (Non-Dim) Sensor, Closed-Loop Light Sensing,Matching Power Pack, RFI & EMI Resistant, Adjust. Delay & Sensitivity	24 VDC Sensor 20A, 120/ 277V Power Pack	NX-DS Sensor & NX-RC1RUNV Power-Pack						
C#)	Clg Mtd Per Manuf	(C)ombo (D)ual-Tech, US/PIR Sensor, Power Pack, RFI & EMI Resistant, Adjust. Delay & Sensitivity 360D-Sensing, 1000 & 2000 SF Range	24 VDC Sensor 20A, 120/ 277V Power Pack	(C1>1000Sf) OMNI-DT1000 (C2>2000Sf) OMNI-DT2000						
COMMENTS & NOTES										
01- Devices To Be UL20, Listed & Labeled Where Applicable. 02- Devices To Be NEMA WD-1 & WD-6 Compliant Where Applicable. 03- Devices To Be NFTA (Buy American) Where Avialable. 04- Devices To Be Hubbell, Spec. Grade Devices, UNO. 05- Color, If Option, Selected By Owner / Tenant Or Architect. 06- Products Of Other Manufactures, Equivalent In Apperance, Features, Performance, Rating & Size, Are Acceptable. 07- Field Verify Exact Final Location Prior To Rough-Ins Per Archt., Owner/ User. 08- Control / Grouping Indicated By Lower Case Letters (i.ea,b,c) 09- Multiple Adjacent Devices Shall Be Mounted In Multi-Gang Box With Multi-Gang Cover										



19121\_E30.dgn 8/15/2019 2:29:46 PM TMG

<sup>o</sup> roj:	LaGrange Police Dept 2019 Mods		LIGHTIN	G FIXTURE	SC	HED	JLE		19.08.12	Date
_oc:	LaGrange, GA. 30240			Smith Design Grou	ıp, Inc				Const	Statu
	Fixture Tag/ ID Designations- 1	st Letter/	Prefix Denotes F	ixture Type; X-Su	ıffix De	notes E	mergency	Featur	e / Use/	
*	ID-Tag Designations> 1st Letter (Prefix) Denotes Status (	D-E-M-N-	R), <u>2nd+</u> Letter Is	The Item ID-Tag-T	ype; <u>Su</u>	ffix " <b>X</b> " D	enotes An E	merge	ncy Use. "c"> Change-Out In-I	Place
	"d"> Demo; "e"> Existing Remains As Is; "m"> Modify	Exist; <u>"n</u>	<u>"&gt; New;                                   </u>	cated, Reuse Existir	ng; <b>"<u>v</u>"&gt;</b>	· Verify; (	Field Verify	Condit	ion(s) Of Existing Fixtures).	
Fixt	General Lighting	Ttl Mean	Lamp	Ballast-Driver	Po	wer	Mount.	Item	Manufacturer	Rev
ID	Fixture Descriptions	Lumens	Qty & Type	Туре	٧	VA	Notes	Notes	Series / Model	#
	1x4 Basic LED Flat-Panel Ltg Fixture, High-Impact		LED, 80-CRI,	0-10V 1%-Dimm;	UNV				Cloumbia Series: CFP-1x4-	
* <u>A</u>	Translucent Polycarbonate Lens, White Aluminum Lens	~ 4,000	<b>35</b> k-CCT;	10%-THD;	120-	40	FIC	-	4035	-
	Frame, DLC, 5-Yr Warranty, L70> 60k-Hr		L70>60kHrs	0.95PF	277				4000	
	2x2 Basic LED Flat-Panel Ltg Fixture, High-Impact		LED, <b>80</b> -CRI,	0-10V 1%-Dimm;	UNV				Cloumbia Series: CFP-2x2-	
* <u>B</u>	Translucent Polycarbonate Lens, White Aluminum Lens	~ 3,380	<b>35</b> k-CCT;	10%-THD;	120-	32	FIC	-	3335	-
	Frame, DLC, 5-Yr Warranty, L70> 60k-Hr		L70>60kHrs	0.95PF	277				0000	
*BG	Same As Type "B, Except Connected To Back-Up	~ 3,300	Ditto	Ditto	Ditto	32	FIC	_	Ditto	_
	Generator Power System	0,000					1.10		D itto	
	2x4 Basic LED Flat-Panel Ltg Fixture, High-Impact		LED, <b>80</b> -CRI,	0-10V 1%-Dimm;	UNV				Cloumbia Series: CFP-2x4-	
* <u>C</u>	Translucent Polycarbonate Lens, White Aluminum Lens	~ 5,445	<b>35</b> k-CCT;	10%-THD;	120-	50	FIC	-	5535	-
	Frame, DLC, 5-Yr Warranty, L70> 60k-Hr		L70>60kHrs	0.95PF	277					
	Center Lens Fixt, 2x2- LED Lamp, Curved White Acrylic		LED, <b>80</b> -CRI,	0-10V 1%-Dimm;	UNV				Columbia: LCAT-22-80CRI-	
* <u>D</u>	Lenses, 5-Yr.Warranty	~3,700	<b>35</b> k-CCT;	10%-THD;	120-	32	FIC	-	35k-HL- G-Curve-NoAir-ED1	-
			L80>60kHrs	0.95PF	277				Unv	
*DG	Same As Type "D, Except Connected To Back-Up	~3,700	Ditto	Ditto	Ditto	32	FIC	_	Ditto	_
	Generator Power System	-,								
* <u>DX</u>	Same As Type "D, Except With Self-Monitoiring	~3,700	Ditto	Ditto	Ditto	32	FIC	_	Ditto	_
	Automatic Battery-Inverter Emergency Source	,								
	Center Lens Fixt, 2x4- LED Lamp, Curved White Acrylic		LED, <b>80</b> -CRI,	0-10V 1% - Dimm;	UNV	·			Columbia: LCAT-24-80CRI-	
* <u>E</u>	Lenses, 5-Yr.Warranty	~5,600	<b>35</b> k-CCT;	10%-THD;	120-	44	FIC	-	35k-HL- G-Curve-NoAir-ED1	-
			L80>60kHrs	0.95PF	277				Unv	
*EG	Same As Type "E, Except Connected To Back-Up	~5,600	Ditto	Ditto	Ditto	44	FIC	_	Ditto	_
_	Generator Power System	,								
	24L, LED Multi-Purpose Strip-Light, Curved Frosted		LED, <b>80</b> -CRI,	Fixed; 10%-	UNV		WM-SM-		Columbia Series MPS -02Ft	
* <u>F</u> 2	Polycarb.Diffuser, Damp Location, 5-Yr Warranty. Occ-	~ 3.450	<b>35</b> k-CCT;	THD; 0.95PF	120-	29	PH	-	80CRI 35kCT ML CP W E	-
	Sensor Fixt Mtd		L80>60kHrs	,	277					
	48L, LED Multi-Purpose Strip-Light, Curved Frosted		LED, <b>80</b> -CRI,	Fixed; 10%-	UNV		WM-SM-		Columbia Series MPS -04Ft	
* <u>F</u> 4	Polycarb.Diffuser, Damp Location, 5-Yr Warranty. Occ-	~ 4,600	<b>35</b> k-CCT;	THD; 0.95PF	120-	41	PH	-	80CRI 35kCT ML CP W E	-
	Sensor Fixt Mtd		L80>60kHrs	·	277				EU M. IL LIEIO LED	
**	05 Inch Dia Wet-Location LED Shower-Light, IC-	000	LED, 85-CRI,	Fixed 10%-THD;	400	4.5	FIO		Elite MaxiLume H5IC-LED-	
* <u>G</u>	Housing, White Trim Ring, Albalite Lens, Alzack Reflector	900	35k-CCT	0.95PF	120	15	FIC	-	900L-Unv-MD-35CCT-	
	& White Plastic Trim Ring; 5-Yr Warranty		LED 00 ODI	0.40\/.40/. Di	1.18157		OM / OD		85CRI-L501L-CL-WH	
*!!2	24L LED Dn+Up Lt Wall Mtd, Steel Housing & End-	~1,397-	LED, 80-CRI,	0-10V 1%-Dimm;	UNV	19	SM / SR Wall Mt		Columbia Series: CWM 2 80	
* <u>H</u> 2	Caps, 5-Yr. Warranty Curved Lens + Bamboo-Insert	Lu	35k-CCT;	10%-THD; 0.95PF	120- 277	19		-	35k MW SM/SR DICB ED1	-
			L80>60kHrs LED, <b>80</b> -CRI,	0.95PF 0-10V 1%-Dimm;	UNV	F	Per Archt SM / SR		Unv Columbia Series: CWM 4 80	
*H4	Same As Type "H2, Except 48-Inch Version	~2,835-	35k-CCT;	10%-THD;	120-	38	Wall Mt		35k MW SM/SR DICB ED1	
<u>п</u> 4	Same As Type Hz, Except 40-mich version	Lu	L80>60kHrs	0.95PF	277	30	Per Archt	_	Unv	-
			LOUPOORITIS				I GI AIGIIL		Elite-MaxiLume: HH4-LED	
	04 In.LED Dnlt, 45D Cut-Off, Diff-Lens, Satin-Haze Alzak	1,500-	LED, 90-CRI,	Fixed / 0-10V	MV				1500-Lu Dim1% MVolt-M-	
* <u>I</u>	Reflector & Trim Ring, Damp/Wet Location, 5-Yr	Lu; M-	35k-CCT	1%-Dimm; 10%-	120V	20	FIC	-	Distb 35K 90-CRI 6501 CL-	-
	Warranty, (Non-)Dimmable To 1%	Distb	33K-001	THD; 0.95PF	277V				WH	
	4 Ft, VR, Auto-Bi-Level (50%/100%), LED, Linear VR									
	Unit, Ribbed White Poly. Lens, DL-Label, UL-1598, UL-	~5,600	LED, <b>80</b> -CRI,	0-10V 1% - Dimm;	Unv-	50	WM Over		New Star Series: VIC tory 4-	
*JX	2108, DLC, LM79, LM80, TM21, 5-Yr Warranty.	(Std)	<b>35</b> k-CCT;	10%-THD;	120-	(Std)	Door Or	-	Ft N 35 Std-Lu 35k 1C RW	-
	+Sensor, +Auto. Emerg. (1,400 Lumen Bat-Invert Unit)	()	L70>50kHrs	0.95PF	277V	(0.0.)	Landing		UV WH SD2 OC	
	12-24-48 Surface-Corner Mt LED Security Grade, 18-									
	Ga Steel, Polycarb. Lens (White-Interior + 0.250"-		LED, <b>80</b> -CRI,	2-Drivers; 0-10V	UNV		SM- Bolt		NewStar Series: <b>55</b> 4	
*KX	Exterior), Integral Drive(s), Tamper-Resistiant	5,750	<b>35</b> k-CCT;	1%-Dimm; 10%-	120-	50	To Clg		18GaCRS LED-2Row 35k-	
	Hardware, DL-Rated, Night-Light Dimming Driver (0-	,	L80>60kHrs	THD; 0.95PF	277		Structural		CCT, 2-Driver, 25OCPL+	
	10V, 1%-100%); Emerg Batt-Inverter (1350-Lu)			,			Per Manuf		125PA Unv E2 TH LN	
				0.40\/ D:						
	LED Tape-Light, 18 LEDs A Foot, 120D-Light Distrib,	405	LED OF OD!	0-10V Dimming	ייים	4.0			Colosfelliele C	
*L	24V-DC, Field Cuttable. UL Wet Location (IP68 Wet &	425	LED, 85-CRI, 35k-CCT; 50-kHr	UL Power	Dual	4.0- Watts A	See Archt		Celestial Lighting Series: SERPENS-FS SER-FX-W35	
L	Dust) With Dimmable UL Class-2, Mtg. Hdwr & Related.		•	'''	120,		Detail	_		-
	Field Verify Lengths, Routing, Mounting, Etc. Before	Per Ft	Life	Wet-Location, -	277V	Fţ			& Related components	
	Ordering. Outdoor Corner Channel & Rouned Lens			40C-60C						
	Linear Flush 2 / 4Inch Slot Fixture, LED, Continuous		IED 00 OD	Matchin = 0.40V	1815 /					
***	Run (1-Inch Units), Frosted Acrylic Lens, Complete	500	LED, 80-CRI,	Matching 0-10V	UNV	4.5	FIC		Elite-Oracle Series: OLS-R-	
*M	With All Related Hardware. Field Verify Final Exact	Lu/Ft	35k-CCT;	Dimming UL	120-	W/FT	FIC	-	LED-4In	-
	Layouts & Lenghts. 5-Yr Warranty		L70>50kHrs	Power Supply	277					
	· - ·									-

-	LaGrange Police Dept 2019 Mods LaGrange, GA. 30240		LIGHTIN	G FIXTURE Smith Design Grou		HEDU	JLE		19.08.12 Cons	
_oc:	Wet-Location Outdoor (W ")	Ttl Mean	Lamp	Ballast-Driver		wer	Mount.	Item	Manufacturer	• (
ID	Lighting Fixture Descriptions	Lumens	Qty & Type	Туре	V	VA	Notes	Notes	Series / Model	
WA	06 In.LED Dnlt, 45D Cut-Off, Diff-Lens, Satin-Haze Alzak Reflector & Trim Ring, Damp/Wet Location, 5-Yr Warranty, (Non-)Dimmable To 1%	1,500- Lu; M- Distb	LED, 90-CRI, 35k-CCT	Fixed / 0-10V 1%-Dimm; 10%- THD; 0.95PF	MV 120V 277V	20	FIC	-	Elite-MaxiLume: HH6-LED 1500-Lu Dim1% MVolt-M- Distb 35K 90-CRI 6501 CL-	
WB	"Decorative LED Wall Mtd. 20_Inch Dia. White Globe With "POLICE" In Balck Letters, 36 Inch OAH, Decorative Wall Bracket, Wet-Location Listed; Verify With	Existing	Existing	Existing	120	Verify	Existing	-	Existing To Remain & Be Reused, Clean & Relamp,	
wc	Archt-Owner Prior TO Ordering Flag & Pole Small Flood Lt, LED, Wet Location Labeled, Tempered Glass Lens, Glare-Sheild, Yoke-Mount, Dark- Bronze Finish, Surge-Prot, 5-Yr.Warr, Beam-Spread	~4,900L	LED, 70-CRI, 50k-CCT	LED Driver & Power Supply	UNV 120V	52	Concrete Base, Aim		Connect To New Ckts/ Hubbell Series FML-LED: 52 4k, 3x3, Unv, K, DB-SP	2
WD	NEMA 3x3  UL-Wet-Location, LED Medium Wall Pack, Full-Cut-Off, Die-Cast AL Housing; Verify Per Archt-Own: Finish>  Bronze; Comfort-Sheild	3,806 (18)	LED, 70-CRI, 40- kCCT, 2,3,4,FT- Distb, 60k Hrs	Per Manuf Fixed; 10%- THD; 0.95PF, TVSS	UV 120- 277	42(18)	High As Possible	-	Hubbell Series: LNC2, 4k- CCT, xx-DC-LED, xx-Distb, Unv, Std Mtg, ##-Finish+	
WE	Surface LED On Exist canopy Box)		Life	1100					CS+PCU, SCP@ xx-Ft, EH  Inspect, Clean & Relamp	1
									mepoo, eream er teramp	
WF	LED Wet-Location (IP65), Linear Facade-Sign Floodlight, Asymmetric Reflector, Single Run As Shown, Bracket Mtg. Complete With All Matching Hardware, Decorative End-Caps & Lens-Sheild; Surge Protected - 30C Rated Driver(s). Std. Finish As Selected By Archt-Owner (Weathered-Bronze UNO). Make Final Light Aiming Adjustments At Night With Archt-Owner.	~ 2,650 Lu/ Ft	LED, 80-CRI, 40k-CCT	Fixed; 10%- THD; 0.95PF	UNV- 120- 277	30 W/LF	Arm- Mount, High Wall; Per Archt Detail		Hubbell Archt Area Lighting Series: Pivot PV-LED 2800 - LK-5300L-xxInch-40K-Arms- Finish-EFW-SLD	-
WP1	Acorn Style Period Lumnaire On Decorative Cast Alumn. Post. 15 Dia-32High, Stipple Acrylic Refractor With Decorative Perf. RIng & Top Finials & Mtg Post Adaptor. Finish (Black) Per Archt-Owner	7,676- Lu; LM80> 60k-Hrs	LED, 35k-CCT, 85+-CRI; Distb> Type 3~5; Night- Sky; LM80> 50kHrs	Fixed; 10%- THD; 0.95PF, TVSS	UNV- 120- 277	100	On Top Brick Pier See Archt Dtls.		Sternberg Ltg: Globe A750- ASR-R1-LED-CDR; Fitter: 5P-PT; Pole: 62-12-TFP6; 6ARC45TMDL03-Black Finish Per Archt/Owner	
WP2	Same As Type "WP1" Except No Post, Mtd. On Top Of Brick Pier	Ditto	Ditto	Ditto	Ditto	Ditto	Ditto		Ditto	
WP3	Same As Type "WP1" Except No Post, Wall Bracket Mtd	Ditto	Ditto	Ditto	Ditto	Ditto	Ditto		Ditto	
	Frit Cinns O Francous and the Unite (IIV III)				 D-					_
Fixt ID	Exit Signs & Emergency Ltg. Units ("X")  Fixture Descriptions	Ft 1 FC Avg	Unit Heads Qty & Type	Unit Battery	Po	wer VA	Mount. Notes	Item Notes	Manufacturer Series / Model	
X0	Dual-Mode LED Extr AC+ Batt Egress Unit, Cast Alumn, VR, IP-66 / 3R Rated, _4F>104F, 5-Yr.Full Warr; Self-Test-Monitor-Alarm, Std. Color Per Archt-Owner; Wide / Forward Throw; Time-Delay, Photo-Cell	Avg.1.0- FC @ 15-MH; 6x40Ft;	640-Lumen, 6.0 W-LED Heads; 50-kHrs	Nick-Metal Hydride	UNV- 120V- 277V	3 / 15(Htr)	WM Abv Door	1	LightAlarms Camray LED: CAM-ACSD-Color-FT-PC- T3	
X1	BLACK Thermoplastic Emerg. Ltg. Unit, 2-LED MR16 Heads, UL924+NFPA101 Self-Diagnostic-Testing. 3-Yr Full & 5-Yr Pro-Rata Warranty	na	(2) 3.6V-3.6W LED-MR16, 50k Hr Life	3.6-V Nickle- Metal-Hydride	UNV- 120, 277	7.5	Clg / WM High	1	LightAlarms: LCA-2LED	
X2	Compact BLACK Thermoplastic Emerg. Ltg. Unit, LED NiCad Battery, 5-Yr.Full-Warr; UL924+NFPA101 Self-Diagnostic-Testing, Vandal-Resistiant	1.0-FC; 15-Hi, 80-OC	(2) 540-Lumen, 6.0 W-LED MR16 Heads	12 VDC Sealed Lead-Calcium	UNV- 120, 277	7.5	Clg or WM @ 15'-0" High	1	LightAlarms Compact-Grande Series: 2Hd-MGR12N4-(2) LD10-W/B-ID-T3-DL +CM/PM	
XU	Combo LED Exit Sign, 1/2 Face, 2-Adjust LED Heads, Univ Mtg. Batt-Back-Up, Red Ltr, Arrows As Needed, Self-Test-Alarm, 3-Yr. Warranty; BLACK; (17W 13H 04D)	~ 89 OC, 07 MH	(2) 6.0 W-LED MR16 Heads; 80Cx15Hx06W	12 VDC- Lead- Calcium With Self- Diagnostics	UNV	5	UM	1	LightAlarms GRANDE Series GR-1224M-R-U-X-2HD- LD10-ID	3:
1-	Connect Emerg Life-Safety Battery To Local Unswitched I	_tg. Ckt. P	SPECIFIC IT	2- 4-	Refer T	o Interio	r Lighting P	ans & S	Schedules For Details.	
				PPLICABLE			-			
A- C-	Document Training Personell In NFPA-101 Testing Stds.	⊢or Egres	ss & Exit Lights.	B- D-	Instruct	Owner-	ı enant In A	ny Dimi	ming Controls Operations.	
	Misc. Abbreviations			/ Ballast / Driver 1					Mounting Terms	
	Furnished By Owner Complete U.N.O.		CRI	Color Rending Ind	•	.amp)	BFC-		Finished Ceiling	
	Fixt Material Cost With Lamps & Hardware Complete Installed Complete By Contractor, U.N.O.		xx K Lum mA	Kelvin (Lamp Cold Lumens (Lamp Lig Milli-Amp (LED Dr	ght Outpu		CB- FIC- FIG-	Flush	ete Base- See Details In Ceiling In Grade	
PBC-	Provided By Contractor		PS STA	Programmed Start Self-Test & Alarm		"'Y <i>)</i>	PH-		Hung,Htg As Ntd; Per Archt	
	Selected By Owner		RS	Rapid Start	-1		SM-	Surfac	ce Mtd On Ceiling Or Structure	!
	ΔΙ ٦	TERNA	THD TES / PRIOR	Total Harmonic Di			WM-	wall N	1td- Htg As Noted; Per Archt.	
	Project Base Quote Shall Be Based On The Lighting As S	cheduled	& Specified.							
							o			
	Lighting Products Of Other Manufactures May Be Submitte				_abeled I	Fixtures	& Lampe D	ata, Cu	t-Sheets & Any Variations	
AB	Lighting Products Of Other Manufactures May Be Submitte  A Complete Submittal Is Required, Including Cover-Page		SUBMITTALS	REQUIRED			·	·	·	



9309 Seminole Road
Jonesboro, Georgai 30236
770 - 471 - 9076
maddoxgroup@comcast.net

TMG Job #: 19-121
Copywright -TMG- 2019

THE MADDOX GROUP, INC.

DESIGN & ENGINEERING CONSULTANTS

# Date Description

# Dotate Description

Project Title:

## RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

Sheet Title:

LIGHTING SCHEDULES SYMBOLS & RELATED

Modified Date:

2019.08.12

Issued Date:


Bid & Permit


SDG Job No:

10

Bid & Permit 2019.08.12

1911





SMITH DESIGN GROUP, INC. 206 WEST HARALSON ST LAGRANGE, GEORGIA 30240



9309 Seminole Road Jonesboro, Georgai 30236 770 - 471 - 9076 maddoxgroup@comcast.net TMG Job #: 19-121 Copywright -TMG- 2019

THE MADDOX GROUP, INC. DESIGN & ENGINEERING CONSULTANTS

Revisions Description RENOVATIONS TO LAGRANGE POLICE DEPT


100 West Haralson St. LaGrange, GA. 30240

Sheet Title:

LIGHTING 100 LEVEL PLAN

SDG Job No: Modified Date: 2019.08.12 1911 Bid & Permit E-3.1

2019.08.12





1911


E-3.2

Bid & Permit

2019.08.12








Architect's Stamp

Signature Required SMITH DESIGN GROUP, INC. 206 WEST HARALSON ST LAGRANGE, GEORGIA 30240

706-882-5511



THE MADDOX GROUP, INC. DESIGN & ENGINEERING CONSULTANTS



## RENOVATIONS TO LAGRANGE POLICE DEPT

100 West Haralson St. LaGrange, GA. 30240

LIGHTING 300 LEVEL PLAN

Modified Date:	SDG Job No:
2019.08.12	1911
Issued Date:	
Bid & Permit	Sheet:
2019.08.12	E-3.3