



January 7, 2022

Hollie R. Casey, CAP, VCA, VCCO  
Procurement Officer  
Dinwiddie County, Virginia

Via Email: [hcasey@dinwiddieva.us](mailto:hcasey@dinwiddieva.us)

RE: Hazardous Materials Testing Report  
Contract # 22-0005  
Pamplin Building Roof Asbestos Sampling  
Dinwiddie, Virginia 23841  
KBJW Project No. 2021-2021

Dear Hollie,

Koontz Bryant Johnson Williams Inc. (KBJW) is pleased to provide you this summary report for the asbestos sampling conducted at the referenced property.

## INTRODUCTION


Ms. Hollie Casey requested an asbestos survey of the Pamplin Building roof located at 14016 Boydton Plank Road, Dinwiddie, Virginia 23841. On January 5, 2021, Mr. Ron Etter, a licensed Virginia Asbestos Building Inspector (License No: 3303001589; Attachment A) conducted a visual inspection and collected bulk samples of suspect asbestos containing building materials (ACBM) from readily accessible areas of the roof. Bulk samples were submitted to Environmental Hazards Services (EHS) Labs in Chesterfield, Virginia for analysis.

## METHODOLOGY - Bulk Sampling

Bulk samples of suspect ACBM were collected of select materials and placed into sealable, plastic bags. Each sample bag was labelled with a unique sample ID number and the ID number, location, and description of the sample was recorded on the field sample log. The samples were submitted for analysis via polarized light microscopy (PLM) for one day turnaround time.

The PLM method is the most commonly used method to analyze building materials to determine asbestos content. This method utilizes the optical properties of minerals to identify the selected constituent, enabling the identification of the type and percentage of asbestos in a sample. The PLM method has a detection limit of approximately one (1) percent asbestos.

A total of 11 bulk asbestos samples were collected and submitted under chain of custody protocols, to EHS Laboratories of Chesterfield, Virginia, a Virginia Licensed Asbestos accredited laboratory (VELAP 460172) for bulk asbestos analysis via PLM.



## FINDINGS

The flat, built-up roof consists of two roof systems, the original graveled covered roof with a smooth, coated roof installed over the original roof. The roof system consists of several layers of asphalt coated roofing felts, gravel, perlite board and foam insulation. The roof has parapet walls along the perimeter. HVAC units are mounted in the middle of the roof, rain drains and vents are located at various locations on the roof.

The visual inspection revealed suspect ACM, including the felts of the roof field, flashing on the parapet walls, flashing on the HVAC mounts, and roofing tar around the penetrations.

A summary of the sampling and analysis results (Attachment B) is presented in the following table. Sample locations are shown on Figure 1.

| SampleID | Description                     | Asbestos Percent/Type | Condition |
|----------|---------------------------------|-----------------------|-----------|
| D-1      | Field roofing felts, insulation | NAD                   | Good      |
| D-2      | Field roofing felts, insulation | NAD                   | Good      |
| D-3      | Field roofing felts, insulation | NAD                   | Good      |
| D-4      | Field roofing felts, insulation | NAD                   | Good      |
| D-5      | Field roofing felts, insulation | NAD                   | Good      |
| D-6      | Field roofing felts, insulation | NAD                   | Good      |
| D-7      | Flashing parapet wall           | NAD                   | Good      |
| D-8      | Flashing parapet wall           | NAD                   | Good      |
| D-9      | Flashing parapet wall           | NAD                   | Good      |
| D-10     | Flashing, pitch pocket HVAC     | Trace <1%             | Good      |
| D-11     | Flashing parapet wall           | NAD                   | Good      |

NAD - No Asbestos Detected

## CONCLUSIONS

Asbestos containing material (ACM) means any material containing more than 1% asbestos. No ACM was identified in the areas surveyed.



## RECOMMENDATIONS

In the event that suspect ACM, that were not included in this survey, are discovered, they must be assumed to contain asbestos until they are sampled and analyzed to determine their asbestos content, if any.

## LIMITATIONS

The field observations, measurements, and research conducted during the execution of this survey are considered adequate in detail and scope to determine the asbestos content of the sampled material in the areas identified by the survey. The findings, conclusions, and recommendations presented in this report are based on specifically limited data. They do not represent all conditions at the subject property.

This report was prepared pursuant to the contract between KBJW and Dinwiddie County. Reliance, or any use of this report by anyone other than the Client, for whom it was prepared, is prohibited. KBJW makes no warranties or representations, expressed, or implied in this report to third parties.

This limited asbestos survey was prepared to provide the Client with information concerning the apparent conditions at the specific locations of accessible materials on the date the survey was conducted. Due to the nature of the work, it is possible that conditions exist that could not be identified within the scope of the survey, or which were not apparent during the visual assessment of the structure. This report is limited only to the samples collected at the locations indicated. Additional sampling and analysis may be required to identify previously inaccessible areas or unidentified areas discovered during demolition activities.


Respectfully,

Ronald W. Etter  
Virginia Asbestos Building Inspector (License No: 3303001589)

cc: J. Patterson, KBJW

Attachments: Figure 1 - Sample Locations  
Appendix A - Inspector Certification  
Appendix B - Asbestos Bulk Analysis Report

**FIGURE 1**  
**SAMPLE LOCATIONS**



● Sample Locations

Not to Scale



Sample Locations  
Pamplin Building  
Dinwiddie, Virginia

Date: January 7, 2022  
Project No. 2021-2021

Figure No:  
1

**APPENDIX A**  
**INSPECTOR CERTIFICATION**

COMMONWEALTH of VIRGINIA

Department of Professional and Occupational Regulation

9960 Mayland Drive, Suite 400, Richmond, VA 23233

Telephone: (804) 367-8500

EXPIRES ON  
08-31-2022

NUMBER  
3303001589

BOARD FOR ASBESTOS, LEAD, AND HOME INSPECTORS  
ASBESTOS INSPECTOR LICENSE



RONALD WAYNE ETTER  
220 PINE LANE  
KING WILLIAM, VA 23086



*Mary Broz-Vaughan*  
Mary Broz-Vaughan, Director

Status can be verified at <http://www.dpor.virginia.gov>

(SEE REVERSE SIDE FOR PRIVILEGES AND INSTRUCTIONS)

DPOR-LIC (02/2017)

**APPENDIX B**

**ASBESTOS BULK ANALYSIS REPORT**





Environmental Hazards Services, L.L.C.  
 7469 Whitepine Rd  
 Richmond, VA 23237  
 Telephone: 800.347.4010

## Asbestos Bulk Analysis Report

Report Number: 22-01-00495

Client: Ronald Etter  
 PO Box 201  
 King William, VA 23086

Received Date: 01/05/2022  
 Analyzed Date: 01/06/2022  
 Reported Date: 01/06/2022

Project/Test Address: Pamplin Bldg Roof; Dinwiddie, VA

Client Number:  
 201608

Fax Number:

# Laboratory Results

| Lab Sample Number | Client Sample Number | Layer Type | Lab Gross Description  | Asbestos | Other Materials   |
|-------------------|----------------------|------------|--|----------|---|
| 22-01-00495-001   | D-1                  |            | White Aggregate; Pale Yellow Foam; Black Tar-Like Fibrous; Yellow Fibrous; Inhomogeneous | NAD      | 22% Cellulose<br>34% Fibrous Glass<br>8% Synthetic<br>36% Non-Fibrous |
| 22-01-00495-002   | D-2                  |            | White Aggregate; Pale Yellow Foam; Black Tar-Like Fibrous; Brown Fibrous; Inhomogeneous  | NAD      | 34% Cellulose<br>8% Fibrous Glass<br>14% Synthetic<br>44% Non-Fibrous |
| 22-01-00495-003   | D-3                  |            | Pale Yellow Foam; White Pliable; Black Tar-Like Fibrous; Inhomogeneous                   | NAD      | 35% Cellulose<br>8% Fibrous Glass<br>14% Synthetic<br>43% Non-Fibrous |
| 22-01-00495-004   | D-4                  |            | Pale Yellow Foam; White Pliable; Black Tar-Like Fibrous; Inhomogeneous                   | NAD      | 35% Cellulose<br>16% Fibrous Glass<br>7% Synthetic<br>42% Non-Fibrous |

# Environmental Hazards Services, L.L.C

Client Number: 201608

Report Number: 22-01-00495

Project/Test Address: Pamplin Bldg Roof; Dinwiddie, VA

| Lab Sample Number  | Client Sample Number | Layer Type | Lab Gross Description  | Asbestos             | Other Materials  |
|--|----------------------|------------|--|----------------------|--|
| 22-01-00495-005  | D-5                  |            | Pale Yellow Foam; White Pliable; Black Tar-Like Fibrous; Inhomogeneous | NAD                  | 45% Cellulose<br>8% Fibrous Glass<br>10% Synthetic<br>37% Non-Fibrous  |
| 22-01-00495-006  | D-6                  |            | Pale Yellow Foam; White Pliable; Black Tar-Like Fibrous; Inhomogeneous | NAD                  | 40% Cellulose<br>10% Fibrous Glass<br>12% Synthetic<br>38% Non-Fibrous |
| 22-01-00495-007  | D-7                  |            | White Pliable; Yellow Fibrous; Black Tar-Like; Inhomogeneous           | NAD                  | 38% Fibrous Glass<br>14% Synthetic<br>48% Non-Fibrous                  |
| 22-01-00495-008  | D-8                  |            | White Pliable; Black Tar-Like; Inhomogeneous                           | NAD                  | 16% Synthetic<br>84% Non-Fibrous                                       |
| 22-01-00495-009  | D-9                  |            | Black Tar-Like Fibrous; Homogeneous                                    | NAD                  | 24% Synthetic<br>76% Non-Fibrous                                       |
| 22-01-00495-010  | D-10                 |            | White Pliable; Black Tar-Like Fibrous; Inhomogeneous                   | Trace <1% Chrysotile | 14% Synthetic<br>86% Non-Fibrous                                       |
| Total Asbestos: Trace <1%  |                      |            |  |                      |  |
| 3% Chrysotile present in tar-like material under white pliable material. |                      |            |  |                      |  |
| 22-01-00495-011  | D-11                 |            | White Pliable; Silver Paint; Black Tar-Like Fibrous; Inhomogeneous     | NAD                  | 16% Synthetic<br>84% Non-Fibrous                                       |

# Environmental Hazards Services, L.L.C

Client Number: 201608

Report Number: 22-01-00495

Project/Test Address: Pamplin Bldg Roof; Dinwiddie, VA

---

| Lab Sample Number | Client Sample Number | Layer Type | Lab Gross Description | Asbestos | Other Materials |
|-------------------|----------------------|------------|-----------------------|----------|-----------------|
|-------------------|----------------------|------------|-----------------------|----------|-----------------|

---

QC Sample: 48-M12017-2

QC Blank: SRM 1866 Fiberglass

Reporting Limit: 1% Asbestos

Method: EPA Method 600/R-93/116, EPA Method 600/M4-82-020

Analyst: Sami Hosn

Reviewed By Authorized Signatory: Melissa Kanode

Melissa Kanode  
QA/QC Clerk

The condition of the samples analyzed was acceptable upon receipt per laboratory protocol unless otherwise noted on this report. Each distinct component in an inhomogeneous sample was analyzed separately and reported as a composite. Results represent the analysis of samples submitted by the client. Sample location, description, area, volume, etc., was provided by the client. This report cannot be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. This report shall not be reproduced except in full, without the written consent of the Environmental Hazards Service, L.L.C. California Certification #2319 NY ELAP #11714 NVLAP #101882-0 VELAP 460172. All information concerning sampling location, date, and time can be found on Chain-of-Custody. Environmental Hazards Services, L.L.C. does not perform any sample collection.

Environmental Hazards Services, L.L.C. recommends reanalysis by point count (for more accurate quantification) or Transmission Electron Microscopy (TEM), (for enhanced detection capabilities) for materials regulated by EPA NESHAP (National Emission Standards for Hazardous Air Pollutants) and found to contain less than ten percent (<10%) asbestos by polarized light microscopy (PLM). Both services are available for an additional fee.

400 Point Count Analysis, where noted, performed per EPA Method 600/R-93/116 with a Reporting Limit of 0.25%.

\* All California samples analyzed by Polarized Light Microscopy, EPA Method 600/M4-82-020, Dec. 1982.

---

LEGEND: NAD = no asbestos detected

---

# ENVIRONMENTAL HAZARDS SERVICES, LLC

## Asbestos Chain of Custody Form

|  |  |
|--|--|
| Company Name: <u>KBSW</u>  | Account #:                             |
| Company Address: <u>1711 Whitepine Rd</u>  | City/State/Zip: <u>W. Chesterfield</u> |
| Phone: <u>804.350.9358</u>   | Email:                                 |
| Project Name/Test Address: <u>Pamplin Bldg Roof Dinwiddie VA.</u>  |  |
| PO Number: <u>2021-2021</u>  | Collected By: <u>RW Etter</u>          |
| Turn-Around Time: <input checked="" type="checkbox"/> 3 DAY <input type="checkbox"/> 2 DAY <input type="checkbox"/> 1 DAY <input type="checkbox"/> SAME DAY OR WEEKEND - Must Call Ahead |  |

PLM New York Protocol     
  PLM New Jersey Protocol     
  PLM South Carolina Protocol

| LAB NUMBER | Client Sample ID | Homogeneous Area | Positive Stop | Collection Date & Time | BULK |                 |                  |          |     |           | AIR        |                       |                    | COMMENTS |                          |
|------------|------------------|------------------|---------------|------------------------|------|-----------------|------------------|----------|-----|-----------|------------|-----------------------|--------------------|----------|--------------------------|
|            |                  |                  |               |                        | PLM  | Point Count 400 | Point Count 1000 | TEM Bulk | PCM | TEM AHERA | NIOSH 7402 | Time In Total Minutes | Flow Rate In L/Min |          | Volume In Total Liters   |
| 1          | D-1              |                  |               | 11/5/22 10:15          |      |                 |                  |          |     |           |            |                       |                    |          | Field<br>↓<br>Flash<br>↓ |
| 2          | D-2              |                  |               | 10:25                  |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 3          | D-3              |                  |               | 10:40                  |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 4          | D-4              |                  |               | 11:00                  |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 5          | D-5              |                  |               | 12:00                  |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 6          | D-6              |                  |               | 1220                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 7          | D-7              |                  |               | 1240                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 8          | D-8              |                  |               | 1300                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 9          | D-9              |                  |               | 1325                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 10         | D-10             |                  |               | 1340                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 11         | D-11             |                  |               | 1400                   |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 12         |                  |                  |               |                        |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 13         |                  |                  |               |                        |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 14         |                  |                  |               |                        |      |                 |                  |          |     |           |            |                       |                    |          |                          |
| 15         |                  |                  |               |                        |      |                 |                  |          |     |           |            |                       |                    |          |                          |

|                                 |                     |                   |
|---------------------------------|---------------------|-------------------|
| Released By: <u>R. RW Etter</u> | Date: <u>1/5/22</u> | Time: <u>1500</u> |
| Signature: <u>[Signature]</u>   |                     |                   |

LAB USE ONLY - BELOW THIS LINE


Received By: A. Walker

Signature: A. Walker

Date: 01/05/2022 Time: 3:29     AM     PM

Portal Contact Added

22-01-00495



Due Date:  
01/10/2022  
(Monday) 11pm  
E  
S