



ADDENDUM NO. 2

Issue Date: November 20, 2023

Project Name: Sporting Clays Facility Improvements
IRC - 1847

Bid Number: 2024016

Bid Opening Date: **November 29, 2023**

The information and documents contained in this addendum are hereby incorporated in the bid documents. **This addendum must be acknowledged where indicated on the bid form, or the bid may be declared non-responsive.**

Questions and Answers

1. All shooting Stations are shown outside of the silt fence limits. Do we need to include silt fence around each station?
Yes, silt fence will need to be placed around the shooting stations. The Itemized Bid Schedule has been updated with the increased length of Item 104-10-3, Sediment Barrier - Silt Fence to 9,580 Linear Feet (LF).
2. Are there any existing utilities in the area of this trail?
There are no known utilities within the range area. Electric terminates in the parking lot area.
3. What, if any, are the compaction requirements for the shell on the trail?
During the permitting process with FDEP, staff had the County Engineering Division remove statements of compaction to the shell. The shell is not to be compacted once in place.
4. Will all shooting in this area be discontinued for the duration of construction?
Yes, all shooting will be discontinued for the duration of construction.
5. To what extent or depth will we be required to root rake?
Under the FDOT specification for this item, Contractor is to remove and dispose vegetation, obstructions, and fill any holes or voids. The County expects the base material for the paths to start as close to existing ground as possible.

6. Will any proof rolling, or densities be required prior to placing the 12" of shell?
Depending the Contractor's means and methods of removing vegetation and leveling of low spots, proof rolling should be acceptable and no densities will be required.

7. Is there a Geotech report for this project?
No Geotech report has been created for this project.

8. Is builder's risk insurance required for this project?
Builder's risk insurance is not required for this project.

ATTACHMENTS

Revised Itemized Bid Schedule dated 11/20/2023