



**Gilbert Street Sidewalk Installation Project #1235
CTC Grant #GC-29
REQUEST FOR BID (RFB)**

**ADDENDUM I
Answers to Questions
August 17, 2022**

1. What are we to do about all of the roots from the oak trees on the Merriman end of the project? For about 2 blocks there will be a good bit of roots that will need to be removed in order for this sidewalk to be installed where it is supposed to go.

The roots must be properly cut back (smooth cut not torn) and removed to install the sidewalk. The selected contractor must do their best effort in minimizing the amount of root damage.

2. What are we to place behind the sidewalk in the places that it crosses driveways? The elevation difference will only be a couple inches in a few places but what are we to install to safe the drives up?

Please refer to our bid documents, Exhibit C – Sidewalk plans. The sidewalk should match the grade of the driveways per notes under sequence of construction. Driveways are required to be saw cut with a straight, clean, vertical edge at all locations where new sidewalk continues through existing driveways. Demolish and remove existing asphalt or concrete as shown in the plans.