

ARLINGTON
VIRGINIA

Plans For: Rosslyn Highlands Park

Rosslyn Highlands Park Site C

18TH STREET
ARLINGTON, VIRGINIA

Table of Contents:

Sheet No.	Sheet Name
L0.1	COVER SHEET
TP.1	TREE INVENTORY
TP.2	TREE PROTECTION PLAN
TP.3	TREE PROTECTION DETAILS
L1.1	MATERIALS PLAN
L1.2	PAVING PLAN
L1.3	LAYOUT PLAN
L1.4	ADA ACCESS PLAN
L3.1	SECTIONS
L3.2	GENERAL NOTES AND CONSTRUCTION DETAILS
L3.3	CONSTRUCTION DETAILS
L3.3A	CONSTRUCTION DETAILS
L3.4	CONSTRUCTION DETAILS
L3.4A	CONSTRUCTION DETAILS
L3.5	CONSTRUCTION DETAILS
L3.6	CONSTRUCTION DETAILS
L3.7	CONSTRUCTION DETAILS
L3.8	CONSTRUCTION DETAILS
L4.1	PLANTING PLAN
L4.2	PLANT SCHEDULE & CALCULATIONS
L4.3	PLANTING DETAILS
L4.4	SOIL VOLUME PLAN
C1.4	EXISTING CONDITIONS
C1.5	GRADING PLAN
C1.6	UTILITY PLAN
C1.7	EROSION AND SEDIMENT CONTROL PHASE 1
C1.8	EROSION AND SEDIMENT CONTROL PHASE 2
C1.9	EROSION & SEDIMENT PLAN & PPP NOTES
C1.10	EROSION & SEDIMENT PLAN & PPP NOTES
C1.11	BMP COMPUTATIONS
C1.12	BMP COMPUTATIONS
C1.13	BMP COMPUTATIONS
C1.14	BMP COMPUTATIONS
C1.15	BMP COMPUTATIONS
C1.16	BMP COMPUTATIONS
C1.17	DEMOLITION PLAN BY OTHERS
C1.18	GEOTECHNICAL REPORT
E001	ELECTRICAL SITE PLAN
S1.1	STRUCTURAL NOTES, ABBREVIATIONS AND PLAN
S2.1	FOUNDATION SECTIONS

DEPARTMENT OF PARKS AND RECREATION


Park Development Division

2100 Clarendon Boulevard, Suite 414, Arlington, VA 22201
Phone: 703.228.3332 Fax: 703.228.3328 www.arlingtonva.us

LANDSCAPE ARCHITECT/CIVIL ENGINEER

LSG LANDSCAPE ARCHITECTURE

1775 GREENSBORO STATION PL
SUITE 110
TYSONS, VIRGINIA 22102
703-821-2045



christopher consultants

engineering · surveying · land planning
9000 main street (fourth floor) Fairfax, VA 22031-3907
703.273.8520 · fax 703.273.6820



DEPARTMENT OF PARKS AND RECREATION

Parks Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB# 21-DPR-ITB-304
SWM# 20-0120

ROSSLYN HIGHLANDS
ROSSLYN HIGHLANDS PARK SITE C

PERMIT SET
09/08/2020
18TH STREET

ARLINGTON COUNTY

DEPARTMENT OF ENVIRONMENTAL SERVICES
WATER-SEWER CONSTRUCTION REQUIREMENTS (REVISED MARCH 2005)

1. ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES CONSTRUCTION STANDARDS & SPECIFICATIONS (LATEST EDITION) AND SHALL BE APPROVED BY THE DEPARTMENT OF ENVIRONMENTAL SERVICES. UPON PHYSICAL INSPECTION, THE COUNTY RESERVES THE RIGHT TO REJECT THE USE OF ANY MATERIAL FOUND TO BE DEFECTIVE OR NOT CONFORMING TO THE STANDARDS AND SPECIFICATIONS.

2. BEFORE START OF CONSTRUCTION, THE CONTRACTOR SHALL FURNISH THE FOLLOWING INFORMATION AND/OR EVIDENCE OF COMPLIANCE WITH ALL APPLICABLE REGULATIONS AND LAWS, TO THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES:

A. THE NAME AND ADDRESS OF THE CONTRACTOR HIRED TO WORK ON THE PROJECT. THE CONTRACTOR SHALL BE REGISTERED IN THE COMMONWEALTH OF VIRGINIA. SATISFACTORY EVIDENCE SHALL BE FURNISHED OF THE CONTRACTOR'S PRIOR EXPERIENCE AS PRIME CONTRACTOR IN THE CONSTRUCTION OF WATER MAINS AND/OR SANITARY SEWER INSTALLATIONS. FURTHER, THE CONTRACTOR SHALL FURNISH A LETTER WITH A LIST OF MATERIALS AND SUPPLIERS FOR PROPOSED PROJECT.

B. A RIGHT OF WAY PERMIT IS REQUIRED TO WORK IN ARLINGTON COUNTY STREETS. IN INSTANCES OF EXCAVATIONS IN STATE RIGHT OF WAY, THE DATE AND NUMBER OF ALL PERMITS REQUIRED BY THE VIRGINIA DEPARTMENT OF TRANSPORTATION (VDOT) SHALL BE FURNISHED.

C. IF ANY OTHER EASEMENT IS NEEDED, TWO (2) COPIES OF THE DESCRIPTION OF SUCH EASEMENT, AS ACTUALLY RECORDED, SHALL BE FURNISHED, INCLUDING THE PLACE, DATE AND REFERENCE OF SUCH RECORDATION.

D. WRITTEN NOTICE OF TENTATIVE STARTING DATE OF CONSTRUCTION, WHICH SHALL BE A MINIMUM OF ONE (1) WEEK FOLLOWING THE DATE OF NOTICE. IN ADDITION, THE CONTRACTOR SHALL FURNISH THE NAMES AND TELEPHONE NUMBERS OF TWO (2) RESPONSIBLE PERSONS WHO CAN BE CONTACTED IN CASE OF EMERGENCY.

ACTUAL CONSTRUCTION SHALL NOT BEGIN UNTIL THE ABOVE ITEMS HAVE BEEN COMPLETED AND THE ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES APPROVED THE STARTING DATE AND ARRANGEMENTS HAVE BEEN MADE FOR THE REQUIRED INSPECTION SERVICE.

3. ALL CONSTRUCTION SHALL BE ACCOMPLISHED FROM APPROVED PLANS, SPECIFICATIONS AND CUT SHEETS SUBMITTED BY A REGISTERED ENGINEER AND APPROVED BY THE COUNTY. TO AVOID CONSTRUCTION DELAYS ALL NECESSARY TEST HOLE INFORMATION SHALL BE OBTAINED PRIOR TO MOBILIZATION AND CONSTRUCTION PLANS SHALL BE REVISED ACCORDINGLY.

4. NO EXISTING WATER MAINS, FIRE HYDRANTS, OR SANITARY SEWERS MAY BE TAKEN OUT OF SERVICE OR MADE INACCESSIBLE BY THE CONTRACTOR WITHOUT THE PRIOR APPROVAL FROM THE DEPARTMENT OF ENVIRONMENTAL SERVICES.

5. UPON COMPLETION OF CONSTRUCTION, ALL FINAL TESTS, AS REQUIRED, SHALL BE PERFORMED IN THE PRESENCE OF THE COUNTY'S REPRESENTATIVE. WATER AND SEWER SERVICE CONNECTIONS SHALL NOT BE MADE UNTIL THE WATER AND/OR SEWER MAINS AND APPURTENANCES HAVE BEEN APPROVED AND ACCEPTED BY ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES.

6. EXISTING WATER SERVICES MAY BE ALLOWED FOR CONSTRUCTION PURPOSES ONLY FOR WHICH CONTRACTOR SHALL REQUEST TO THE ARLINGTON COUNTY'S UTILITY SERVICES BY CALLING 703-228-3636. PRIOR TO THE FINAL ACCEPTANCE OF THE PROJECT, THE DEVELOPER SHALL REQUEST TO THE UTILITY SERVICES IN WRITING FOR THE DISCONTINUATION OF ALL EXISTING WATER SERVICES. ALSO, THE CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING METER BOXES RELATED TO THE SERVICES BEING DISCONTINUED.

7. THE CONTRACTOR SHALL MAINTAIN BACKFILL FOR UTILITY EXCAVATIONS UNTIL ARLINGTON COUNTY HAS FINALLY ACCEPTED THE PROPOSED WATER AND/OR SEWER MAIN. ALSO, ALL SURFACES OVER THE UTILITY EXCAVATIONS SHALL EITHER BE RESTORED TO THE ORIGINAL CONDITION OR FINISHED AS PER THE PROPOSED DESIGN BEFORE THE ACCEPTANCE OF THE PROJECT. PAVEMENT PATCHING FOR UTILITY CUTS IN THE PUBLIC STREETS SHALL BE PERFORMED IN ACCORDANCE WITH ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES CONSTRUCTION STANDARDS AND SPECIFICATIONS OR AS PER VDOT ROAD AND BRIDGE STANDARDS AND SPECIFICATIONS DEPENDING UPON THE STREET JURISDICTION. PRIOR TO FINAL PAVING, THE CONTRACTOR SHALL ADJUST ALL EXISTING VALVE BOXES AND SANITARY SEWER MANHOLE FRAME AND COVERS AS PER COUNTY STANDARDS, REMOVE ALL ABANDONED SANITARY MANHOLES AND VALVE BOXES OVER THE ABANDONED WATER MAINS, AND COMPLETE ALL NECESSARY WATER MAIN "CUT AND CAPS".

8. UPON COMPLETION, APPROVAL, AND ACCEPTANCE OF WATER AND/OR SEWER MAINS AND APPURTENANCES, THE DEVELOPER'S REGISTERED ENGINEER SHALL SUBMIT TO ARLINGTON COUNTY DEPARTMENT OF ENVIRONMENTAL SERVICES, A SET OF MYLAR TRACINGS INDICATING THE AS-BUILT CONDITIONS AND A SIGNED STATEMENT CONFIRMING THAT THE WORK, AS INDICATED, IS ACCEPTABLE TO THE ENGINEER. SUCH SUBMITTALS SHALL BE MADE BEFORE REQUESTING REDUCTION AND/OR RELEASE OF THE SURETY BOND.

PROJECT DESCRIPTION

THIS PROJECT CONSISTS OF AN APPROXIMATELY 9,000 SQUARE FOOT SITE WITH A CHILDREN'S PLAYGROUND SERVING TWO (2) AGE GROUPS: FROM 2-5 YEARS OLD AND FROM 5-12 YEARS OLD, A TERRACED SEATING AREA, URBAN BIORETENTION, TREE CANOPY REQUIREMENT TREE PLANTING, AND A PORTION OF THE 18TH STREET STREETSCAPE. MOST OF THE PROJECT WILL BE CONSTRUCTED ABOVE THE QUEENS COURT PARKING GARAGE STRUCTURE AND ADJACENT TO THE QUEENS COURT MULTI-FAMILY HOUSING BUILDING.

ARLINGTON COUNTY

DEPARTMENT OF ENVIRONMENTAL SERVICES

NOTES

1. ALL CONSTRUCTION SHALL CONFORM TO THE CURRENT ARLINGTON COUNTY DES STANDARDS AND SPECIFICATIONS.

2. THE CONTRACTOR SHALL REMOVE AND REPLACE, TO THE CURRENT ARLINGTON COUNTY DES STANDARDS AND SPECIFICATIONS, ANY EXISTING ENTRANCES, CURB AND GUTTER OR SIDEWALK ALONG THE FRONTAGE OF THIS SITE IN POOR CONDITION, OR DAMAGED DURING CONSTRUCTION.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND CLOSING, TO ARLINGTON COUNTY STANDARDS, ANY EXISTING ENTRANCES NOT BEING USED IN CONJUNCTION WITH THIS DEVELOPMENT.

4. THE CONTRACTOR SHALL OBTAIN ARLINGTON COUNTY PERMITS FOR ALL OF THIS SITE.

5. THERE MAY BE UNDERGROUND CONDUIT, CABLES AND TRAFFIC DETECTION DEVICES IN THIS AREA. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING ANY TRAFFIC CONTROLS THAT ARE DISTURBED DURING CONSTRUCTION. NOTIFY THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU AT (703) 228-3575, 24 HOURS PRIOR TO STARTING WORK.

6. THE CONTRACTOR SHALL NOT DISTURB OR REMOVE ANY TRAFFIC CONTROL SIGNS, PARKING METERS OR ANY OTHER TRAFFIC CONTROL DEVICE WITHOUT PRIOR PERMISSION FROM THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU. CONTACT TRANSPORTATION ENGINEERING AT (703) 228-3575.

7. THE CONTRACTOR SHALL OBTAIN A PERMIT FROM THE TRANSPORTATION ENGINEERING & OPERATIONS BUREAU PRIOR TO PLACING ANY OBSTRUCTION WITHIN THE PUBLIC RIGHT OF WAY, OR ON SIDEWALKS ALONG THE FRONTAGE OF THIS DEVELOPMENT.

8. THE CONTRACTOR SHALL OBTAIN PERMITS FROM THE INSPECTION SERVICES DIVISION PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION OF ON-SITE FACILITIES. FOR INFORMATION AND PERMIT REQUIREMENTS TELEPHONE (703) 228-3800.

UTILITY MARKING REQUIREMENTS:

9. THE CONTRACTOR SHALL NOTIFY "MISS UTILITY" AT 811, 72 HOURS PRIOR TO THE START OF ANY EXCAVATION OR CONSTRUCTION, FOR THE MARKING OF UNDERGROUND UTILITIES IN THE RIGHT-OF-WAY.

10. UTILITY LOCATIONS SHOWN ON THIS PLAN ARE APPROXIMATE LOCATIONS DETERMINED FROM VISIBLE EVIDENCE AND AVAILABLE RECORDS. ADDITIONAL UNDERGROUND UTILITY LINES MAY BE PRESENT THAT ARE NOT SHOWN. THE CONTRACTOR SHALL LOCATE AND PRESERVE ALL EXISTING UTILITIES.

HORIZONTAL DATUM:

THE SITE SHOWN HEREON IS REFERENCED TO THE VIRGINIA COORDINATE SYSTEM OF 1983 AS COMPUTED FROM A FIELD RUN BOUNDARY AND HORIZONTAL CONTROL SURVEY.


VERTICAL DATUM:

THE SITE SHOWN HEREON IS REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 AS COMPUTED FROM A FIELD RUN VERTICAL CONTROL SURVEY.









VICINITY MAP
SCALE 1" = 250'

Approvals	Date
Park Development Division Chief	
Design Manager	
Sheet	L0.1



LEGEND

-  EXISTING TREE TO BE PRESERVED
-  EXISTING TREE TO BE REMOVED
-  EXISTING TREE CRITICAL ROOT ZONE
-  SILT FENCE
-  LIMITS OF DISTURBANCE
-  TREE PROTECTION FENCE

TREE INVENTORY & REPLACEMENT CALCULATIONS
Queens Court, Arlington, VA
Date of site visit: December 4, 2015
Certified Arborist: Gregg D. Eberly (MA-4616A)

Tree #	Botanic Name	Common Name	Caliper (DBH)	Condition Rating	Species Rating	Total Rating	Replacement(s) Required	Preserve/Remove
1	Quercus phellos	Willow Oak	14	0.80	0.70	7.84	-	Preserve
2	Quercus phellos	Willow Oak	14	0.80	0.70	7.84	-	Preserve
3	Quercus phellos	Willow Oak	12	0.80	0.70	6.72	-	Preserve
4	Alnus incana	Tree of Heaven	8	0.50	0.40	1.60	-	Preserve
5	Prunus serotina	Black Cherry	12	0.80	0.50	4.80	N/A (Note #5)	Remove
6	Alnus incana	Tree of Heaven	8	0.50	0.40	1.60	N/A (Note #6)	Remove
7	Picea canadensis	Norway Spruce	12	0.60	0.70	5.04	N/A (Note #6)	Remove
8	Fraxinus pennsylvanica	Green Ash	12	0.70	0.40	3.36	-	Preserve
9	Fraxinus pennsylvanica	Green Ash	12	0.70	0.40	3.36	-	Preserve
10	Fraxinus pennsylvanica	Green Ash	12	0.70	0.40	3.36	-	Preserve
11	Fraxinus pennsylvanica	Green Ash	12	0.70	0.40	3.36	-	Preserve
12	Fraxinus pennsylvanica	Green Ash	12	0.70	0.40	3.36	-	Preserve
13	Platanus x acerifolia	London Plane	9	0.80	0.70	5.04	-	Preserve
14	Platanus x acerifolia	London Plane	11	0.80	0.70	6.16	-	Preserve
15	Platanus x acerifolia	London Plane	11	0.80	0.70	6.16	-	Preserve
16	Platanus x acerifolia	London Plane	11	0.80	0.70	6.16	-	Preserve
17	Platanus x acerifolia	London Plane	16	0.80	0.70	8.96	-	Preserve
18	Platanus x acerifolia	London Plane	14	0.80	0.70	7.84	-	Preserve
19	Cedrus deodara	Deodar Cedar	18	0.70	0.60	7.56	-	Preserve
20	Platanus x acerifolia	London Plane	14	0.80	0.70	7.84	-	Preserve
21	Platanus x acerifolia	London Plane	15	0.80	0.70	8.40	-	Preserve
22	Acer rubrum	Red Maple	24	0.60	0.70	10.08	3	Remove
23	Taxus canadensis	Eastern Hemlock	11	0.70	0.60	4.62	1	Remove
24	Picea canadensis	Norway Spruce	9	0.50	0.70	3.15	1	Remove
25	Taxus canadensis	Eastern Hemlock	20	0.70	0.60	8.40	2	Remove
26	Taxus canadensis	Eastern Hemlock	18	0.70	0.60	7.56	2	Remove
27	Prunus serotina	Black Cherry	16	0.70	0.50	5.60	2	Remove
28	Taxus canadensis	Eastern Hemlock	16	0.80	0.60	7.68	2	Remove
29	Cedrus deodara	Deodar Cedar	32	0.70	0.60	13.44	3	Remove
30	Ilex opaca	American Holly	4	0.50	0.70	1.40	1	Remove
31	Picea canadensis	Norway Spruce	16	0.60	0.70	6.72	N/A (Note #5)	Remove
32	Chamaecyparis pisifera	Shore Pine	12	0.70	0.70	5.88	N/A (Note #5)	Remove
33	Chamaecyparis pisifera	Shore Pine	8	0.70	0.70	4.48	N/A (Note #5)	Remove
34	Comus florida	Flowering Dogwood	5	0.50	0.60	1.50	N/A (Note #6)	Remove
35	Betula nigra	River Birch	30	0.70	0.70	14.70	3	Remove
36	Betula nigra	River Birch	30	0.70	0.70	14.70	3	Remove
37	Betula nigra	River Birch	25	0.70	0.70	11.25	3	Remove
38	Juglans nigra	Black Walnut	15	0.40	0.70	4.20	1	Remove
39	Comus florida	Flowering Dogwood	6	DEAD	0.60	0.00	-	Preserve
40	Acer rubrum	Red Maple	8	0.70	0.70	3.92	1	Remove
41	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
42	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
43	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
44	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
45	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
46	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
47	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
48	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
49	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
50	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
51	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
52	Ulmus americana	American Elm	20	0.60	0.60	7.20	2	Remove
53	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
54	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
55	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
56	Juniperus virginiana	Eastern Redcedar	3	0.50	0.70	1.05	1	Remove
57	Ulmus americana	American Elm	8	0.60	0.60	2.88	1	Remove
58	Ulmus americana	American Elm	18	0.60	0.60	6.48	2	Remove
59	Picea canadensis	Norway Spruce	14	0.70	0.60	5.88	-	Preserve
60	Picea canadensis	Norway Spruce	10	0.70	0.50	3.50	-	Preserve
61	Ulmus americana	American Elm	24	0.40	0.60	5.76	-	Preserve

- Notes:**
- Condition Rating based on formula provided by the *Guide for Plant Appraisal* published by the ISA.
 - Species Rating based on formula provided by the *Guide for Plant Appraisal* published by the ISA.
 - All trees with a minimum 3" D.B.H. were inventoried and rated.
 - The developer agrees to make a contribution to the County's Tree Canopy Fund of at least \$2,400 per tree, or a greater amount if the contribution policy changes at the time of payment, for every tree that cannot be planted onsite. The contribution shall be required when tree planting requirements cannot be met on the property. The payment shall be delivered to the Department of Parks and Recreation Office prior to the issuance of the Excavation/Streeting and Shoring Permit.
 - Per Site Plan Conditions the applicant shall be responsible for replacement of all existing trees on their site with the exception of any trees in the 9,000 square foot area subject to a public park easement. No replacements are required for the removal of trees T5, T6, T7, T8, T9, T10, T11, T12, T13, T14, T15, T16, T17, T18, T19, T20, T21, T22, T23, T24, T25, T26, T27, T28, T29, T30, T31, T32, T33, T34, T35, T36, T37, T38, T39, T40, T41, T42, T43, T44, T45, T46, T47, T48, T49, T50, T51, T52, T53, T54, T55, T56, T57, T58, T59, T60, T61.
 - Off-site tree removal consent letter from adjacent property owner is provided on sheet #72.00.

TOTAL: 46

- NOTE:**
- FOR INFORMATION ONLY. REFER TO APPROVED SITE PLAN #444 QUEENS COURT.
 - NOT IN CONTRACT.

1 TREE INVENTORY
NTS

Bowman CONSULTING
Bowman Consulting Group, Ltd. Phone: (703) 464-1000
14020 Thunderbolt Place, Suite 300 Fax: (703) 481-9720
Chantilly, Virginia 20151
www.bowmanconsulting.com



ARLINGTON COUNTY, VIRGINIA
DEPARTMENT OF ENVIRONMENTAL SERVICES
TREE PRESERVATION PLAN
QUEENS COURT
CIVIL ENGINEERING PLAN
SITE PLAN #444
1615 18TH STREET NORTH
ARLINGTON, VIRGINIA 22209
ARLINGTON COUNTY, VIRGINIA

SCALE: 1"=25' SHEET T1.00

ARLINGTON VIRGINIA
DEPARTMENT OF PARKS AND RECREATION
Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET
ARLINGTON, VIRGINIA

Sheet Title
TREE INVENTORY

Approval Date
LUKE VANBELLEGHEM 7.9.2018
Design Supervisor

Revisions Date
LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV
Filename:
Plotted: Sep. 9, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal
COMMONWEALTH OF VIRGINIA
JAMES HUI FAN
Lic. No. 001316
4/15/2020
LANDSCAPE ARCHITECT


Sheet **TP.1**

Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 9, 20
Scale: AS SHOWN
Date: JULY 15, 2019




LEGEND

- TPF — TPF —
- ④ TREE PROTECTION BARRIERS FOR RESTRICTED SPACE AND TREE PITS, TYP.

NOTE:
I. TREE PROTECTION NOT NECESSARY IF TREES NOT YET INSTALLED.

TREE PRESERVATION

1. BEFORE ANY GRADING, DEMOLITION, OR OTHER DISTURBANCE, INCLUDING TREE REMOVAL, A PRECONSTRUCTION MEETING SHALL BE HELD WITH AN ARLINGTON COUNTY URBAN FORESTER. CHANGES TO THE PLAN, BASED ON FIELD CONDITIONS, MAY BE REQUESTED BY THE URBAN FORESTER AT THE TIME OF THE PRECONSTRUCTION MEETING.
2. TREE PROTECTION SHALL BE INSTALLED PER PLAN, WITH ANY CHANGES REQUESTED AT THE PRECONSTRUCTION MEETING, AND INSPECTED BY AN ARLINGTON COUNTY URBAN FORESTER. EROSION AND SEDIMENT CONTROLS ARE INSPECTED BY THE DEPARTMENT OF ENVIRONMENTAL SERVICES.
3. REMOVAL OF TREES, NOTED FOR REMOVAL ON THE PLAN, INSIDE A TREE PRESERVATION AREA SHALL BE PERFORMED, BY HAND, WITHOUT GROUND DISTURBANCE, OR DISTURBANCE TO NEARBY PRESERVED TREES. TREES IN THESE AREAS SHALL BE CUT FLUSH TO THE GROUND, WITHOUT STUMP GRINDING.
4. NO CHANGES SHALL BE MADE TO TREE PRESERVATION OR PROPOSED LANDSCAPE UNLESS DIRECTED BY AN ARLINGTON COUNTY URBAN FORESTER.
5. FOLLOW ANSI STANDARDS WHEN PRUNING TREES. ANY PRUNING BEYOND 5% OF THE CANOPY SHALL BE COMMUNICATED AND APPROVED TO THE URBAN FORESTER.
6. DO NOT REMOVE TREES ON OTHER PROPERTIES, OR RIGHTS-OF-WAY, WITHOUT WRITTEN PERMISSION OF THE OWNER.
7. TREE PROTECTION AREAS SHALL HAVE ALL NON-NATIVE INVASIVE VINES REMOVED AT THE END OF THE PROJECT. WHERE DEEMED NECESSARY BY THE COUNTY URBAN FORESTER TO ENSURE TREE SURVIVAL, THE PROTECTION AREA SHALL BE COVERED WITH SHREDDED HARDWOOD MULCH, OR OTHER ORGANIC MULCH AS APPROVED BY THE COUNTY URBAN FORESTER.
8. AT THE END OF THE PROJECT, PRESERVED AND PLANTED TREES MUST BE INSPECTED AND APPROVED BY AN ARLINGTON COUNTY URBAN FORESTER.



① **TREE PROTECTION PLAN**
1/8"=1'-0"

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

**ROSSLYN
HIGHLANDS
PARK**

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

**TREE
PROTECTION
DETAILS**

Approval Date

LUKE VANBELLEGHEM 7.9.2018
Design Supervisor

Revisions Date

LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: CF

Drawn: SM, LV, KN

Checked: CF, LV


Filename:

Plotted: Sep. 9, 20



Scale: AS SHOWN

Date: JULY 15, 2019

Seal



Sheet **TP.3**





ARLINGTON VIRGINIA

DEPARTMENT OF PARKS AND RECREATION

Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

MATERIALS PLAN

Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018


Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20
ADDENDUM 1	9/25/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 24, 20

Scale: AS SHOWN
Date: JULY 15, 2019

Seal



Sheet L1.1

PAVING LEGEND

- (P1) CONCRETE JOINTING EXPANSION JOINT
- (P2) CONCRETE PAVING
- (P3) CONCRETE JOINTING CONTROL JOINT
- (P4) CONTINUOUS SOIL PANEL
- (P5) POURED IN PLACE RUBBER

WALL LEGEND

- (W1) PLANTER WALL
- (W2) SEAT WALL
- (W3) SEAT STEPS
- (W4) SIGN WALL
- (W5) FLUSH CURB WITH METAL PICKET FENCE
- (W6) BIORETENTION EDGE WALL
- (W7) TREE PIT FENCE

FURNITURE LEGEND

- (F1) TRASH/RECYCLING RECEPTACLES
- (F2) BENCH


LIGHTING LEGEND

- (L1) WALL LIGHT ADD ALTERNATE 1
- (L2) STREET LIGHT

SIGN LEGEND

- (S1) PARK ENTRANCE SIGN
- (S2) PARK RULES SIGN

NOTE:
BASE BID SHALL NOT INCLUDE THE L1 WALL LIGHT 4/L3.8 OR GEOFOAM FOAM









LAYOUT NOTES:

- ON-SITE VERIFICATION OF ALL DIMENSIONS AND CONDITIONS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. NOTED DIMENSIONS TAKE PRECEDENCE OVER SCALE, LARGER SCALE OVER SMALLER SCALE, ADDENDA AND CLARIFICATIONS OVER PREVIOUS DOCUMENTS.
- CONTRACTOR TO LAY OUT HARDSCAPE ELEMENTS AND VERIFY LAYOUT WITH PROJECT OFFICER PRIOR TO CONSTRUCTION.
- ANY DISCREPANCIES OR CONFLICTS WITH EXISTING CONDITIONS OR OTHER DRAWINGS SHALL BE REPORTED TO THE PROJECT OFFICER IMMEDIATELY FOR PROPER CLARIFICATION OR ADJUSTMENT.
- WHERE DIMENSIONS ARE CALLED AS "EQUAL," SPACE REFERENCED ITEMS EQUALLY, MEASURED TO THEIR CENTER LINES.
- MEASUREMENTS ARE TO FACE OF BUILDING, WALL OR FIXED SITE IMPROVEMENT. DIMENSIONS TO CENTER LINES IS AS INDICATED.
- INSTALL INTERSECTING ELEMENTS AT 90° ANGLES TO EACH OTHER UNLESS OTHERWISE NOTED.
- PROVIDE EXPANSION JOINTS WHERE CONCRETE FLATWORK MEETS VERTICAL STRUCTURES SUCH AS WALLS, CURBS, STEPS AND BUILDING ELEMENTS.
- NEW WORK SHALL MEET AND MATCH ALIGNMENT OF EXISTING FEATURES AND FINISHED GRADES AT LIMITS OF WORK AND AT EXISTING PAVEMENT OR OTHER FACILITIES TO REMAIN.
- CONTRACTOR SHALL VERIFY THE CORRECT LOCATION OF ALL UTILITIES AND EXISTING TREES TO REMAIN IN THE FIELD PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL STAKE ALIGNMENT FOR ALL WALLS, CURBS, BOULDERS, SIGNS, FURNISHINGS, COURTS, PATHS, HARDSCAPE, BENCHES, TABLES, TRASH RECEPTACLES, RECYCLING RECEPTACLES, LIGHT POLES, STORMWATER MANAGEMENT FACILITIES, MANHOLES AND UTILITY STATIONS FOR PROJECT OFFICER'S APPROVAL PRIOR TO INSTALLATION.
- FOR LAYOUT, ALL ANGLES ARE 90° UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONS SHALL PREVAIL. DO NOT SCALE FROM THE PLAN.
- MINOR ADJUSTMENTS IN HORIZONTAL LAYOUT AND TOP OF WALL ELEVATIONS SHALL NOT RESULT IN AN INCREASE IN PRICE BY THE CONTRACTOR.
- CONTRACTOR SHALL STAKE-OUT THE LOCATIONS OF BENCHES, AND TRASH RECEPTACLES FOR REVIEW AND APPROVAL BY LANDSCAPE ARCHITECT PRIOR TO CONTRACTOR INSTALLATION.

JOINT LAYOUT NOTES:

- CONTRACTOR SHALL CLEARLY MARK JOINT LOCATIONS IN THE FIELD FOR REVIEW AND APPROVAL BY PROJECT OFFICER. THIS TEMPORARY MARKING SHALL OCCUR, AT MINIMUM, 12 HOURS PRIOR TO THE POURING OF CONCRETE FLATWORK.
- WHEN THE PROJECT OFFICER IS ON-SITE TO INSPECT THE PROPOSED JOINT LOCATIONS THE CONTRACTOR SHALL ALSO PRESENT THEIR PROPOSED JOINTING METHODOLOGY AND TOOL(S) FOR REVIEW AND APPROVAL BY PROJECT OFFICER. THIS IS TO ENSURE THE ACCEPTABLE QUALITY AND ADEQUATE DEPTH OF THE JOINTS.
- EXPANSION JOINTS ARE NOT SHOWN ON THIS SHEET IF THEY ARE SPECIFIED ON THE CONSTRUCTION DETAIL FOR THE PARTICULAR STRUCTURE. FOR EXAMPLE, EJS ARE NOT SHOWN HEREON IMMEDIATELY ADJACENT TO WALLS BECAUSE THE EJS ARE SPECIFIED ON THE WALL NOTED. THIS IS FOR GRAPHICAL CLARITY AND TO AVOID REPETITIVE INFORMATION ACROSS THE CONSTRUCTION DOCUMENT SET. CONTRACTOR IS RESPONSIBLE FOR IMPLEMENTING JOINTS AS SHOWN ON THIS SHEET AND APPLICABLE DETAILS.
- INSTALL JOINTS PER DETAIL.



NOTE:
BASE BID SHALL NOT INCLUDE THE L2 WALL LIGHT 4/L3.8 OR GEOFOAM FOAM

ITB# 21-DPR-ITB-304
SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET
ARLINGTON, VIRGINIA

Sheet Title
LAYOUT PLAN



Approval	Date
LUKE VANBELLEGHEM	7.9.2018
Design Supervisor	

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20
ADDENDUM 1	9/25/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV
Filename:
Plotted: Sep. 24, 20
Scale: AS SHOWN
Date: JULY 15, 2019



Sheet **L1.3**



PAVING LEGEND

- 2 CONCRETE JOINTING EXPANSION JOINT (L3.2)
- 3 CONCRETE PAVING (L3.2)
- 2 CONCRETE JOINTING CONTROL JOINT (L3.2)
- 4 CONTINUOUS SOIL PANEL (L3.2)
- 5 POURED IN PLACE RUBBER (L3.2)

WALL LEGEND

- 1 PLANTER WALL (L3.3)
- 2 SEAT WALL (L3.3)
- 3 SEAT STEPS (L3.3)
- 4 SIGN WALL (L3.3)
- 2 FLUSH CURB WITH METAL PICKET FENCE (L3.3A)
- 3 BIORETENTION EDGE WALL (L3.3A)
- 3 TREE PIT FENCE (L3.4)

FURNITURE LEGEND

- 18.2 TRASH/RECYCLING RECEPTACLES (L3.5)
- 3 BENCH (L3.5)

LIGHTING LEGEND

- 4 WALL LIGHT ADD ALTERNATE 1 (L3.8)
- 2 STREET LIGHT (L3.8)

SIGN LEGEND

- 4 PARK ENTRANCE SIGN (L3.4)
- 5 PARK RULES SIGN (L3.4)


ADA LEGEND

- ADA ACCESSIBLE PARK ENTRY POINT
- ADA ACCESSIBLE SEATING
- ADA ACCESSIBLE ROUTE
- END OF ADA ACCESSIBLE ROUTE


ADA NOTES

1. ADA COMPLIANCE NOTE: THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL ELEMENTS ARE CONSTRUCTED IN ACCORDANCE WITH THE LATEST VERSION OF ADA STANDARDS FOR ACCESSIBLE DESIGN, BY THE DEPARTMENT OF JUSTICE. SHOULD ANY QUESTIONS ARISE DURING CONSTRUCTION, INSTALLATION, OR IF ANY CLARIFICATIONS ARE NEEDED, THE CONTRACTOR SHALL CONTACT THE CONSTRUCTION MANAGER.
2. SEE GRADING PLANS FOR SPOT ELEVATIONS AND GENERAL NOTES.

NOTE:
BASE BID SHALL NOT INCLUDE THE L2 WALL LIGHT
4/L3.8 OR GEOFOAM FOAM



KEY



PAVING LEGEND

- (P1) (3/ L3.2) CONCRETE PAVING
- (P2) (4/ L3.2) CONTINUOUS SOIL PANEL
- (P3) (5/ L3.2) POURED IN PLACE RUBBER


WALL LEGEND

- (W1) (1/ L3.3) PLANTER WALL
- (W2) (2/ L3.3) SEAT WALL
- (W3) (3/ L3.3) SEAT STEPS
- (W4) (4/ L3.3) SIGN WALL
- (W5) (2/ L3.3A) FLUSH CURB WITH METAL PICKET FENCE
- (W6) (3/ L3.3A) BIORETENTION EDGE WALL

LIGHTING LEGEND



- (L1) (1/ L3.8) STREET LIGHT
- (L2) (4/ L3.8) WALL LIGHT ADD ALTERNATE 1

NOTE:
BASE BID SHALL NOT INCLUDE THE L2 WALL LIGHT 4/L3.8 OR GEOFOAM FOAM




SECTION A

1/4"=1'



SECTION B

1/4"=1'




Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20
ADDENDUM 1	9/25/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV



Filename:
Plotted: Sep. 24, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal



1. PROVIDE MOCKUPS, SHOP DRAWINGS, PRODUCT DATA, AND FINISH SAMPLES FOR ARCHITECT'S REVIEW AND APPROVAL PRIOR TO FABRICATION/CONSTRUCTION.
2. ALL METAL IS HOT-DIPPED GALVANIZED STEEL UNLESS OTHERWISE INDICATED.
3. ALL METAL-TO-METAL CONNECTIONS ARE FULL-LENGTH WELDS UNLESS OTHERWISE INDICATED.
4. GRIND SMOOTH ALL WELDS, REMOVE ALL BURRS, AND PRIME ALL BARE SPOTS PRIOR TO FINISHING.
5. WELDING AND GRINDING ARE PROHIBITED FOLLOWING SHOP FINISHING.

1 NOTES




PAVEMENT THICKNESS	DOWEL BAR SIZE
6" TO 8"	1" x 18" @ 12"
9" TO 11"	1 1/4" x 18" @ 12"
12" & GREATER	1 1/2" x 18" @ 12"

THICKENED EDGE DETAIL
(NOT NEEDED FOR TYPE A JOINTS WIDTH $d \geq 10"$)
(NOT NEEDED FOR TYPE B JOINTS WIDTH $d \geq 9"$)

- NOTES:**
1. WHERE REQUIRED AT TRANSVERSE JOINTS, DOWEL BARS SHALL BE SIZED AS SHOWN IN THE TABLE, SMOOTH ROUND GRADE 60 OR BETTER WITH ENDS WRAPPED IN TAR PAPER.
 2. TRANSVERSE JOINT SPACE SHALL NOT EXCEED SPACING INDICATED IN PLANS. THE AREA OF THE PAVEMENT PANEL SHALL NOT EXCEED 225 SQUARE FEET.
 3. JOINT OFFSETS AT RADIUS POINTS SHOULD BE AT LEAST 1'-6" LONG.
 4. JOINT INTERSECTION ANGLES OF LESS THAN 60 DEGREES SHALL BE USED.
 5. WHEN A JOINT IS CLOSER THAN 1'-0" TO A CASTING, THEN A MINOR ADJUSTMENT IN THE JOINT LOCATION SHOULD BE MADE BY SKEWING OR SHIFTING THE JOINT ALIGNMENT TO MEET THE CASTING AT 90° OR NORMAL TO THE CASTING.
 6. DOWEL BARS SHALL NOT BE PLACED WITHIN 1'-0" OF THE EDGE OF PAVEMENT OR A PARALLEL JOINT.

2 CONCRETE PAVING JOINT DETAILS

NTS ARLINGTON COUNTY DETAIL





4A THICKENED SLAB AT TREE PIT

1"=1'-0"

4B THICKENED SLAB AT SOIL PANEL

1"=1'-0"




- NOTES:**
1. TRENCH DRAIN GRATE DOES NOT CONTINUE OVER CATCH BASIN
 2. PROVIDE SHOP DRAWINGS FOR REVIEW BY ARCHITECT

7 TRENCH DRAIN

1"=1'-0"

7A WUNDERCOVER


NTS



12"x12", STAINLESS STEEL, CONCRETE TYPE WITH CORNER LUGS.

5 POURED IN PLACE PLAY SURFACE (PIP)

1"=1'-0"




- NOTES:**
1. SEE PLANS FOR EXACT EDGE CONDITIONS.
 2. INSTALL SO THAT NO TRIPPING HAZARDS OR IMPEDIMENTS TO PERSONS WITH DISABILITIES EXIST WHEN COMPLETED.

8 PIP EDGE CONDITION AT NEW CONCRETE

1"=1'-0"

6 FLUSH CURB

1"=1'-0"




- NOTES:**
1. SEE PLANS FOR EXACT EDGE CONDITIONS.
 2. INSTALL SO THAT NO TRIPPING HAZARDS OR IMPEDIMENTS TO PERSONS WITH DISABILITIES EXIST WHEN COMPLETED.

9 PIP EDGE CONDITION AT SITE WALLS

1"=1'-0"

3 CONCRETE PAVEMENT (4" THICKNESS)

1"=1'-0"




NOTES:

1. PROVIDE EXPANSION AND CONTROL JOINTS AS SHOWN ON THE PLANS, OR EXPANSION JOINTS EVERY 20' O.C. AND CONTROL JOINTS EVERY 5' O.C. IF NOT SHOWN.
2. ALL EXPANSION JOINTS SHALL BE FINISHED WITH SEALANT. COLOR TO MATCH COLOR OF CONCRETE PAVEMENT.
3. FINISH IN ACCORDANCE WITH VDOT 404.07, SIDEWALK FINISH, WITH CLEAR CURING COMPOUND.
4. DISTURBED LAWN AREAS ADJACENT TO CONCRETE PAVEMENT SHALL BE BACKFILLED AND SEEDED AS DESCRIBED IN SPECIFICATIONS.
5. REFER TO CONCRETE DETAILS, THIS SHEET FOR ADDITIONAL CONDITIONS AND REQUIREMENTS, AS NEEDED.

4 CONTINUOUS SOIL PANEL

3/4"=1'




NOTES:

1. #4 @ 12" OC IN 6' LENGTHS ACROSS AMENDED SOIL PANEL
2. PROVIDE CONTINUOUS BAR SUPPORTS @ 3' +/- OC
3. 6x6 #2x#2 WWM CONTINUOUS WITHIN 4" CONCRETE SLAB
4. SIDEWALK SLAB SHALL BE AMENDED AS REQUIRED AND SHOWN ON APPROVED PLANS.

NOTES:

1. POURED-IN-PLACE RUBBER CUSHION LAYER SHALL BE, AT A MINIMUM, AN ADEQUATE THICKNESS FOR THE FALL HEIGHT OF THE PLAY EQUIPMENT IN THE AREA, AS PER THE MANUFACTURER'S RECOMMENDATIONS.
2. IF TRANSITIONS BETWEEN DEPTHS OF POURED-IN-PLACE ARE NEEDED, ACCOMMODATE THE TRANSITIONS BELOW GRADE SO THAT FINISHED GRADE IS ALWAYS FLUSH.
3. WEARING LAYER COLORS SHALL BE SELECTED BY LANDSCAPE ARCHITECT.
4. CONCRETE BASE USED UNDER POURED-IN-PLACE RUBBER SURFACE SHALL HAVE 4" x 4" WELDED WIRE MESH REINFORCEMENT IN THE CONCRETE.



- NOTES:**
1. SEE PLANS FOR EXACT EDGE CONDITIONS.
 2. INSTALL SO THAT NO TRIPPING HAZARDS OR IMPEDIMENTS TO PERSONS WITH DISABILITIES EXIST WHEN COMPLETED.

Approval	Date
LUKE VANBELLEGHEM	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 8, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal



Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20
ADDENDUM 1	9/25/20


Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 28, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal




Sheet **L3.3**



1 WI - PLANTER WALL


1/2"=1'



2 W2 - SEAT WALL

1/2"=1'


ELEVATION



3 W3 - SEAT STEPS

1/2"=1'

SECTION



4 W4 - SIGN WALL

3/4"=1'

ROSSLYN HIGHLANDS PARK

Playground

POWDER COATED METAL
BOX LETTERS
COLOR TBD


POWDER COATED METAL
PLINTH

1/4" POWDER COATED METAL
LETTERS, PIN MOUNTED
COLOR TBD

RUBBED FINISH

FINISHED GRADE

NOTE:
1. COLOR OF BOX AND PIN MOUNTED LETTERS
TO BE APPROVED BY LANDSCAPE ARCHITECT.



MANUFACTURER: FITZGERALD FORMLINERS
PRODUCT: I6938 RANDOM PLANK
PATTERN TO BE APPLIED HORIZONTALLY
OR APPROVED EQUAL

7 FORM LINER FINISH


NTS

6 NOT USED

1"=1'-0"

5 NOT USED

NTS



ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

**ROSSLYN
HIGHLANDS
PARK**

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

**CONSTRUCTION
DETAILS**

Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20


Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 8, 20
Scale: AS SHOWN
Date: JULY 15, 2019


Seal




Sheet **L3.3A**




1 WALK AND BIORETENTION SECTION
3/4" = 1'




2 W5 - 9" FLUSH CURB WITH METAL PICKET FENCE
1" = 1'-0"




3 W6 - BIORETENTION EDGE WALL
1" = 1'-0"




4 CONTINUOUS SOIL PANEL AT BIORETENTION TREE PIT
3/4" = 1'




1 METAL PICKET FENCE
3/4"=1'




2 METAL PICKET FENCE-GATE
3/4"=1'




2A GATE STOP
1 1/2"=1'




3 TREE PIT FENCE
1" = 1'-0"




3A TREE PIT FENCE PLAN
1/2" = 1'-0"




4 PARK ENTRY SIGN
NTS



4A PARK SIGN MOUNTING
NTS



5 PARK RULES SIGN
NTS



5A PARK RULES SIGN FOOTING
1" = 1'-0"

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
**ROSSLYN
HIGHLANDS
PARK**
BID SET

18TH STREET
ARLINGTON, VIRGINIA

Sheet Title
**CONSTRUCTION
DETAILS**


Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20
ADDENDUM 1	9/25/20


Designed: cf
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 25, 20
Date:

Scale: AS SHOWN
Date: JULY 15, 2019




Sheet
L3.4A




NOTES:

1. DESIGN INTENT ONLY. CONTRACTOR TO PROVIDE SHOP DRAWINGS.
2. ALL METAL BRIDGE PARTS SHALL BE STEEL.
3. WELD ALL CONNECTIONS.
4. PAINT ALL METAL BRIDGE PARTS BLACK PER SPECIFICATIONS EXCEPT FOR BAR GRATING DECK.


1 BAR GRATING BRIDGE
3/4"=1'-0"



2 BRIDGE RAILING
3/4"=1'-0"



3 BAR GRATING BRIDGE SECTION
3/4"=1'-0"



4 BAR GRATING BRIDGE FOOTING
3/4"=1'-0"

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA

Sheet Title
CONSTRUCTION DETAILS


Approval Date
 LUKE VANBELLEGHEM 7.9.2018
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20


Designed: CF
 Drawn: SM, LV, KN
 Checked: CF, LV

Filename:
 Plotted: Sep. 3, 20
 Date: JULY 15, 2019


Scale: AS SHOWN
 Date: JULY 15, 2019




Sheet **L3.5**




1 FI - TRASH RECEPTACLE
 3/4"=1'



2 FI - RECYCLING RECEPTACLE
 3/4"=1'



3 F2 - 1964 WORLD'S FAIR BENCH
 3/4"=1'



4 1964 WORLD'S FAIR BENCH ENLARGEMENTS
 3"=1'

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

**ROSSLYN
HIGHLANDS
PARK**

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

**CONSTRUCTION
DETAILS**

Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018

Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV


Filename:
Plotted: Sep. 3, 20

Scale: AS SHOWN
Date: JULY 15, 2019

Seal



Sheet **L3.6**




1 DNA TOWER




2 EVOS STRUCTURE



3 WEEVOS STRUCTURE




4 DOUBLE CLOUD NINE




5 BUCKET SWINGS

DESIGNATION	MANUFACTURER	MODEL	SIZE	FINISH	COLOR	OTHER
PLAY EQUIPMENT						
WEEVOS STRUCTURE	LANDSCAPE STRUCTURES; (888) 438-6574 601 7TH STREET SOUTH DELANO, MN 55328	DESIGN ID: 3464	36X31 FT	MNFR'S STANDARD	TBD	INSTALL PER MANUFACTURERS INSTRUCTIONS AND RECOMMENDATIONS. COLORS TO BE SELECTED BY LANDSCAPE ARCHITECT FROM MANUFACTURER'S FULL RANGE.
EVOS STRUCTURE	HTTPS://WWW.PLAYLSI.COM/	DESIGN ID: 3641	51X38 FT	MNFR'S STANDARD	TBD	
DNA TOWER L.04	BERLINER; 1 (877) 837-367696 BROOKFIELD OAKS DRIVE, SUITE 140, GREENVILLE, SC 29607	90.295.014	23X23 FT	MNFR'S STANDARD	TBD	
DOUBLE CLOUD NINE	HTTPS://WWW.BERLINER-PLAYEQUIPMENT.CO M/US/	95.171.311	33X27 FT	MNFR'S STANDARD	TBD	
BUCKET SWINGS	LANDSCAPE STRUCTURES; (888) 438-6574 601 7TH STREET SOUTH DELANO, MN 55328	DESIGN ID: 3407	22X17 FT	MNFR'S STANDARD	TBD	

6 PLAY EQUIPMENT SCHEDULE



3 CLIMBING WALL AND PLAY MOUND - SECTION
3/8" = 1'-0"




4 CLIMBING WALL AND PLAY MOUND - ELEVATION
3/8" = 1'-0"


NOTES:

1. PLACE MINIMUM 1 HOLD PER SQUARE FOOT OF WALL AREA.
2. PROVIDE SHOP DRAWINGS AND SAMPLES PRIOR TO CONSTRUCTION.
3. PROVIDE VARIETY OF HANDHOLDS AND FOOTHOLDS.
60% MEDIUM SIZED BOLT-ON HOLDS OF EVERY STYLE (EDGES, POCKETS, PINCHES, SLOPERS, ETC.)
20% FOOTHOLDS
10% SMALL HANDHOLDS (SIM TO FOOTHOLDS BUT SLIGHTLY LARGER AND MORE POSITIVE)
10% JUG HOLDS
OR APPROVED ALTERNATE MIX PER SHOP DRAWINGS


HANDHOLD/FOOTHOLD BASIS OF DESIGN PRODUCT:
MANUFACTURER: EVERLAST CLIMBING, EVERLASTCLIMBING.COM, 800-476-7366
PRODUCT: GROPERZ




1 CLIMBING WALL AND PLAY MOUND
1/4" = 1'-0"




2 CLIMBING WALL AND PLAY MOUND - SECTION
3/8" = 1'-0"



1 LI STREETLIGHT
NTS




2 STREETLIGHT - POLE
NTS



3 STREETLIGHT - POLE FOUNDATION
NTS



4 L2 WALL LIGHT
NTS



5 WALL LIGHT ELEVATION
1"=1'-0"

NOTE:
BASE BID SHALL NOT INCLUDE WALL LIGHT 4/L3.8 OR STRUCTURAL FOAM

ITB# 21-DPR-ITB-304
SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET
ARLINGTON, VIRGINIA

Sheet Title
CONSTRUCTION DETAILS

Approval Date
LUKE VANBELLEGHEM 7.9.2018
Design Supervisor

Revisions Date
LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV
Filename:
Plotted: Sep. 3, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal
COMMONWEALTH OF VIRGINIA
JAMES HUI FAN
Lic. No. 001316
4/15/2020
LANDSCAPE ARCHITECT

Sheet **L3.8**

ITB# 21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

**ROSSLYN
HIGHLANDS
PARK**

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

**PLANT
SCHEDULE &
CALCULATIONS**

Approval Date

LUKE VANBELLEGHEM 7.9.2018
Design Supervisor

Revisions Date

LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: CF

Drawn: SM, LV, KN

Checked: CF, LV

Filename:

Plotted: Sep. 3, 20

Scale: AS SHOWN

Date: JULY 15, 2019

Seal



Sheet **L4.2**

QUEENS COURT FOR INFORMATION ONLY	
TREE CANOPY COVER CALCULATIONS	
AREA WITHIN PROPERTY LINE	44,732 SF (1.03 ACRES)
PUBLIC RIGHT-OF-WAY DEDUCTION	6,900 SF
SITE AREA	37,832 SF
TREE CANOPY COVER REQUIRED	3,783 SF

TREE CANOPY COVER (ESTIMATED CANOPY AT 20 YEARS)

TREE CANOPY COVER PROVIDED BY APAH/QUEEN'S COURT FOR INFORMATION ONLY			
QTY.	TREE TYPE	VALUE	TOTAL
4	LARGE NATIVE SHADE TREE	393.75 SF	1,575 SF
2	MEDIUM NATIVE TREE	218.75 SF	438 SF
4	MEDIUM TREE	175 SF	700 SF

TREE CANOPY COVER PROVIDED BY PARKS DEPARTMENT			
QTY.	TREE TYPE	VALUE	TOTAL
3	LARGE SHADE TREE	315 SF	945 SF
2	MEDIUM-LARGE TREE	250 SF	500 SF
3	SMALL TREE	110 SF	330 SF

SUMMARY	
MIN. TREE CANOPY COVER PROVIDED BY APAH	2,713 SF
MIN. TREE CANOPY COVER PROVIDED BY PARKS DEPARTMENT	1,775 SF
TOTAL TREE CANOPY PROVIDED	4,488 SF
TREE CANOPY COVER REQUIRED	3,783 SF

PLANT SCHEDULE							
TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	TYPE	SPACING	REMARKS
ARI	3	ACER RUBRUM "OCTOBER GLORY" TM	OCTOBER GLORY MAPLE	2.5" CAL	B&B	AS SHOWN	
ACI	3	AMELANCHIER CANADENSIS "AUTUMN BRILLIANCE"	AUTUMN BRILLIANCE SERVICEBERRY	10' HT	B&B	AS SHOWN	
N52	2	NYSSA SYLVATICA "WILDFIRE"	BLACK GUM	2.5" CAL	B&B	AS SHOWN	
QB	3	QUERCUS BICOLOR	SWAMP WHITE OAK	2.5" CAL	B&B	AS SHOWN	
SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	TYPE	SPACING	REMARKS
HA	6	HYDRANGEA ARBORESCENS "ANNABELLE"	ANNABELLE SMOOTH HYDRANGEA	24"HT.	B&B	48" OC	
IG	50	ILEX GLABRA "SHAMROCK"	SHAMROCK INKBERRY	24"HT.	CONT.	30" OC	
PSI	28	PRUNUS LAUROCERASUS "SCHIPKAENSIS"	SCHIP LAUREL	36" HT.	B&B	42" OC	
RA	16	RHODODENDRON ATLANTICUM	COAST AZALEA	24"HT.	CONT.	36" OC	
RC	3	RHODODENDRON CATAWBIENSE	CATAWBA RHODODENDRON	30" HT.	CONT.	48" OC	
RG	42	RHUS AROMATICA "GRO-LOW"	GRO-LOW FRAGRANT SUMAC	18" HT.	CONT.	30" OC	
RK	4	ROSA X "KNOCKOUT" TM	KNOCK OUT ROSE	36" HT.	CONT.	36" OC	
RD	7	ROSA X "MEIJOCOS"	PINK DRIFT ROSE	30" HT.	CONT.	30" OC	
GRASSES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	TYPE	SPACING	REMARKS
CLA	8	CHASMANTHIUM LATIFOLIUM	NORTHERN SEA OATS	3 GAL	CONT.	24" OC	
PVS	21	PANICUM VIRGATUM "SHENANDOAH"	SWITCH GRASS	3 GAL	CONT.	36" OC	
GROUND COVERS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	TYPE	SPACING	REMARKS
AOR	57	ASTER OBLONGIFOLIUS "RAYDON'S FAVORITE"	AROMATIC ASTER	1 GAL	CONT.	12" OC	
BAA	134	BAPTISIA AUSTRALIS	FALSE INDIGO	1 GAL	CONT.	12" OC	
HAD	73	HEUCHERA AMERICANA "DALE'S STRAIN"	AMERICAN ALUMROOT	1 GAL	CONT.	15" OC	
IV	222	IRIS VERSICOLOR	BLUE FLAG	4" POT	CONT.	9" O.C.	
JT	112	JUNCUS TENUIS	POVERTY RUSH	1 GAL	CONT.	15" OC	
NFB	55	NEPETA X FAASSENII "WALKERS LOW"	CATMINT	1 GAL	CONT.	15" OC	
PAB	44	PEROVSKIA ABROTANOIDES "LITTLE SPIRE"	LITTLE SPIRE RUSSIAN SAGE	1 GAL	CONT.	15" OC	
SR	72	SOLIDAGO RUGOSA "FIREWORKS"	WRINKLELEAF GOLDENROD	1 GAL	CONT.	15" OC	

1 PLANT SCHEDULE

NTS

2 TREE CANOPY COVERAGE CALCULATIONS

NTS

TREE REPLACEMENT CALCULATIONS FOR INFORMATION ONLY	
TREE REPLACEMENT REQUIRED (REFER TO SHEET T1.00 FOR TREE PRESERVATION PLAN)	48
LARGE-MEDIUM TREES REPLACED ON SITE- PROVIDED BY APAH (1:1 RATIO)	20
LARGE-MEDIUM TREES REPLACED ON SITE- PROVIDED BY PARK (1:1 RATIO)	8
TOTAL ON SITE TREE REPLACEMENT	28

NOTE:


- THE DEVELOPER OF QUEEN'S COURT AGREES TO MAKE A CONTRIBUTION TO THE COUNTY'S TREE CANOPY FUND OF AT LEAST \$2,400 PER TREE, OR A GREATER AMOUNT IF THE CONTRIBUTION POLICY CHANGES AT THE TIME OF PAYMENT, FOR EVERY TREE THAT CANOPY BE PLANTED ONSITE. THE CONTRIBUTION SHALL BE REQUIRED WHEN TREE PLANTING REQUIREMENTS CANNOT BE MET ON THE PROPERTY. THE PAYMENT SHALL BE DELIVERED TO THE DEPARTMENT OF PARKS AND RECREATION OFFICE PRIOR TO THE ISSUANCE OF THE EXCAVATION/SHEETING AND SHORING PERMIT.

3 TREE REPLACEMENT CALCULATIONS

NTS

NOTES

1. AT PLANTING PRUNE ONLY CROSSING LIMBS, BROKEN OR DEAD BRANCHES, AND ANY BRANCHES THAT POSE A HAZARD TO PEDESTRIANS PER ANSI STANDARD A300. DO NOT PRUNE INTO OLD WOOD ON EVERGREENS.
2. CONTRACTOR SHALL MAXIMIZE EXCAVATED AREA FOR TREE PIT WITHOUT ADVERSELY IMPACTING ADJACENT SITE FEATURES.
3. UNLESS OTHERWISE DIRECTED BY ARLINGTON COUNTY URBAN FORESTER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE URBAN FORESTER; PEAT MOSS SHALL NOT BE USED).
4. CONTRACTOR SHALL LEGALLY REMOVE EXCESS SOIL & DEBRIS FROM SITE.
5. TREES PLANTED WITHOUT THE TRUNK FLARE VISIBLE WILL BE REJECTED.
6. TREES MAY ONLY BE STAKED IF REQUIRED BY THE COUNTY URBAN FORESTER. REFER TO STAKING DETAILS.





ALL PLANTS MUST BE WATERED TWICE: ONCE AT INSTALLATION AND AGAIN WITHIN 48 HOURS OF INSTALLATION, PER THE SPECIFICATIONS.

THIS DETAIL SUPERSEDES ALL OTHER TREE PLANTING DETAILS IN ARLINGTON COUNTY.

1 TREE PLANTING DETAIL
NTS

NOTES


1. AT PLANTING PRUNE ONLY BROKEN OR DEAD BRANCHES
 2. PLANTING PIT/TRENCH SHALL BE DUG DEEP ENOUGH TO ALLOW AT LEAST 1/8TH OF ROOT BALL TO SET ABOVE EXISTING GRADE.
 3. SET PLANTS IN ERECT, STABLE, AND UNIFORM POSITIONS IN THE CENTER OF THE PLANTING PIT. ORIENT BEST FACE OF PLANT TO BE THE MOST VISIBLE.
 4. UNLESS OTHERWISE DIRECTED BY PROJECT OFFICER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE PROJECT OFFICER; PEAT MOSS MAY NOT BE USED).
 5. CONTRACTOR SHALL REMOVE EXCESS SOIL & DEBRIS FROM SITE.
 6. DO NOT PLACE MULCH IN CONTACT WITH STEM OF SHRUBS
- THIS DETAIL SUPERSEDES ALL OTHER SHRUB PLANTING DETAILS IN ARLINGTON COUNTY.
- ALL PLANTS MUST BE WATERED TWICE: ONCE AT INSTALLATION AND AGAIN WITHIN 48-HOURS OF INSTALLATION, PER THE SPECIFICATIONS.




2 SHRUB PLANTING
NTS

NOTES

1. AT PLANTING PRUNE ONLY BROKEN OR DEAD BRANCHES.
2. PLANTING PIT/TRENCH SHALL BE DUG DEEP ENOUGH TO ALLOW AT LEAST 1/8TH OF ROOT BALL TO SET ABOVE EXISTING GRADE.
3. SET PLANTS IN ERECT, STABLE, AND UNIFORM POSITIONS. ORIENT BEST FACE OF PLANT TO BE THE MOST VISIBLE.
4. GROUND COVERS AND PERENNIALS SHALL BE INSTALLED WITH TRIANGULAR SPACING. REFER TO CHART.
4. UNLESS OTHERWISE DIRECTED BY PROJECT OFFICER, BACKFILL SOIL MIXTURE WILL BE 3/4 EXISTING SOIL CLEANED OF DEBRIS (GRAVEL, ROCKS, STICKS, TRASH, ETC.) AND MIXED WITH 1/4 ORGANIC MATERIAL (COMPOSTED BARK, LEAF MOLD, OR OTHER PLANT DEBRIS PROCESSED TO A POINT OF DECAY AND APPROVED BY THE PROJECT OFFICER; PEAT MOSS MAY NOT BE USED).
5. CONTRACTOR SHALL REMOVE EXCESS SOIL & DEBRIS FROM SITE.
6. DO NOT PLACE MULCH IN CONTACT WITH STEM OF PLANTS.




PLANT SPACING "D" O.C.	ROW "A" O.C.	PLANTS PER S.F.
6"	5"	4.00
8"	7"	2.25
9"	8"	1.77
12"	10"	1.00
15"	13"	0.77
18"	16"	0.44



THIS DETAIL SUPERSEDES ALL OTHER GROUND COVER PLANTING DETAILS IN ARLINGTON COUNTY.

3 GROUND COVERS & PERENNIAL PLANTING
NTS



4 BIORETENTION TREE PIT
NTS


Approval	Date
LUKE VANBELLEGHEM Design Supervisor	7.9.2018


Revisions	Date
LDA SUBMISSION	4/15/20
LDA SUBMISSION REV.	7/14/20
LDA SUBMISSION REV.	9/08/20

Designed: CF
Drawn: SM, LV, KN
Checked: CF, LV

Filename:
Plotted: Sep. 3, 20
Scale: AS SHOWN
Date: JULY 15, 2019

Seal





LEGEND

	SIGN
	POWER POLE
	LIGHT POLE
	GUY WIRE
	CLEAN OUT
	STORM MH
	WATER VALVE
	FIRE HYDRANT
	EXISTING STORM SEWER
	EXISTING BUILDING
	EXISTING CONTOUR
	FENCE
	EXISTING LOT LINE
	TELECOM LINE
	OVERHEAD ELECTRIC
	GASLINE
	WATERLINE
	STORM DRAIN
	STEAM LINE
	EDGE OF GRAVEL
	EDGE OF PAVEMENT
	DITCH C/L
	CURB & GUTTER
	BUILDING OUTLINE
	EDGE OF PAVED ROAD
	SIDEWALK
	TELEPHONE EASEMENT
	EX TREES
	LIMITS OF DISTURBANCE

EXISTING STORM SEWER LEGEND

	STM TOP=172.91 IN=161.40 (15"RCP Fr 26044) IN=161.45 (15"RCP Fr 2683) OUT=161.17 (15"RCP To 4682)
	STM TOP=172.85 IN=162.10 (15"RCP Fr 26045) OUT=161.48 (15"RCP To 26043)
	STM TOP=173.62 IN=163.94 (15"RCP Fr 4682) OUT=163.88 (15"RCP To 26044)
	STM TOP=165.29 (FULL OF DEBRIS) IN=(NO DIP) (15"RCP Fr 26045) OUT=(NO DIP) (15"RCP To 4506)



DEPARTMENT OF PARKS AND RECREATION
 Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA
 Sheet Title

EXISTING CONDITIONS


Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20


Designed: FA
 Drawn: EF
 Checked: KMM

Filename:
 Plotted: Sep. 9, 20

Scale: AS SHOWN
 Date: APRIL 15, 2020



Sheet **C1.4**



LEGEND

	EXISTING CONTOUR
	LIGHT POLE
	FENCE
	STORM MH
	STORM DRAIN
	EXISTING STORM SEWER
	ELECTRIC LINE
	FIBER OPTIC LINE
	PROPERTY BOUNDARY
	LIMITS OF DISTURBANCE
	PROP MAJOR CONTOUR
	PROP MINOR CONTOUR
	SPOT ELEVATION
	BUILDING ENTRANCE
	PROP LIGHTING
	PROP SIDEWALK
	PROP BUILDING OUTLINE
	PROP BUILDING OVERHANG
	PROP BUILDING GARAGE
	PROP UNDERDRAIN
	PROP PERFORATED PIPE
	PROP CURB W/ FENCE
	PROP FLUSH CURB
	PROP STORM SLOT DRAIN/CLEANOUT
	PROP PLANTER WALL
	PROP SEAT WALL
	PROP SEAT STEPS
	PROP SIGN WALL
	PROP CONCRETE PAVING
	PROP CONTINUOUS SOIL PANEL
	PROP POUR IN PLACE RUBBER
	PROP BMP PLANTING (BIORETENTION AND PLANTER BOXES)
	PROP BAR GRATING BRIDGE
	PROP GRAVEL PRETREATMENT

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

GRADING PLAN

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor


Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20
 ADDENDUM 1 9/25/20

Designed: FA
 Drawn: EF
 Checked: KMM

Filename:
 Plotted: Sep. 25, 20
 Scale: AS SHOWN
 Date: APRIL 15, 2020



Sheet **C1.5**




LEGEND

- SIGN
- POWER POLE
- LIGHT POLE
- GUY WIRE
- CLEAN OUT
- STORM MH
- WATER VALVE
- FIRE HYDRANT
- EXISTING STORM SEWER
- EXISTING CONTOUR
- FENCE
- EXISTING LOT LINE
- TELECOM LINE
- OVERHEAD ELECTRIC
- GASLINE
- WATERLINE
- STORM DRAIN
- STEAM LINE
- LIMITS OF DISTURBANCE
- PROPERTY BOUNDARY
- EDGE OF GRAVEL
- EDGE OF PAVEMENT
- DITCH C/L
- CURB & GUTTER
- BUILDING OUTLINE
- EDGE OF PAVED ROAD
- SIDEWALK
- TELEPHONE EASEMENT
- EX TREES

EROSION & SEDIMENT CONTROL LEGEND

- SSF
- PRE-DRAINAGE DIVIDE
- CE
- SILT FENCE, SPEC. 3.05
- TEMPORARY CONSTRUCTION ENTRANCE, SPEC. 3.38



ITB#21-DPR-ITB-304
 SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA

Sheet Title
EROSION & SEDIMENT CONTROL PHASE 1

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor


Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20

Designed: FA
 Drawn: EF
 Checked: KMM

Filename:
 Plotted: Sep. 9, 20
 Date: APRIL 15, 2020



Sheet **C1.7**
 5 of 16




LEGEND

	SIGN
	POWER POLE
	LIGHT POLE
	GUY WIRE
	CLEAN OUT
	STORM MH
	WATER VALVE
	FIRE HYDRANT
	EXISTING STORM SEWER
	SPOT ELEVATION
	BUILDING ENTRANCE
	PROP LIGHTING
	PROP LIGHT POLE
	PROP STORM SLOT DRAIN/CLEANOUT
	EXISTING CONTOUR
	CHAIN LINK FENCE
	STORM DRAIN
	LIMITS OF DISTURBANCE
	PROP MAJOR CONTOUR
	PROP MINOR CONTOUR
	ELECTRIC LINE
	FIBER OPTIC LINE
	ELECTRIC CONDUIT LIGHTPOLE
	PROP FENCE
	PROP SIDEWALK
	PROP BUILDING OUTLINE
	PROP BUILDING OVERHANG
	PROP BUILDING GARAGE
	PROPERTY BOUNDARY
	PROP STORM DRAIN
	PROP PERFORATED PIPE
	PROP CURB W/ FENCE
	PROP FLUSH CURB
	PROP PLANTER WALL
	PROP SEAT WALL
	PROP SEAT STEPS
	PROP SIGN WALL
	PROP CONCRETE PAVING
	PROP CONTINUOUS SOIL PANEL
	PROP POUR IN PLACE RUBBER
	PROP BIORETENTION PLANTING
	PROP BIORETENTION PLANTING
	PROP GRAVEL PRETREATMENT

EROSION & SEDIMENT CONTROL LEGEND

	SSF
	SF SILT FENCE, SPEC. 3.05
	PRE-DRAINAGE DIVIDE
	CE TEMPORARY CONSTRUCTION ENTRANCE, SPEC. 3.38



ITB#21-DPR-ITB-304
 SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA


Sheet Title
EROSION & SEDIMENT CONTROL PHASE 2

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20

Designed: FA
 Drawn: EF
 Checked: KMM

Filename:
 Plotted: Sep. 9, 20
 Scale: AS SHOWN
 Date: APRIL 15, 2020



Sheet **C1.8**
 6 of 16

EROSION AND SEDIMENT CONTROL PLAN NARRATIVE

WE ACKNOWLEDGE THAT THE TREE PROTECTION/LANDSCAPE PLANS SHALL BE REVIEWED AND APPROVED PRIOR TO THE ISSUANCE OF THE ASSOCIATED LAND DISTURBANCE PERMIT. THE APPROVED TREE PROTECTION AND/OR LANDSCAPE PLAN MUST BE SUBMITTED AS PART OF THE LDA PERMIT PACKAGE ALONG WITH ANY ADDITIONAL REQUIRED ITEMS.

PROJECT DESCRIPTION:

THIS PROJECT IS LOCATED IN ARLINGTON COUNTY, VIRGINIA. THE CURRENT SITE ADDRESS FOR ROSSLYN HIGHLANDS PARK IS 1801 18TH STREET. THIS PROJECT PROPOSES NEW PARK CONSTRUCTION. A TOTAL OF APPROXIMATELY 0.23 ACRES WILL BE DISTURBED WITH THIS PROJECT. THE PROJECT IS EXPECTED TO START SOON FOLLOWING THE APPROVAL OF THESE PLANS.

EXISTING SITE CONDITIONS:

THE EXISTING PROJECT AREA CONSISTS OF A CLEARING DESIGNATED FOR A PLAYGROUND. THE SITE DRAINS SOUTH TOWARD STORM DRAIN INLETS. THE SITE IS STABILIZED AND THERE ARE NO EXISTING DRAINAGE PROBLEMS ON SITE.

DATE OF CONSTRUCTION:

CONSTRUCTION IS ANTICIPATED TO START AT TIME OF PLAN APPROVAL.

ADJACENT PROPERTIES:

THE SITE LIES IS BORDERED BY RESIDENTIAL PROPERTIES IN ALL DIRECTIONS. ADJACENT PROPERTIES WILL BE PROTECTED BY THE SILT FENCE PROTECTING THE PERIMETER OF THE SITE DURING DEMOLITION. THE SITE IS NOT IN THE PROXIMITY OF AN RPA OR A FLOODPLAIN.

OFF-SITE AREAS:

THE PROJECT WILL NOT REQUIRE ANY OFF-SITE LAND DISTURBING ACTIVITIES.

CRITICAL AREAS:

THE SITE IS NOT WITHIN AN RPA OR A FLOODPLAIN. THE SITE IS CURRENTLY STABILIZED AND WILL REMAIN STABILIZED THROUGHOUT CONSTRUCTION.

SOILS:

SEE SHEET C1.9 FOR SOILS INFORMATION.

STRUCTURAL PRACTICES:

1. CONSTRUCTION ENTRANCE - 3.02: TEMPORARY CONSTRUCTION ENTRANCES WITH WASH RACK SHALL BE INSTALLED AS SHOWN ON THE PLAN. CONSTRUCTION VEHICLES SHALL BE REQUIRED TO WASH THEIR WHEELS BEFORE LEAVING THE SITE. A WATER TANK TRUCK SHALL PROVIDE WATER IF PUBLIC WATER IS NOT AVAILABLE. THE ENTRANCE SHALL BE FIELD ADJUSTED AS REQUIRED DURING CONSTRUCTION. DURING PHASE I, THE CONSTRUCTION ENTRANCE WILL UTILIZE THE EXISTING SIDEWALK PARK ENTRANCE ON THE SOUTH SIDE OF THE SITE. THIS IS CURRENTLY LOCATED ON CONCRETE AND GRASS, BUT WILL NOT CONTRIBUTE ANY

SEDIMENT. WASHDOWN WILL OCCUR SUCH THAT THE RUNOFF IS CAPTURED BY THE PIT AND TREATED BEFORE BEING RELEASED TO THE EXISTING STORM SYSTEM.

2. **SILT FENCE BARRIER - 3.05:** SILT FENCE SEDIMENT BARRIERS WITH WIRE SUPPORT SHALL BE INSTALLED AS SHOWN ON THE APPROVED PLAN TO FILTER SEDIMENT-LADEN RUNOFF FROM THE CONSTRUCTION AREA.
3. **INLET PROTECTION - 3.07:** INLET PROTECTION WILL BE INSTALLED TO PREVENT SEDIMENT FROM ENTERING STORM DRAINAGE SYSTEMS PRIOR TO PERMANENT STABILIZATION OF THE DISTURBED AREA.

SEDIMENT CONTROL PROGRAM:
PHASE I EROSION CONTROL

THE INITIAL CONTROL MEASURES SHALL BE AS FOLLOWS:

1. CONSTRUCTION ENTRANCE WITH WASH RACK SHALL BE INSTALLED AS INDICATED IN THE PLAN. MUD AND DEBRIS SHALL BE WASHED FROM ALL VEHICLES AND EQUIPMENT BEFORE LEAVING THE SITE.
2. SILT FENCE SHALL BE INSTALLED WHERE INDICATED IN THE PLAN.
3. AFTER ESTABLISHMENT OF ALL INITIAL CONTROL MEASURES, THE CONTRACTOR SHALL PROCEED WITH DEMOLITION AND INSTALLATION OF IMPROVEMENTS.

GENERAL EROSION AND SEDIMENT CONTROL NOTES:

- ES-1 UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS 4VAC50-30 EROSION AND SEDIMENT CONTROL REGULATIONS.
- ES-2 THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE RE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- ES-3 ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING.
- ES-4 A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- ES-5 PRIOR TO COMMENCING LAND DISTURBING ACTIVITIES IN AREAS OTHER THAN INDICATED ON THESE PLANS (INCLUDING, BUT NOT LIMITED TO, OFF-SITE BORROW OR WASTE AREAS), THE CONTRACTOR SHALL SUBMIT SUPPLEMENTARY EROSION CONTROL PLAN TO THE OWNER FOR REVIEW AND APPROVAL BY THE PLAN APPROVING AUTHORITY.

- ES-6 THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION AS DETERMINED BY THE PLAN APPROVING AUTHORITY.
- ES-7 ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBING ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL FINAL STABILIZATION IS ACHIEVED.
- ES-8 THE CONTRACTOR SHALL INSPECT ALL EROSION CONTROL MEASURE PERIODICALLY AND AFTER EACH RUNOFF-PRODUCING RAINFALL EVENT. ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES SHALL BE MADE IMMEDIATELY.

GENERAL LAND CONSERVATION NOTES:

1. NO AREA WILL REMAIN DENUDE FOR MORE THAN 7 CALENDAR DAYS UNLESS OTHERWISE AUTHORIZED BY THE DIRECTOR OR HIS AGENT.
2. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN GRADING. FIRST AREAS TO BE CLEARED ARE TO BE THOSE REQUIRED FOR THE PERIMETER CONTROLS.
3. ALL STORM SEWER LINES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 5 DAYS AFTER BACKFILL. NO MORE THAN 500 FEET ARE TO BE OPEN AT ANY ONE TIME.
4. DURING CONSTRUCTION, ALL STORM SEWER INLETS WILL BE PROTECTED BY INLET PROTECTION DEVICES, MAINTAINED AND MODIFIED AS REQUIRED BY CONSTRUCTION PROGRESS.
5. ANY DISTURBED AREA NOT COVERED BY NOTE #1 ABOVE AND NOT PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST, OR DISTURBED AFTER THAT DATE, SHALL BE MULCHED WITH HAY OR STRAW MULCH AT THE RATE OF 2 TONS PER ACRE AND OVER-SEEDED NO LATER THAN MAY 15TH.
6. AT THE COMPLETION OF CONSTRUCTION PROJECT AND PRIOR TO BOND RELEASE, ALL TEMPORARY SEDIMENT CONTROLS SHALL BE REMOVED AND ALL DENUDE AREAS SHALL BE STABILIZED. ARLINGTON COUNTY INSPECTOR TO APPROVE REMOVAL OF ALL TEMPORARY SILTATION MEASURES.

MAINTENANCE PROGRAM:

THE SITE SUPERINTENDENT OR HIS OR HER REPRESENTATIVE SHALL MAKE A VISUAL INSPECTION OF ALL MECHANICAL CONTROLS AND NEWLY STABILIZED AREAS (I.E. SEEDED AND MULCHED AND/OR SODDED AREAS) ON A DAILY BASIS, ESPECIALLY AFTER A HEAVY RAINFALL EVENT TO INSURE THAT ALL CONTROLS ARE MAINTAINED AND PROPERLY FUNCTIONING. ANY DAMAGED CONTROLS SHALL BE REPAIRED PRIOR TO THE END OF THE WORKDAY INCLUDING RE-SEEDING AND

MULCHING OR RE-SODDING, IF NECESSARY.

STORMWATER MANAGEMENT:

THIS PROJECT DISTURBS APPROXIMATELY 0.23 ACRES. THE PROJECT SITE IS NOT WITHIN AN RPA OR FLOODPLAIN. IT DISCHARGES INTO EXISTING STORM DRAIN ON THE ADJACENT STREET. PER THE QUEEN'S COURT PLANS FOR THE ADJACENT BUILDING, A BIORETENTION POND AND THREE PLANTER BOXES ARE PROPOSED TO MEET STORMWATER MANAGEMENT AND BMP CRITERIA. THERE ARE, THEREFORE, NO ADVERSE IMPACT TO ADJACENT OR DOWNSTREAM PROPERTIES. THIS MEETS THE STORMWATER MANAGEMENT REQUIREMENTS FOR WATER QUANTITY AND QUALITY. SEE DETAILS ON SHEETS C-1.11-1.15.

MS4 NOTE:

ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT SOURCE OF POLLUTANTS TO SURFACE WATERS:

WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.

POLLUTION PREVENTION NOTES:

1. ONLY THE FOLLOWING NON-STORMWATER DISCHARGES ARE AUTHORIZED BY ARLINGTON COUNTY'S MS4 PERMIT, UNLESS THE STATE WATER CONTROL BOARD, THE VIRGINIA SOIL AND WATER CONSERVATION BOARD (BOARD), OR ARLINGTON COUNTY DETERMINES THE DISCHARGE TO BE A SIGNIFICANT

SOURCE OF POLLUTANTS TO SURFACE WATERS: WATER LINE FLUSHING; LANDSCAPE IRRIGATION; DIVERTED STREAM FLOWS; RISING GROUND WATERS; UNCONTAMINATED GROUND WATER INFILTRATION (AS DEFINED AT 40 CFR 35.2005(20)); UNCONTAMINATED PUMPED GROUND WATER; DISCHARGES FROM POTABLE WATER SOURCES; FOUNDATION DRAINS; AIR CONDITIONING CONDENSATION; IRRIGATION WATER; SPRINGS; WATER FROM CRAWL SPACE PUMPS; FOOTING DRAINS; LAWN WATERING; INDIVIDUAL RESIDENTIAL CAR WASHING; FLOWS FROM RIPARIAN HABITATS AND WETLANDS; DECHLORINATED SWIMMING POOL DISCHARGES; DISCHARGES OR FLOWS FROM FIRE FIGHTING; AND, OTHER ACTIVITIES GENERATING DISCHARGES IDENTIFIED BY THE DEPARTMENT OF ENVIRONMENTAL QUALITY AS NOT REQUIRING VPDES AUTHORIZATION.

2. APPROPRIATE CONTROLS MUST BE IMPLEMENTED TO PREVENT ANY NON-STORMWATER DISCHARGES NOT INCLUDED ON THE ABOVE LIST (E.G., CONCRETE WASH WATER, PAINT WASH WATER, VEHICLE WASH WATER, DETERGENT WASH WATER, ETC.) FROM BEING DISCHARGED INTO ARLINGTON COUNTY'S MS4 SYSTEM, WHICH INCLUDES THE CURB AND GUTTER SYSTEM, AS WELL AS CATCH BASINS AND OTHER STORM DRAIN INLETS, OR STREAM NETWORK.
3. PER CHAPTER 26 OF THE ARLINGTON COUNTY CODE, IT SHALL BE UNLAWFUL FOR ANY PERSON TO DISCHARGE DIRECTLY OR INDIRECTLY INTO THE STORM SEWER SYSTEM OR STATE WATERS, ANY SUBSTANCE LIKELY, IN THE OPINION OF THE COUNTY MANAGER, TO HAVE AN ADVERSE EFFECT ON THE STORM SEWER SYSTEM OR STATE WATERS.



DEPARTMENT OF PARKS AND RECREATION

Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

EROSION & SEDIMENT PLAN & PPP NOTES

Approval Date
LUKE VANBELLEGHEM 4.15.2020
Design Supervisor

Revisions Date
LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: FA
Drawn: EF
Checked: KMM


Filename:
Plotted: Sep. 9, 20
Scale: AS SHOWN
Date: APRIL 15, 2020

Seal






Sheet **C1.9**

1992 3.05



Source: Adapted from Installation of Straw and Fabric Filter Barriers for Sediment Control, Sherwood and Wyant Plate 3.05-2



4B 3 to 8 percent slopes. This unit is gently sloping and consists of about 70 percent Urban land, 15 percent Sassafras, and 10 percent Neoscos soils. Areas disturbed by cutting and grading make up 5 percent of this unit.

12 Urban land-Udorthents complex, 2 to 15 percent slopes. This mapping unit consists of areas where more than 65 percent of the surface is Urban land, covered by buildings, asphalt, concrete, or other impervious materials. The other 15 percent consists of areas of deep to very deep, nearly level to moderately sloping, well and moderately well drained soils. The Urban land and Udorthents are so intermingled it was not practical to map them separately. This complex occurs throughout the survey area but is largely located in the Rosslyn-Ballston and Crystal City areas. This unit is about 65 percent Urban land, 10 percent Udorthents, and 5 percent other soils.

The Udorthents consist of material that has been graded, cut, filled, or otherwise disturbed during urbanization. The disturbed material is loamy and generally reflects the soils in the adjacent area.

Included in this mapping unit are small areas of soils that have not been disturbed. Also included are moderately steep and steep slopes.

Project Name: ROSSLYN HIGHLANDS PARK
 Address: 18TH STREET Date: 1/16/2019

General Items	yes	n/a	no	sheet
Pollution Prevention Plan				
1 Include the following on the Pollution Prevention Plan				
a Standard notes from Stormwater Manual Section 2.4	X			C-1.10
Authorized Non-Stormwater Discharge (Section 2.0), Potential Sources of Pollution & Pollution Prevention Practices (Section 5.0), and Spill Prevention & Response (Section 7.0) from SWPPP Template (Appendix B) of the Stormwater Manual	X			C-1.10

2.0 Authorized Non-Stormwater Discharges

Type of Authorized Non-Stormwater Discharge Likely Present at Your Project Site?

Type of Discharge	Likely Present	Yes	No
External buildings wash down	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Uncontaminated foundation or footing drains	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Uncontaminated excavation dewatering	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Landscape irrigation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Others [describe]	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

STORMWATER POLLUTION PREVENTION PLAN
Insert Project/Site Name

5.0 Potential Sources of Pollution & Pollution Prevention Practices

Pollutant-Generating Activity	Likely Present at your Project Site?	Pollutants										Responsible Party		
		Sediment	Nutrients	Heavy Metals	pH (acids and bases)	Pesticides & Herbicides	Oil & Grease	Bacteria & Viruses	Trash, Debris, Solids	Other Toxic Chemicals	Pollution Prevention Practice			
Clearing, grading, excavating, and un-stabilized areas	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X									X	(1)	Construction Activity Operator (See Cover Page of this SWPPP)	
Paving operations	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X					X	X			X	(2)		
Concrete washout and cement waste	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			X	X						X	(3)		
Structure construction, stucco, painting, and cleaning	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			X	X						X	X		(4)
Dewatering operations	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	X	X	X							X	(5)		
Material delivery and storage	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X	X	X	X	X					X	X		(6)
Material use during building process	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X	X	X		X					X	X		(7)
Solid waste disposal	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No										X	X		(8)
Sanitary waste	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X		X							X			(9)
Landscape operations	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	X	X			X					X	X		(10)
Others [describe]	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		(11)

Arlington County – SWPPP 9/2016

Pre-Storm Erosion and Sediment Control Checklist

Per Erosion and Sediment Control General Note 6, the Contractor is responsible for the installation and maintenance of any additional erosion and sediment control (ESC) measures necessary to prevent erosion and sedimentation as determined by the County. These supplementary practices are in addition to those shown in an ESC plan. ESC practices shall be modified as needed to ensure only clear water is discharged from the site.

The following actions shall be taken prior to storm events with predicted heavy and/or large volume rainfall to prevent sediment discharges from a construction site. A typical summer thunderstorm is an example of a storm event with predicted heavy and/or large volume rainfall.

- Perimeter controls**
- Silt fence shall be checked for undermining, holes, or deterioration of the fabric. Fencing shall be replaced immediately if the fabric is damaged or worn. Silt fence must be trenched into the ground per state specifications (Std & Spec 3.09).
 - Wooden stakes or steel posts shall be properly secured upright into the ground. Damaged posts or stakes must be replaced.
 - Sediment that has accumulated against the silt fence should be removed. Accumulated sediment must be removed when the level reaches one-half the height of the fencing.
 - Hay bales or a stone berm should be placed across the construction entrance to prevent sediment from leaving the construction site.

- Exposed slopes and soil**
- Exposed slopes not at the final stabilization phase shall be covered with tarps, plastic sheeting, or erosion control matting. Covering material shall be properly secured/anchored.
 - Controls shall be installed to prevent concentrated flow down an exposed slope. Berms or diversion dikes shall be installed at the top of cut / exposed slopes to direct storm flow around the disturbed area.
 - Exposed slopes at the final stabilization phase shall be stabilized using slope stabilization practices such as soil stabilization blankets or matting as specified in the Virginia Erosion and Sediment Control Handbook (VESH) Std & Spec 3.36. Blankets or mats must be properly secured and anchored to the slope using staples, pins, or stakes.
 - Seeded areas shall be checked and reseeded as necessary to cover exposed soil. Recently seeded areas shall be protected by straw or soil stabilization blankets to prevent seeding from being washed away.

- Stockpiles**
- Stockpiled soil and other loose materials that can be washed away shall be covered with a tarp, plastic sheeting, or other stabilization matting. The cover must be properly secured / anchored down to prevent it from being blown off and exposing materials to rain. Controls such as hay bales or booms should be placed along the perimeter of the stock pile (downhill side).

- Inlet protection**
- Inlet protection controls shall be inspected to ensure they are functioning properly and flooding will not occur. Clogged or damaged controls must be replaced immediately. Ensure controls allow for overflow / bypass of stormwater runoff during significant storm events.

In addition to these pre-storm actions, all erosion and sediment control (ESC) measures must be checked daily and after each significant rainfall.

- Pollution Prevention Practices:**
- Clearing, grading, excavating and un-stabilized areas** – Utilize erosion and sediment controls to prevent sediment laden or turbid runoff from leaving the construction site. Dispose of clearing debris at acceptable disposal sites. Apply permanent or temporary stabilization, sodding and/or mulching to denuded areas in accordance with the erosion and sediment control specifications and the general VPDES permit for discharges of stormwater from construction activities.
 - Paving operations** – Cover storm drain inlets during paving operations and utilize pollution prevention materials such as drip pans and absorbent/dry for all paving machines to limit leaks and spills of paving materials and fluids.
 - Concrete washout and cement waste** – Direct concrete wash water into a leak-proof container or leak-proof settling basin that is designed so that no overflow can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wastes.
 - Structure construction, stucco, painting and cleaning** – Enclose, cover or berm building material storage areas if susceptible to contaminated stormwater runoff. Conduct painting operations consistent with local air quality and OSHA regulations. Mix paint indoors, in a containment area or in a flat unpaved area. Prevent the discharge of soaps, solvents, detergents and wash water from construction materials, including the clean-up of stucco paint, form release oils and curing compounds.
 - Dewatering operations** – Construction site dewatering from building footings or other sources may not be discharged without treatment. Sediment laden or turbid water shall be filtered, settled or similarly treated prior to discharge.
 - Material delivery and storage** – Designate areas of the construction site for material delivery and storage. Place near construction entrances, away from waterways, and avoid transport near drainage paths or waterways.
 - Material use during building process** – Use materials only where and when needed to complete the construction activity. Follow manufacturer's instructions regarding uses, protective equipment, ventilation, flammability and mixing of chemicals.
 - Solid waste disposal** – Designate a waste collection area on the construction site that does not receive a substantial amount of runoff from upland areas and does not drain directly to a waterway. Ensure that containers have lids so they can be covered before periods of rain, and keep containers in a covered area whenever possible. Schedule waste collection to prevent the containers from overflowing.
 - Sanitary waste** – Prevent the discharge of sanitary waste by providing convenient and well-maintained portable sanitary facilities. Locate sanitary facilities in a convenient location away from waterways.
 - Landscape operations** – Maintain as much existing vegetation as practicable. Apply permanent or temporary stabilization, sodding and/or mulching to denuded areas in accordance with the erosion and sediment control specifications and the general VPDES permit for discharges of stormwater from construction activities. Apply nutrients in accordance with manufacturer's recommendations and not during rainfall events.
 - Others** – If applicable, describe your Pollution Prevention Practice.

Quangian Li, P.E.
 ESC Program Administrator
 Department of Environmental Services
 2100 Clarendon Boulevard, Suite 813
 Arlington, Virginia 22201

Re: Erosion and Sediment Control Permit Application for:

street address _____
 lot, block, section subdivision _____
 permit number _____

Dear Mrs. Li:
 I hereby certify that I accept the responsibilities of Responsible Land Disturber for the above referenced project. I understand that these responsibilities include:

- Reviewing the erosion and sedimentation (E&S) plan for the project.
- Walking the site prior to construction to identify critical areas.
- Conducting a pre-construction briefing with earth moving and site contractor to present the E&S plan and highlight the presence of critical areas, the limits of clearing and the required E&S controls and tree protection measures to be installed. Call 703-228-0760 to schedule pre-construction meeting.
- Regularly inspecting the site during construction to ensure that all E&S controls are functioning and are adequate to address erosion and sedimentation. Inspect the site 48 hours after a rainoff-generating storm, and provide a copy of the inspection findings to the county.
- Reporting to the owner the presence of inadequate or non-functioning E&S controls when they are observed.
- Ensuring that temporary soil stabilization is applied within 7 days to areas denuded that will remain undisturbed for longer than 14 days. Permanent stabilization shall be applied to areas that are to be left dormant for more than one year.
- Calling (703) 228-0760 at least 80 hours before demolishing any structure.

I may be reached at _____ with questions about this plan or my execution of the duties of Responsible Land Disturber.

Sincerely,

 name printed

professional registration (type and number)

7.0 Spill Prevention & Response

Most spills can be cleaned up following manufacturer specifications. Absorbent/dry, sealable containers, plastic bags, and shovels/brooms are suggested minimum spill response items that should be available at this location.

- 1st Priority: Protect all people
 2nd Priority: Protect equipment and property
 3rd Priority: Protect the environment
- Check for hazards (flammable material, noxious fumes, cause of spill) – If flammable liquid, turn off engines and nearby electrical equipment. If serious hazards are present leave the area and call 911. LARGE SPILLS ARE LIKELY TO PRESENT A HAZARD.
 - Make sure the spill area is safe to enter and that it does not pose an immediate threat to health or safety of any person.
 - Stop the spill source.
 - Call co-workers and supervisor for assistance and to make them aware of the spill and potential dangers.
 - If possible, stop spill from entering drains (use absorbent or other material as necessary).
 - Stop spill from spreading (use absorbent or other material).
 - If spilled material has entered a storm sewer, contact locally's storm water department.
 - Clean up spilled material according to manufacturer specifications, for liquid spills use absorbent materials and do not flush area with water.
 - Properly dispose of cleaning materials and used absorbent material according to manufacturer specifications.

Emergency Contacts:

Normal Working Hours
 DEQ Northern Regional Office 703-583-3800

Nights, Holidays & Weekends
 VA Dept. of Emergency Management 804-674-2400
 24 Hour Reporting Service

Local Contacts
 Arlington County Fire & Police 703-558-2222
 DES Water, Sewer, Streets 24-Hour Emergency 703-228-6555
 Washington Gas Emergency 703-750-1400

TABLE 3.31-B
(Revised June 2003)
TEMPORARY SEEDING SPECIFICATIONS
QUICK REFERENCE FOR ALL REGIONS

APPLICATION DATES	SEED SPECIES	APPLICATION RATES
Sept. 1 - Feb. 15	50/50 Mix of Annual Ryegrass (olium multi- forum) & Cereal (Winter) Rye (Secale cereale)	50 -100 (lbs/acre)
Feb. 16 - Apr. 30	Annual Ryegrass (olium multi- forum)	60 - 100 (lbs/acre)
May 1 - Aug. 31	German Millet	50 (lbs/acre)

FERTILIZER & LIME

- Apply 10-10-10 fertilizer at a rate of 450 lbs./acre (or 10 lbs./1,000 sq. ft.)
- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs./1,000 sq. ft.)

NOTE:
 1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
 2 - Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means.
 3 - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin #4, 2003 Nutrient Management for Development Sites at <http://www.dcr.state.va.us/sw/e&s.htm#pubs>

TABLE 3.32-D
(Revised June 2003)
PERMANENT SEEDING SPECIFICATIONS FOR PIEDMONT AREA

LAND USE	SEED ¹	
	SPECIES	APPLICATION PER ACRE
Minimum Care Lawn (Commercial or Residential)	Tall Fescue ¹	95-100%
	Perennial Ryegrass	0-5%
	Kentucky Bluegrass ²	0-5%
		TOTAL: 175-200 lbs.
High-Maintenance Lawn	Tall Fescue ¹	TOTAL: 200-250 lbs.
General Slope (3:1 or less)	Tall Fescue ¹	128 lbs.
	Red Top Grass or Creeping Red Fescue	2 lbs.
	Seasonal Nurse Crop ²	20 lbs.
		TOTAL: 150 lbs.
Low-Maintenance Slope (Steeper than 3:1)	Tall Fescue ¹	108 lbs.
	Red Top Grass or Creeping Red Fescue	2 lbs.
	Seasonal Nurse Crop ²	20 lbs.
	Crownvetch ³	20 lbs.
		TOTAL: 150 lbs.

- When selecting varieties of turfgrass, use the Virginia Crop Improvement Association (VCIA) recommended turfgrass variety list. Quality seed will bear a label indicating that they are approved by VCIA. A current turfgrass variety list is available at the local County Extension office or through VCIA at 804-746-4884 or at <http://dustan.ces.vt.edu/html/TurfgrassPublications/Publications2.html>
- Use seasonal nurse crop in accordance with seeding dates as stated below:
 February 16th - April Annual Rye
 May 1st - August 15th Foxtail Millet
 August 16th - October Annual Rye
 November - February 15th Winter Rye
- Substitute Sericea lepedeza for Crownvetch east of Farmville, VA (May through September use hulled seed, all other periods, use unhulled Sericea). If Flatpea is used, increase rate to 30 lbs./acre. If Weeping Lovegrass is used, include in any slope or low maintenance mixture during warmer seeding periods, increase to 30-40

FERTILIZER & LIME

- Apply 10-20-10 fertilizer at a rate of 500 lbs./acre (or 12 lbs./1,000 sq. ft.)
- Apply Pulverized Agricultural Limestone at a rate of 2 tons/acre (or 90 lbs./1,000 sq. ft.)

NOTE:
 1 - A soil test is necessary to determine the actual amount of lime required to adjust the soil pH of site.
 2 - Incorporate the lime and fertilizer into the top 4 – 6 inches of the soil by disking or by other means.
 3 - When applying Slowly Available Nitrogen, use rates available in Erosion & Sediment Control Technical Bulletin #4, 2003 Nutrient Management for Development Sites at <http://www.dcr.state.va.us/sw/e&s.htm#pubs>



DEPARTMENT OF PARKS
AND RECREATION

Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA

Sheet Title
EROSION & SEDIMENT PLAN & PPP NOTES

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20

Designed: FA
 Drawn: EF
 Checked: KMM

Filename:
 Plotted: Sep. 9, 20

Scale: AS SHOWN
 Date: APRIL 15, 2020



Sheet **C1.10**
 8 of 16

Construction Inspection Checklist: Bioretention

Address/Location: _____ Building Permit #: _____
 LDA Permit #: _____ SWM#: _____
 Contractor: _____ Telephone: _____
 Certifying Professional*: _____ Telephone: _____
 Date Started: _____ Final Inspection Date: _____



The following checklist provides a basic outline of the anticipated items for the construction inspection of bioretention facilities. This checklist does not necessarily distinguish between all the design variations and differences in construction between the family of practices. Inspectors should review the plans carefully, and adjust these items and the timing of inspection as needed to ensure the intent of the design is met. The standard for design of this practice is based on Virginia Stormwater BMP Clearinghouse and Arlington County Stormwater Guidance Manual.

All items should be checked when completed. Items labeled "Certification of..." must be crossed off, dated and initialed by certifying inspector.

PRE-CONSTRUCTION MEETING	DATE
<input type="checkbox"/> Identify the tentative schedule for construction and verify the requirements and schedule for interim inspections.	
<input type="checkbox"/> All pervious areas of the contributing drainage areas have been adequately stabilized with a thick layer of vegetation or erosion control measures are still in place and stormwater has been diverted around the area.	
<input type="checkbox"/> Area of bioretention practice has not been impacted during construction.	
<input type="checkbox"/> Pre-construction meeting with the contractor designated to install the bioretention practice, County DES inspector, and person completing this checklist has been conducted.	

EXCAVATION	DATE
<input type="checkbox"/> Area of bioretention excavation is marked and the size and location conforms to plan.	
<input type="checkbox"/> If the excavation area has been used as a sediment trap, verify that the bottom elevation of the proposed stone reservoir is lower than the bottom elevation of the existing trap.	
<input type="checkbox"/> For Level 2 bioretention, ensure the bottom of the excavation is scarified prior to placement of stone.	
<input type="checkbox"/> Subgrade surface is free of rocks and roots, and large voids. Any voids should be filled with the base aggregate to create a level surface for the placement of aggregates and underdrain (if required).	
<input type="checkbox"/> No groundwater seepage or standing water is present. Any standing water is dewatered to an acceptable dewatering device.	
<input type="checkbox"/> Excavation of the bioretention practice has achieved proper grades and the required geometry and elevations without violating the bottom of the excavation.	
<input type="checkbox"/> Sides of excavation covered with geotextile; no tears or holes, or excessive wrinkles are present.	
<input type="checkbox"/> Certification of Excavation Inspection: Inspector certifies the successful completion of the excavation steps listed above.	
<input type="checkbox"/> Photos required include: <ul style="list-style-type: none"> Excavated area prior to installation of stone, including measurements (L x W x D); Non-woven geotextile fabric installed on sides of excavated subgrade only. 	
<input type="checkbox"/> Material delivery tickets required include: <ul style="list-style-type: none"> Geotextile installed on sides 	

FILTER LAYER, UNDERDRAIN, AND STONE RESERVOIR PLACEMENT	DATE
<input type="checkbox"/> All aggregates conform to specifications as certified by quarry.	
<input type="checkbox"/> Underdrain size and perforations meet the specifications (if applicable).	
<input type="checkbox"/> If the underdrain is directly tied into the public storm sewer system, the connection has been witnessed by DES inspector.	
<input type="checkbox"/> For Level 2 installations: placement of filter layer and initial lift of stone reservoir layer aggregates with underdrain or infiltration sump, spread (not dumped) to avoid aggregate segregation	
<input type="checkbox"/> Placement of underdrain, observation wells, and underdrain fittings are in accordance with the approved plans.	
<input type="checkbox"/> Elevations of underdrain and outlet structure are in accordance with approved plans, or as adjusted to meet field conditions and denoted in Comments section.	
<input type="checkbox"/> Placement of remaining lift of stone reservoir layer as needed to achieve the required reservoir depth.	
<input type="checkbox"/> Certification of Filter Layer and Underdrain Placement Inspection: Inspector certifies the successful completion of the filter layer and underdrain placement steps listed above. Photos and material delivery tickets for these items are attached.	
<input type="checkbox"/> Photos required include: <ul style="list-style-type: none"> Perforated underdrain pipe (if applicable) with a solid vertical overflow pipe; Depth of #57 stone; Depth of choker stone (pea gravel or #8). 	
<input type="checkbox"/> Material delivery tickets required include: <ul style="list-style-type: none"> #57 stone; Choker stone (pea gravel or #8). 	

BIORETENTION SOIL MEDIA PLACEMENT	DATE
<input type="checkbox"/> Soil media is certified by supplier or contractor as meeting the project specifications.	
<input type="checkbox"/> Soil media is placed in 12-inch lifts to the design top elevation of the bioretention area. Elevation has been verified after settlement (2 to 4 days after initial placement).	
<input type="checkbox"/> Side slopes of ponding area are feathered back at the required slope (no steeper than 3H:1V).	
<input type="checkbox"/> Certification of Soil Media Placement Inspection: Inspector certifies the successful completion of the soil media steps listed above and any necessary photos are attached.	
<input type="checkbox"/> Photo required of a measurement of the soil media installed.	
<input type="checkbox"/> Material delivery ticket required from an approved soil media vendor.	

PRETREATMENT AND PLANT INSTALLATION	DATE
<input type="checkbox"/> Riser, overflow weir, or other outflow structure is set to the proper elevation and functional.	
<input type="checkbox"/> Placement of energy dissipaters and pretreatment practices (forebays, gravel diaphragms, etc.) are installed in accordance with the approved plans.	
<input type="checkbox"/> Appropriate number and spacing of plants are installed in accordance with the approved plans.	
<input type="checkbox"/> Ponding depth verification after plant and mulch placement.	
<input type="checkbox"/> Certification of Pretreatment and Plant Installation: Inspector certifies the successful completion of any pretreatment measures, plants and mulch as listed above.	
<input type="checkbox"/> Photos required for this step include: <ul style="list-style-type: none"> Overall photos of showing mulch and plants installed; Location of inflow and appropriate energy dissipater; Any pretreatment measures required per the approved plans; Distance from the top of the mulch to the top of the overflow (either pipe or berm). 	
<input type="checkbox"/> Material delivery tickets required for this step include: <ul style="list-style-type: none"> Approved plants listing number and species; Shredded hardwood mulch. 	

All items checked above have been inspected by me (or by an individual under my responsible charge) and have been completed to my satisfaction and meet the approved plans (or deviations are noted here).

Signature: _____ Date: _____

Certifying Professional's License Number (or Seal): _____

Construction Inspection Checklist: Urban Bioretention

Address/Location: _____ Building Permit #: _____
 LDA Permit #: _____ SWM#: _____
 Contractor: _____ Telephone: _____
 Certifying Professional*: _____ Telephone: _____
 Date Started: _____ Final Inspection Date: _____



The following checklist provides a basic outline of the anticipated items for the construction inspection of urban bioretention facilities. This checklist does not necessarily distinguish between all the design variations and differences in construction between the family of practices. Inspectors should review the plans carefully, and adjust these items and the timing of inspection verification as needed to ensure the intent of the design is met. The standard for design of this practice is based on Virginia Stormwater BMP Clearinghouse and Arlington County Stormwater Guidance Manual.

All items should be crossed off when completed. Items labeled "Certification of..." must be crossed off, dated and initialed by the certifying inspector.

PRE-CONSTRUCTION MEETING	DATE
<input type="checkbox"/> Pre-construction meeting with the contractor designated to install the planter boxes, County DES inspector, and person completing this checklist has been conducted.	
<input type="checkbox"/> Stormwater has been diverted around the area of the bioretention practice and perimeter erosion control measures to protect the facility during construction have been installed.	

EXCAVATION AND BOX CONSTRUCTION	DATE
<input type="checkbox"/> Area is marked and the size and location conforms to plan.	
<input type="checkbox"/> Excavation has achieved proper grades and the required geometry and elevations.	
<input type="checkbox"/> Box is constructed using the material specified and to the required dimensions as shown on the approved plans. Constructed interior dimensions:	
<input type="checkbox"/> Waterproofing is installed on sides and bottom of interior of the box as specified.	
<input type="checkbox"/> Certification of Excavation and Box Construction Inspection: Inspector certifies the successful completion of the steps listed above and any necessary photos are attached.	
<input type="checkbox"/> Photo required of entire interior (sides and bottom) of planter box waterproofed.	
<input type="checkbox"/> Material ticket required of waterproofing membrane if plastic membrane is used (no receipt required for liquid membrane).	

FILTER LAYER, UNDERDRAIN, AND STONE RESERVOIR PLACEMENT	DATE
<input type="checkbox"/> All aggregates conform to specifications as certified by quarry.	
<input type="checkbox"/> Underdrain size and perforations meet the specifications (holes should be spaced 6" apart, maximum of 3 rows of holes). Placement of underdrain, observation wells, and underdrain fittings are in accordance with the approved plans.	
<input type="checkbox"/> Elevations of underdrain and outlet structure are in accordance with approved plans, or as adjusted to meet field conditions and denoted in Comments section below.	
<input type="checkbox"/> Placement of remaining lift of stone reservoir layer as needed to achieve the required reservoir depth.	
<input type="checkbox"/> Certification of Filter Layer and Underdrain Placement Inspection: Inspector certifies the successful completion of the filter layer and underdrain placement steps listed above. Photos and material delivery tickets for these items are attached.	
<input type="checkbox"/> Photos required include: <ul style="list-style-type: none"> Perforated underdrain pipe with a solid vertical overflow pipe; Depth of #57 stone; Depth of choker stone (pea gravel or #8). 	
<input type="checkbox"/> Material delivery tickets required: <ul style="list-style-type: none"> #57 stone and choker stone (pea gravel or #8) 	

BIORETENTION SOIL MEDIA PLACEMENT	DATE
<input type="checkbox"/> Soil media is certified by supplier or contractor as meeting the project specifications.	
<input type="checkbox"/> No filter fabric is to be used between the stone layer and the soil layer. Soil media is placed in 12-inch lifts to the design top elevation of the bioretention area. Elevation has been verified after settlement (2 to 4 days after initial placement).	
<input type="checkbox"/> Certification of Soil Media Placement Inspection: Inspector certifies the successful completion of the soil media steps listed above. Photos and material delivery tickets for these items are attached.	
<input type="checkbox"/> Photo required includes a measurement of the soil media installed.	
<input type="checkbox"/> Material delivery ticket required from an approved soil media vendor.	


PRETREATMENT AND PLANT INSTALLATION	DATE
<input type="checkbox"/> Placement of energy dissipaters and pretreatment practices (splash block/rocks, gutter guards, etc.) are installed in accordance with the approved plans.	
<input type="checkbox"/> Overflow has aluminum grate installed.	
<input type="checkbox"/> Downspouts are installed in accordance with the approved plans providing the correct drainage area.	
<input type="checkbox"/> The number and spacing of plants are installed in accordance with the approved plans. If there is no approved landscape plan for the planter boxes, the plant are to be chosen from VA DEQ Stormwater Design Specification No. 9: Table 9-4 Popular Native Plant Materials for Bioretention.	
<input type="checkbox"/> A 2-3 inch layer of shredded hardwood mulch has been installed.	
<input type="checkbox"/> Certification of Pretreatment and Plant Installation Inspection: Inspector certifies the successful completion of the pretreatment, energy dissipaters, plants, overflow grates and mulch as listed above. Photos and copies of material delivery tickets are attached.	
<input type="checkbox"/> Photos required for this step for each planter include: <ul style="list-style-type: none"> Overall photo showing the number of plants installed; Location of downspout/overflow pipe with the appropriate splash block/rocks; Distance from the top of mulch to the top of the overflow pipe; Distance from the top of mulch to the top of the planter box. 	
<input type="checkbox"/> Material delivery tickets required for this step include: <ul style="list-style-type: none"> Approved plants listing number and species; Shredded hardwood mulch. 	

DRY WELL OR CONNECTION TO STORM SEWER	DATE
<input type="checkbox"/> Dry well is constructed to the correct dimensions and proper materials including the proper geotextile, stone, and overflow mechanism (pop-up emitter) per the plan (if applicable).	
<input type="checkbox"/> Underdrain is directly tied into the public storm sewer system and the connection has been witnessed by DES inspector (if applicable).	
<input type="checkbox"/> Certification of Dry Well or Connection to Storm Sewer: Inspector certifies the successful completion of the dry well or connection to the storm sewer. Photos and material delivery tickets for these items are attached.	
<input type="checkbox"/> Photos required for dry well include: <ul style="list-style-type: none"> Excavated dry well with fabric installed on sides (no fabric on bottom); Dimensions of dry well (L x W x D); Perforated pipe installed inside of dry well; Solid pipe for any pipe located outside of dry well (above gravel to grade); Depth of #57 stone; Fabric installed on top of gravel; Completed dry well with turf cover and pop-up emitter installed. 	
<input type="checkbox"/> Material Tickets required: <ul style="list-style-type: none"> Geotextile used; #57 stone. 	

All items checked above have been inspected by me (or by an individual under my responsible charge) and have been completed to my satisfaction and meet the approved plans (or deviations are noted here).

Signature: _____ Date: _____


Certifying Professional's License Number (or Seal): _____




- TRENCH DRAIN GRATE DOES NOT CONTINUE OVER CATCH BASIN
- PROVIDE SHIP DRAWINGS FOR REVIEW BY ARCHITECT

4 TRENCH DRAIN DETAIL


1" = 1'-0"



1 TRENCH DRAIN CONNECTION #1 TYPICAL SECTION
(ALONG UNDERDRAIN)



2 TRENCH DRAIN CONNECTION #2 TYPICAL SECTION
(ALONG UNDERDRAIN)



3 TRENCH DRAIN CONNECTION #3 TYPICAL SECTION
(ALONG UNDERDRAIN)

Facility Type**	Description	Location	LDA Permit	Project SWM#	Building Permit	Facility ID	BMP downstr am of another BMP (in Primary Series)?	Upstrea m BMP	Chesapeake Bay Segment	Watershed	HUC6	Soils	Runoff Treated (in)	Volume Treated (ft ³)	Treated Area (acres)	Forest Area (acres)	Turf Area (acres)	Impervio us Area (acres)	Phosphorus Efficiency (%)	Nitrogen Efficiency (%)	Sediment Efficiency (%)	TP load removed (lbs)	TN load removed (lbs)	
BIORETENTION LEVEL 1	Bioretention	Queens Ct Park	LD14382	20-0120	0	20-0120A	No		POTTE_VA	Colonial Village Branch	PL24	C/D	1.00	689.4	0.2318	0.0000	0.0433	0.1885	16034PCB	55.00	64.00	75.00	0.24	1.98
URBAN BIORETENTION LEVEL 1	Urban Bioretention	#16	LD14382	20-0120	0	20-0120B			POTTE_VA	Colonial Village Branch		C/D	1.00	72.7	0.0211	0.0000	0.0000	0.0211	16034PCB	55.00	64.00	75.00	0.03	0.21
URBAN BIORETENTION LEVEL 1	Urban Bioretention	#17	LD14382	20-0120	0	20-0120C			POTTE_VA	Colonial Village Branch		C/D	1.00	71.6	0.0208	0.0000	0.0000	0.0208	16034PCB	55.00	64.00	75.00	0.02	0.21
URBAN BIORETENTION LEVEL 1	Urban Bioretention	#18	LD14382	20-0120	0	20-0120D			POTTE_VA	Colonial Village Branch		C/D	1.00	46.1	0.0134	0.0000	0.0000	0.0134	16034PCB	55.00	64.00	75.00	0.02	0.13



DEPARTMENT OF PARKS AND RECREATION

Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

BMP COMPUTATIONS

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20

Designed: FA
 Drawn: EF
 Checked: KMM




Filename:
 Plotted: Sep. 9, 20
 Date: APRIL 15, 2020

Scale: AS SHOWN
 Date: APRIL 15, 2020



Seal



Sheet **C1.12**



- Pre-Construction Meeting**
- Pre-construction meeting with the contractor designated to install the bioretention practice has been conducted.
 - Identify the tentative schedule for construction and verify the requirements and schedule for interim inspections and sign-off.
 - Subsurface investigation and soils report supports the placement of an bioretention practice in the proposed location.
 - Impervious cover has been constructed installed and area is free of construction equipment, vehicles, material storage, etc.
 - All pervious areas of the contributing drainage areas have been adequately stabilized with a thick layer of vegetation and erosion control measures have been removed.
 - Area of bioretention practice has not been impacted during construction.
 - Stormwater has been diverted around the area of the bioretention practice and perimeter erosion control measures to protect the facility during construction have been installed.
- Excavation**
- Compare the bioretention surface and invert design elevations with the actual constructed elevations of the inflow and outlet inverts and adjust design elevations as needed.
 - Area of bioretention excavation is marked and the size and location conforms to plan.
 - If the excavation area has been used as a sediment trap, verify that the bottom elevation of the proposed stone reservoir is lower than the bottom elevation of the existing trap.
 - For Level 2 bioretention, ensure the bottom of the excavation is scarified prior to placement of stone.
 - Subgrade surface is free of rocks and roots, and large voids. Any voids should be refilled with the base aggregate to create a level surface for the placement of aggregates and underdrain (if required).
 - No groundwater seepage or standing water is present. Any standing water is dewatered to an acceptable dewatering device.
 - Excavation of the bioretention practice has achieved proper grades and the required geometry and elevations without compacting the bottom of the excavation.
 - Certification of Excavation Inspection:** Inspector certifies the successful completion of the excavation steps listed above.
- Filter Layer, Underdrain, and Stone Reservoir Placement**
- All aggregates, including, as required, the filter layer (choker stone & sand), the stone reservoir layer or infiltration sump conform to specifications as certified by quarry.
 - Underdrain size and perforations meet the specifications.
- Bioretention Soil Media Placement**
- Soil media is certified by supplier or contractor as meeting the project specifications.
 - Soil media is placed in 12-inch lifts to the design top elevation of the bioretention area. Elevation has been verified after settlement (2 to 4 days after initial placement).
 - Side slopes of ponding area are feathered back at the required slope (no steeper than 3H:1V).
 - Certification of Soil Media Placement Inspection:** Inspector certifies the successful completion of the soil media steps listed above.
- Pretreatment and Plant Installation**
- Placement of energy dissipators and pretreatment practices (forebays, gravel diaphragms, etc.) are installed in accordance with the approved plans.
 - Riser, overflow weir, or other outflow structure is set to the proper elevation and functional; or,
 - External bypass structure is built in accordance with the approved plans.
 - Appropriate number and spacing of plants are installed in accordance with the approved plans.
 - All erosion and sediment control practices have been removed.
 - Follow-up inspection and as-built survey/certification has been scheduled.
- For Level 2 installations:** placement of filter layer and initial lift of stone reservoir layer aggregates with underdrain or infiltration sump, spread (not dumped) to avoid aggregate segregation; or
- Impermeable liner, when required, meets project specifications and is placed in accordance with manufacturers specifications.
- Sides of excavation covered with geotextile, when required, prior to placing stone reservoir aggregate; no tears or holes, or excessive wrinkles are present.
- Placement of underdrain, observation wells, and underdrain fittings (45 degree wees, cap at the upstream end, etc.) are in accordance with the approved plans.
- Elevations of underdrain and outlet structure are in accordance with approved plans, or as adjusted to meet field conditions.
- Placement of remaining lift of stone reservoir layer as needed to achieve the required reservoir depth.
- Certification of Filter Layer and Underdrain Placement Inspection:** Inspector certifies the successful completion of the filter layer and underdrain placement steps listed above.



July 2014 (Revised April 2015). Sizing spreadsheet for SW planters for compliance with Arlington County Stormwater Management Ordinance
Enter data into highlighted cells. WQV needs to > 100% for credit.

Facility name/type	Impervious Area to Facility (SF)	Pervious Area to Facility (SF)	Total Drainage Area (SF)	Total Drainage Area (acre)	Rainfall Depth (P) (in)	Rv	Target storage (WQV) (CF)	Width (ft)	Length (ft)	Ponding depth (in)	Filter depth (in)	Gravel depth (in)	Surface Area (SF)	Ponding Volume (1.00 void) (CF)	Soil Storage Volume (0.25 void) (CF)	Gravel Storage Volume (0.4 void) (CF)	Available Storage (CF)	% Water Quality Volume Captured (Must be ≥ 100% (Max. 200%))
Stormwater Planter Box #16	918	72	990	0.0227	1.00	0.90	74.00	12.00	6.00	6	45	12	72.00	36.00	67.50	28.80	132.30	178.8%
Stormwater Planter Box #17	904	75	979	0.0225	1.00	0.89	72.94	12.00	6.00	6	45	12	72.00	36.00	67.50	28.80	132.30	181.4%
Stormwater Planter Box #18	582	75	657	0.0151	1.00	0.87	47.45	12.00	6.00	3	27	12	72.00	18.00	40.50	28.80	87.30	184.0%

URBAN BIORETENTION SPECIFICATIONS & MAINTENANCE

Material Specifications: Below is the table of material specifications for stormwater planter boxes.

Material	Specification	Notes
Waterproofing	Water Tight shell or impermeable liner	Use a thirty mil (minimum) PVC Geomembrane liner or equivalent.
Filter Media Composition	Filter Media to contain: <ul style="list-style-type: none"> 80%-90% sand with >75% being coarse to very coarse 10%-20% soil fines 3%-5% organic matter in the form of plant based compost meeting Clearinghouse Design Specification #4, Section 6.5 	The volume of filter media based on 110% of the plan volume, to account for settling or compaction.
Filter Media Testing	Plant available P within Low+ (+) to Medium (M) per DCR 2014 Nutrient Management Criteria (18-40 mg/kg P for the Mehlich III procedure) and CEC >5	The media must be procured from approved filter media vendors.
Mulch Layer	Use aged, shredded hardwood bark mulch 3 inch layer of pea gravel or VDOT #8 stone which is laid over the underdrain stone.	Lay a 2 to 3 inch layer on the surface of the filter bed.
Choking Layer	1 inch stone should be double-washed and clean and free of all fines (e.g., VDOT #57 stone).	12 inches for the underdrain
Stone Jacket for Underdrain and/or Storage Layer	Use 4 inch rigid schedule 40 PVC pipe with 3/8-inch perforations at 6 inches on center, maximum of 3 rows of perforations; position each underdrain on a 1% or 2% slope.	Lay the perforated pipe under the length of the planter box, and install non-perforated pipe as needed to connect with the storm drain system. Install T's and Y's as needed, depending on the underdrain configuration. Extend overflow pipes to the surface with vented caps.
Underdrains and Overflows	1 quart-sized perennial installed per 1-2 sf and/or 1 3-gallon shrub installed per 7.5 sf over entire ponding area from DEQ Specification 9: Table 9.5	Choose either herbaceous and/or shrubs

Planter Box Maintenance Schedule

Maintenance	Frequency
Spot weeding, erosion repair, trash removal, and mulch raking	Twice during growing season
Add reinforcement planting to maintain the desired vegetation density	As needed
Remove invasive plants using recommended control methods	As needed
Stabilize the contributing drainage area to prevent erosion	As needed
Spring inspection and cleanup	Annually
Supplement mulch to maintain a 2-3 inch layer	Annually
Prune trees and shrubs	Annually
Examine for the ponding depth and adjust accordingly	Annually
Inspect inflows and overflow for erosion	Annually
Inspect for structural deficiencies and repair	Annually
Remove sediment in pre-treatment cells and inflow points	Once every 2 to 3 years
Replace the mulch layer	Every 3 years
Inspected and certified by a professional licensed in the State of Virginia	Once every 5 years



DEPARTMENT OF PARKS AND RECREATION
Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET
ARLINGTON, VIRGINIA

Sheet Title

BMP COMPUTATIONS


Approval Date
LUKE VANBELLEGHEM 4.15.2020
Design Supervisor

Revisions Date
LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20


Designed: FA
Drawn: EF
Checked: KMM

Filename:
Plotted: Sep. 9, 20

Scale: AS SHOWN
Date: APRIL 15, 2020



Sheet **C1.13**
11 of 16



SWM/BMP NARRATIVE:

THE 44,727 SQ. FT (1.03 ACRE) SITE IS LOCATED AT 1801 N. QUINN ST. THE PROJECT PROPOSES REDEVELOPMENT OF THE EXISTING QUEENS COURT APARTMENTS, LOCATED AT 1801 N. QUINN ST. IN THE WESTERN ROSSLYN COORDINATED REDEVELOPMENT DISTRICT. THE TOTAL LAND DISTURBED AREA FOR THIS PROJECT IS APPROXIMATELY 1.38 ACRES THIS AREA INCLUDES THE WORK WITHIN THE RIGHT OF WAY.

THE PROPOSED DRAINAGE AREA 'A', CONTAINS A PORTION OF THE ROOFTOP AREA, STORMWATER RUNOFF WITHIN THIS DRAINAGE AREA WILL BE ROUTED THROUGH A STORMWATER MANAGEMENT/BEST MANAGEMENT PRACTICE (SWM/BMP) VAULT, LOCATED WITHIN THE UNDERGROUND PARKING GARAGE. A NON-PROPRIETARY BMP PRACTICE IS PROPOSED IN DRAINAGE AREA 'A' TO REDUCE RUNOFF TO THE PROPOSED SWM/BMP FACILITY. APPROXIMATELY 0.08 ACRES OF ROOF AREA IS GREEN ROOF.

MANUFACTURED TREATMENT DEVICE(MTD) WITH A 50% ACCEPTED PHOSPHORUS REMOVAL RATE WILL BE PLACED WITHIN THE GARAGE TO TREAT THE REQUIRED WATER QUALITY VOLUME THAT WAS COMPUTED USING THE VIRGINIA RUNOFF REDUCTION SPREADSHEET. 0.0809 AC OF THE REMAINING ROOFTOP RUNOFF AS WELL AS TREATMENT TRAINS FROM THE GREEN ROOF IN DRAINAGE AREA 'A' WILL BE TREATED BY THIS MTD LOCATED IN THE NORTHWEST CORNER OF THE PARKING GARAGE.

THE PROPOSED DRAINAGE AREA 'B' CONTAINS PART OF THE PROPOSED BUILDING. STORMWATER RUNOFF WITH THIS DRAINAGE AREA WILL BE ROUTED THROUGH A BIORETENTION, LOCATED EAST OF THE PROPOSED BUILDING. A NON-PROPRIETARY BMP PRACTICE IS PROPOSED IN DRAINAGE AREA 'B' TO REDUCE RUNOFF TO THE PROPOSED SWM/BMP FACILITY. APPROXIMATELY 0.08 ACRES OF ROOF AREA IS GREEN ROOF THAT WILL DRAIN INTO THE PROPOSED STORMWATER PLANTERS(BIORETENTION) LOCATED AT THE SOUTHEAST CORNER OF THE BUILDING.

THE PROPOSED DRAINAGE AREA 'C' CONTAINS THE PARK AREA AND WILL BE TREATED BY TWO LEVEL 1 BIORETENTION AREAS. APPROXIMATELY 0.21 ACRES OF THE PARK AREA WILL DRAIN INTO A BIORETENTION (LEVEL 1) PROVIDED BY OTHERS.

THE PROPOSED DRAINAGE AREA 'D' CONTAINS THE ROW AND SIDEWALK AREA AND WILL BE TREATED BY THIRTEEN(13) LEVEL 1 URBAN BIORETENTION AREAS. APPROXIMATELY 0.44 ACRES OF THE STREET WILL DRAIN INTO THIRTEEN(13) URBAN BIORETENTIONS (LEVEL 1) CONSISTING OF 0.04 AC SURFACE AREA AND THREE (3) URBAN BIORETENTIONS (LEVEL 1) CONSISTING OF 0.04 AC SURFACE AREA.

WATER QUALITY TREATMENT WILL BE PROVIDED IN MANY FORMS FOR THE SUBJECT SITE. THE TOTAL PHOSPHOROUS LOAD REDUCTION REQUIRED IS 1,1840 (LB/YEAR) PER THE VRRM SPREADSHEET COMPUTATIONS LOCATED ON SHEET C17.05. 1,1967 LB/YEAR REMOVAL WAS ACHIEVED. THEREFORE WATER QUALITY HAS BEEN MET.



THE SWM/BMP FACILITY TREATING DRAINAGE AREA 'A' HAS BEEN SIZED TO PROVIDE A TOTAL OF 3,260 CUBIC FEET OF STORAGE, EXCEEDING THE 3,158 CUBIC FOOT REQUIREMENT SET FORTH BY THE ENERGY BALANCE EQUATION, FOUND ON SHEET C17.10. FLOW WILL BE DETAINED BEHIND AN INTERNAL CONTROL STRUCTURE BEFORE BEING RELEASED INTO THE EXISTING STORM NETWORK ALONG N QUINN STREET. IT IS THE OPINION OF THE SUBMITTING ENGINEER THAT THE PROPOSED DESIGN WILL HAVE NO ADVERSE IMPACTS TO ADJACENT PROPERTIES.

NOTE:

ARLINGTON COUNTY DOES NOT REVIEW THE WATERPROOFING DESIGN AND THE OWNER/DEVELOPER AGREES TO HOLD ARLINGTON COUNTY HARMLESS IN THE EVENT OF FAILURE.

* INSTALLED AND MAINTAINED BY APAH
 ** INSTALLED BY DPR AND MAINTAINED BY APAH
 *** INSTALLED AND MAINTAINED BY DPR


Matthew K. Koirtyohann
 Digitally signed by Matthew K. Koirtyohann
 Date: 2019.02.28 14:07:05 -05'00'



Bowman CONSULTING

Bowman Consulting Group, Ltd.
 14020 Thunderbolt Place, Suite 300
 Chantilly, Virginia 20151
 © Bowman Consulting Group, Ltd.

Phone: (703) 464-1000
 Fax: (703) 481-9720
 www.bowmanconsulting.com



ARLINGTON COUNTY, VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES
 STORMWATER MANAGEMENT PLAN
QUEENS COURT
 CIVIL ENGINEERING PLAN
 SITE PLAN #444
 1615 18TH STREET NORTH
 ARLINGTON, VIRGINIA 22209
 ARLINGTON COUNTY, VIRGINIA

SCALE: 1"=25'
 SHEET C17.00

ARLINGTON VIRGINIA DEPARTMENT OF ENVIRONMENTAL SERVICES

DENNIS W. LEACH
 DEPUTY DIRECTOR, DES - TRANSPORTATION & DEVELOPMENT

3/18/2019
 APPROVAL DATE



DEPARTMENT OF PARKS AND RECREATION

Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB#21-DPR-ITB-304
 SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA
 Sheet Title

BMP COMPUTATIONS

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20

Designed: FA
 Drawn: EF
 Checked: KMM
 Filename:
 Plotted: Sep. 9, 20
 Scale: AS SHOWN
 Date: APRIL 15, 2020



Sheet **C1.14**
 12 of 16

VIRGINIA RUNOFF REDUCTION METHOD COMPUTATIONS

DEQ Virginia Runoff Reduction Method Re-Development Compliance Spreadsheet - Version 3.0

BMP Design Specifications List: 2013 Draft Stds & Specs

Site Summary

Update Summary Sheet

Print Preview Print

Total Rainfall (in):	43
Total Disturbed Acreage:	1.3764

Site Land Cover Summary

Pre-ReDevelopment Land Cover (acres)

	A Soils	B Soils	C Soils	D Soils	Totals	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
Managed Turf (acres)	0.0000	0.0000	0.0000	0.6264	0.6264	61.0051
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.4004	0.4004	38.9949
				1.0268	1.0268	100.0000

Post-ReDevelopment Land Cover (acres)

	A Soils	B Soils	C Soils	D Soils	Totals	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0160	0.0160	1.5582
Managed Turf (acres)	0.0000	0.0000	0.0000	0.0343	0.0343	3.3405
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.9765	0.9765	95.1013
				1.0268	1.0268	100.0000

* Forest/Open Space areas must be protected in accordance with the Virginia Runoff Reduction Method

Site Tv and Land Cover Nutrient Loads

	Final Post-Development (Post-ReDevelopment & New Impervious)	Post-ReDevelopment	Post-Development (New Impervious)	Adjusted Pre-ReDevelopment
Site Rv	0.9136	0.8648	0.9500	0.8719
Treatment Volume (ft ³)	3,401.4915	1,414.8107	1,986.6809	1,426.4267
TP Load (lb/yr)	2.1371	0.8889	1.2482	0.8962

Pre-ReDevelopment TP Load per acre (lb/acre/yr)	Final Post-Development TP Load per acre (lb/acre/yr)	Post-ReDevelopment TP Load per acre (lb/acre/yr)
1.9900	2.0800	1.9700

Drainage Area B Summary

Land Cover Summary

	A Soils	B Soils	C Soils	D Soils	Total	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Managed Turf (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.2003	0.2003	100

BMP Selections

Practice	Managed Turf Credit Area (acres)	Impervious Cover Credit Area (acres)	BMP Treatment Volume (ft ³)	TP Load from Upstream Practices (lbs)	Untreated TP Load to Practice (lbs)	TP Removed (lb/yr)	TP Remaining (lb/yr)	Downstream Treatment to be Employed
1.b. Vegetated Roof #2 (Spec #5)		0.0787	271.3970		0.1703	0.1022	0.0681	6.a. Bioretention #1
6.a. Bioretention #1 or Micro-Bioretention #1 or Urban Bioretention (Spec #9)		0.1216	527.8964	0.0681	0.2632	0.1822	0.1491	14.a. MTD - Hydrodynamic
14.a. Manufactured Treatment Device-Hydrodynamic			316.7378	0.1491	0.0000	0.0298	0.1193	

Total Impervious Cover Treated (acres)	0.2003
Total Turf Area Treated (acres)	0.0000
Total TP Load Reduction Achieved in D.A. (lb/yr)	0.3142
Total TN Load Reduction Achieved in D.A. (lb/yr)	2.2479

VIRGINIA RUNOFF REDUCTION METHOD DRAINAGE AREA C COMPUTATIONS

Drainage Area C Summary

Land Cover Summary

	A Soils	B Soils	C Soils	D Soils	Total	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0160	0.0160	7
Managed Turf (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.1982	0.1982	93
				0.2142	0.2142	

BMP Selections

Practice	Managed Turf Credit Area (acres)	Impervious Cover Credit Area (acres)	BMP Treatment Volume (ft ³)	TP Load from Upstream Practices (lbs)	Untreated TP Load to Practice (lbs)	TP Removed (lb/yr)	TP Remaining (lb/yr)	Downstream Treatment to be Employed
6.a. Bioretention #1 or Micro-Bioretention #1 or Urban Bioretention (Spec #9)	0.0000	0.1982	683.4927	0.0000	0.4290	0.2359	0.1930	

Total Impervious Cover Treated (acres)	0.1982
Total Turf Area Treated (acres)	0.0000
Total TP Load Reduction Achieved in D.A. (lb/yr)	0.2359
Total TN Load Reduction Achieved in D.A. (lb/yr)	1.9639

VIRGINIA RUNOFF REDUCTION METHOD DRAINAGE AREA D COMPUTATIONS

Drainage Area D Summary

Land Cover Summary

	A Soils	B Soils	C Soils	D Soils	Total	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Managed Turf (acres)	0.0000	0.0000	0.0000	0.0319	0.0319	7
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.4089	0.4089	93
				0.4408	0.4408	

BMP Selections

Practice	Managed Turf Credit Area (acres)	Impervious Cover Credit Area (acres)	BMP Treatment Volume (ft ³)	TP Load from Upstream Practices (lbs)	Untreated TP Load to Practice (lbs)	TP Removed (lb/yr)	TP Remaining (lb/yr)	Downstream Treatment to be Employed
6.a. Bioretention #1 or Micro-Bioretention #1 or Urban Bioretention (Spec #9)	0.0319	0.4089	1,439.0409	0.0000	0.9031	0.4967	0.4064	

Total Impervious Cover Treated (acres)	0.4089
Total Turf Area Treated (acres)	0.0319
Total TP Load Reduction Achieved in D.A. (lb/yr)	0.4967
Total TN Load Reduction Achieved in D.A. (lb/yr)	4.1349

STRUCTURAL BMP POLICY COMPLIANCE:

THE TREATMENT TRAINS IN THIS PLAN WERE DESIGNED IN ACCORDANCE WITH THE ARLINGTON COUNTY MEMO "USE OF STRUCTURAL STORMWATER TREATMENT SYSTEMS", DATED MARCH 30, 2018. SEE MANUFACTURED TREATMENT DEVICE DRAINAGE AREA COMPUTATIONS BELOW:

MTD (FILTERING):

TOTAL TP REMOVED WITH BOTH RR AND NON-RR SWMF: 0.1499 LB/YR (100% ROOF AREA, 0% VEHICULAR USE)
TOTAL ROOF TP TREATED BY RR SWMF: 0.1051 LB/YR
PERCENTAGE OF TP TREATED PRIOR TO MTD: 0.1051/0.1499 = 70% = ACCEPTABLE

RUNOFF VOLUME AND CN CALCULATIONS

Runoff Volume and CN Calculations

Target Rainfall Event (in)	1-year storm	2-year storm	10-year storm
	2.69	3.10	4.84

Drainage Areas	RV & CN	Drainage Area A	Drainage Area B	Drainage Area C	Drainage Area D	Drainage Area E
CN		98	98	96	97	0
RR (ft ³)		167.3902	373.9967	273.3971	575.6164	0.0000
1-year return period	RV w RR (ws-in)	2.4597	2.4597	2.2474	2.3514	0.0000
	RV w RR (ws-in)	2.0323	1.9453	1.8958	1.9917	0.0000
2-year return period	RV w RR (ws-in)	2.8679	2.8679	2.6506	2.7574	0.0000
	RV w RR (ws-in)	2.4405	2.3535	2.2990	2.3977	0.0000
10-year return period	RV w RR (ws-in)	4.6034	4.6034	4.3736	4.4877	0.0000
	RV w RR (ws-in)	4.1761	4.0891	4.0219	4.1279	0.0000
	CN adjusted	94	93	92	93	0

Site Compliance Summary

Maximum % Reduction Required Below Pre-ReDevelopment Load	20%
---	-----

Total Runoff Volume Reduction (ft ³)	1,390.4004
Total TP Load Reduction Achieved (lb/yr)	1.1967
Total TN Load Reduction Achieved (lb/yr)	9.0983
Remaining Post Development TP Load (lb/yr)	0.9405
Remaining TP Load Reduction (lb/yr) Required	0.0000

** TARGET TP REDUCTION EXCEEDED BY 0.0127 LB/YEAR **

VIRGINIA RUNOFF REDUCTION METHOD DRAINAGE AREA A COMPUTATIONS

Drainage Area A Summary

Land Cover Summary

	A Soils	B Soils	C Soils	D Soils	Total	% of Total
Forest/Open (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Managed Turf (acres)	0.0000	0.0000	0.0000	0.0000	0.0000	0
Impervious Cover (acres)	0.0000	0.0000	0.0000	0.1079	0.1079	100
				0.1079	0.1079	

BMP Selections

Practice	Managed Turf Credit Area (acres)	Impervious Cover Credit Area (acres)	BMP Treatment Volume (ft ³)	TP Load from Upstream Practices (lbs)	Untreated TP Load to Practice (lbs)	TP Removed (lb/yr)	TP Remaining (lb/yr)	Downstream Treatment to be Employed
1.b. Vegetated Roof #2 (Spec #5)		0.0809	278.9837		0.1751	0.1051	0.0700	14.a. MTD - Hydrodynamic
14.a. Manufactured Treatment Device-Hydrodynamic		0.0090	142.6300	0.0700	0.0195	0.0448	0.0448	

Total Impervious Cover Treated (acres)	0.0899
Total Turf Area Treated (acres)	0.0000
Total TP Load Reduction Achieved in D.A. (lb/yr)	0.1498
Total TN Load Reduction Achieved in D.A. (lb/yr)	0.7515

THIS SHEET IS FOR INFORMATIONAL PURPOSES ONLY



DEPARTMENT OF PARKS AND RECREATION

Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

BMP COMPUTATIONS

Approval Date

LUKE VANBELLEGHEM 4.15.2020
Design Supervisor

Revisions Date

LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: FA

Drawn: EF

Checked: KMM

Filename:

Plotted: Sep. 9, 20

Scale: AS SHOWN

Date: APRIL 15, 2020

Seal



Sheet

C1.15

13 of 16

Bowman CONSULTING
Bowman Consulting Group, Ltd.
14020 Thunderbolt Place, Suite 300
Chantilly, Virginia 20151
www.bowmanconsulting.com

Phone: (703) 464-1000
Fax: (703) 481-9720

ARLINGTON COUNTY, VIRGINIA
DEPARTMENT OF ENVIRONMENTAL SERVICES
WATER QUALITY COMPUTATIONS
QUEENS COURT
CIVIL ENGINEERING PLAN
SITE PLAN #444
1615 18TH STREET NORTH
ARLINGTON, VIRGINIA 22209
ARLINGTON COUNTY, VIRGINIA

SCALE: 1"=25' SHEET: C17.05

3/18/2019 APPROVAL DATE

DENNIS W. LEACH
DEPUTY DIRECTOR, DES - TRANSPORTATION & DEVELOPMENT

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK

BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

BMP COMPUTATIONS

Approval Date

LUKE VANBELLEGHEM 4.15.2020
Design Supervisor

Revisions Date

LDA SUBMISSION 4/15/20
LDA SUBMISSION REV. 7/14/20
LDA SUBMISSION REV. 9/08/20

Designed: FA

Drawn: EF

Checked: KMM

Filename:

Plotted: Sep. 9, 20

Scale: AS SHOWN

Date: APRIL 15, 2020

Seal



Sheet

C1.16

STORMWATER MANAGEMENT FACILITY INFORMATION

Stormwater Management Facility Information- Revised 6/3/2016

Facility Type**	Description	Location	LDA Permit #	Project SWM #	Building Permit #	Facility ID	BMP downstream of another BMP (in Series)?	Upstream (Primary) BMP	Watershed	Sub-basin	HUC6	Soils	Runoff Treated (in)	Volume Treated (ft ³)	Treated Area (acres)	Forest Area (acres)	Turf Area (acres)	Impervious Area (acres)	RPC	Phosphorus Efficiency (%)	Nitrogen Efficiency (%)	Sediment Efficiency (%)	TP load removed (lbs)	TN load removed (lbs)
BIORETENTION #1	Urban Bioretention #1	East of the building		18-0016		18-0016A	Yes	18-0016D	POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	527.9	0.0000	0.0000	0.0000	0.1216	16034017	55	64	75	0.18	1.52
BIORETENTION #1	Bioretention #2	South of the park		18-0016	0	18-0016B	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	646.5	0.1959	0.0000	0.0178	0.1781	16034017	55	64	75	0.22	1.86
VEGETATED ROOF #1	Vegetated Roof #1	West vegetated rooftop		18-0016	0	18-0016C	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	279.0	0.0809	0.0000	0.0000	0.0809	16034017	45	45	75	0.11	0.75
VEGETATED ROOF #1	Vegetated Roof #2	East vegetated rooftop		18-0016	0	18-0016D	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	271.4	0.0787	0.0000	0.0000	0.0787	16034017	45	45	75	0.10	0.73
UNDERGROUND	Vault	Vault		18-0016	0	18-0016E	Yes	18-0016C	POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	0.00	0.0	0.0000	0.0000	0.0000	0.0000	16034017	0	0	0	0.00	0.00
MANUFACTURED BMP	Jellyfish or approved Equal	MTD		18-0016	0	18-0016F	Yes	18-0016C	POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	204.7	0.0000	0.0000	0.0000	0.0809	16034017	0	0	0	0.00	0.00
BIORETENTION #1	Urban Bioretention #3	Eastern Key Boulevard Urban Bioretention		18-0016	0	18-0016G	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	96.3	0.0295	0.0000	0.0020	0.0275	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #4	2nd from the east end of Key Boulevard Urban Bioretentions		18-0016	0	18-0016H	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	73.2	0.0228	0.0000	0.0020	0.0208	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #5	2nd from the west end of Key Boulevard Urban Bioretentions		18-0016	0	18-0016I	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	144.8	0.0442	0.0000	0.0028	0.0413	16034017	55	64	75	0.05	0.00
BIORETENTION #1	Urban Bioretention #6	Western Key Boulevard Urban Bioretention		18-0016	0	18-0016J	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	63.5	0.0211	0.0000	0.0034	0.0176	16034017	55	64	75	0.02	0.00
BIORETENTION #1	Urban Bioretention #7	Northern N. Quinn Street Bioretention		18-0016	0	18-0016K	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	59.8	0.0186	0.0000	0.0017	0.0169	16034017	55	64	75	0.02	0.00
BIORETENTION #1	Urban Bioretention #8	2nd from the north end of Quinn Street Urban Bioretentions		18-0016	0	18-0016L	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	71.9	0.0221	0.0000	0.0017	0.0205	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #9	3rd from the north end of Quinn Street Urban Bioretentions		18-0016	0	18-0016M	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	64.3	0.0199	0.0000	0.0017	0.0183	16034017	55	64	75	0.02	0.00
BIORETENTION #1	Urban Bioretention #10	3rd from the south end of Quinn Street Urban Bioretentions		18-0016	0	18-0016N	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	88.4	0.0269	0.0000	0.0017	0.0253	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #11	2nd from the south end of Quinn Street Urban Bioretentions		18-0016	0	18-0016O	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	88.4	0.0269	0.0000	0.0017	0.0253	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #12	Southern N. Quinn Street Urban Bioretention		18-0016	0	18-0016P	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	193.2	0.0595	0.0000	0.0045	0.0550	16034017	55	64	75	0.07	0.00
BIORETENTION #1	Urban Bioretention #13	Western 18th Street Urban Bioretention		18-0016	0	18-0016Q	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	77.3	0.0237	0.0000	0.0017	0.0220	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #14	2nd from the west end of 18th Street Urban Bioretentions		18-0016	0	18-0016R	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	90.8	0.0276	0.0000	0.0017	0.0259	16034017	55	64	75	0.03	0.00
BIORETENTION #1	Urban Bioretention #15	3rd from the west end of 18th Street Urban Bioretentions		18-0016		18-0016S	No		POTTF_VA	COLONIAL VILLAGE BRANCH	PL24	C/D	1.00	75.5	0.0232	0.0000	0.0017	0.0215	16034017	55	64	75	0.03	0.00

SITE INFORMATION

Project SWM #	LDA Permit #	Disturbed Area (acres)	% Pre-Impervious	% Post-Impervious	Pre-Development TP load (lb/yr)	Post-Development TP load (lb/yr)	TP load reduction achieved (lb/yr)	Pre-Development TN load (lb/yr)	Post-Development TN load (lb/yr)	TN load reduction achieved (lb/yr)	Total Site Area (acres)	Pre-Forest Area (acres)	Pre-Turf Area (acres)	Pre-Impervious Area (acres)	Post-Forest Area (acres)	Post-Turf Area (acres)	Post-Impervious Area (acres)	Site Latitude (Decimal Degrees)	Site Longitude (Decimal Degrees)	Anticipated Start Date
18-0016		1.3764	39.0	95.1	1.22	2.14	1.20	8.76	15.29	9.10	1.0268	0.0000	0.6264	0.4004	0.0160	0.0343	0.9765	38.895734	-77.078044	1/1/2019

URBAN BIORETENTION SIZING

July 2014 (Revised April 2015). Sizing spreadsheet for SW planters for compliance with Arlington County Stormwater Management Ordinance
Enter data into highlighted cells. WQV needs to > 100% for credit.

Facility name/type	Impervious Area to Facility (SF)	Perforated Area to Facility (SF)	Total Drainage Area (SF)	Total Drainage Area (acre)	Rainfall Depth (P) (in)	Rv	Target storage (WQV) (CF)	Width (ft)	Length (ft)	Ponding depth (in)	Filter depth (in)	Gravel depth (in)	Surface Area (SF)	Ponding Volume (1.00 void) (CF)	Soil Storage Volume (0.25 void) (CF)	Gravel Storage Volume (0.4 void) (CF)	Available Storage (CF)	% Water Quality Volume Captured (Must be ≥ 100%)
Stormwater Planter Box #1	8724	0	8724	0.2003	1.00	0.95	690.65	8.00	67.75	6	18	12	542.00	271.00	203.25	216.80	691.05	100.1%
Stormwater Planter Box #3	1196	89	1285	0.0295	1.00	0.90	96.32	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	142.0%
Stormwater Planter Box #4	904	89	993	0.0228	1.00	0.88	73.20	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	186.9%
Stormwater Planter Box #5	684	152	836	0.0192	1.00	0.82	56.94	6.00	18.00	6	48	12	108.00	54.00	108.00	43.20	205.20	360.4%
Stormwater Planter Box #7	738	72	810	0.0186	1.00	0.89	59.75	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	229.0%
Stormwater Planter Box #8	892	72	964	0.0221	1.00	0.90	71.94	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	190.2%
Stormwater Planter Box #9	795	72	867	0.0199	1.00	0.89	64.26	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	214.9%
Stormwater Planter Box #10	1320	72	1392	0.0320	1.00	0.91	105.82	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	129.3%
Stormwater Planter Box #11	1112	72	1184	0.0272	1.00	0.91	89.35	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	153.1%
Stormwater Planter Box #12	2451	139	2590	0.0595	1.00	0.91	196.59	8.00	17.38	6	48	12	139.04	69.52	139.04	55.62	264.18	134.4%
Stormwater Planter Box #13	1594	74	1668	0.0383	1.00	0.92	127.55	6.00	12.34	6	48	12	74.04	37.02	74.04	29.62	140.68	110.3%
Stormwater Planter Box #14	950	72	1022	0.0235	1.00	0.90	76.53	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	178.8%
Stormwater Planter Box #15	914	72	986	0.0226	1.00	0.90	73.68	6.00	12.00	6	48	12	72.00	36.00	72.00	28.80	136.80	185.7%

ENERGY BALANCE COMPUTATIONS

SWM Water Quantity Energy Balance Worksheet

SITE AREA (acre) 1.03

	PRE	POST (adjusted)	PRE	POST (adjusted)
P	2.69	2.69	4.84	4.84
CN	87	93	87	94
S=1000/CN-10	1.49	0.75	1.49	0.64
0.25	0.30	0.15	0.30	0.13
RV=(P-0.25) ² /(P-0.25)+5	1.47	1.96	3.42	4.15

QPost Development <= I.F.* (Qpre-development* RVpre-development)/RV(Developed)

I.F. 0.8

CHANNEL PROTECTION	From TR55	FLOOD CONTROL	
Qpre-development	2.34	Qpre-development	5.31
QPost Development	3.03	QPost Development	6.1
RVPost Development (with runoff reduction)	1.96	RVPost Development (with runoff reduction)	4.15
Qallowable	1.41	Qallowable	4.37

Qallowable/QPost Development 0.46

Vs/Vr 0.29

Vs 0.57

Storage required (cf) 2135

Qallowable/QPost Development 0.72

Vs/Vr 0.20

Vs 0.84

Storage required (cf) 3158

Fig 11.7 of DEQ Manual

where $V_s/V_r = \frac{V_s}{V_r} = C_s + C_1 \left(\frac{V_s}{V_r} \right)^2 + C_2 \left(\frac{V_s}{V_r} \right)^3$

where V_s/V_r = ratio of storage volume (V_s) to runoff volume (V_r)
 C_s = ratio of peak outflow discharge (Q_s) to peak inflow discharge (Q_i)
 C_1, C_2, C_3 = coefficients from table F-2

Table F-2 Coefficients for the equation used to generate Figure 6-1

Rainfall distribution (Appendix B)	C _s	C ₁	C ₂	C ₃
I, IA	0.600	-1.70	1.80	-0.700
II, III	0.682	-1.40	1.84	-0.800

TR-55 COMPUTATION REPORTS

ARB

Arlington County, Virginia

Watershed Peak Table

Sub-area or Reach Identifier	Peak Flow by Rainfall Return Period	
	1-Yr (cfs)	10-Yr (cfs)
SUBAREAS		
Pre	2.34	5.31
Post	3.03	6.31
Post 1 YR	3.03	6.01
Post 10 YR	3.14	6.10

Matthew K. Koiryohann


Digitally signed by Matthew K. Koiryohann
Date: 2019.02.28 14:08:04 -05'00'

Bowman CONSULTING

Bowman Consulting Group, Ltd.
14020 Thunderbolt Place, Suite 300
Chantilly, Virginia 20151
www.bowmanconsulting.com

Phone: (703) 464-1000
Fax: (703) 481-9720

ARLINGTON COUNTY, VIRGINIA
DEPARTMENT OF ENVIRONMENTAL SERVICES
WATER QUANTITY COMPUTATIONS
QUEENS COURT
CIVIL ENGINEERING PLAN
SITE PLAN #4444
1615 18



MISS UTILITY
 CALL "MISS UTILITY" AT 1-800-552-7001, 48 HOURS PRIOR TO THE START OF WORK. THE EXCAVATOR MUST NOTIFY ALL PUBLIC UTILITY COMPANIES WITH UNDERGROUND FACILITIES IN THE AREA OF PROPOSED EXCAVATION AND HAVE THOSE FACILITIES LOCATED BY THE UTILITY COMPANIES PRIOR TO COMMENCING EXCAVATION. THE EXCAVATOR IS RESPONSIBLE FOR COMPLIANCE WITH REQUIREMENTS OF LOCAL CODES AND REGULATIONS.

CAUTION!!
 THE LOCATIONS OF ALL EXISTING UNDERGROUND UTILITIES SHOWN ON THIS PLAN ARE BASED UPON ABOVE GROUND EVIDENCE (INCLUDING, BUT NOT LIMITED TO, MANHOLES, INLETS, VALVES, AND MARKS MADE UPON THE GROUND BY OTHERS) AND ARE SPECULATIVE IN NATURE. THERE MAY ALSO BE OTHER EXISTING UNDERGROUND UTILITIES FOR WHICH THERE IS NO ABOVE GROUND EVIDENCE OR FOR WHICH NO ABOVE GROUND EVIDENCE WAS OBSERVED. THE EXACT LOCATIONS OF SAID EXISTING UNDERGROUND UTILITIES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ANY AND ALL CONSTRUCTION.

NOTE!
 CONTRACTOR SHALL EXERCISE CAUTION WHEN EXCAVATING OVER AND AROUND EXISTING UTILITY SERVICES WITHIN THE PROJECT LIMITS. EXISTING UTILITY SERVICES TO BE PROTECTED FROM CONSTRUCTION ACTIVITIES AT ALL TIMES.

EXISTING CAPITAL BIKESHARE
 TO BE RELOCATED BY CAPITAL BIKESHARE TO A LOCATION REMOTE FROM THE QUEEN'S COURT PROJECT IN CONSULTATION WITH ARLINGTON COUNTY D.E.S. RELOCATION TO OCCUR BY JUNE, 2018.


HAZARDOUS MATERIALS
 ALL HAZARDOUS MATERIALS, INCLUDING ANY DOMESTIC WATER MATERIALS, MUST BE PROPERLY ABATED PRIOR TO DISTURBANCE IN ACCORDANCE WITH ENVIRONMENTAL SITE ASSESSMENTS PHASES I AND II.

DEMOLITION LEGEND:

	LIMITS OF CLEARING & GRADING
	SAW CUT PAVEMENT LINE (SEE PAVEMENT PLAN SHEET C11.00)
	EX. UTILITIES TO BE REMOVED
	EX. UTILITIES TO BE ABANDONED
	EXISTING BRICK SIDEWALK TO BE REMOVED
	EXISTING BUILDING TO BE DEMOLISHED
	EXISTING ASPHALT TO BE REMOVED
	EXISTING TO REMAIN
	EXISTING TO BE DEMOLISHED/REMOVED
	EXISTING TO BE ABANDONED
	EXISTING TO BE RELOCATED
	EXISTING TO BE REPLACED
	FOR EXISTING TREE TO BE REMOVED/PRESERVED, REFER TO TREE PRESERVATION PLAN ON SHEET T1.00

NOTE: EXISTING WATER METER(S) MAY BE USED DURING CONSTRUCTION WITH PROPER NOTIFICATION. PRIOR TO FINAL ACCEPTANCE, ALL INACTIVE WATER METERS SHALL BE PERMANENTLY DISCONNECTED BY THE CONTRACTOR AT THE WATER MAIN. ARLINGTON COUNTY WILL REMOVE THE EXISTING WATER METER FROM THE METER BOX AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING THE REMAINING WATER METER BOX.

* DENOTES UTILITY ITEM PROPOSED WITH 18TH STREET ROAD IMPROVEMENTS PLAN (BY OTHERS) *



THIS SHEET IS FOR INFORMATIONAL PURPOSES ONLY

Bowman CONSULTING
 Bowman Consulting Group, Ltd.
 14020 Thunderbolt Place, Suite 300
 Chantilly, Virginia 20151
 Phone: (703) 464-1000
 Fax: (703) 461-9720
 www.bowmanconsulting.com

ARLINGTON COUNTY, VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL SERVICES

DEMOLITION PLAN
QUEENS COURT
 CIVIL ENGINEERING PLAN
 SITE PLAN #444
 1615 18TH STREET NORTH
 ARLINGTON, VIRGINIA 22209
 ARLINGTON COUNTY, VIRGINIA

SCALE: 1"=25'
 SHEET C6.00

ARLINGTON VIRGINIA
 DEPARTMENT OF PARKS AND RECREATION
 Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB#21-DPR-ITB-304

SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
 BID SET

18TH STREET
 ARLINGTON, VIRGINIA
 Sheet Title

DEMOLITION PLAN BY OTHERS

Approval Date
 LUKE VANBELLEGHEM 4.15.2020
 Design Supervisor

Revisions Date
 LDA SUBMISSION 4/15/20
 LDA SUBMISSION REV. 7/14/20
 LDA SUBMISSION REV. 9/08/20


Designed: FA
 Drawn: EF
 Checked: KMM
 Filename:
 Plotted: Sep. 9, 20
 Scale: AS SHOWN
 Date: APRIL 15, 2020

Seal

Sheet **C1.17**
 15 of 16

Luminaire Schedule										
Symbol	Label	Quantity	Manufacturer	Catalog Number	Description	Lamp	Number Lamps	Lumens Per Lamp	Wattage	Notes
■	L1	5	Performance in Lighting	071407	Recessed LED area light 300x	11 WATT LED	1 LED's	490	11	2' RECESSED MTG HT
⊙	A	2	Arlington County Single Canyle	Arlington Details: LT-5, LT-7, LT-8, LT14.1	Arington Co. Standard "Canyle" Streetlight: 18ft Pole, Single Asym. Globe Fixture	55.4 WATT LED	32 LED's	5324	57	SEE NOTE BELOW

Pull 2-#6 + #6G wire from existing jbox through existing conduit and connect to existing street lighting circuits. Pole base is existing to remain.



1 ELECTRICAL SITE PLAN

SCALE: 1/8" = 1'-0"

NOTE: LIGHTS ON THE EAST SIDE OF THE PARK ARE NOT TO BE INCLUDED IN BASE BID. LIGHTS SHALL BE INCLUDED IN ADD ALTERNATE 1. LIGHTS WILL BE CONTROLLED BY A TIMER AND WILL PROVIDE MINIMUM FOOT CANDLES REQUIRED TO ILLUMINATE EMERGENCY EGRESS ROUTE FROM QUEENS COURT BUILDING THROUGH THE PARK. THE BUILDING CONTRACTOR SHALL LEAVE A SLEEVE OPEN FOR THE PLAYGROUND LIGHTING CONDUIT TO TIE INTO.



DEPARTMENT OF PARKS AND RECREATION
 Park Development Division
 2100 Clarendon Boulevard, Suite 414
 Arlington, VA 22201
 Phone: 703.228.3332
 Fax: 703.228.3328

ITB# 21-DPR-ITB-304


SWM# 20-0120

Project Name and Location
ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET
 ARLINGTON, VIRGINIA

Sheet Title
ELECTRICAL SITE PLAN

SUMMIT PRJ# 2017102.00




Approval	Date
---	---

Revisions	Date
BID SET	7/09/20
ADDENDUM 1	9/25/20

Designed: AW
 Drawn: --
 Checked: --

Filename:
 Plotted: ---

Scale: AS SHOWN
 Date: Sep 23, 2020



Sheet

E001

STRUCTURAL NOTES


1. GENERAL
- A. THE STRUCTURES ARE DESIGNED UNDER THE PROVISIONS OF THE 2012 INTERNATIONAL BUILDING CODE AND ASCE 7-10.
- B. ALLOWANCE FOR LOADS OVER BUILDING STRUCTURE:
- LIVE LOAD 100 PSF
DEAD LOAD (5 FT. MAX SOIL + SIDEWALKS, PLAY EQUIP., AND PLANTER WALLS) 660 PSF
- C. SUBMIT SHOP DRAWINGS FOR THE FOLLOWING ITEMS. SUBMITTALS INCLUDE BUT MAY NOT BE LIMITED TO:
- CONCRETE MIX DESIGN
 - REINFORCING STEEL
 - PLAY EQUIPMENT STRUCTURE AND FOUNDATIONS
- DO NOT USE CONTRACT DRAWINGS AS A BASE FOR SHOPS. REVIEW IS LIMITED TO DESIGN CONFORMANCE. CONTRACTOR IS RESPONSIBLE FOR DIMENSIONS.

2. EARTHWORK
- A. FOUNDATIONS ARE TO BEAR ON ENGINEERED FILL WITH A CAPACITY OF 1,500 PSF, THIS VALUE IS TO BE VERIFIED IN THE FIELD BY THE BUILDING INSPECTOR OR A QUALIFIED TESTING AGENCY.
- B. BOTTOM OF ALL EXTERIOR FOOTINGS SHALL BE A MINIMUM OF 2 FOOT-6 INCH BELOW FINISH EXTERIOR GRADE. WHERE REQUIRED, STEP FOOTINGS IN RATIO OF 2 HORIZONTAL TO 1 VERTICAL.
- C. COMPACTED BACKFILL BELOW FOOTINGS: ALL SOIL FILL MATERIAL MUST BE APPROVED BY SOILS ENGINEER PRIOR TO PLACEMENT. PROOFROLL SUBGRADE REMOVING AND REPLACING SOFT OR COMPRESSIVE MATERIALS. FILL MATERIAL SHALL BE PLACED IN LAYERS NOT TO EXCEED 8 INCHES AND COMPACTED TO MIN. 95 PERCENT OF THE DRY MAXIMUM DENSITY AS DETERMINED BY ASTM D698.

3. CONCRETE
- A. CONCRETE CONSTRUCTION SHALL BE PER THE APPLICABLE BUILDING CODE, ACI 318 AND ACI 301, LATEST EDITIONS.
- B. CONCRETE SHALL ATTAIN THE FOLLOWING 28 DAY COMPRESSIVE STRENGTHS PER ASTM A39.
- FOOTINGS AND FOUNDATION WALLS 3,000 PSI
- C. VERIFY CONCRETE STRENGTHS WITH A MINIMUM OF ONE SET OF NINE 4X8-INCH COMPRESSION CYLINDERS, (3 @ 7 DAYS, 3 @ 28, 3 SPARE).
- D. EXTERIOR CONCRETE SHALL BE AIR-ENTRAINED TO PROVIDE AN AIR CONTENT OF 6+/-1.5 PERCENT BY VOLUME.
- E. PROVIDE CLEAR DISTANCE TO OUTERMOST REINFORCING AS FOLLOWS:
- CONCRETE CAST AGAINST EARTH 3 INCHES
CONCRETE EXPOSED TO EARTH OR WEATHER:
#5 OR SMALLER 1-1/2 INCHES
#6 OR LARGER 2 INCHES
- F. REINFORCING STEEL SHALL CONFORM TO A615-GR60; MESH SHALL CONFORM TO ASTM A185 WITH MINIMUM LAPS OF 8 INCHES. PLACING PLANS AND SHOP FABRICATION DETAILS SHALL BE IN ACCORDANCE WITH "THE MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES". FURNISH SUPPORT BARS AND ACCESSORIES IN ACCORDANCE WITH C.R.S.I. STANDARDS.
- G. PROVIDE CORNER BARS TO MATCH HORIZONTAL REINFORCING IN WALLS AND FOOTINGS. SPLICE LAPS SHALL BE A MINIMUM OF 36 BAR DIAMETERS, UNLESS NOTED OTHERWISE. PROVIDE DOWELS BETWEEN FOOTINGS AND WALLS OR PIERS TO MATCH SIZE AND SPACING OF VERTICAL REINFORCING.

ABBREVIATIONS LEGEND

A	ANCHOR BOLT	F	FOOTING MARK	P	PIER MARK
ADL	ADDITIONAL FLOOR DRAIN	FD	FLOOR DRAIN	PC	PRECAST CONCRETE
ADJ	ADJACENT	FDN	FOUNDATION	PEB	PRE-ENGINEERED BUILDING
AFF	ABOVE FINISH FLOOR	FOM	FACE OF MASONRY WALL	PERIM	PERIMETER
ALT	ALTERNATE	FOS	FACE OF STUD	PL	PLATE
APPROX	APPROXIMATE(LY)	FS	FOOTING STEP	PLF	POUNDS PER LINEAR FOOT
ARCH	ARCHITECT(URAL)	FTG	FOOTING	PP	PRECAST PLANK MARK
B	BEAM MARK	FUT	FUTURE	PROJ	PROJECTION
BF	BOTTOM OF FOOTING ELEVATION	G	GAGE, GAUGE	PSF	POUNDS PER SQ. FOOT
BLKG	BLOCKING	GA	GALVANIZED	PSI	POUNDS PER SQ. INCH
BLDGD	BUILDING	GC	GENERAL CONTRACT(OR)	PSL	PARALLEL STRAND LUMBER COLUMN
BM	BEAM	GT	GIRDER TRUSS	PT	POST TENSION/PRESSURE TREATED
BOD	BOTTOM OF DECK	H	HORIZONTAL	Q	QUANTITY
BOS	BOTTOM OF STEEL	HP	HIP TRUSS	R	RADIUS
BOTT	BOTTOM	HS	HIGH STRENGTH	RD	ROOF DRAIN
BP	BEARING PLATE MARK	HT	HEIGHT	REV	REVISION, REVISE(D)
BRG	BEARING	HTR	HIP TRUSS	REINF	REINFORCE(D), (ING)
BSMT	BASEMENT	I	INFORMATION	REMA	REMAINDER
BTWN	BETWEEN	IF	INSIDE FACE	REQD	REQUIRED
C	COLUMN MARK	RTU	ROOF TOP UNIT	S	SOIL BORING
CIP	CAST IN PLACE	J	JOIST BEARING ELEVATION	SB	SLIP CRITICAL
CJ	CONTROL JOINT	JST	JOIST	SC	SPECIALTY DESIGN ENGINEER
CLR	CLEAR(ANCE)	JT	JOINT	SE	SIMILAR
CMU	CONCRETE MASONRY UNIT	JTR	JACK TRUSS	SJI	STEEL JOIST INSTITUTE
COL	COLUMN	K	KIP	SOG	SLAB ON GRADE
COM	CENTER OF MASONRY WALL	KO	KNOCK-OUT	SQ	SQUARE
COMP	COMPOSITE	KSI	KIPS PER SQ. INCH	STD	STANDARD
CONC	CONCRETE	L	LINTEL MARK	STL	STEEL
CONN	CONNECTION	LL	LONG LEG HORIZONTAL	STRUCT	STRUCTURAL
CONST	CONSTRUCTION	LLV	LONG LEG VERTICAL	SPA	SPACES
CONT	CONTINUOUS	LL	LIVE LOAD	SI	SNOW LOAD
COORD	COORDINATE(TION)	LL	LOW POINT	SS	STAINLESS STEEL
COS	CENTER OF STUD	LP	LAMINATED VENEER LUMBER	T	TEMPORARY
D	DEFORMED BAR ANCHORS	LVL	LAMINATED VENEER LUMBER	TF	TOP OF FOOTING ELEVATION
DBA	DETAILED BAR ANCHORS	M	MANUFACTURER(ED)	THK	THICK(NESS), (ENED)
DTL	DETAIL	MAS	MASONRY	TJ	WOOD T JOIST
DIAM	DIAMETER	MAX	MAXIMUM	TO	THROUGH OUT
DIAG	DIAGONAL	MIN	MINIMUM	TOC	TOP OF CONCRETE
DN	DOWN	MISC	MISCELLANEOUS	TOP	TOP OF PIER ELEVATION
DWG	DRAWING	MO	MASONRY OPENING	TOS	TOP OF STEEL ELEVATION
DBL	DOUBLE	MATL	MATERIAL	TOW	TOP OF WALL ELEVATION
DL	DEAD LOAD	MTL	METAL	TYP	TYPICAL
E	EACH	N	NOT TO SCALE	U	UNEXCAVATED
EA	EACH END	NTS	NOT TO SCALE	UNO	UNLESS NOTED OTHERWISE
EE	EACH FACE	NS	NEAR SIDE	UMD	UNDERSIDE METAL DECK ELEVATION
EF	EACH FACE	NIC	NOT IN CONTRACT	V	VERTICAL
ES	EACH SIDE	O	ON CENTER(S)	VIF	VERIFY IN FIELD
ELEV	ELEVATION	OC	ON CENTER(S)	W	WITH
ELEV	ELEVATION	OPNG	OPENING	WF	WIND FRAME
EQJ	EDGE OF JOIST	OPP	OPPOSITE	WP	WORK POINT
EQ	EQUAL	OF	OUTSIDE FACE	WWF	WELDED WIRE FABRIC
EQUIP	EQUIPMENT				
EW	EACH WAY				
EXIST, EX	EXISTING				
EXP	EXPANSION				
EXT	EXTERIOR				



PARK STRUCTURAL PLAN

SCALE: 1/8" = 1'-0"

NOTES: SEE LANDSCAPE DRAWINGS FOR ALL SLABS, SIDEWALKS, CURBS, AND OTHER MISCELLANEOUS ITEMS.

□ DENOTES GEOFOAM OR OTHER LIGHT WEIGHT FILL (N.I.C.) OVER RES. BUILDING SLAB. COORDINATE DEPTH OF FILL TO MAINTAIN A TOTAL SUPERIMPOSED DEAD LOAD OF LESS THAN 660 PSF OVER STRUCTURAL SLAB. (5'-0" MAX SOIL DEPTH).

BASE BID SHALL NOT INCLUDE GEOFOAM (ADD ALTERNATE 2).

EHLERT BRYAN
consulting structural engineers
8609 Westwood Center Drive, Suite 800
Tysons, VA 22182
(703) 827-9552
Fax (703) 356-2031
www.ehlerbryan.com
EB#1550121



DEPARTMENT OF PARKS AND RECREATION
Park Development Division
2100 Clarendon Boulevard, Suite 414
Arlington, VA 22201
Phone: 703.228.3332
Fax: 703.228.3328

ITB# 21-DPR-ITB-304

SWM#20-0120

Project Name and Location

ROSSLYN HIGHLANDS PARK
BID SET

18TH STREET

ARLINGTON, VIRGINIA

Sheet Title

STRUCTURAL NOTES, ABBREVIATIONS AND PLAN

Approval _____ Date _____

Design Supervisor _____

Revisions _____ Date _____

Designed: BG

Drawn: AG

Checked: WB

Filename: _____

Plotted: APRIL 15, 2020


Scale: AS SHOWN

Date: APRIL 16, 2020

Seal


Sheet

S1.1




SEAT WALL

SECTION 5
SCALE: 1/2" = 1'-0"




TYPICAL CONC. RETAINING WALL - L-SHAPED FOOTING

SECTION 4
SCALE: 1/2" = 1'-0"




SEAT STEPS

SECTION 3
SCALE: 1/2" = 1'-0"




TYPICAL CONC. RETAINING WALL

SECTION 2
SCALE: 1/2" = 1'-0"




TYPICAL PLAY EQUIPMENT FOOTING

SECTION 1
SCALE: 1/2" = 1'-0"




ENTRY BRIDGE

SECTION A
SCALE: 1/2" = 1'-0"




SECTION 8
SCALE: 1/2" = 1'-0"



FOOTING @ BIO RETENTION

SECTION 7
SCALE: 1/2" = 1'-0"



SIGN WALL

SECTION 6
SCALE: 1/2" = 1'-0"