

BID FORM - CIVIL SITE IMPROVEMENTS

PROJECT: WRIGHT FAMILY PARK
 LOCATION: BLUFFTON, SC
 OWNER: TOWN OF BLUFFTON
 CEG PROJECT # : 2019-0032



CRANSTON
ENGINEERING

DATE: 3/7/2019

DEMOLITION					
Item	Description	Quantity	Units	Unit Price	Total
1	Tree Removal/Clearing	15	EA		
2	1" Asphalt Milling	3,949	SF		
3	Sawcut and remove existing asphalt	1,925	SF		
4	Remove sidewalks and driveway	1,159	SF		
5	Selective underbrushing +/-15' strip along eastern brick wall	3,975	SF		
6	Grind existing stumps as needed	15	EA		
DEMOLITION, SUBTOTAL					

EROSION CONTROL					
Item	Description	Quantity	Units	Unit Price	Total
1	Silt Fence	816	LF		
2	Tree Protection Fencing	1,156	LF		
3	Type A Inlet Protection	7	EA		
4	Temporary Grassing/Mulching	8,325	SY		
EROSION CONTROL, SUBTOTAL					

PAVING					
Item	Description	Quantity	Units	Unit Price	Total
1	8" GABC	1,724	SF		
2	6" GABC	3,706	SF		
3	1.5" Asphalt Intermediate Course (200 #/SY)	1,724	SF		
4	1.5" Asphaltic Concrete Surface Course (200 #/SF)	5,673	SF		
5	Tack coat-(2 applications-milled surface, leveling)	3,949	SF		
6	12" concrete ribbon curb	678	LF		
7	Pervious Parking, crushed stone/shell mix	3,706	SF		
8	4000 PSI concrete pavement, 6" thick	1,185	SF		
PAVING, SUBTOTAL					

GRADING/DRAINAGE					
Item	Description	Quantity	Units	Unit Price	Total
1	12" RCP	38	LF		
2	24"x24" Drop Inlet	1	EA		
3	6" Perforated HDPE Pipe w/ Geotextile sock	180	LF		
4	6" HDPE Pipe	80	LF		
5	HDPE Fittings and Couplers	5	EA		
6	24" NDS Square Catch Basins kit w/grate	7	EA		
7	6" NDS Pop up emitter with elbow	1	EA		
8	#57 Aggregate	720	CF		
9	Geotextile fabric, Infiltration trench	1,440	SF		
10	Sand layer, Infiltration trench	90	CF		
GRADING/DRAINAGE, SUBTOTAL					

SIGNAGE AND MARKING					
Item	Description	Quantity	Units	Unit Price	Total
1	Handicap parking signs (R7-8)	2	EA		
2	Handicap parking symbol (MUTCD Fig. 3B-22)	2	EA		
3	Handicap parking striping - 4" blue traffic striping	144	SF		
4	Pedestrian Crosswalk - 12" solid white striping	44	LF		
SIGNAGE AND MARKING SUBTOTAL					

BID FORM - CIVIL SITE IMPROVEMENTS

PROJECT: WRIGHT FAMILY PARK
LOCATION: BLUFFTON, SC
OWNER: TOWN OF BLUFFTON



CRANSTON
ENGINEERING

DATE: 3/7/2019

UTILITIES					
Item	Description	Quantity	Units	Unit Price	Total
1	2" PVC Conduit	300	LF		
2	4" PVC Conduit	300	LF		
3	6" Sanitary sewer service	1	LS		
4	1" Water service	1	LS		
5	Water meter with backflow preventer	1	LF		
7	Utility cut repair	2	EA		
6	BJWSA wet tap fee 2" and smaller	1	EA		
UTILITIES, SUBTOTAL					

ADDITIONAL EXPENSES					
Item	Description	Quantity	Units	Unit Price	Total
1	Mobilization	1	LS		
2	Bonds and insurance	1	LS		
ADDITIONAL EXPENSES, SUBTOTAL					

WRIGHT FAMILY PARK CONSTRUCTION COSTS FOR CIVIL SITE IMPROVEMENTS - TOTAL					
---	--	--	--	--	--

*Bidder is responsible for verifying all quantities shown on the plans and this bid form.