

Addendum #2- 2223-001 8/24/22

- 1) Is primary electric already provided to the exterior channel letter sign installation site? **No.**
- 2) Is primary electric already provided to the LED Exterior sign installation site? **No.**
- 3) Page 10 of the IFB states that a SC licensed electrical engineer is to be engaged to engineer electrical systems for each sign based on the sign type location and governing codes. Will a licensed electrician be adequate? **Yes.**
- 4) Is Watchfire LED an approved equal for the Daktronics LED? **As long as the specifications are comparable to the Daktronics LED.**
- 5) Are the internally illuminated channel letters mounted on raceways? **There are no raceways present on the building.**
- 6) Are the internally illuminated channel letters mounted flush to the wall? **Yes.**
- 7) Is there adequate access behind the wall at the location of the internally illuminated channel letters to allow for installation personnel to work? **The access for the internally illuminated sign is above a restroom.**
- 8) Will a lift be needed to reach behind the wall at the location of the internally illuminated channel letters? **Yes a Lift will be needed**
- 9) Are there construction drawings for the building showing the wall sections? **Yes, we do have drawings, we are waiting to get those from the contractor and can provide them to the awarded contractor.**
- 10) The drawing seems to indicate there may be a sign on the side elevation of the building. Please clarify. **There is no signage on the building presently. The signage requested in the bid is shown on the drawing.**
- 11) Are the 10" aluminum lettering on the building to be flush mounted or mounted with stand-offs? **The aluminum lettering is flush mounted to match the lettering for Greenwood High School.**
- 12) Is there a site plan showing the location of the LED exterior sign? **Please see attached.**
- 13) If there is no site plan, where is the LED Exterior sign to be located? **Please see attached.**
- 14) Please Confirm the aluminum lettering on the LED Exterior sign is non-illuminated. **It is illuminated per drawing.**
- 15) Is the aluminum lettering on the LED Exterior sign to be flush mounted or mounted with stand-off? **The lettering on the illuminated LED Exterior sign is to be flush mounted.**
- 16) The drawing indicates the LED Exterior Sign is to have a continuous spread footing. If the engineer determines an augered footing is adequate will that be acceptable? **As long as you can provide the Engineer's Opinion that this is adequate footing.**
- 17) Will the School District provide school colors for the internally illuminated channel letters? **Yes upon award.**
- 18) Are city and/or county permits required? **No.**
- 19) Will working hours be restricted? **No. The working hours will not be restricted because all work will be done on the outside of the building.**
- 20) Is sales tax to be included in the bid? **No.**

21) Are there any special warranties/guarantees **Please see bid.**