



# St. Johns River

## Water Management District

Ann B. Shortelle, Ph.D., Executive Director

---

525 Community College Parkway S.E. • Palm Bay, FL 32909 • 321-984-4940  
On the internet at [www.sjrwmd.com](http://www.sjrwmd.com).

DATE: November 16, 2018  
TO: Prospective Respondents  
FROM: Amy Lucey, Contracts Administrator  
SUBJECT: Addendum #1 to Quote Request # 33907, Gopher Tortoise Exclusion Fence Phase II

The following clarifications/changes are provided for your information. Please make all appropriate changes to your quote documents. Note: changes are reflected with original language shown with strike-through and new language is underlined.

1. Stakes shall be steel posts with a maximum of **8-foot** spacing between stakes.
2. At the beginning and end of each run of exclusion fencing the contractor shall turn/curl the fencing to the west. The diameter of the turn should be approximately 4-feet and extend 6-feet once the turn has been made.
3. The District is evaluating installing/replacing 0.1-0.2 miles of fencing between US192 and S161. (Fencing to be replaced will be removed by others). The remainder of the fencing was being consider for placement south of the Kempfer gate, however at this time this need has not materialized. Therefore, approximately 2,600 LF of fencing may not be required.

Additional Information:  
Pre-bid Meeting Recording – separate file

**NOTE:** The Quote Due Date remains 3:00 p.m., Thursday, December 6, 2018

Please acknowledge receipt of this Addendum on the **Quote Cost Schedule** FORM provided in the quote request package.

If you have any questions, please e-mail me at [alucey@sjrwmd.com](mailto:alucey@sjrwmd.com).