

Curb Ramp ADA Compliance

“Scope of Work” Summary

This project consists of upgrading for compliance for concrete ramps for new and or existing and some sidewalks that may need to be removed and reinstalled at various locations for pedestrian route throughout Escambia County. These concrete ramps shall be built per the LASTEST Americans with Disabilities Act (ADA), Design Standards and PROWAG. This project may also include other work associated with the ramp construction such as any additional sidewalk for connectivity, maintenance of traffic, stormwater pollution prevention's, sod, seed and mulch, and shoulder work as necessary (all included in each of the Concrete Ramp unit cost).

NO CHANGES ORDERS WILL BE ACCEPTED

Related Documents:

All construction shall require a permit which can be obtain from Jason Walters JJWalters@co.escambia.fl.us 595-3422. Each project shall follow Escambia County's Technical Specifications, latest edition, ADA Standards, ADA Guidelines, the latest addition of Design Standards and PROWAG all interim standards that apply to these editions.

Any reference to FDOT Standard Specifications for Road and Bridge Construction, latest edition, Division 1, General Requirements and Covenants, shall be excluded and not applicable to any specification referred herein or otherwise listed in these documents or in the Escambia County Technical Specifications.

Licenses:

General Contractors License

Contract completion & Liquidated Damages:

The work shall be substantially completed within **Ninety (90)** calendar days from the Date of notice to proceed. **Liquidated damages of \$1000.00 each day will be assessed for each day that completion of the project is delayed.**

Bid Items:

SY of 4" to 6" thick fiber reinforced concrete per location as needed.

SY of centipede sod per location as needed. All grading, and fill material shall be considered incidental to the project if needed.

Truncated Domes are needed.