

Leith Creek Wastewater Facility
Bar Screen Repair – Scope of Work

Provide labor, materials, and equipment to perform the following:

- Screen will be pulled from the channel and torn apart
- All new upper lamina will be installed
- Majority of lower lamina will be replaced
- All moving parts in the linkage system will be replaced
- All bearings will be replaced
- The brake on the motor will be replaced
- Machine will be installed back in the channel and put back in service