

**East Laurinburg Pump Station**  
**Pump Replacements – Scope of Work**

Provide labor, materials, and equipment to perform the following:

- Demo and remove both (2) pumps and motors from service
- Provide and install new pump/motor units
  - (2) Hydromatic 40 MP, direct drive pumps and motors, or equal
- Modify suction and discharge piping as required to install new pumps
- Provide and install new 4" AWWA check valve, or equal, to replace defective check valve
- Startup both pumps and place into automatic operation

This scope does not include any electrical work (to be by others)