

City of Kilgore

Crescent St- 2 inch Waterline replacement

12/17/2019

Company Name		Contact Name		Phone #	
		..			
Item Number	Quantity	Unit	Item Description	Unit Cost	Total Cost
1	600	LF	6" PVC water main- DR 18		\$ -
2	2	EA	standard fire hydrant assembly (B-84 clow medallion with 5" Storz pumper Connection		\$ -
3	3	EA	6" gate valve MJ		\$ -
4	1	EA	6" Tapping Valve- Flange to MJ		\$ -
5	1	EA	6" x 6" Tapping Sleeve		\$ -
6	2	EA	6" x 6" x 6" Ductile Iron Tee		\$ -
7	7	EA	6" x 1" saddles		\$ -
8	7	EA	1 inch Corporations- brass		\$ -
9	4	EA	1 inch Curb stops- brass		\$ -
10	4	EA	1 inch Angle curb stops- brass		\$ -
11	200	Ft	1 inch poly pipe with tracer wire		\$ -
12	500	Ft	tracer wire		\$ -
13	1	Box	stainless steel 1" inserts		\$ -
14	4	EA	adjustable valve box riser/ drop in lid		\$ -
15	1	EA	6 inch flange kit- stainless bolts		\$ -
16	6	EA	6 inch MJ kit - stainless steel bolts		\$ -
17	2	EA	6 inch MJ plug with 2" threaded opening		\$ -
					\$ -
					\$ -
			Due by 4:00 Pm- 12/19/2019		\$ -
Materials Total					\$ -
Contact Kevin Olson at 903-988-4115 if you have any questions or kevin.olson@cityofkilgore.com					