

Finance Department
Fifty Raupp Blvd.
Buffalo Grove, IL 60089-2198
Phone 847-459-2500
Fax 847-459-7906

Bernard Drive Contract 1 Project Addendum #4

TO: Prospective Respondents and Other Interested Parties

FROM: The Village of Buffalo Grove Finance Department

ISSUE DATE: November 13, 2023

SUBJECT: ADDENDUM #4

Note: This Addendum is hereby declared a part of the original bid and contract documents and in case of conflict, the provisions in the following Addendum shall govern.

The following changes and clarifications shall be made to the Bid Documents for the Bernard Drive Contract 1 Project.

Q1. Can you see if for the “adjust water service line item” if they will allow us to splice the water services and reconnect or will they require the contractor to replace the water line all the way to the main. I did not see a spec for this item.

A1. These are all new water services therefore no splices will be permitted. See below Special Provision for 'Adjusting Water Service Lines'.

ADJUSTING WATER SERVICE LINES

Description: This work shall include all labor, material, and equipment necessary to adjust new copper water service lines, regardless of the diameter, in accordance with Section 562 of the Standard Specifications, Section 41 of the Standard Specifications for Water and Sewer Construction in Illinois, applicable Special Provisions in the original contract documents and as specified herein.

Construction Requirements: This item shall be used, when determined by the Engineer, where existing water service lines conflict with the proposed utility improvements. The water service line shall be removed and replaced from the existing tap to the existing buffalo box at an elevation that eliminates the known conflict.

The replacement service line shall be one continuous length (no couplings in the new copper piping will be allowed) and be of sufficient length to allow for some movement for trench settling after placement of the backfill material. The Engineer shall inspect each new water service line prior to backfill operations.

Trench backfill required for excavations to make connections under sidewalks or driveways will be paid for separately.

The Contractor shall refer to the Village of Buffalo Grove Materials List in Appendix A for all material requirements. All work as listed and as shown on the plan and details shall be included with this

pay item. All fittings for copper service lines shall be of the "flare" type regardless of temporary or permanent use.

Method of Measurement: This work will be measured for payment in place in units per foot of water service line installed.

Basis of Payment: This item will be paid for at the contract unit price per foot for ADJUSTING WATER SERVICE LINES.

Q2. On sheet 7 and 8 of the spec book for Buffalo Grove project in the title (storm sewer construction) it states that laterals need to be done with flaggers and 4" of asphalt placed to final surface. My concern is that the main line is shown in the middle of the road and using flaggers would be difficult since there won't be any room for a passing lane also considering the laterals. Will the Village consider a road closure and/or detour for storm sewer install or at least daily road closures?

A2. The main line is approximately 5' south of the centerline of the road. The intent is that the laterals would be completed under traffic with the utilization of a flagger, and steel plates OR during the second phase of the project. No roads or segments shall be closed without prior written approval from the Village and Engineer. If the Contractor determines that a daily lane closure is warranted, they must present a detour plan with a detailed description addressing how resident access will be maintained and all applicable signage in accordance with the Highway Standards. Any additional traffic control devices required for daily lane closures at the Contractor's request shall not be paid for separately but shall be included in the cost of the contract.

PROSPECTIVE RESPONDENTS ARE TO ACKNOWLEDGE RECEIPT OF
ADDENDUM #4. AND SHALL INCLUDE AND NOTE THIS ADDENDUM IN
YOUR RESPONSE.

RESPONDENT: _____

SIGNED: _____ DATE: _____

TITLE : _____