

## CONTRACT, LEASE, AGREEMENT CONTROL FORM

Date: 10/06/2022

Contract/Lease Control #: C21-3017-PW

Procurement #: ITB PW 65-02

Contract/Lease Type: AGREEMENT

Award To/Lessee: ANDERSON COLUMBIA CO., INC.

Owner/Lessor: OKALOOSA COUNTY

Effective Date: 11/17/2020

Expiration Date: 02/19/2025

Description of: SOUTH CRESTVIEW BYPASS

Department: PW

Department Monitor: AUTREY

Monitor's Telephone #: 850-689-5772

Monitor's FAX # or E-mail: JAUTREY@MYOKALOOSA.COM

Closed:

Cc: BCC RECORDS

## CHANGE ORDER FORM

Date: 09-20-2022 Contract No.: C21-3017-PW Change Order No.: 2

Owner: OKALOOSA COUNTY BOARD OF COUNTY COMMISSIONERS

Contractor: Anderson Columbia Co., Inc.

The Contract/Agreement is modified as follows upon execution of this Change Order:

Description: This change order incorporates into the Contract plan revisions 4 and 5, and a total of 22 weather days allowed per contract for the period 11/30/2021 through 07-31-2022. Revision 4 includes the modification of the offset turn lane at the intersection of Phase V with the eastern portion of the East-West Connector and the addition of an eastbound right turn lane from Eastbound US 90 to Southbound Phase V. Revision 5 includes changes to the pavement design on US 90 and additional drainage for B Street.

Attachments: List of plan sheet revisions and summary of additional costs pursuant to those revisions.


CHANGE TO CONTRACT PRICE	
DESCRIPTION	AMOUNT
Original Contract Price:	\$43,964,475.43
Net change by previously authorized Change Orders:	\$10,033.10
Present Contract Price:	\$43,974,508.53
This Change Order will add:	\$205,717.69
New Contract Price:	\$44,180,226.22
CHANGE TO CONTRACT TIME	
DESCRIPTION	DATE or NUMBER OF DAYS
Original Contract Time:	Substantial Completion - 1,095 days; Final Completion 1,155 days
Original Substantial Completion Date:	Substantial: 11/29/2024; Final 01/28/2025
Net change by previously authorized Change Orders:	0 days
This Change Order will add:	22 days
New Contract Time:	Substantial Completion - 1,117 days; Final Completion 1,177 days
New Substantial Completion Date:	Substantial: 12/21/2024; Final 02/19/2025

### APPROVALS

REQUESTED BY: Jason T. Autrey, P.E., C.P.M. Digitally signed by Jason T. Autrey, P.E., C.P.M. Date: 2022.09.26 11:03:19 -0500 DATE: \_\_\_\_\_

PROJECT ENGINEER: Bradley J Brenneke Digitally signed by Bradley J Brenneke Date: 2022.09.26 11:03:19 -0500 DATE: \_\_\_\_\_

CONTRACTOR: Hampton S Jordan Digitally signed by Hampton S Jordan Date: 2022.09.26 11:03:19 -0500 DATE: \_\_\_\_\_

OWNER:  DATE: October 4, 2022  
Mel Pontier, Chairman



This Change Order is an amendment to the Contract/Agreement between Contractor and the Owner, and all other contract provisions shall remain in full force and effect unless specifically amended in writing, signed by both parties.

CONTRACT: C21-3017-PW  
 ANDERSON COLUMBIA CO., INC.  
 SOUTHWEST CRESTVIEW BYPASS  
 EXPIRES: 02/19/2025

## CHANGE ORDER FORM

Date: 09-20-2022 Contract No.: C21-3017-PW Change Order No.: 2

Owner: OKALOOSA COUNTY BOARD OF COUNTY COMMISSIONERS

Contractor: Anderson Columbia Co., Inc.

---

**Contractor to incorporate the following drawing revisions:**

• **Revision 4 changes dated 11/02/2020:**

ROADWAY SHEETS: 1, 1A, 3-4, 6-9, 16- 17, 19-21, 35-37, 52, 53, 66-67, 91-92, 94, 102-110, 129 , 130A, 244-258, 326, 341-344C, 360-362, 377-377A, 396A, 405-406, 424-424A, 437-438, 440-441, 443-444, 470-472, 487-488, SQ-7 - SQ-8, SQ-10 - SQ-14, SQ-16 - SQ-21, SQ-26

SIGNING AND PAVEMENT MARKING SHEETS: 5-3, 5-5, 5-13 - 5-15, 5-30 - 5-31

SIGNALIZATION SHEETS: T-6 - T-7, T-9, T-13

• **Revision 5 changes dated 12/20/2021:**

ROADWAY SHEETS: 1A, 3, 9, 16, 20-23, 50, 55, 80, 127, 130, 149, 375, 464-473, 485- 489, SQ-7, SQ-13

REVISION 4 PLAN CHANGES

PHASE V ROADWAY

Item No.	FDOT Pay Item	Item Description	Unit	Quantity	Unit Price	Total	Rev. Seg. Qty
6	102-3	COMMERCIAL MATL FOR TEMP DRIVEWAY MAINT	CY	9.5	\$ 57.73	\$ 548.44	44.8
8	102-74-1	CHANNEL DEVICE-TYPS I,II,DI,VP, DRUM, LCD	ED	510	\$ 0.19	\$ 96.90	17490
13	102-115	TYPE III BARRICADE	ED	75	\$ 0.41	\$ 30.75	4664
14	104-10-3	SEDIMENT BARRIER	LF	12878	\$ 2.04	\$ 26,271.12	54490
20	110-1-1	CLEARING & GRUBBING <sup>1</sup>	LS	0.35	\$ 1,232,169.45	\$ 3,193.80	135.38
23	120-1	REGULAR EXCAVATION	CY	269.5	\$ 1.06	\$ 285.67	833768.5
25	120-6	EMBANKMENT	CY	-662.1	\$ 4.15	\$ (2,747.72)	507716.6
28	160-4	TYPE B STABILIZATION	SY	2741	\$ 3.94	\$ 10,799.54	152267
29	285-701	OPTIONAL BASE,BASE GROUP 01	SY	151	\$ 10.89	\$ 1,644.39	14117
30	285-706	OPTIONAL BASE,BASE GROUP 06	SY	1907	\$ 11.39	\$ 21,720.73	92127
32	286-1	TURNOUT CONSTRUCT/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	140	\$ 26.39	\$ 3,694.60	1604
33	327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	-180	\$ 3.39	\$ (610.20)	6175
34	334-1-53	SUPERPAVE ASPH CONC, TRAF C, PG76-22	TN	524.7	\$ 95.73	\$ 50,229.53	19387
35	337-7-25	ASPH CONC FC,INC BIT,FC-5,PG76-22	TN	39.2	\$ 123.02	\$ 4,822.38	3306.3
36	337-7-82	ASPH CONC FC,TRAFFIC C,FC-9.5,PG 76-22	TN	-13.6	\$ 110.57	\$ (1,503.75)	1441.3
37	339-1	MISCELLANEOUS ASPHALT PAVEMENT	TN	2.3	\$ 226.40	\$ 520.72	67
44	425-1-361	INLETS, CURB, TYPE P-6, <10'	EA	1	\$ 6,451.29	\$ 6,451.29	6
52	425-1-701	INLETS, CURB, TYPE S, <10'	EA	1	\$ 4,570.04	\$ 4,570.04	6
60	430-175-118	PIPE CULV, OPT MATL, ROUND, 18"S/CD	LF	47	\$ 47.93	\$ 2,252.71	4438
61	430-175-124	PIPE CULV, OPT MATL, ROUND, 24"S/CD	LF	-3	\$ 61.81	\$ (185.43)	2997
69	430-982-125	MITERED END SECT, OPTIONAL RD, 18"S,CD	EA	2	\$ 1,168.48	\$ 2,336.96	20
76	520-1-7	CONCRETE CURB & GUTTER, TYPE E	LF	436	\$ 21.24	\$ 9,260.64	5662
77	520-1-10	CONCRETE CURB & GUTTER, TYPE F	LF	-17	\$ 22.42	\$ (381.14)	4086
79	520-6	SHOULDER GUTTER- CONCRETE	LF	272	\$ 23.60	\$ 6,419.20	2625
84	522-2	CONCRETE SIDEWALK AND DRIVEWAYS, 6"	SY	-4	\$ 63.72	\$ (254.88)	377
88A	536-73	GUARDRAIL REMOVAL	LF	177	\$ 3.54	\$ 626.58	177
89	536-85-20	GUARDRAIL END TREAT- TRAILING ANCHORAGE	EA	1	\$ 1,120.84	\$ 1,120.84	4
94	570-1-1	PERFORMANCE TURF	SY	-1335	\$ 1.18	\$ (1,575.30)	309054
95	570-1-2	PERFORMANCE TURF, SOD	SY	54	\$ 2.36	\$ 127.44	127954
97	710-11-101	PAINTED PAVT MARK,STD,WHITE,SOLID,6"	GM	0.21	\$ 943.87	\$ 198.21	3.219
102	711-17-1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	144	\$ 2.36	\$ 339.84	2484
<b>SUBTOTAL: Rev 4 Phase V Roadway</b>						<b>\$ 150,303.91</b>	

<sup>1</sup> Unit of Measure for Item 20 (Pay Item No. 110-1-1, Clearing and Grubbing) is LS/Ac where Ac is the calculated acreage for the project and basis for the LS price. The basis for bid acreage for Phase V was 135.03. This change order increases the acreage by 0.35 acres and the lump sum cost cost by \$3,193.80 (prorated from bid price and basis quantity). Upon approval of this change order the quantity for Item 20 will remain one (1) with an adjusted lump sum price of \$1,235.363.25 and will have a basis of 135.38 acres.

PHASE V SIGNING AND PAVEMENT MARKINGS

Item No.	FDOT Pay Item	Item Description	Unit	Quantity	Unit Price	Total	Rev. Seg. Qty
104	700-1-11	SINGLE POST SIGN, F&I GM, <12 SF	AS	1	\$ 383.45	\$ 383.45	3608
112	711-11-123	THERMOPLASTIC, STD, WHITE, SOLID, 12"	LF	29	\$ 2.48	\$ 71.92	1136
114	711-11-125	THERMOPLASTIC, STD, WHITE, SOLID, 24"	LF	16	\$ 4.13	\$ 66.08	4
115	711-11-141	THERMOPLASTIC, STD, WHITE, DOT GUIDE, 6"	GM	0.048	\$ 2,123.72	\$ 101.94	6
117	711-111-70	THERMOPLASTIC, STD, WHITE, ARROW	EA	3	\$ 70.79	\$ 212.37	8
120	711-14-125	THERMOPLASTIC, PREFORM, WHITE, SOLID, 24"	LF	17	\$ 14.15	\$ 240.55	2
121	711-14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2	\$ 147.48	\$ 294.96	15
122	711-14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2	\$ 135.69	\$ 271.38	6
123	711-15-101	THERMOPLASTIC, STANDARD OG ASPHALT SURFACES, WHITE, 6"	GM	0.152	\$ 4,660.38	\$ 708.38	5,295
127	711-15-231	THERMOPLASTIC, STD OG ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.002	\$ 1,946.73	\$ 3.89	0.154
128	711-16-101	THERMOPLASTIC, STD-OTH, WHITE, SOLID, 6"	GM	-0.069	\$ 4,542.40	\$ (313.43)	2,291
<b>SUBTOTAL: REV 4 PHASE V SIGNING AND PAVEMENT MARKINGS</b>						<b>\$ 2,351.03</b>	
<b>SUBTOTAL REV 4 PHASE V ROADWAY</b>					<b>\$ 150,303.91</b>		
<b>SUBTOTAL REV 4 PHASE V SIGNING AND PAVEMENT MARKINGS</b>					<b>\$ 2,351.03</b>		
<b>REVISION 4 NET CHANGE</b>					<b>\$ 152,654.93</b>		

REVISION 5 PLAN CHANGES

PHASE V ROADWAY

Item No.	FDOT Pay Item	Item Description	Unit	Quantity	Unit Price	Total	Rev. Seg. Qty
9A	102-78	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	150	\$ 5.50	\$ 825.00	150
33	327-70-1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	-6175	\$ 3.39	\$ (20,933.25)	0
33A	327-70-8	MILLING EXIST ASPH PAVT, 2 1/2" AVG DEPTH	SY	6175	\$ 3.39	\$ 20,933.25	6175
49	425-1-521	INLETS, DT BOT, TYPE C, <10'	EA	5	\$ 4,278.26	\$ 21,391.30	33
55	425-2-62	MANHOLES, P-8, >10'	EA	2 <sup>2</sup>	\$ 7,275.32	\$ 14,550.64	3
60	430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18" S/CD	LF	299	\$ 47.93	\$ 14,331.07	4737
62	430-175-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30" S/CD	LF	-3	\$ 94.75	\$ (284.25)	807
97A	710-11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	250	\$ 3.30	\$ 825.00	250
98A	710-11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	LF	2000	\$ 0.50	\$ 1,000.00	2000
101A	710-11-231	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	400	\$ 0.61	\$ 244.00	400
101B	710-11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL CHEVRON, 18"	LF	25	\$ 4.40	\$ 110.00	12
101C	710-11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	LF	140	\$ 0.50	\$ 70.00	140
<b>SUBTOTAL: REV 5 PHASE V ROADWAY</b>						<b>\$ 53,062.76</b>	

<sup>2</sup> Two (2) structures added this change order. One (1) new at B Street per drawing revision and adds one (1) shown on plans when bid but not included in the bid form provided to bidders.

REVISION 4 NET CHANGE	\$ 152,654.93
REVISION 5 NET CHANGE	\$ 53,062.76
<b>NET CHANGE THIS CHANGE ORDER:</b>	<b>\$ 205,717.69</b>