ARLINGTON COUNTY, VIRGINIA AGREEMENT NO. <u>243-11</u> AMENDMENT NUMBER 3

This **Amendment Number 3** ("Amendment") is made on $\frac{6/12/2023}{2}$ and amends **Agreement Number 243-11**, dated October 16, 2012 ("Main Agreement") between **Westnet, Inc.**, 15542 Chemical Lane, Huntington Beach, CA 92649 ("Contractor") and the County Board of Arlington County, Virginia ("County").

The County and the Contractor amend certain provisions of the Main Agreement as follows:

1. SECTION 3: CONTRACT TERM:

RETROACTIVELY EXTEND THE AGREEMENT FROM OCTOBER 1, 2022 TO SEPTEMBER 30, 2025 to allow the Contractor to provide construction services (as defined in Exhibit A: Scope of Services). This extension is for the design and construction of the new Fire Station Alerting System (FSA) for Fire Station 8 to be installed and configured to function with the existing County Fire Station Alerting System. The major components of this construction include hardware, installation services, and software configuration for FS8 equipment. Any Construction of additional FSA on future fire stations will require an amendment.

- 2. Exhibit A: SCOPE OF SERVICES is hereby replaced in its entirety. See attached.
- **3. EXHIBIT B: PRICING is hereby replaced in its entirety . See attached.** The revised exhibit reflects costs associated with the installation of Fire Alerting System for Fire Station 8.
- 4. A new EXHIBIT H: TECHNICAL DRAWINGS is hereby incorporated as part of the agreement.
- 5. Amend SECTION 6: PAYMENT to read as follows:

The Contractor must submit invoices to the County's Project Officer, who will either approve the invoice or require corrections. The County will pay the Contractor within 45 days after approval of an invoice for completed work which is reasonable and allocable to the Contract. All payments will be made from the County to the Contractor via ACH. The number of the County Purchase Order pursuant to work has been performed must appear on all invoices.

6. Amend SECTION 20. WARRANTY to read as follows:

The Contractor warrants to furnish the services described herein at the times and places and in the manner and subject to the conditions set forth.

A. A one-year full parts and labor warranty is specified. Note that the full one year parts and labor warranty is subject to the terms and conditions of Westnet's Standard Limited Warranty and covers all portions of this system from failure, except for acts of God ,misuse by the owner or owner's third-party representative. During this one-year period, meet the following performance requirements:

 Provide 24/7 toll-free technical support and on-site maintenance for all current, existing equipment ("System") under Arlington County Agreement No. 425-04 as of November 1, 2011. If the system at a Fire Station is out of service, the Contractor agrees to provide a response time for a technician to arrive on site not later than the next business day from the time that the Contractor is notified of any problem with the System.

- 2. Service technicians certified on the specified systems and products.
- 3. Available 7 days a week, 24 hours a day.

B. The system components shall be guaranteed against all defective materials, design and workmanship for a period of one-year from the date of acceptance by the client after final testing. New replacement parts shall be furnished promptly and defects in design and workmanship shall be corrected, without cost to the Owner, promptly upon receipt of notice from the Owner of failure and confirmation by the Contractor that the part is not working as designed, of any part of the system during the guarantee period.

7. Amend the Project Officer contact information in SECTION 49. NOTICES as follows:

Maire Bourque, Project Officer

Department of Environmental Services – Facilities Design & Construction
1400 N Uhle Street, Suite 403

Arlington, Virginia 22201

Phone (703) 228-0488

Email mbourque@arlingtonva.us

8. Adding a new SECTION 54. SURETY REQUIREMENTS, as agreed by the parties, is hereby addedas follows:

PERFORMANCE SURETY – A fully completed and properly executed original Performance Bond in the amount of 100% of Westnet's cost proposal shall be required to ensure that Westnet satisfactorily completes their work. The bond shall be a corporate surety bond issued by a surety company authorized to do business in the Commonwealth of Virginia and acceptable to the County. Where applicable, the Performance Bond shall be renewable annually in the original amount through the completion of the contract, including all warranty and guarantee periods.

9. Adding a new SECTION 55. PERMIT REQUIREMENTS, as agreed by the parties, is hereby added as follows:

Westnet shall make the necessary arrangements for and obtain all filings and permits required to perform the WORK, including the preparation of drawings, sketches, calculations and other documents and information that may be required therefor. If Westnet is required to pay an application fee for filing, a fee to obtain a Building permit, a fee to obtain a Trade permit or any other permit fee, then the amount of a such fee paid by Westnet for which a receipt is obtained shall be treated as a Reimbursable Task to be paid with mark-up. The County shall pay all such fees with a 10% mark-up to Westne, including Westnet labor hours, t for all filings and permits required and obtained. To get reimbursed, Westnet shall submit written documentation of such fees. The 10% mark-up shall cover all costs over and above the filing and permit fees. The cost of expediting services or equipment use fees are not reimbursable.

All other terms and conditions of the Main Agreement shall remain unchanged.

WITNESS these signatures:

THE COUNTY BOARD OF ARLINGTON

WESTNET, INC.

COUNTY, VIRGINIA

AUTHORIZED SIGNATURE:	Dr. Sharon T Lewis	AUTHORIZED SIGNATURE:	Down Matheny	
NAME:	Sharon T Lewis	NAME: Dawn M	atheny Financial Officer	
TITLE: Purcha DATE: 6/12/20		TITLE:		

ARLINGTON COUNTY AGREEMENT 243-11 EXHIBIT A NEW INSTALLATION FOR FIRE STATION 8 AS REVISED BY CONTRACT AMENDMENT 3

Table of Contents

Introduction	Error! Bookmark not defined.
References	3
Hardware & Installation Services	Error! Bookmark not defined.
Software Configuration & Interfaces	Error! Bookmark not defined.
Timely Communication	Error! Bookmark not defined.
Project Schedule & Milestones	4
Design Submissions and Reviews	4
Schematic Design	4
Design Development	4
Construction Documents	4
Milestone 1: Hardware Configuration & Delivery	Error! Bookmark not defined.
Milestone 2: Installation	5
Electrical, Cabling and Conduit Installation Requirements	5
Transition from Temporary FS8 to New Permanent FS8	5
Final Submitals	6
Milestone 3: System Testing, Training & Acceptance	6
Milestone 4: System Reliability: Hardware/Software	6
Milestone 5: System Reliability: Automated Voice Dispatch (AVD)	7

Introduction

This project is for the design and construction of the new Fire Station Alerting System (FSA) for Fire Station 8 to be installed and configured to function with the existing County Fire Station Alerting System. The major components of this construction include hardware, installation services, and software configuration for FS8 equipment.

References

The Codes and Regulations listed below form a part of this specification to the extent referenced. Work shall be performed in accordance with the applicable international, federal, state, and local codes or standards current at the commencement of installation. The following list summarizes applicable standards:

- 1. Underwriter's Laboratories UL-1069.
- 2. Electronics Industry Association / Telecommunications Industry Association.
- 3. National Electrical Code.
- 4. U.S. Dept. of Labor / Occupational Safety and Health Administration.
- 5. National Fire Protection Association 1221.

Where more than one code or regulation is applicable, the more stringent shall apply. Cable and equipment installation, identification and termination shall be performed in accordance with the applicable codes above.

Hardware & Installation Services

Hardware requiring installation are identified in the attached quote and shall be installed in conformance with the attached technical drawings and as required to provide a complete functioning system. The Contractor shall coordinate layout and installation of Station Alerting System equipment with all other disciplines and trades.

Software Configuration & Interfaces

Upon successful installation and passing of reliability period, all FSA System components shall be covered by existing Maintenance Agreement 23-FIR-SLA-411. All software upgrades shall be subject to the Software Change Control Methodology described within the Maintenance Agreement Scope of Services. This system shall be capable of interfacing to, and receiving alerts from a data network, radio network, and two-tone paging system. The system shall be based on standard EIA/TIA 568-B Category 5 data network cabling.

Timely Communication

Time is of the essence with this project, so County and Contractor agree to respond to one another no more than 2 business days from receipt of any written communications (digital such as email, or physical letter).

Project Schedule & Milestones

Design Submissions and Reviews

For all new construction work, the Contractor shall provide coordination and input during the different design phases as described below:

Schematic Design

Following completion of the Schematic Design, the County will forward their Architect and Engineer's (A/E's) Schematic Design Drawings to Contractor, who will perform their required programming and develop the design. Contractor will be given 10 days to perform programming, develop the design, and return the drawings to the County or their agent.

Design Development

Following receipt of Contractor's initial programming during Schematic Design, the A/E will incorporate the Contractor equipment into the design developed during the Design Development (DD) phase. The A/E will include Westnet's drawings in the set, and coordinate the locations of the equipment, but shall not be required to reproduce the design except to show coordination of the locations of equipment.

The Contractor shall anticipate receiving a Progress set of drawings from the County at the end of the DD phase, which the Contractor shall review and mark up designs with their review comments and return to the County within 10 days of receipt. The contractor shall update their drawings.

Construction Documents

Following receipt of Contractor's DD review comments, the A/E will prepare Construction Documents (CD) and incorporate Contractor's comments. The Contractor shall anticipate receiving a Progress set of drawings from the County during the CD phase, which the Contractor shall review and mark up with their review comments and return to the County within 10 days of receipt. The contractor shall update their drawings.

Milestone 1: Hardware Configuration & Delivery

- Contractor shall configure all hardware based on Arlington County current configurations for hardware. Where new
 information is required, County will provide the required configuration information within 10 days of Amendment
 Execution.
- 2) Contractor shall have 30 days from confirmation of successful submission by the County of all required information, to complete the following:
 - a. Factory Configuration and Provisioning
 - i. Configuration Sign-Off
 - ii. Dispatch Server and Workstation Staging
 - iii. RIC Configuration and Testing
 - iv. MCU Configuration and Testing
 - v. System Level Integration Testing
 - b. Shipment of equipment to local offices
- County shall not be required to submit documentation detailing anything other than specifications for FS8. FS8 shall conform to the existing County standards.
- 4) Until the resources are confirmed as scheduled for mobilization with the County, this milestone will be considered incomplete.

Milestone 2: Installation

Installation shall be coordinated with the designated contacts from the following County agencies: Fire Department, Dept. of Environmental Services (DES) and Public Safety Information Technology (PSIT) equipment for each station.

Installation shall conform with DES guidelines, and at a minimum Contractor shall:

- 1) Following issuance of the Building Permit, be responsible for obtaining Trade Permit from County Inspection Services Division (ISD) for their work,
- 2) Verify all the following conditions and requirements for County infrastructure (e.g., conduits, junction boxes, etc.) are met and in compliance before walls are closed in:
 - a. Ensure all cabling is installed in rigid conduit (by others),
 - b. Ensure all cabling installed above ceilings is plenum-rated cable and installed in cable tray or on J Hooks.
 - c. No surface-mounted conduit is permitted.
- 3) Coordinate wall and ceiling inspections with General Contractor and the County's Inspection Office (ISD).
- 4) Only manufacturer's trained installers shall install, service, and maintain the specified system.
- 5) Mount equipment and enclosures plumb, level, straight and square. Mount enclosures onto plywood backboards securely mounted to the wall and painted to match the wall surface.
- 6) Permanently install equipment to be firmly and safely held in place. Fastenings and supports shall be adequate to support their loads with a safety factor of at least three. All equipment shall be installed in a fashion as to present no safety hazard to operating personnel.

Electrical, Cabling and Conduit Installation Requirements

- 1) Wires shall be in dedicated conduit separate from the low voltage security conduit. AC power shall not be run in conduit containing signal wires. Lines in conduit shall not be spliced.
- 2) Coordinate with the general contractor and division 26 electrical to assure that conduit is properly installed and coordinated including but not limited to conduit at doors which must be properly installed before doors are set and grouted and other conduits used by the protection systems.
- 3) Wiring and Cable: Wiring shall be neat and sturdy. Wires shall not be bent sharply where they enter insulating material. Wires and conduit shall be properly placed in conduit and supported to prevent undue stress on the conductors and terminals and prevent any undue change in the position of conductors. All wires shall be tagged and coded indicating their use. Each tag shall clearly state its use. It should note the alarm zone and/or point code number and transponder number. Tags shall be placed with such frequency as to enable easy tracing of wires. AC power shall not be run in conduit containing signal cables. Lines in conduit shall not be spliced.
- 4) Cable Identification: All wires shall be color coded and color codes shall be maintained throughout. Record drawings shall indicate color codes if they deviate from a standard plan. Data cables shall be labeled on each end for identification.
- 5) Use solderless crimp on connectors in a secure manner installed according to the manufacturer's recommendations.
- 6) Ground the system according to the manufacturer's recommendations and detail the method in your submittals.

Provide all wires and all installation of wires and all cabinets, control and detection equipment and similar equipment, unless noted otherwise.

Transition from Temporary FS8 to New Permanent FS8

During the design phase the Contractor shall have a qualified Contractor representative walk through the temporary facility and inventory the existing equipment. Following the walkthrough / inventory assessment, the Contractor shall provide, as a minimum, the following:

- Written recommendations for what existing equipment can be transferred to and re-used in the permanent station should the County desire to transfer and re-use any of the existing equipment. Equipment to be considered for re-use must result in minimal downtime between the transfer from the temporary to the permanent station.
- 2) Provide a written Transition Plan that includes details of how a smooth transition can occur with minimal or no disruption of services and operations. Detailed plan should include dates, sequencing, and other measures necessary to ensure continuity of operations for the Fire Department.

Final Submittals:

As-Built Drawings: During system installation, contractor to maintain a separate hard copy set of drawings, elementary diagrams, and wiring diagrams of the SMS to be used for record drawings. This set shall be accurately kept up to date by the Contractor with all changes and additions to the SMS. The contractor shall provide copies of the final as-built drawings to the County per paragraph 10 (section 53 of the contract) in amendment #2 to the contract between The County and Westnet.

Milestone 3: System Testing, Training & Acceptance

- 1) System Testing & Acceptance shall begin and complete no later than 10 business days from occupancy of new permanent FS8.
- 2) System Testing and Acceptance shall include unit and integration testing of all equipment for FS8.
- 3) Also included in the final acceptance, Contractor shall obtain written approval from the Fire Department's Communication Officer (FDCO) regarding a fully functioning Contractor system.
- 4) PSIT shall review and approve status of network connectivity and manage coordination with DTS for any troubleshooting.
- 5) Upon completion of their installation, Contractor shall provide as-built drawings of their installed work. This can be accomplished by Contractor marking up (red lining) the approved permit drawings anywhere their installation differs from what was shown on the approved drawings.
- 6) Should the General Contractor and/or ISD cite concerns with Contractor's installed work, Contractor shall be responsible for making the necessary corrections to their work subject to County Project Officer's review and approval of the completed work.

Milestone 4: System Reliability: Hardware/Software

The purpose of the Reliability Test, as part of the overall System acceptance requirements, is to demonstrate the operational capability and reliability of the System and System Components for the new Permanent FS8.

- The Reliability Test will be conducted at the successful completion of System Testing and Acceptance.
- 2) To complete the Reliability Test successfully the following must occur:
 - a. All Systems and System Components for FS8 must demonstrate full availability for 30 consecutive calendar days.
 - This includes endpoint mapping displaying street views accurately.
 - b. System and System Component performance will continue to meet the Performance requirements of the Contract, as tested, or verified by County personnel at any time.
- 3) If the System or any System Component falls below the required availability mark, the Reliability Test will be stopped. At this time the Contractor should correct any deficiencies in preparation for a retest. If the deficiencies are of such severity that the retest cannot be initiated within fifteen (15) calendar days of the initial failure, the Contractor should prepare a correction plan that details the reason for the failure and proposed correction.
- 4) The Contractor will have three (3) opportunities to complete the Reliability Test over a period of 120 (One-hundred and twenty) calendar day period. In the event the Contractor is unable to complete the reliability testing within 120 calendar days from completion of System Testing & Acceptance, Contractor shall forfeit the reliability payment.

Milestone 5: System Reliability: Automated Voice Dispatch (AVD)

The purpose of the Reliability Test, as part of the overall System acceptance requirements, is to demonstrate the operational capability and reliability of the System and System Components for the new Permanent FS8.

- The Reliability Test will be conducted at the successful completion of System Testing and Acceptance.
- 2) To complete the Reliability Test successfully the following must occur:
 - a. All Systems and System Components for FS8 must demonstrate full availability for 30 consecutive calendar days.
 - This includes endpoint mapping displaying street views accurately.
 - b. System and System Component performance will continue to meet the Performance requirements of the Contract, as tested, or verified by County personnel at any time.
- 3) If the System or any System Component falls below the required availability mark, the Reliability Test will be stopped. At this time the Contractor should correct any deficiencies in preparation for a retest. If the deficiencies are of such severity that the retest cannot be initiated within fifteen (15) calendar days of the initial failure, the Contractor should prepare a correction plan that details the reason for the failure and proposed correction.
- 4) The Contractor will have three (3) opportunities to complete the Reliability Test over a period of 120 (One-hundred and twenty) calendar day period. In the event the Contractor is unable to complete the reliability testing within 120 calendar days from completion of System Testing & Acceptance, Contractor shall forfeit the reliability payment.



15542 Chemical Lane Huntington Beach, CA 92649 Phone: 714-548-3500 Fax: 714-901-5610 www.FirstInAlerting.com



Quote: Arlington New Fire Station #8 First-In Alerting Smart Station System Revised 4

To: Arlington County Fire Department

Arlington County Fire Department

2100 Clarendon Blvd,. Ste 400

Arlington, VA 22201

Contact:

From: Zulema Perez

Summary

Total Amount: **\$539,629.07** Quote ID: Q-07954-Z4Z2 Revision: 5

 Shipping Method:
 Ground
 Date:
 12/21/2022

 Payment Terms:
 Net 30
 Effective To:
 3/1/2023

Description: This quote is for Arlington New Fire Station #8 First-In Alerting Smart Station System including installation and

technical support.

Clarifying Comments: This quote is based upon installation occurring in one (1) trip. If the station is not ready and additional trips are

required, customer agrees to pay additional fees. Customer is responsible for all network connectivity between dispatch and station, as well as the CAD interface if network activation is desired. Customer is responsible to have the network equipment and power within 6 feet of the Master Control Unit and radio location. Quote does not include conduit of more than 20 feet, if required. Customer to provide VPN access to Westnet for remote

adjustments and support.

Customer is responsible for the difference in sales and use tax if applicable. Payment terms are net 30 with

payment milestones.

Quote was revised 9/23/2021 to update quote to match drawing revision dated 9/20/2021.

Quote was revised 6/6/2022 to update pricing and the effective to date.

Quote was revised 12/1/2022 to update the effective to date and pricing and add the Bond Fee.

Quote was revised 12/21/2022 to remove the sales tax.

Shipping Information

Ship To: Bill To:

Details				
Product ID	Product	QTY	Price	Sub Total
2U-SLT-SH-KIT	2U Slotted Shelf - Kit	8.00	\$85.00	\$680.00
APP-DUAL-KL	Apparatus Bay Dual Knight Light Strips	25.00	\$1,393.80	\$34,845.00
DLSP	MCU Data Line Surge Protector	1.00	\$95.00	\$95.00
DL-STROBE-BB	Dorm Light / Strobe Light Back Box - Kit	4.00	\$34.50	\$138.00
FiAP-ISS	FiAP Information System Software	1.00	\$6,475.00	\$6,475.00
FIN-AUX-L01	First-In MCU Auxiliary Module Lite	1.00	\$635.00	\$635.00
FIN-Eth-T10	Ethernet Data Activated First-In Type 10 MCU	1.00	\$9,495.95	\$9,495.95
FINISO4P	Radio Isolation Unit - Four Channel	1.00	\$831.00	\$831.00
FIS-SDP-32-TCH-MAP	Information System 32" Touch Screen Display Point with Mapping	8.00	\$3,956.86	\$31,654.88
FIS-SDP-40-MAP	Information System 40" Non-Touch Display Point with Mapping	3.00	\$2,775.00	\$8,325.00
FRMKit-Dual	MCU and Radio Rack Mount Kit	1.00	\$193.95	\$193.95

Product ID	Product	QTY	Price	Sub Total
HPA-200	High Power Paging Audio Module (includes one speaker)	1.00	\$1,875.00	\$1,875.00
HPA-200D	High Power Paging Audio Module (includes two speakers)	2.00	\$2,175.49	\$4,350.98
RK-WM-1U	Wire Management - 1 Unit - Kit	8.00	\$65.00	\$520.00
SCR26-24VC5	Control Remote (each controls up to 8 functions)	1.00	\$1,175.95	\$1,175.95
SDBS1	Doorbell Button	2.00	\$225.00	\$450.00
SDRM38V-FM-2192	Dorm Remote - Flush Mount Kit also required	12.00	\$898.25	\$10,779.00
SDRMKIT-TBD	Dorm Remote Mounting Kit - TBD	12.00	\$218.25	\$2,619.00
SKL-LS	Knight Light Strip (7.5 ft.)	77.00	\$584.80	\$45,029.60
SPC28-HS-1K2PS	Power Module w/ Hub & Spoke Controller, UPS & Dual Power Supplies	4.00	\$2,255.99	\$9,023.96
SPC28-PL-1K2PS	Power Module w/ Light Controller, UPS & Dual Power Supplies	4.00	\$1,972.00	\$7,888.00
SS-AST-LF	Alerting Strobe Light Fixture	4.00	\$225.00	\$900.00
SSAT	Satellight (driven off Satellight Controller)	38.00	\$295.00	\$11,210.00
SSATKIT-TBD	Satellight Mounting Kit - TBD	71.00	\$48.00	\$3,408.00
SSAT-M	Satellight Controller	33.00	\$599.98	\$19,799.34
SS-CI5C-M	Company Indicator (Apparatus Bay) Medium 17.37 inch	3.00	\$825.00	\$2,475.00
SS-CI5C-M-OS	Company Indicator (Outside) Medium 17.37 inch	5.00	\$950.00	\$4,750.00
SSETS	Emergency Button	2.00	\$225.00	\$450.00
SSPK-SW-M	Smart Station Speaker Switch - Main	3.00	\$225.00	\$675.00
SS-SLA-4L	Alerting Strobe Light Adaptor	1.00	\$95.00	\$95.00
SS-TAM-S	Tone Alerting Module (includes one speakers)	3.00	\$598.98	\$1,796.94
SS-TIM-01	Telephone Interface Module	1.00	\$1,199.95	\$1,199.95
SVC-LIFT+1D	Lift Service Fee for Additional Day	2.00	\$245.00	\$490.00
SVC-LIFT-FEE	Lift Service Fee	2.00	\$1,350.00	\$2,700.00

NOTES:

- 1. In the event that taxes, other than sales tax apply to the purchase of this equipment, said taxes will be paid by the customer.
- 2. Quote is based on a properly working and installed CAD, radio system(s), station radio(s) and does not include costs for repair or modifications of the CAD, radio system(s), or station radio(s).
- Any equipment drawings included with this quote are for quoting purposes only and are not to be used as working drawings unless such drawings are labeled "Installation Drawings". See attached Limited Warranty.

Equipment Total	\$227,029.50
Install Supplies	\$11,500.00
Total Tax (6.000 %)	\$0.00
Shipping and Handling	\$12,500.00
Station Equipment Install	\$225,115.41
FiAP Install, Commissioning, and Testing	\$2,960.00
FiAP Training	\$1,480.00
One Year Toll Free Technical Support	\$28,588.74
Project Coordination	\$6,650.00
Permitting and Bonding	\$21,305.42
Special Engineering Services	\$2,500.00
Total Amount	\$539,629.07


Manufacturer's warranties apply on all parts. First-In warranty is provided by Westnet and consists of one-year parts and labor. Warranty does not apply to damage resulting from outside agencies or extraneous circumstances. Installation labor for any other items is ninety days. This quote is based on the reasonable assumption that the fire station is prepared to accept the above listed parts and that any existing equipment involved with the fire station alarm be in good working order or that it will be prior to commencement of the First-In installation. Westnet has made reasonable attempts to verify that conditions are satisfactory such that installation may occur. However, should an occurrence arise where further parts, labor and/or engineering are required, the customer may be billed at the Purchase Order rate. Any additional parts, labor and/or engineering exceeding \$250 will have prior approval, unless otherwise specified by the customer prior to commencement.

If payment is not received by 30 (thirty) days from the date of invoice, a late charge of 1.5% per month of the unpaid balance will be charged to that particular invoice.

Xref _TB_arlington8_perm.dwg

EXHIBIT H - TECHNICAL DRAWINGS





SHEET NO.	SHEET CONTENTS
COVER	COVER SHEET
AS.01	ALERT SYSTEM DEVICE SCHEDULE
AS1.1	ALERTING SYSTEM DEVICE PLAN - 1ST FLOOR
AS1.2	ALERTING SYSTEM DEVICE PLAN - 2ND FLOOR
AS1.3	ALERTING SYSTEM DEVICE PLAN - 3RD FLOOR
AS1.1.1	KNIGHT LIGHTING CORRIDOR LAYOUT/ELEVATION
AS3.1	ALERTING SYSTEM CONDUIT LAYOUT - 1ST FLOOR
AS3.2	ALERTING SYSTEM CONDUIT LAYOUT - 2ND FLOOR
AS3.3	ALERTING SYSTEM CONDUIT LAYOUT - 3RD FLOOR
AS4.1	ALERT SYSTEM DEVICE DETAILS
AS4.2	ALERT SYSTEM DEVICE DETAILS
AS4.3	ALERT SYSTEM DEVICE DETAILS
AS4.4	ALERT SYSTEM DEVICE DETAILS
AS4.5	ALERT SYSTEM DEVICE DETAILS
AS4.6	ALERT SYSTEM DEVICE DETAILS





ВҮ	MAC			
DATE	02/06/23			
REVISION	DIMENSION REVISIONS			
REV	\triangleleft			

REV	\bigcirc			
	96-			
			Tree delinite	
		7.1/	compare and	

ARLINGTON FIRE STATION #8 ARLINGTON FIRE DEPARTMENT 4845 LEE HIGHWAY ARLINGTON, VIRGINIA 22207

NOTE:

IF THIS SCALE IS NOT 1".

THIS SHEET IS NOT TO SCALE.

JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB TITLE: COVER

COVER

Xref _TB_arlington8_perm.dwg

SYMBOL	MODEL NAME	MODEL NUMBER	DETAIL SHEET NUMBER	MOUNTING	CONDUIT - PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR	ADDITIONAL NOTES / COMMENTS
MCU	MASTER CONTROL UNIT	FIN-ETH	AS4.1 AS4.2	LOCATE WITHIN 6'-0" OF RADIO UNIT, IN CLOSET, CABINET, DISPATCH CENTER, OR I.T. EQUIPMENT RACK	1 1/2" C. STUBBED INTO ACCESSIBLE CEILING SPACE. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	IF MOUNTED IN MCU CABINET, A 4-11/16" JUNCTION BOX MOUNTED AT +6'-0" TO CENTER WILL BE FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. IF MCU IS MOUNTED IN I.T. RACK, NO WALL ROUGH IS REQUIRED. COORDINATE FINAL LOCATION WITH WESTNET.
CR	CONTROL REMOTE	SCR26-24VC5 (SMART STATION)	AS4.1 AS4.2	LOCATED NEAR MCU AND / OR ABOVE CEILING IF CONTROLLING EQUIPMENT	3/4" C. STUBBED INTO ACCESSIBLE CEILING SPACE (IF APPLICABLE). RE: ADDITIONAL NOTES/COMMENTS FOR INSTRUCTION. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	CONTROL REMOTE HAS DRY CONTACTS, RATED AT 24 VOLTS - IF USED FOR EQUIPMENT CONTROL. MECHANICALLY HELD CONTACTOR(S) - (24V COIL) - WILL BE NEEDED FOR CONTROLLED DEVICE(S). ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL NECESSARY POWER FOR CONTROLLED DEVICES. COORDINATE WITH DESIGNATED TRADE/SUPPLIER FOR FINAL LOCATION.
TIM	TELEPHONE INTERFACE MODULE	SPMTI	AS4.1 AS4.2	LOCATED WITHIN 6'-0" OF MCU	3/4" CONDUIT SLEEVE TO TELEPHONE OR COMM. ROOM	PAGING UNIT REQUIRES ANALOG DRY CONTACTS FROM TELEPHONE SYSTEM, OR A DEDICATED ANALOG PAGING PORT PROVIDED BY CUSTOMER. COORDINATE WITH OTHER TRADES/WESTNET.
RIU	RADIO ISOLATION UNIT	FINISO1P (SINGLE CHANNEL) FINISO4P (FOUR CHANNEL)	AS4.1 AS4.2	LOCATE WITHIN 6'-0" OF RADIO UNIT, IN CLOSET, CABINET, DISPATCH CENTER, OR I.T. EQUIPMENT RACK	NOT APPLICABLE	REQUIRES #6 THHN GREEN STRANDED TO 5 OHM EARTH GROUND 8 FOOT MAXIMUM LENGTH.
PM UPS	POWER MODULE AND UPS	SPC100028V	AS4.2 (POWER MODULE) AS4.2 (UPS)	RACK MOUNT OR SURFACE WALL MOUNT.	1" C. STUBBED INTO ACCESSIBLE CEILING SPACE. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	UNIT REQUIRES 120V RECEPTACLE @ 7'-0" TO CENTER AND DEEP 4 SQUARE, SINGLE GANG BOX MOUNTED AT +6'-6" TO CENTER FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR MINIMUM WORKING CLEARANCE SPACE REQUIRED FOR EQUIPMENT MOUNTING IS 3'-0" SQUARE.
SC	SATELLIGHT CONTROLLER	SSATKIT-A (ACOUSTIC CEILING) SSATKIT-H (HARD CEILING) SSATKIT-90 (0-90 DEGREES)	AS4.2	CEILING MOUNT OR WALL MOUNTED - VERIFY WITH DRAWINGS	3/4" C ONLY REQUIRED IN SHEETROCK CEILINGS AND/OR EXPOSED AREAS. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO INSTALL HOFFMAN BOX - PART #43050, CAT #A-SE10X8X4 - APPLIES TO SHEETROCK CEILINGS AND/OR EXPOSED AREAS. BOX MUST BE RECESSED 1/4" IN SHEET ROCK. IF MOUNTED ON WALL OR IN EXPOSED AREAS, MOUNT AT A MAXIMUM HEIGHT OF 15'-0". COORDINATE FINAL LOCATION WITH TRADES / WESTNET HOFFMAN BOX FURNISHED BY WESTNET DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACK BOX
S	SATELLIGHT SPEAKER	SSATKIT-A (ACOUSTIC CEILING) SSATKIT-H (HARD CEILING) SSATKIT-90 (0-90 DEGREES)	AS4.2	CEILING MOUNT OR WALL MOUNTED - VERIFY WITH DRAWINGS	3/4" C ONLY REQUIRED IN SHEETROCK CEILINGS AND/OR EXPOSED AREAS. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO INSTALL HOFFMAN BOX - PART #43050, CAT #A-SE10X8X4 - APPLIES TO SHEETROCK CEILINGS AND/OR EXPOSED AREAS. BOX MUST BE RECESSED 1/4" IN SHEET ROCK. IF MOUNTED ON WALL OR IN EXPOSED AREAS, MOUNT AT A MAXIMUM HEIGHT OF 15'-0". COORDINATE FINAL LOCATION WITH TRADES / WESTNET HOFFMAN BOX FURNISHED BY WESTNET DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACK BOX
FSSL	ALERTING SYSTEM STROBE	SSATKIT-A (ACOUSTIC CEILING) SSATKIT-H (HARD CEILING) SSATKIT-90 (0-90 DEGREES)	AS4.3 AS4.6	CEILING MOUNT OR WALL MOUNTED - VERIFY WITH DRAWINGS	3/4" C ONLY REQUIRED IN SHEETROCK CEILINGS AND/OR EXPOSED AREAS. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO INSTALL STROBE BACK BOX - PART #4097- APPLIES TO SHEETROCK CEILINGS. BOX MUST BE RECESSED ¼" IN SHEET ROCK. IF MOUNTED ON WALL OR IN EXPOSED AREAS, MOUNT AT 72"A.F.F. VERTICALLY OFF THE BOTTOM OF THE BOX. COORDINATE FINAL LOCATION WITH TRADES/WESTNET. STROBE BACK BOX FURNISHED BY WESTNET. DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACK BOX.
DR	DORM REMOTE	SDRM38V-FM	AS4.3	FLUSH WALL MOUNTED	3/4" C. STUBBED INTO ACCESSIBLE CEILING. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO INSTALL HOFFMAN BOX - PART #43050, CAT #A-SE10X8X4 - MOUNTED AT +48" TO TOP OF BOX. MUST BE MOUNTED 2'-0" FROM HEAD OF BED. IF LOCATED BY DOOR JAMBS AND/OR SWITCHES, MUST HAVE 18" OF CLEARANCE FOR EQUIPMENT HOUSING. BOX MUST BE RECESSED ¼" FROM SHEETROCK SURFACE - HOFFMAN BOX FURNISHED BY WESTNET. BOX TO BE MOUNTED WITH THE 10" OPENING HORIZONTAL, NOT VERTICAL.
DL	DORM LIGHT	SDRM38V-FM (REMOTE/LIGHT KIT)	AS4.3	CEILING MOUNTED	3/4" C. TO DORM REMOTE - ONLY REQUIRED IN SHEETROCK CEILINGS. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	IF MOUNTED IN SHEETROCK CEILING - A CUSTOM BUILT BACK BOX WILL BE FURNISHED BY WESTNET. DORM LIGHT IS TO BE MOUNTED AT FOOT OF BED, TOWARDS CENTER OF THE ROOM. COORDINATE FINAL LOCATION WITH TRADES / WESTNET. DEVICES MOUNTED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACK BOX
HPS HPA AMP	HIGH-POWER PAGING AMPLIFIER AND SPEAKER	SPHA150	AS4.4	CEILING MOUNT OR WALL MOUNTED - VERIFY WITH DRAWINGS.		IF MOUNTED ON EXTERIOR WALL, ELECTRICAL CONTRACTOR TO FURNISH A SINGLE GANG WEATHERPROOF BOX MOUNTED AT 10'-0" AFF MINIMUM. FURNISH A 3/4" C. SLEEVE TO A 4 SQUARE SINGLE GANG RING BOX MOUNTED ON INSIDE AT ACCESSIBLE HEIGHT. IF MOUNTED IN EXPOSED AREAS, FURNISH A 4 SQUARE BOX MOUNTED AT 10'-0" AFF MINIMUM - 12'-0" MAXIMUM HPA DEVICES MUST BE FREE FROM OBSTRUCTION - STRUT RACK MAY BE REQUIRED - COORDINATE FINAL LOCATION WITH TRADES / WESTNET.
OSC OS)	OUTSIDE SATELLIGHT OUTSIDE SPEAKER	SSAT35C-OS	AS4.4	CONTROL MOUNTED ABOVE ACCESSIBLE CEILING - SPEAKER MOUNTED ON EXTERIOR WALL	3/4" C. RE: ADDITONAL NOTES/COMMENTS FOR INSTRUCTION. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL A STANDARD SINGLE GANG WEATHERPROOF BOX FOR OUTSIDE SPEAKER MOUNTED AT A MINIMUM OF 10'-0" AFF. FURNISH A 3/4"C. TO A 4 SQUARE BOX MOUNTED IN ACCESSIBLE CEILING SPACE. COORDINATE FINAL LOCATION WITH TRADES / WESTNET.
DB	DOORBELL	SDBS	AS4.5	WALL MOUNTED	3/4" C. STUBBED INTO ACCESSIBLE CEILING. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL A 4 SQUARE DEEP BOX, WITH SINGLE GANG PLATE MOUNTED AT +48" TO TOP OF BOX. COORDINATE FINAL LOCATION WITH TRADES / WESTNET. ADJUST HEIGHT PER ADA REGULATIONS.
ES	EMERGENCY SWITCH	SSETS	AS4.5	WALL MOUNTED	3/4" C. STUBBED INTO ACCESSIBLE CEILING. REFER TO CONDUIT LAYOUT FOR SPECIFIC SYSTEM REQUIREMENTS.	ELECTRICAL CONTRACTOR TO FURNISH AND INSTALL A 4 SQUARE DEEP BOX, WITH SINGLE GANG PLATE MOUNTED AT +48" TO TOP OF BOX. COORDINATE FINAL LOCATION WITH TRADES / WESTNET. ADJUST HEIGHT PER ADA REGULATIONS.

WESTAET



COPYRIGHT 2023
WESTNET INC.
ALL RIGHTS RESERVED

EV REVISION DATE BY



ARLINGTON FIRE STATION #8
ARLINGTON FIRE DEPARTMENT
4845 LEE HIGHWAY
ARLINGTON, VIRGINIA 22207

NOTE:

IF THIS SCALE IS NOT 1".

THIS SHEET IS NOT TO SCALE.

JOB NUMBER: XXX

JOB NUMBER: XXX

DATE: 11/05/2018


DRAWN BY: SYB

DRAWN BY: SYB


SCALE: N.T.S.

TITLE: DEVICE PLAN


AS.01



AS1.1




AS1.2






THIS SHEET IS NOT TO SCALE.

AS1.3






KNIGHT LIGHT DEVICE LAYOUT - PLAN SOUTH - 3RD FLOOR

SCALE: 1/4"=1'-0"

KNIGHT LIGHT DEVICE LAYOUT - PLAN EAST ELEVATOR CORRIDOR - 3RD FLOOR

KNIGHT LIGHT DEVICE LAYOUT - PLAN WEST ELEVATOR CORRIDOR - 3RD FLOOR

SCALE: 1/4"=1'-0"



KNIGHT LIGHT DEVICE LAYOUT - PLAN EAST

ELEVATOR CORRIDOR - 2ND FLOOR

SCALE: 1/4"=1'-0"

KNIGHT LIGHT DEVICE LAYOUT - PLAN WEST ELEVATOR CORRIDOR - 2ND FLOOR

SCALE: 1/4"=1'-0"

FIRE STATION #8
FIRE DEPARTMENT
EE HIGHWAY
N, VIRGINIA 22207 ARLINGTON FIRARLINGTON FIRARLINGTON, ARLINGTON,

COPYRIGHT 2023
WESTNET INC.


ALL RIGHTS RESERVED

JOB NUMBER: XXX

TITLE: DEVICE PLAN

AS1.1.1

KNIGHT LIGHT DEVICE LAYOUT - PLAN NORTH - 3RD FLOOR SCALE: 1/4"=1'-0"



GENERAL NOTES

① DEVICES ARE TYPICAL AND FOR REFERENCE ONLY.

SPECIFIED FOR NEW CONSTRUCTION.

- 2 ALL BACK BOXES & CONDUITS ARE TO BE FLUSH MOUNTED UNLESS OTHERWISE
- DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACKBOXES
- DEVICES LOCATED IN ACOUSTICAL CEILINGS REQUIRE ACOUSTICAL WESTNET MOUNTING
- KIT (SSATKIT-A) 5 DEVICES ONLY LOCATED IN SHEETROCK OF EXPOSED CEILINGS REQUIRE HOFFMAN
- 6 DEVICES ONLY LOCATED IN SHEETROCK OR EXPOSED CEILINGS REQUIRE APPROPRIATE WESTNET MOUNTING KIT (SURFACE MOUNT
- OR FLUSH MOUNT) FOR NEW CONSTRUCTION. C LOCATIONS OF DEVICES DETERMINED AT INSTALLATION BY INSTALLER FOR NEW
- 8 SEE ARCHITECTURAL SPECIFICATION FOR ALL ROUGH-IN AND INSTALLATION DETAILS FOR NEW CONSTRUCTION.

BRAND 8X10X4 BACKBOX

CONSTRUCTION.

- 9 INSTALLER TO VERIFY WALL AND CEILING TYPE TO DETERMINE NEED FOR FLUSH OR SURFACE MOUNT INSTALLATION OF EQUIPMENT SPECIFIED FOR NEW CONSTRUCTION.
- ALL WIRING AND DEVICES TO BE INSTALLED BY WESTNET.
- ALL PENETRATION TO EXTERIOR DEVICES MUST BE WEATHERPROOF AND FIRE CAULKED FOR CONSTRUCTION BY OTHERS
- DEVICES LOCATED IN BATHROOM/SHOWER AREAS MUST BE VISIBLE FROM SHOWERS. INSTALLER TO FIELD VERIFY DEVICE LOCATION. (TYPICAL)
- ALL DEVICES MUST BE KEPT CLEAR OF OBSTRUCTIONS & CEILING FAN BLADES.
- IN ACOUSTICAL CEILING (T-BAR), WIRE CABLING IS FREE WIRE (NOT IN CONDUIT).
- 15 IN GYPSUM BOARD CEILING (SHEET ROCK / HARD LID), WIRE CABLING IN IN 3/4" CONDUIT UNLESS CONDUIT SIZE OTHERWISE NOTED
- 16 IN EXPOSED AREAS ONLY 8X10X4 HOFFMAN BACK BOX MOUNTED AT +10'-0" A.F.F. MAX. WITH OPEN FACE DOWN IN CENTER OF ROOM WITH 3/4" CONDUIT TO ACCESSIBLE CEILING SPACE, KEEP CLEAR OF OBSTRUCTIONS.
- AN INDIVIDUAL GAS CONTROL VALVE IS REQUIRED FOR EACH COOKING APPLIANCE WITH A RESET SWITCH WITHIN 6'-0" FT. OF EACH COOKING APPLIANCE.
- A 5 OHM EARTH GROUND MUST BE CONNECTED TO THE RADIO ISOLATION UNIT IN THE COMMUNICATION RACK.
- THE RADIO RECEIVING THE DISPATCH INFORMATION SHALL BE LOCATED WITHIN 6'-0" FT. OF THE RADIO ISOLATION UNIT.
- INSTALLER TO PROVIDE ONE ADDITIONAL UNCONNECTED BLUE CAT5 CABLE WITH RJ45 CONNECTORS ON BOTH ENDS BETWEEN THE MCU LOCATION AND EACH ALERTING END POINT FOR NETWORK CONNECTIVITY.

FIRST-IN FIRE STATION ALERTING SYMBOL LEGEND

MCU MASTER CONTROL UNIT DLSP DATA LINE SURGE PROTECTOR

TIM TELEPHONE INTERFACE MODULE

CR CONTROL REMOTE

RIU RADIO ISOLATION UNIT

AUX AUXILLIARY MODULE

POWER MODULE WITH UPS - BLACK

POWER MODULE DUAL WITH UPS - GREEN SC SATELLIGHT CONTROLLER

S SATELLIGHT

FSSL STROBE LIGHT - IN CONJUNCTION WITH ASLA ASLA ALERTING STROBE LIGHT ADAPTER

DR DORM REMOTE DL DORM LIGHT

HIGH-POWERED AMPLIFIED SPEAKER HPA AMP HIGH-POWERED AMPLIFIER MODULE

OSA OUTSIDE SPEAKER AUDIO MODULE

OS OUTSIDE SPEAKER - IN CONJUNCTION WITH OSA DB DOORBELL BUTTON

ES EMERGENCY SWITCH SW SPEAKER SWITCH

CI COMPANY INDICATOR OCI OUTSIDE COMPANY INDICATO

TT TURNOUT TIMER - MEDIUM MAPPING END POINT

ALERT SYSTEM - 1ST FLOOR CONDUIT PLAN

SCALE: N.T.S.



COPYRIGHT 2023 NESTNET INC. ALL RIGHTS RESERVED




ARLINGTON FIRE STATION
ARLINGTON FIRE DEPARTMI
4845 LEE HIGHWAY
ARLINGTON, VIRGINIA 22207

IF THIS SCALE IS NOT 1" THIS SHEET IS NOT TO SCALE. JOB NUMBER: XXX

DRAWN BY: SYB SCALE: N.T.S.

ITLE: CONDUIT PLAN SHEET

AS3.1



GENERAL NOTES

- ① DEVICES ARE TYPICAL AND FOR REFERENCE ONLY.
- 2 ALL BACK BOXES & CONDUITS ARE TO BE FLUSH MOUNTED UNLESS OTHERWISE
- SPECIFIED FOR NEW CONSTRUCTION.
- DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACKBOXES
- KIT (SSATKIT-A)
- DEVICES ONLY LOCATED IN SHEETROCK OR EXPOSED CEILINGS REQUIRE HOFFMAN BRAND 8X10X4 BACKBOX
- 6 DEVICES ONLY LOCATED IN SHEETROCK OR EXPOSED CEILINGS REQUIRE APPROPRIATE WESTNET MOUNTING KIT (SURFACE MOUNT OR FLUSH MOUNT) FOR NEW CONSTRUCTION.
- O LOCATIONS OF DEVICES DETERMINED AT INSTALLATION BY INSTALLER FOR NEW
- 8 SEE ARCHITECTURAL SPECIFICATION FOR ALL ROUGH-IN AND INSTALLATION DETAILS
- 9 INSTALLER TO VERIFY WALL AND CEILING TYPE TO DETERMINE NEED FOR FLUSH OR SURFACE MOUNT INSTALLATION OF EQUIPMENT SPECIFIED FOR NEW
- ALL WIRING AND DEVICES TO BE INSTALLED BY WESTNET.

COPYRIGHT 2023

NESTNET INC. ALL RIGHTS RESERVED

- ALL PENETRATION TO EXTERIOR DEVICES MUST BE WEATHERPROOF AND FIRE
- DEVICES LOCATED IN BATHROOM/SHOWER AREAS MUST BE VISIBLE FROM SHOWERS. INSTALLER TO FIELD VERIFY DEVICE LOCATION. (TYPICAL)
- ALL DEVICES MUST BE KEPT CLEAR OF OBSTRUCTIONS & CEILING FAN BLADES.
- 14 IN ACOUSTICAL CEILING (T-BAR), WIRE CABLING IS FREE WIRE (NOT IN CONDUIT).
- 15 IN GYPSUM BOARD CEILING (SHEET ROCK / HARD LID), WIRE CABLING IN IN 3/4" CONDUIT UNLESS CONDUIT SIZE OTHERWISE NOTED.
- 16 IN EXPOSED AREAS ONLY 8X10X4 HOFFMAN BACK BOX MOUNTED AT +10'-0" A.F.F. MAX. WITH OPEN FACE DOWN IN CENTER OF ROOM WITH 3/4" CONDUIT TO ACCESSIBLE CEILING SPACE, KEEP CLEAR OF
- AN INDIVIDUAL GAS CONTROL VALVE IS REQUIRED FOR EACH COOKING APPLIANCE WITH A RESET SWITCH WITHIN 6'-0" FT. OF EACH COOKING APPLIANCE.
- A 5 OHM EARTH GROUND MUST BE CONNECTED TO THE RADIO ISOLATION UNIT IN THE COMMUNICATION RACK.
- THE RADIO RECEIVING THE DISPATCH INFORMATION SHALL BE LOCATED WITHIN 6'-0" FT. OF THE RADIO ISOLATION UNIT.
- INSTALLER TO PROVIDE ONE ADDITIONAL UNCONNECTED BLUE CAT5 CABLE WITH RJ45 CONNECTORS ON BOTH ENDS BETWEEN THE MCU LOCATION AND EACH

FIRST-IN FIRE STATION ALERTING SYMBOL LEGEND

DLSP DATA LINE SURGE PROTECTOR TIM TELEPHONE INTERFACE MODULE

CR CONTROL REMOTE RIU RADIO ISOLATION UNIT

AUX AUXILLIARY MODULE POWER MODULE WITH UPS - BLACK

POWER MODULE DUAL WITH UPS - GREEN

S SATELLIGHT FSSL STROBE LIGHT - IN CONJUNCTION WITH LASLA

ASLA ALERTING STROBE LIGHT ADAPTER DR DORM REMOTE

HIGH-POWERED AMPLIFIED SPEAKER

HPA AMP HIGH-POWERED AMPLIFIER MODULE OSA OUTSIDE SPEAKER AUDIO MODULE

OS OUTSIDE SPEAKER - IN CONJUNCTION WITH OSA DB DOORBELL BUTTON

ES EMERGENCY SWITCH SW SPEAKER SWITCH

CI COMPANY INDICATOR OCI OUTSIDE COMPANY INDICATOR

TT TURNOUT TIMER - MEDIUM MEP MAPPING END POINT

ARLINGTON ARLINGTON F 4845 LE ARLINGTON

ON FIRE STATION #8


N FIRE DEPARTMENT
5 LEE HIGHWAY
TON, VIRGINIA 22207

F THIS SCALE IS NOT 1". THIS SHEET IS NOT TO SCALE. JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB SCALE: N.T.S. TITLE: CONDUIT PLAN

AS3.2

ALERT SYSTEM - 2ND FLOOR CONDUIT PLAN SCALE: N.T.S.



- ① DEVICES ARE TYPICAL AND FOR REFERENCE ONLY.
- 2 ALL BACK BOXES & CONDUITS ARE TO BE FLUSH MOUNTED UNLESS OTHERWISE
- DEVICES LOCATED IN ACOUSTICAL CEILINGS DO NOT REQUIRE BACKBOXES
- DEVICES LOCATED IN ACOUSTICAL CEILINGS
 REQUIRE ACOUSTICAL WESTNET MOUNTING KIT (SSATKIT-A)
- DEVICES ONLY LOCATED IN SHEETROCK OF EXPOSED CEILINGS REQUIRE HOFFMAN BRAND 8X10X4 BACKBOX
- 6 DEVICES ONLY LOCATED IN SHEETROCK OR EXPOSED CEILINGS REQUIRE APPROPRIATE WESTNET MOUNTING KIT (SURFACE MOUNT OR FLUSH MOUNT) FOR NEW
- CONSTRUCTION. O LOCATIONS OF DEVICES DETERMINED AT INSTALLATION BY INSTALLER FOR NEW
- 8 SEE ARCHITECTURAL SPECIFICATION FOR ALL ROUGH-IN AND INSTALLATION DETAILS FOR NEW CONSTRUCTION.

CONSTRUCTION.

- 9 INSTALLER TO VERIFY WALL AND CEILING TYPE TO DETERMINE NEED FOR FLUSH OR SURFACE MOUNT INSTALLATION OF EQUIPMENT SPECIFIED FOR NEW CONSTRUCTION.
- 10 ALL WIRING AND DEVICES TO BE INSTALLED BY WESTNET.
- ALL PENETRATION TO EXTERIOR DEVICES MUST BE WEATHERPROOF AND FIRE CAULKED FOR CONSTRUCTION BY OTHERS
- DEVICES LOCATED IN BATHROOM/SHOWER AREAS MUST BE VISIBLE FROM SHOWERS. INSTALLER TO FIELD VERIFY DEVICE LOCATION. (TYPICAL)
- ALL DEVICES MUST BE KEPT CLEAR OF OBSTRUCTIONS & CEILING FAN BLADES.
- 14 IN ACOUSTICAL CEILING (T-BAR), WIRE CABLING IS FREE WIRE (NOT IN CONDUIT).
- IN GYPSUM BOARD CEILING (SHEET ROCK / HARD LID), WIRE CABLING IN IN 3/4" CONDUIT UNLESS CONDUIT SIZE OTHERWISE NOTED
- 16 IN EXPOSED AREAS ONLY 8X10X4 HOFFMAN BACK BOX MOUNTED AT +10'-0" A.F.F. MAX. WITH OPEN FACE DOWN IN CENTER OF ROOM WITH 3/4" CONDUIT TO ACCESSIBLE
- AN INDIVIDUAL GAS CONTROL VALVE IS REQUIRED FOR EACH COOKING APPLIANCE WITH A RESET SWITCH WITHIN 6'-0" FT. OF EACH COOKING APPLIANCE.

CEILING SPACE, KEEP CLEAR OF

OBSTRUCTIONS.

A 5 OHM EARTH GROUND MUST BE CONNECTED TO THE RADIO ISOLATION UNIT IN THE COMMUNICATION RACK.

BETWEEN THE MCU LOCATION AND EACH

ALERTING END POINT FOR NETWORK

- THE RADIO RECEIVING THE DISPATCH INFORMATION SHALL BE LOCATED WITHIN
- 6'-0" FT. OF THE RADIO ISOLATION UNIT. 20 INSTALLER TO PROVIDE ONE ADDITIONAL UNCONNECTED BLUE CAT5 CABLE WITH RJ45 CONNECTORS ON BOTH ENDS

CONNECTIVITY.

FIRST-IN FIRE STATION ALERTING SYMBOL LEGEND

MCU MASTER CONTROL UNIT DLSP DATA LINE SURGE PROTECTOR

TIM TELEPHONE INTERFACE MODULE CR CONTROL REMOTE

RIU RADIO ISOLATION UNIT AUX AUXILLIARY MODULE

POWER MODULE WITH UPS - BLACK

POWER MODULE DUAL WITH UPS - GREEN

SC SATELLIGHT CONTROLLER

FSSL STROBE LIGHT - IN CONJUNCTION WITH ASLA ASLA ALERTING STROBE LIGHT ADAPTER

DR DORM REMOTE DL DORM LIGHT

HIGH-POWERED AMPLIFIED SPEAKER

HPA AMP HIGH-POWERED AMPLIFIER MODULE OSA OUTSIDE SPEAKER AUDIO MODULE

OS OUTSIDE SPEAKER - IN CONJUNCTION WITH OSA DB DOORBELL BUTTON

ES EMERGENCY SWITCH SW SPEAKER SWITCH

CI COMPANY INDICATOR

OCI OUTSIDE COMPANY INDICATOR TT TURNOUT TIMER - MEDIUM MAPPING END POINT

GENERAL NOTES

SPECIFIED FOR NEW CONSTRUCTION.



COPYRIGHT 2023 NESTNET INC. ALL RIGHTS RESERVED



ALERT SYSTEM

EN EN LINGTON FIRE STATION
INGTON FIRE DEPARTME
4845 LEE HIGHWAY
ARLINGTON, VIRGINIA 22207

ARLING1 ARLINGT

IF THIS SCALE IS NOT 1". THIS SHEET IS NOT TO SCALE. JOB NUMBER: XXX

DATE: 04/06/2021

RAWN BY: SYB SCALE: N.T.S. TITLE: CONDUIT PLAN

SHEET AS3.3

MCU - MASTER CONTROL UNIT

THE MASTER CONTROL UNIT IS THE COMMAND CENTER OF THE SMART

 THE MASTER CONTROL UNIT SHALL ACCEPT ALARM INPUTS FROM UP TO (4) RADIOS, DEDICATED PHONE LINES, POTS TELEPHONE LINES, SERIAL DATA LINES AS WELL AS TCP/IP ETHERNET NETWORKS.

 THE MASTER CONTROL UNIT SUPPORTS THE FULL ZIR COMMAND SET. THE MASTER CONTROL UNIT SHALL MEET THE NFPA REQUIREMENT 1221 FOR SUPERVISED COMMUNICATIONS FOR ALERTING WITH THE DISPATCH

 ALARM AUDIO LEVELS SHALL BE CONTROLLABLE OVER A (30) DECIBEL RANGE IN (1) DECIBEL INCREMENTS.

 RADIO AUDIO LEVELS SHALL BE CONTROLLABLE OVER A (30) DECIBEL RANGE IN (1) DECIBEL INCREMENTS.

 THE ENTIRE FIRE STATION ALERTING LEVEL SHALL BE AUTOMATICALLY REDUCED AT NIGHT AND RETURNED TO NORMAL LEVELS IN THE


MORNING AUTOMATICALLY. OUTSIDE SPEAKERS SHALL BE AUTOMATICALLY TURNED OFF AT NIGHT AND TURNED BACK ON IN THE MORNING AUTOMATICALLY.


 PRIMARY PROGRAMMING SHALL BE ACCOMPLISHED FROM THE FRONT PANEL, WHILE SECONDARY PROGRAMMING IS ACCOMPLISHED WITH THE

SMART STATION SERVICE VIA COMPUTER. FRONT PANEL PROGRAMMING SHALL BE LIMITED TO PLACING THE STATION ON RADIO WATCH OR REMOVING THE STATION FROM RADIO

 THE MASTER CONTROL UNIT SHALL BE POWERED FROM AN "ON-LINE" UPS FOR UNINTERRUPTIBLE ALERTING SERVICE.

MASTER CONTROL UNIT - MCU





CONTROL REMOTE - CR SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS

CR - CONTROL REMOTE

WHEN THE ALARM SYSTEM TRIGGERS, THE CONTROL REMOTE CAN SHUT OF GAS APPLIANCES, OPEN BAY DOORS, TURN ON BAY LIGHTS, OPEN GATES, SENSE DOOR TROUBLE, AND/OR SENSE INPUTS FROM CO DETECTORS IN APPARATUS BAYS.

 PROVIDES (8) DOUBLE POLE, DOUBLE THROW (DPDT) RELAYS UNDER SOFTWARE CONTROL OF THE MASTER CONTROL UNIT (MCU).

PROVIDES (4) REMOTE SENSING INPUTS TO COLLECT DATA RELEVANT TO THE CONTROL FUNCTIONS. ENABLES THE MASTER CONTROL UNIT TO OPERATE FIRE STATION


ALERTING EQUIPMENT THAT IS NOT SMART STATION COMPATIBLE. ALL RELAYS SHALL BE ZONE, TIME DELAY AND TIME OF DAY CONTROLLABLE IN ANY COMBINATION NECESSARY.

 SHALL PROVIDE CONTROL AND SENSE CAPABILITY THROUGHOUT THE NETWORK AT ANY LOCATION.

 RELAYS SHALL BE RATED AT (5) AMPS AT 24VOLTS DC OR AC. MECHANICAL LIFE OF THE RELAY CONTACTS SHALL BE A MINIMUM OF (5)

MILLION OPERATIONS. RELAYS SHALL BE USED TO CONTROL THE OVEN/RANGES IN THE KITCHEN, OPERATION OF EACH APPARATUS BAY DOOR INDEPENDENTLY, AND CONNECTION OF CARBON MONOXIDE SENSORS TO THE SYSTEM. COORDINATE ALL ELECTRICAL CONTACTS AND RELAYS REQUIRED FOR LINE VOLTAGE CIRCUITS TO INTERFACE WITH CONTROL REMOTE

 WESTNET ALERT SYSTEM PROVIDES ONLY DRY CONTACTS RATED AT 24VOLTS MAX. NO VOLTAGE IS SUPPLIED.




TIM - TELEPHONE INTERFACE MODULE

 SHALL BE UTILIZED FOR PAGING PERSONNEL WITHIN THE FIRE STATION. SHALL INTEGRATE THE FIRE STATION TELEPHONE SYSTEM INTO ALL AUDIO DEVICES SUCH AS COMBINATION SPEAKER/LED LIGHT DEVICES. PROGRAMMABLE SPEAKER/RED GLOW LIGHT DEVICES AND HIGH POWERED AMPLIFIERS.

REQUIRES CONDUIT SLEEVE TO STATION TELEPHONE/COMMUNICATION

TELEPHONE INTERFACE MODULE - TIM



RADIO ISOLATION UNIT — RIU

SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS

RIU - RADIO ISOLATION UNIT SURGE PROTECTION DEVICE CONNECTED TO RADIO ANTENNAS.

 EXTEND GROUNDING WIRE FROM RIU TO BUILDING LIGHTING PROTECTION SYSTEM.

ALERTING SYSTEM OVERVIEW - PLEASE READ

MOST CONTRACTORS ARE UNFAMILIAR WITH WHAT THE ALERTING SYSTEM IS AND THE CAPABILITIES OF THE SYSTEM. THE OVERALL FUNCTION OF THE ALERTING SYSTEM IS TO REDUCE THE RESPONSE TIME OF THE RECEIVED CALLS TO BETWEEN 15 TO 45 SECONDS USING AUDIO AND VISUAL ALERTS FOR DISPATCHED UNITS. THIS SYSTEM IS INSTALLED AS A LARGE COMMUNICATION LOOP UTILIZING CAT 5 CABLING WITH VERY LIMITED CONNECTIONS TO THE EXISTING BUILDING.

THERE ARE SEVERAL COMMON QUESTIONS THAT ARE GENERALLY ASKED DURING THE ROUGH IN STAGES ABOUT OUR SYSTEM.

DOES THE BACK BOX SPECIFIED NEED TO BE A HOFFMAN BRAND - PART #43050 - CAT #A-SE 10x8x4 FOR

DORM REMOTES (DR) AND SATELLIGHT CONTROLLERS (SC)? YES, THE MOUNTING FLANGES FOR THESE DEVICES ARE SPECIFICALLY MADE FOR THIS TYPE OF BOX. THIS ELIMINATES RE-TAPPING SCREW HOLES FOR THIS BOX, TO MATCH THE MOUNTING FLANGE, AND QUICKER INSTALLATION.

CAN POWER RECEPTACLES BE RELOCATED FROM THOSE SHOWN ON THE PLANS? YES, AT A MAXIMUM OF SIX (6) FEET FROM WHERE SHOWN ON THE PLANS.

CAN CONDUIT LAYOUT DIFFER FROM PLANS?

NO, THE ROUTING OF THE CONDUITS IS VERY SPECIFIC AND IS THE LINK FROM DEVICE TO DEVICE CREATING THE OVERALL COMMUNICATION LOOP.

THERE IS A SPACING CONFLICT WITH THE DORM REMOTE (DR), THERMOSTAT, LIGHT SWITCH AND TELEPHONE LOCATION NEXT TO THE DOOR JAMB. CAN THIS BE RELOCATED?

YES, THIS CAN BE MOVED AWAY FROM THE DOOR JAMB. GENERALLY BETWEEN THE LIGHT SWITCH AND THERMOSTAT IS MOST COMMON FOR THE OCCUPANTS TO MONITOR THEIR DISPATCHED CALLS. REFER TO NOTES ON AS.01. THE MOUNTING FLANGE WILL REQUIRE 18" OF SPACE BETWEEN LIGHT SWITCH AND THE ADJACENT DEVICE TO ALLOW FOR THE HORIZONTAL MOUNTING OF THE HOFFMAN BOX.

CAN ALERT SYSTEM DEVICES BE RELOCATED?

YES, BUT AT A MAXIMUM OF SIX (6) FEET FROM LOCATIONS SHOWN ON THE PLANS. PLEASE KEEP IN MIND THE EQUAL SPACING OF THE DEVICES PROVIDES FOR EVEN AUDIO AND VISUAL COVERAGE. THIS IS IMPORTANT WHEN ANNOUNCING DISPATCHED CALLS. ALSO, THE CABLING IS PRE-ASSEMBLED AND IS DESIGNATED FOR THAT DEVICE. RELOCATION OF DEVICES BY MORE THAN SIX (6) FEET FROM INDICATED LOCATIONS, WILL NEED APPROVAL BY WESTNET.

HOW ARE THE HOFFMAN BRAND - PART #43050 - CAT #A-SE 10x8x4 BOXES TO BE MOUNTED? FOR DORM REMOTES (DR) THE BACK BOX IS TO BE MOUNTED HORIZONTALLY, 10" WIDE, 8" TALL AND RECESSED 1/8" INTO THE SHEETROCK WALL, AT 48" TO THE TOP OF THE BOX, ABOVE FINISHED FLOOR (AFF). THE MOUNTING FLANGE COVERS THE BACK BOX OPENING AND PULLS FLUSH AGAINST THE

FOR SATELLIGHT CONTROLLERS (SC), THE BOX IS TO BE MOUNTED INTO THE SHEETROCK CEILING, THE BACK BOX WILL BE INSTALLED WITH THE 10" SIDE ALIGNED WITH THE LENGTH OF THE ROOM/CORRIDOR. BOXES SHOULD GENERALLY BE INSTALLED IN THE CENTER OF ROOMS FREE FROM OBSTRUCTIONS AND AVOIDING OTHER TRADES, RECESSED 1/8" INTO THE SHEETROCK AND MOUNTED AT A MAXIMUM OF 15'

BACK BOXES INSTALLED IN OPEN AREAS WILL BE MOUNTED AT A MAXIMUM OF 15' ABOVE FINISHED SURFACES, FREE FROM OBSTRUCTIONS AND AVOIDING OTHER TRADES, RECESSED 1/8" INTO THE SHEETROCK. BACK BOXES IN OPEN AREAS SHALL BE VISIBLE FROM ALL POINTS IN THE ROOM/HALLWAY. INSTALLER TO VERIFY VISIBILITY FROM ALL AREAS PRIOR TO FINALIZING INSTALLATION LOCATION. WESTNET DOES NOT ASSUME RESPONSIBILITY FOR POOR AND IMPROPER INSTALLATION OF BACK BOXES. REFER TO NOTES ON AS.01.

WHAT IS THE FUNCTION OF THE CONTROL REMOTE? THE CONTROL REMOTE (CR) CAN PERFORM MULTIPLE FUNCTIONS, SUCH AS OPENING BAY DOORS, OPENING GATES, SHUTTING OFF EQUIPMENT, KITCHEN STOVES AND APPLIANCES, CORRIDOR LIGHTING, ETC. ANY EQUIPMENT THAT SHOWS TO BE CONNECTED AND CONTROLLED BY THE CR WILL NEED A CONTROL VOLTAGE OF 24 VOLTS THAT IS NOT SUPPLIED BY WESTNET. THE TERMINAL RATING IS A MAXIMUM OF 24V ON THE CR.

WHAT IS THE MASTER CONTROL UNIT?

SHEETROCK.

ABOVE FINISHED FLOOR.

THE MCU IS THE BRAINS OF THE SYSTEM. RECEIVED CALLS GO THROUGH THIS DEVICE AND ARE ANNOUNCED THROUGHOUT THE SYSTEM. THIS IS MOST COMMONLY THE ONLY CONNECTION THAT IS MADE TO THE EXISTING COMMUNICATIONS. THIS UNIT IS TO BE LOCATED WITHIN SIX (6) FEET OF THE DISPATCH RADIO IN WATCH ROOM OR COMMUNICATION ROOM OF THE STATION.

THESE ARE JUST A FEW OF THE MOST COMMON QUESTIONS. THERE IS TO BE NO ALTERATION OF THE SYSTEM, DEVICES OR LAYOUT WITHOUT THE APPROVAL OF WESTNET. MOST INFORMATION CAN BE FOUND ON AS.01.

IF THERE ARE ANY QUESTIONS OR CONCERNS ABOUT THE ROUGH IN FOR INSTALLATION, PLEASE CALL WESTNET AT 1-800-807-1700.



ALL RIGHTS RESERVED

ВҮ				
DATE				
REVISION				
REV				



ALERT SYSTEM

ARLINGTON FIRE STATION #8 ARLINGTON FIRE DEPARTMEN 4845 LEE HIGHWAY ARLINGTON, VIRGINIA 22207

IF THIS SCALE IS NOT 1' THIS SHEET IS NOT TO SCALE.


JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB SCALE: N.T.S.


TITLE: DEVICE DETAILS SHEET


MTG KIT PIC.JPG

FINISHED FLOOR




SMART STATION RACK DIAGRAM





FINISHED FLOOR

SATELLIGHT CONTROLLER COUNDUIT MOUNTING DETAIL



S

FIRE STATION.

DEPARTMENT DISPATCH CENTER.

TO THE LAMP ASSEMBLY.

SATELLIGHT, SPEAKER/LED LIGHT

- SHALL OPERATE ON A CAT 5 ALARM SUBNETWORK, WHICH IS DRIVEN FROM A DEVICE CONTROLLER.
- AUDIO OUTPUT FROM THE DEVICES SHALL BE SET BY THE SOFTWARE FROM THE CONTROLLER.
- AUDIO OUTPUT SHALL BE ADJUSTABLE ACROSS A (90) DECIBEL RANGE.
- THE LIGHTING OUTPUT SHALL INCREASE AUTOMATICALLY DURING THE FIRST FEW SECONDS OF THE ALARM SEQUENCE.

- SHALL OPERATE ON A CAT 5 SMART STATION PRIMARY ALARM NETWORK, WHICH IS DRIVEN FROM THE MCU.
- OPERATE INDEPENDENTLY OR DRIVE UP TO (3) OR (4) DEVICES DEPENDING UPON THE LOCATION IN THE

UTILIZE BI-DIRECTIONAL DATA THROUGHOUT THE SMART STATION NETWORK AND EXTEND CAPABILITY TO THE FIRE

- SHALL BE CAPABLE OF INTELLIGENT SENSING AND CONTROL OF FIRE STATION SYSTEMS AND EQUIPMENT. CONTROLLER SHALL

- ACOUSTICAL CEILING MOUNTING SECURES THE DEVICE TO THE T-BAR RAILS AND THE SUPERSTRUCTURE OF THE BUILDING.
- DRYWALL AND PLASTER CEILING MOUNTING HARDWARE SHALL UTILIZE METAL HARDWARE THAT IS COLOR-MATCHED

- AUDIO OUTPUT SHALL BE CONTROLLED BY SOFTWARE FROM THE MASTER CONTROL UNIT.

- SHALL BE MOUNTED IN THE CEILING TO PROVIDE ALARM COVERAGE THROUGHOUT THE STATION.

- AUDIO OUTPUT SHALL BE ADJUSTABLE ACROSS A (90) DECIBEL RANGE.

- THE LIGHTING OUTPUT SHALL INCREASE AUTOMATICALLY DURING THE PIRST FEW SECONDS OF THE ALARM SEQUENCE.


- SHALL BE MOUNTED IN CEILING TO PROVIDE ALARM COVERAGE THROUGHOUT THE STATION.

- ACOUSTICAL CEILING MOUNTING SECURES THE DEVICE TO THE T-BAR RAILS AND THE SUPERSTRUCTURE OF THE BUILDING.

- DRYWALL AND PLASTER CEILING MOUNTING HARDWARE INSTALLS DEVICES INTO THESE CEILINGS.



COPYRIGHT 2023
WESTNET INC.
ALL RIGHTS RESERVED





ON FIRE STATION #8 ON FIRE DEPARTMENT

ARLINGTO ARLINGTO

NOTE:

IF THIS SCALE IS NOT 1".

THIS SHEET IS NOT TO SCALE.


JOB NUMBER: XXX

DATE: 04/06/2021


DRAWN BY: SYB

SCALE: N.T.S.


TITLE: DEVICE DETAILS
SHEET







DORM REMOTE WITH ATTACHED FACEPLATE







SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS




- SPEAKER/LIGHT DEVICES SHALL BE FIREFIGHTER PROGRAMMED TO ACTIVATE ON ALL ALARMS STARTING AT SHIFT CHANGE.
- THE DEVICE AUDIO SHALL BE ADJUSTED OVER A (60) DECIBEL RANGE IN (1) DECIBEL INCREMENTS TO AID IN THE REDUCTION OF AUDIBLE SHOCK THAT OCCURS WHEN THE FIREFIGHTER AWAKENS TO AN ALARM.
- THE LIGHTING SHALL INCREASE IN INTENSITY DURING THE FIRST FEW SECONDS OF THE ALARM SEQUENCE, TO REDUCE OPTICAL SHOCK UPON AWAKENING.
- THE LIGHT OUTPUT SHALL BE ADJUSTABLE BY EACH FIREFIGHTER. THE TWO-LINE DISPLAY SHALL BE USED FOR DISPLAYING TEXT MESSAGING.
 THE DEVICE SHALL OPERATE UP TO (4) COMBINATION SPEAKER/LED LIGHT
- DEVICES FOR ZONE CONTROLLED SLEEP AREAS.
- THE DEVICE SHALL BE DESIGNED TO BE WALL OR ROOM DIVIDER MOUNTED AT
 (2) FEET ABOVE THE HEIGHT OF THE BED TO PROVIDE ILLUMINATION FOR THE
- BED AND THE FLOOR. THE DEVICE SHALL BE SURFACE MOUNTED.
- ALL CONNECTIONS SHALL BE MODULAR PLUGS ENABLING RELOCATION OF DORM REMOTE WITH MINIMUM EFFORT.




ALERTING STROBE — FSSL SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS





FSSL ALERTING STROBE LAYOUT





IF THIS SCALE IS NOT 1".
THIS SHEET IS NOT TO SCALE.


JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB SCALE: N.T.S.

TITLE: DEVICE DETAILS SHEET

SINGLE GANG BOX — NEW 7/8" CORE -¾" CONDUIT TO BOX — SPEAKER CONE HIGH POWER AMPLIFIER

SIDE VIEW



HPA
AMP

HIGH POWER PAGING AMPLIFIER AND SPEAKER

HIGH POWER AMPLIFIERS SHALL PROVIDE DYNAMIC CONTROL OF THE FIRE ALARM SOUND LEVELS IN HIGH NOISE AREAS OF THE FIRE STATION.

• AMPLIFIERS SHALL BE USED THROUGHOUT THE APPARATUS BAYS AND ALONG THE PERIMETER OF EACH STATION.

•INCREASED VOLUME SHALL PROVIDE AUDIBLE DISPATCH IN HIGH NOISE LEVEL AREAS. INCREASED VOLUME SHALL PROVIDE AUDIBLE DISPATCH IN HIGH NOISE LEVEL AREAS.

AN AMBIENT NOISE DETECTOR SHALL SENSE SOUND LEVELS IN THE IMMEDIATE AREA AND CONTROL THE OUTPUT POWER FROM (0) TO (128) DECIBELS.

MAXIMUM OUTPUT POWER SHALL BE SET BY SERVICE SOFTWARE.

A BUILT IN VOLUME LED INDICATOR SHALL DISPLAY THE OUTPUT LEVEL CONTROL ACTIVITY.

BUILT IN LED STATUS INDICATORS SHALL INDICATE THE OPERATING MODE OF THE HIGH POWER AMPLIFIER.

MULTIPLE HIGH POWER AMPLIFIERS SHALL BE OPERATED ON THE SMART STATION NETWORK.

SPEAKERS SHOWN OUTDOORS SHALL BE WEATHERPROOF AND DESIGNED FOR OUTDOOR USE.

SPEAKER MOUNTS SHALL BE ADJUSTABLE TO ANY ANGLE AS NEEDED BY THE INSTALLATION.

LIQUID-TIGHT FLEXIBLE CONDUIT OUTSIDE SPEAKER

HEIGHT VARIES REFER TO DEVICE LAYOUT

∕ 3⁄4" CONDUIT WITH FIRE ALERTING CABLE

FRONT VIEW

WALL PENETRATION-

OUTSIDE SPEAKER -

AMPLIFIER

DATA BACKBOX —

OUTSIDE SPEAKER — OS
SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS

HIGH POWER AMPLIFIER AND INTERIOR/EXTERIOR SPEAKER
SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS

NOTE: ALL THRU PENETRATIONS MUST BE SEALED WITH DAP - PREMIUM RUBBER CONCRETE, TYPICAL.

IT IS MANDATORY TO INSTALL SCREWS IN ALL MOUNTING HOLES.

I 12'-0" A.F.F. TYPICAL

10'-0" MIN A.F.F.

12'-0" MAX A.F.F.

FLOOR

LIQUID-TIGHT FLEXIBLE CONDUIT

COPYRIGHT 2023 WESTNET INC. ALL RIGHTS RESERVED



ARLINGTON FIRE STATION #8
ARLINGTON FIRE DEPARTMEN
4845 LEE HIGHWAY
ARLINGTON, VIRGINIA 22207

IF THIS SCALE IS NOT 1". THIS SHEET IS NOT TO SCALE. JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB SCALE: N.T.S. TITLE: DEVICE DETAILS


SHEET






DOORBELL

- SHALL NOTIFY PERSONNEL OF VISITOR ON FIRE STATION GROUNDS.
- NOTIFICATION OF VISITOR SHALL BE RELAYED TO DISPATCH CENTER.
- SHALL NOTIFY FIRE PERSONNEL AT WHICH DOOR THE VISITOR IS WAITING.
- PROVIDE CUSTOMIZED MESSAGES AND ALERT TONES.





EMERGENCY BUTTON — EB SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS



EMERGENCY BUTTON

- SHALL NOTIFY PERSONNEL OF EMERGENCY ON FIRE STATION GROUNDS.
- SHALL NOTIFY DISPATCH CENTER OF INCIDENT OCCURANCE AT THE FIRE STATION.
- SHALL ENABLE THE FIRE FIGHTER TO ANSWER THE DOOR AND ATTEND TO THE PROBLEM IMMEDIATLY.
- SHALL PROVIDE BOTH AUDIBLE AND VISUAL NOTIFICATION OF AN EMERGENCY.
- PROVIDE CUSTOMIZED MESSAGES AND ALERT TONES.







ARLINGTON FIRE STATION #8
ARLINGTON FIRE DEPARTMENT
4845 LEE HIGHWAY
ARLINGTON, VIRGINIA 22207

NOTE:


IF THIS SCALE IS NOT 1".

THIS SHEET IS NOT TO SCALE. JOB NUMBER: XXX DATE: 04/06/2021

DRAWN BY: SYB

TITLE: DEVICE DETAILS SHEET

AS4.5






RE: WESTNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS.




SPEAKER SWITCH

- SHALL BE UTILIZED TO CONTROL THE ACTIVE/INACTIVE OPERATION OF THE SATELLIGHT CONTROLLER IN ROOM (COMBINATION SPEAKER/LED LIGHT DEVICE).



SWITCH/BUTTON MOUNTING DETAIL
SEE WESNET SPECIFICATIONS FOR OVERALL DEVICE DIMENSIONS



TYP. (FSSL) ALERTING STROBE LIGHT & ADAPTER (ASLA)
see wesnet specifications for overall device dimensions

WESTAE



COPYRIGHT 2023
WESTNET INC.
ALL RIGHTS RESERVED

REV REVISION DATE BY



ALERT SYSTEM

REINGTON FIRE STATION #8
LINGTON FIRE DEPARTMENT
4845 LEE HIGHWAY

PROJECT NAME:

ARLINGTO

NOTE:

IF THIS SCALE IS NOT 1".

THIS SHEET IS NOT TO SCALE.

JOB NUMBER: XXX

DATE: 04/06/2021

DRAWN BY: SYB SCALE: N.T.S.

TITLE: DEVICE DETAILS