



OKALOOSA COUNTY WATER & SEWER ADMINISTRATION

March 28, 2024

CONTRACT #: C23-3361-WS
DONALD SMITH COMPANY, INC.
MAINTENANCE & EMERGENCY REPAIR OF
OKALOOSA COUNTY WATER WELLS, WATER
BOOSTER PUMP STATIONS, WASTEWATER EFFLUENT
PUMP STATIONS & STOREWATER PUMP STATIONS
EXPIRATION: 07/18/2023 W/2 1 YR RENEWALS

Mr. Bob Baker, Project Manager
Donald Smith Company, Inc.
746 East Main Street
Headland, AL 36345

**RE: Notice to Proceed – Rehab Annex Well
County Contract #C23-3361-WS**

Dear Mr. Baker:

Please consider this letter as notice to proceed with the purchase and delivery of materials, as outlined in your quote dated March 28, 2024 (attached). We expect the work performed to not exceed the price quoted in that correspondence. Your total estimate is \$146,847.50 for the scope of services described. Work is per the terms and conditions of the above-mentioned contract and the attached scope of work.

Please note that any work that may be charged in excess of your estimate will require prior written approval from Okaloosa County. When this work is invoiced, please make sure to include proper backup for the additional services listed in Line Item 18 (showing documentation of the cost, plus 25% markup).

Should you need any further information or have any questions, don't hesitate to contact your primary point of contact at Okaloosa County Water & Sewer.

Sincerely,
Robert Bass

Digitally signed by Robert
Bass
Date: 2024.03.28
14:59:28 -05'00'

Robert "Clay" Bass
Okaloosa County Water Operations Manager

Donald Smith Company, Inc.

746 East Main Street • Headland, Alabama 36345 • (334) 693-2969 • Fax (334) 693-3089

March 27, 2024


Chris Pelfrey
Okaloosa Water & Sewer System
1804 Lewis Turner Blvd.
Ft. Walton Beach, FL 32547

Re: Annex Well

Dear Mr. Pelfrey:

Based on the data provided and field observations we recommend the following services in accordance with our Okaloosa County Maintenance & Emergency Repair to Wells Agreement to rehabilitate the existing well and replace the existing well pump with a new pump capable of 1000 gallons per minute.

Item # 1	Pre-Performance Testing	
	Post-performance testing (including vibration, flow meter and pumping testing) in accordance with specifications	\$9,300.00
Item # 6	Well Pulling & Reinstallation	
	Mobilize and remove pump, motor (100 to < 150 HP), column assembly, etc. from well, disassemble, complete inspection & report, reassemble & reinstall pump, etc., back into well, including disinfection and site restoration, complete and in place for the lump sum price of	\$39,910.00
Item # 13.	Well Cleaning	
	Complete well casing cleaning and video recorded inspection of well in accordance with specifications, complete and in place for the lump sum price of	\$35,510.00



Donald Smith Company, Inc.

746 East Main Street • Headland, Alabama 36345 • (334) 693-2969 • Fax (334) 693-3089

Item # 14	Oil Disposal	
	Disposal of oil in well column, measured by the barrel, in Contractor supplied container(s)	
	Estimated 5 barrels at \$155.00/barrel	\$775.00
Item # 11	Post-Performance Testing	
	Post-performance testing (including vibration, flow meter and pumping testing) in accordance with specifications	\$9,300.00
Item # 18	Fixed 25% Mark Up	
	Fixed 25% - Mark-up for replacement parts to include overhead & profit. (NOTE: Base price before mark-up should include taxes and freight.)	
	Nidec VHS 100HP/1800RPM/460V/3PH/60HZ/ INV DUTY//WPI/NRR/PREM EFF MOTOR	\$9,929.00
	8" (0.322) X 1.5" x 190' W/L Column Assembly Complete with 416SS Shaft & 416SS Coupling, Vesconite Insert, 304SS Spiders, Mill Finish Coating ID/OD	\$19,995.00
	FloWise 12HC - 3 Stage W/L Bowl Assembly with 10" Suction, Vitraeous Enameled Bowls, 907LF Bronze Bearings, 416SS Shaft, 304SS Impellers, 416SS Taperlocks, 10" Discharge, 18-8SS Bolts, Factory Standard Coating OD	\$4,441.00



Water Wells • Pumps & Service • Utility Construction

Drilling Wells and Pumping Water Since 1946

BRANCH
P.O. Box 38
Shannon, MS 38868
Phone: (662) 767-9777
Fax: (662) 767-3107

Donald Smith Company, Inc.

746 East Main Street • Headland, Alabama 36345 • (334) 693-2969 • Fax (334) 693-3089

8" x 30' Suction Pipe with Mill Finish Coating ID/OD	\$1,868.00
8" 304SS MNPT Cone Strainer	\$409.00
Estimated Miscellaneous Materials, Consumables, Freight and Taxes	<u>\$5,000.00</u>
Estimated Materials Total	\$41,642.00
25% Mark Up	<u>\$52,052.50</u>
Grand Total	\$146,847.50

Delivery of pump equipment is estimated at 4-5 weeks. Our plan includes the acquisition of the replacement pump prior to beginning work at the site. Throughout the execution of this work, every effort will be made to identify potential savings in time and money for Okaloosa County Water & Sewer.

Once the initial well video is performed, Donald Smith Company will immediately meet with Okaloosa County Water & Sewer to discuss the results and any changes to the scope of work, if needed. Once the well is deemed ready for pump installation, work toward the installation of the pump and completion of the project will begin immediately.


We estimate the completion of this scope of work should be approximately 4 weeks.

Thank you very much for the opportunity to provide Okaloosa County Water & Sewer with water supply solutions. Should you have any questions or comments, please do not hesitate to contact me at 334-550-8860 or Bob.Baker@dsco.com.

Sincerely,



Bob Baker
Project Manager



Water Wells • Pumps & Service • Utility Construction

Drilling Wells and Pumping Water Since 1946

BRANCH
P.O. Box 38
Shannon, MS 38868
Phone: (662) 767-9777
Fax: (662) 767-3107