

TASK ORDER APPROVAL FORM

CONTRACT #: C23-3262-PW

TASK ORDER #: 1

TASK ORDER AMOUNT: \$ 140,884.00

**CONTRACT #: C23-3262-PW
VORTEX SERVICES, LLC
PROVIDE TRENCHLESS
PIPELINE REHABILITATION
EXPIRES: 06/30/2023**


OFFERED BY CONSULTANT:

Vortex Services, LLC

FIRM'S NAME

Ben Roese

REPRESENTATIVE'S PRINTED NAME



SIGNATURE

Regional Vice President

9/23/22

TITLE

DATE

**RECOMMENDED FOR APPROVAL
(Department Director)**

**Jason T. Autrey,
P.E., C.P.M.**

Digitally signed by Jason T. Autrey, P.E., C.P.M.
Date: 2022.09.27 08:05:01 -05'00'

SIGNATURE

Public Works Director

TITLE

09.27.22

DATE

John Hofstad

Digitally signed by John Hofstad
Date: 2022.09.27 11:05:28 -05'00'

COUNTY ADMINISTRATOR (if applicable)

09.27.22

DATE

Revised January 21, 2020

**APPROVED BY OKALOOSA COUNTY
(Per Purchasing Manual) Table 1**

**Jeffrey A
Hyde**

Digitally signed by Jeffrey A Hyde
Date: 2022.09.27 09:17:19 -05'00'

PURCHASING MANAGER

09.27.22

DATE


Faye Douglas

Digitally signed by Faye Douglas
Date: 2022.09.27 09:27:32 -05'00'

OMB DIRECTOR/DATE

09.27.22

DATE



CHAIRMAN (if applicable) Mel Ponder, Chairman

October 4, 2022

DATE





VORTEX

services

To: Okaloosa County	Contact:
Address: 5479A Old Bethel Rd	Phone: (850) 689-5960
	Email:
Project Name: FL - Mary Esther - Brookwood Blvd	Bid Number: 2213800
Project Location:	Bid Date: 8/3/2022

Proposal is figured on utilizing HGAC Contract #TP07-18

Item #	Item Description	Estimated Quantity	Unit	Unit Price	Total Price
P35	Travel And Mobilization - Florida	1.00	EACH	\$30,000.00	\$30,000.00
B2	42" STORM PIPE - QLS REHABILITATION - 1." Thickness	120.00	LF	\$430.00	\$51,600.00
B37	Rebuild Invert (*not Anticipated But Will Bill If Needed)	121.00	CF	\$75.00	\$9,075.00
A54	37"- 42" Post TV Inspection After Rehabilitation	120.00	LF	\$12.00	\$1,440.00
A64	Vactor Truck Services (figured 1 Day To Clean All Three Pipes & 1 Day For Rebound Cleanup) *will Bill As Needed, Port To Port	20.00	HR	\$500.00	\$10,000.00
B30	Each Additional .5" Thickness	1,384.00	SF	\$15.00	\$20,760.00
B35	Infiltration Control- Chemical Grout - * To Be Billed As Needed	0.00	GAL	\$100.00	\$0.00
B36	INFILTRATION CONTROL- QUAD-PLUG	43.00	EACH	\$50.00	\$2,150.00
B38	JOINT PREPARATION (*will Bill As Needed)	120.00	LF	\$20.00	\$2,400.00
J1	Set up 4" pump and piping including up to 1000 feet of bypass discharge line	1.00	EACH	\$2,559.00	\$2,559.00
J10	Operate 4" Pumping System Per Pump	10.00	DY	\$500.00	\$5,000.00
J221	TEAR DOWN 4" PUMP AND PIPING INCLUDING 1000 FEET OF BYPASS DISCHARGE LINE	1.00	EACH	\$2,400.00	\$2,400.00
O11	Barricades, Signs, and Traffic Handling (per setup)	1.00	EACH	\$3,500.00	\$3,500.00
O12	Traffic Control Plan (per Setup) (not Anticipated But Will Bill If Required)	0.00	EACH	\$2,500.00	\$0.00
O13	Flagmen (not Anticipated But Will Bill If Required)	0.00	HR	\$40.00	\$0.00

Total Bid Price: \$140,884.00

Notes:

- Proposal includes standard signs and cones. If Flaggers are required, they will billed at the above unit rate.
- Owner will provide a portable hydrant meter and access to onsite water for our use free of charge.
- Owner will provide a local area and pay disposal fees to dispose the debris that is pulled from the cleaning process after it is decanted. Disposal site must be less than 10 miles away from job site.
- Water used to clean pipe segment or box culvert to be decanted in the pipe segment or adjacent pipe/outfall area. Any turbidity control will be provided by Others.
- If bond is needed please add 1.5%.
- Our Bid Proposal is valid for 90 days from the bid date.
- Site Restoration will be performed by Others.
- This is a unit priced contract and the actual billing will be based on installed quantities. If the installed quantities vary greater than 10% of the bid quantities, Vortex reserves the right to adjust our unit price accordingly.
- Standard wages are included. Therefore, Prevailing wages and or Union Wage Rates are not included in this bid proposal.
- Our bid proposal as submitted reflects the current material pricing established on or before the bid date listed within our proposal. In the event of unforeseen price increases of our raw materials, Vortex reserves the right to adjust our unit rate or overall bid proposal accordingly to account for such price increases.
- Payment terms: Net 30 days. Interest will be added to balances outstanding after 30 days
- 7% Material Sales Tax is included in our bid proposal. If the owner is exempt, we will need them to provide an exemption certificate prior to contract execution. Service Tax is not included. If required, it will be invoiced separately.
- Vortex's bid proposal shall be incorporated into the subcontract agreements. Vortex will initiate this project upon an agreement or receipt of a subcontract or purchase order. Copies of payment and performance bonds must be provided to Vortex.

- **Scope of work performed by VLS:**

- Provide pre-work submittal
- Manufacturer Calculation for Fully Deteriorated Pipe Conditions
- Mobilize equipment and personnel necessary to complete rehabilitation
- Compressive Material testing
- Surface Preparation of pipe to receive geopolymer lining
- Spray application of specified structural GeoKrete liner

- **Proposal does NOT include following:**

- Cold weather provisions - required when operating in temperatures 40 degrees F or below (no estimated field execution date provided)
- Pre and Post CCTV (GoPro Style provided)
- Heavy infiltration control (see note below)
- Point repairs or pipe jacking
- Pressure grouting
- Well point/dewatering to lower water table
- Site clearing or excavation
- Invert Repair

- VLS advises a minimum 30 day cure time of liner prior to any overhead or lateral construction (i.e. excessive vibrations, pile driving, etc.).

- **General Notes & Conditions:**

- Non-weather related delays (may include, but NOT limited to: Owner requested changes; Road closures due to community, city or private events; Utility conflicts or relocations not within our scope, any work stoppages outside the control of VLS) will result in additional fees of \$10,000/day.
- Owner to provide access for equipment within 50ft of pipe. Site access to be determined by physical inspection
- Owner to provide potable water supply (i.e. hydrant & meter in place)
- Pricing based on one (1) shift (10-12 hours/day; 6 days/week) and does not include working holidays and/or Sundays.
- Quantities and pipe segments relative to depth, condition and degree of ovality are subject to field verification.
- Heavy infiltration means infiltration that meets the definition of a "runner" or "gusher", as defined by NASSCO's Pipeline Assessment Certification Program. Runner - water running into the sewer through a faulty joint or pipe wall. A continuous flow will be visible. Gusher - water entering the pipe "under pressure" through a defect or faulty joint.

<p>ACCEPTED: The above prices, specifications and conditions are satisfactory and are hereby accepted.</p> <p>Buyer: _____</p> <p>Signature: _____</p> <p>Date of Acceptance: _____</p>	<p>CONFIRMED: Vortex Services LLC</p> <p>Authorized Signature: _____</p> <p>Estimator: Brandon Gerber (813) 326-8928 Bgerber@vortexcompanies.com</p>
---	--